

---

# **PsychoPy - Psychology software for Python**

***Release 3.1.5***

**Jonathan Peirce**

**Jul 12, 2019**



# CONTENTS

<b>1</b>	<b>About PsychoPy</b>	<b>1</b>
<b>2</b>	<b>General issues</b>	<b>3</b>
<b>3</b>	<b>Installation</b>	<b>29</b>
<b>4</b>	<b>Getting Started</b>	<b>33</b>
<b>5</b>	<b>Builder</b>	<b>41</b>
<b>6</b>	<b>Coder</b>	<b>75</b>
<b>7</b>	<b>Running studies online</b>	<b>95</b>
<b>8</b>	<b>Reference Manual (API)</b>	<b>103</b>
<b>9</b>	<b>Troubleshooting</b>	<b>387</b>
<b>10</b>	<b>Recipes (“How-to”s)</b>	<b>391</b>
<b>11</b>	<b>Frequently Asked Questions (FAQs)</b>	<b>403</b>
<b>12</b>	<b>Resources (e.g. for teaching)</b>	<b>405</b>
<b>13</b>	<b>For Developers</b>	<b>407</b>
<b>14</b>	<b>PsychoPy Experiment file format (.psyexp)</b>	<b>421</b>
	<b>Python Module Index</b>	<b>425</b>
	<b>Index</b>	<b>427</b>



## ABOUT PSYCHOPY

### 1.1 Citing PsychoPy

If you use this software, please cite one of the publications that describe it. For most people **the 2019 paper is probably the most relevant** (the papers from 2009, 2007 did not mention Builder at all, for instance).

- Peirce, J. W., Gray, J. R., Simpson, S., MacAskill, M. R., Höchenberger, R., Sogo, H., Kastman, E., Lindeløv, J. (2019). *PsychoPy2: experiments in behavior made easy*. *Behavior Research Methods*. 10.3758/s13428-018-01193-y
- Peirce, J. W., & MacAskill, M. R. (2018). *Building Experiments in PsychoPy*. London: Sage.
- Peirce J. W. (2009). Generating stimuli for neuroscience using PsychoPy. *Frontiers in Neuroinformatics*, **2** (10), 1-8. doi:10.3389/neuro.11.010.2008
- Peirce, J. W. (2007). PsychoPy - Psychophysics software in Python. *Journal of Neuroscience Methods*, **162** (1-2):8-13 doi:10.1016/j.jneumeth.2006.11.017

Citing these papers gives the reviewer/reader of your study information about how the system works and it attributes some credit for its original creation. Academic assessment (whether for promotion or even getting appointed to a job in the first place) prioritises publications over making useful tools for others. Citations provide a way for the developers to justify their continued involvement in the development of the package.



## GENERAL ISSUES

These are issues that users should be aware of, whether they are using Builder or Coder views.

### 2.1 Monitor Center

PsychoPy provides a simple and intuitive way for you to calibrate your monitor and provide other information about it and then import that information into your experiment.

Information is inserted in the Monitor Center (Tools menu), which allows you to store information about multiple monitors and keep track of multiple calibrations for the same monitor.

For experiments written in the Builder view, you can then import this information by simply specifying the name of the monitor that you wish to use in the *Experiment settings* dialog. For experiments created as scripts you can retrieve the information when creating the *Window* by simply naming the monitor that you created in Monitor Center. e.g.:

```
from psychopy import visual
win = visual.Window([1024, 768], mon='SonyG500')
```

Of course, the name of the monitor in the script needs to match perfectly the name given in the Monitor Center.

#### 2.1.1 Real world units

One of the particular features of PsychoPy is that you can specify the size and location of stimuli in units that are independent of your particular setup, such as degrees of visual angle (see *Units for the window and stimuli*). In order for this to be possible you need to inform PsychoPy of some characteristics of your monitor. Your choice of units determines the information you need to provide:

Units	Requires
'norm' (normalised to width/height)	n/a
'pix' (pixels)	Screen width in pixels
'cm' (centimeters on the screen)	Screen width in pixels and screen width in cm
'deg' (degrees of visual angle)	Screen width (pixels), screen width (cm) and distance (cm)

#### 2.1.2 Calibrating your monitor

PsychoPy can also store and use information about the gamma correction required for your monitor. If you have a Spectrascan PR650 (other devices will hopefully be added) you can perform an automated calibration in which PsychoPy will measure the necessary gamma value to be applied to your monitor. Alternatively this can be added

manually into the grid to the right of the Monitor Center. To run a calibration, connect the PR650 via the serial port and, immediately after turning it on press the *Find PR650* button in the Monitor Center.

Note that, if you don't have a photometer to hand then there is a method for determining the necessary gamma value psychophysically included in PsychoPy (see `gammaMotionNull` and `gammaMotionAnalysis` in the demos menu).

The two additional tables in the Calibration box of the Monitor Center provide conversion from *DKL* and *LMS* colour spaces to *RGB*.

## 2.2 Units for the window and stimuli

One of the key advantages of PsychoPy over many other experiment-building software packages is that stimuli can be described in a wide variety of real-world, device-independent units. In most other systems you provide the stimuli at a fixed size and location in pixels, or percentage of the screen, and then have to calculate how many cm or degrees of visual angle that was.

In PsychoPy, after providing information about your monitor, via the *Monitor Center*, you can simply specify your stimulus in the unit of your choice and allow PsychoPy to calculate the appropriate pixel size for you.

Your choice of unit depends on the circumstances. For conducting demos, the two normalised units ('norm' and 'height') are often handy because the stimulus scales naturally with the window size. For running an experiment it's usually best to use something like 'cm' or 'deg' so that the stimulus is a fixed size irrespective of the monitor/window.

For all units, the centre of the screen is represented by coordinates (0,0), negative values mean down/left, positive values mean up/right.

### 2.2.1 Height units

With 'height' units everything is specified relative to the height of the window (note the window, not the screen). As a result, the dimensions of a screen with standard 4:3 aspect ratio will range (-0.6667,-0.5) in the bottom left to (+0.6667,+0.5) in the top right. For a standard widescreen (16:10 aspect ratio) the bottom left of the screen is (-0.8,-0.5) and top-right is (+0.8,+0.5). This type of unit can be useful in that it scales with window size, unlike *Degrees of visual angle* or *Centimeters on screen*, but stimuli remain square, unlike *Normalised units*. Obviously it has the disadvantage that the location of the right and left edges of the screen have to be determined from a knowledge of the screen dimensions. (These can be determined at any point by the *Window.size* attribute.)

Spatial frequency: cycles **per stimulus** (so will scale with the size of the stimulus).

Requires : No monitor information

### 2.2.2 Normalised units

In normalised ('norm') units the window ranges in both x and y from -1 to +1. That is, the top right of the window has coordinates (1,1), the bottom left is (-1,-1). Note that, in this scheme, setting the height of the stimulus to be 1.0, will make it half the height of the window, not the full height (because the window has a total height of 1:-1 = 2!). Also note that specifying the width and height to be equal will not result in a square stimulus if your window is not square - the image will have the same aspect ratio as your window. e.g. on a 1024x768 window the size=(0.75,1) will be square.

Spatial frequency: cycles **per stimulus** (so will scale with the size of the stimulus).

Requires : No monitor information



### 2.2.3 Centimeters on screen

Set the size and location of the stimulus in centimeters on the screen.

Spatial frequency: cycles per cm

Requires : information about the screen width in cm and size in pixels

Assumes : pixels are square. Can be verified by drawing a stimulus with matching width and height and verifying that it is in fact square. For a *CRT* this can be controlled by setting the size of the viewable screen (settings on the monitor itself).

### 2.2.4 Degrees of visual angle

Use degrees of visual angle to set the size and location of the stimulus. This is, of course, dependent on the distance that the participant sits from the screen as well as the screen itself, so make sure that this is controlled, and remember to change the setting in *Monitor Center* if the viewing distance changes.

Spatial frequency: cycles per degree

Requires : information about the screen width in cm and pixels and the viewing distance in cm

There are actually three variants: 'deg', 'degFlat', and 'degFlatPos'

**'deg'** : Most people using degrees of visual angle choose to make the assumption that a degree of visual angle spans the same number of pixels at all parts of the screen. This isn't actually true for standard flat screens - a degree of visual angle at the edge of the screen spans more pixels because it is further from the eye. For moderate eccentricities the error is small (a 0.2% error in size calculation at 3 deg eccentricity) but grows as stimuli are placed further from the centre of the screen (a 2% error at 10 deg). For most studies this form of calculation is preferred, as it does not result in a warped appearance of visual stimuli, but if you need greater precision at far eccentricities then choose one of the alternatives below.

**'degFlatPos'** : This accounts for flat screens in calculating position coordinates of visual stimuli but leaves size and spatial frequency uncorrected. This means that an evenly spaced grid of visual stimuli will appear warped in position but will

**'degFlat'** : This corrects the calculations of degrees for flatness of the screen for each vertex of your stimuli. Square stimuli in the periphery will, therefore, become more spaced apart but they will also get larger and rhomboid in the pixels that they occupy.

### 2.2.5 Pixels on screen

You can also specify the size and location of your stimulus in pixels. Obviously this has the disadvantage that sizes are specific to your monitor (because all monitors differ in pixel size).

Spatial frequency: ``cycles per pixel`` (this catches people out but is used to be in keeping with the other units. If using pixels as your units you probably want a spatial frequency in the range 0.2-0.001 (i.e. from 1 cycle every 5 pixels to one every 100 pixels).

Requires : information about the size of the screen (not window) in pixels, although this can often be deduce from the operating system if it has been set correctly there.

Assumes: nothing

## 2.3 Color spaces

The color of stimuli can be specified when creating a stimulus and when using `setColor()` in a variety of ways. There are three basic color spaces that PsychoPy can use, RGB, DKL and LMS but colors can also be specified by a name (e.g. 'DarkSalmon') or by a hexadecimal string (e.g. '#00FF00').

examples:

```
stim = visual.GratingStim(win, color=[1,-1,-1], colorSpace='rgb') #will be red
stim.setColor('Firebrick') #one of the web/X11 color names
stim.setColor('#FFFAF0') #an off-white
stim.setColor([0,90,1], colorSpace='dkl') #modulate along S-cone axis in isoluminant_
↪plane
stim.setColor([1,0,0], colorSpace='lms') #modulate only on the L cone
stim.setColor([1,1,1], colorSpace='rgb') #all guns to max
stim.setColor([1,0,0]) #this is ambiguous - you need to specify a color space
```

### 2.3.1 Colors by name

Any of the [web/X11 color names](#) can be used to specify a color. These are then converted into RGB space by PsychoPy.

These are not case sensitive, but should not include any spaces.

### 2.3.2 Colors by hex value

This is really just another way of specifying the r,g,b values of a color, where each gun's value is given by two hexadecimal characters. For some examples see [this chart](#). To use these in PsychoPy they should be formatted as a string, beginning with # and with no spaces. (NB on a British Mac keyboard the # key is hidden - you need to press Alt-3)

### 2.3.3 RGB color space

This is the simplest color space, in which colors are represented by a triplet of values that specify the red green and blue intensities. These three values each range between -1 and 1.

Examples:

- [1,1,1] is white
- [0,0,0] is grey
- [-1,-1,-1] is black
- [1.0,-1,-1] is red
- [1.0,0.6,0.6] is pink

The reason that these colors are expressed ranging between 1 and -1 (rather than 0:1 or 0:255) is that many experiments, particularly in visual science where PsychoPy has its roots, express colors as deviations from a grey screen. Under that scheme a value of -1 is the maximum decrement from grey and +1 is the maximum increment above grey.

Note that PsychoPy will use your monitor calibration to linearize this for each gun. E.g., 0 will be halfway between the minimum luminance and maximum luminance for each gun, if your monitor gammaGrid is set correctly.

### 2.3.4 HSV color space

Another way to specify colors is in terms of their Hue, Saturation and ‘Value’ (HSV). For a description of the color space see the [Wikipedia HSV entry](#). The Hue in this case is specified in degrees, the saturation ranging 0:1 and the ‘value’ also ranging 0:1.

Examples:

- [0,1,1] is red
- [0,0.5,1] is pink
- [90,1,1] is cyan
- [anything, 0, 1] is white
- [anything, 0, 0.5] is grey
- [anything, anything,0] is black

Note that colors specified in this space (like in RGB space) are not going to be the same another monitor; they are device-specific. They simply specify the intensity of the 3 primaries of your monitor, but these differ between monitors. As with the RGB space gamma correction is automatically applied if available.

### 2.3.5 DKL color space


To use DKL color space the monitor should be calibrated with an appropriate spectrophotometer, such as a PR650.

In the Derrington, Krauskopf and Lennie<sup>1</sup> color space (based on the Macleod and Boynton<sup>2</sup> chromaticity diagram) colors are represented in a 3-dimensional space using spherical coordinates that specify the *elevation* from the isoluminant plane, the *azimuth* (the hue) and the contrast (as a fraction of the maximal modulations along the cardinal axes of the space).

---

<sup>1</sup> Derrington, A.M., Krauskopf, J., & Lennie, P. (1984). Chromatic Mechanisms in Lateral Geniculate Nucleus of Macaque. *Journal of Physiology*, 357, 241-265.

<sup>2</sup> MacLeod, D. I. A. & Boynton, R. M. (1979). Chromaticity diagram showing cone excitation by stimuli of equal luminance. *Journal of the Optical Society of America*, 69(8), 1183-1186.



In PsychoPy these values are specified in units of degrees for elevation and azimuth and as a float (ranging -1:1) for the contrast.

Note that not all colors that can be specified in DKL color space can be reproduced on a monitor. [Here](#) is a movie plotting in DKL space (showing *cartesian* coordinates, not spherical coordinates) the gamut of colors available on an example CRT monitor.

Examples:

- [90,0,1] is white (maximum elevation aligns the color with the luminance axis)
- [0,0,1] is an isoluminant stimulus, with azimuth 0 (S-axis)
- [0,45,1] is an isoluminant stimulus, with an oblique azimuth

### 2.3.6 LMS color space

To use LMS color space the monitor should be calibrated with an appropriate spectrophotometer, such as a PR650.

In this color space you can specify the relative strength of stimulation desired for each cone independently, each with a value from -1:1. This is particularly useful for experiments that need to generate cone isolating stimuli (for which modulation is only affecting a single cone type).

## 2.4 Preferences

The Preferences dialog allows to adjust general settings for different parts of PsychoPy. The preferences settings are saved in the configuration file *userPrefs.cfg*. The labels in brackets for the different options below represent the abbreviations used in the *userPrefs.cfg* file.

In rare cases, you might want to adjust the preferences on a per-experiment basis. See the API reference for the Preferences class [here](#).

### 2.4.1 Application settings (App)

These settings are common to all components of the application (Coder and Builder etc)

**show start-up tips (showStartupTips):** Display tips when starting PsychoPy.

**large icons (largeIcons):** Do you want large icons (on some versions of wx on macOS this has no effect)?

**default view (defaultView):** Determines which view(s) open when the PsychoPy app starts up. Default is 'last', which fetches the same views as were open when PsychoPy last closed.

**reset preferences (resetPrefs):** Reset preferences to defaults on next restart of PsychoPy.

**auto-save prefs (autoSavePrefs):** Save any unsaved preferences before closing the window.

**debug mode (debugMode):** Enable features for debugging PsychoPy itself, including unit-tests.

**locale (locale):** Language to use in menus etc.; not all translations are available. Select a value, then restart the app. Think about [adding translations for your language](#).

### 2.4.2 Builder settings (Builder)

**reload previous exp (reloadPrevExp):** Select whether to automatically reload a previously opened experiment at start-up.

**uncluttered namespace (unclutteredNamespace):** If this option is selected, the scripts will use more complex code, but the advantage is that there is less of a chance that name conflicts will arise.

**components folders (componentsFolders):** A list of folder path names that can hold additional custom components for the Builder view; expects a comma-separated list.

**hidden components (hiddenComponents):** A list of components to hide (e.g., because you never use them)

**unpacked demos dir (unpackedDemosDir):** Location of Builder demos on this computer (after unpacking).

**saved data folder (savedDataFolder):** Name of the folder where subject data should be saved (relative to the script location).

**Flow at top (topFlow):** If selected, the “Flow” section will be shown topmost and the “Components” section will be on the left. Restart PsychoPy to activate this option.

**always show readme (alwaysShowReadme):** If selected, PsychoPy always shows the Readme file if you open an experiment. The Readme file needs to be located in the same folder as the experiment file.

**max favorites (maxFavorites):** Upper limit on how many components can be in the Favorites menu of the Components panel.

### 2.4.3 Coder settings (Coder)

**code font (codeFont):** A list of font names to be used for code display. The first found on the system will be used.

**comment font (commentFont):** A list of font names to be used for comments sections. The first found on the system will be used

**output font (outputFont):** A list of font names to be used in the output panel. The first found on the system will be used.

**code font size (codeFontSize):** An integer between 6 and 24 that specifies the font size for code display in points.

**output font size (outputFontSize):** An integer between 6 and 24 that specifies the font size for output display in points.

**show source asst (showSourceAsst):** Do you want to show the source assistant panel (to the right of the Coder view)? On Windows this provides help about the current function if it can be found. On macOS the source assistant is of limited use and is disabled by default.

**show output (showOutput):** Show the output panel in the Coder view. If shown all python output from the session will be output to this panel. Otherwise it will be directed to the original location (typically the terminal window that called PsychoPy application to open).

**reload previous files (reloadPrevFiles):** Should PsychoPy fetch the files that you previously had open when it launches?

**preferred shell (preferredShell):** Specify which shell should be used for the coder shell window.

**newline convention (newlineConvention):** Specify which character sequence should be used to encode newlines in code files: unix = n (line feed only), dos = rn (carriage return plus line feed).

### 2.4.4 General settings (General)

**window type (winType):** PsychoPy can use one of two ‘backends’ for creating windows and drawing; pygame, pyglet and glfw. Here you can set the default backend to be used.

**units (units):** Default units for windows and visual stimuli (‘deg’, ‘norm’, ‘cm’, ‘pix’). See *Units for the window and stimuli*. Can be overridden by individual experiments.

**full-screen (fullscr):** Should windows be created full screen by default? Can be overridden by individual experiments.

**allow GUI (allowGUI):** When the window is created, should the frame of the window and the mouse pointer be visible. If set to False then both will be hidden.

**paths (paths):** Paths for additional Python packages can be specified. See more information *here*.

**audio library (audioLib):** As explained in the *Sound* documentation, currently two sound libraries are available, pygame and pyo.

**audio driver (audioDriver):** Also, different audio drivers are available.

**flac audio compression (flac):** Set flac audio compression.

**parallel ports (parallelPorts):** This list determines the addresses available in the drop-down menu for the *Parallel Port Out Component*.

### 2.4.5 Connection settings (Connections)

**proxy (proxy):** The proxy server used to connect to the internet if needed. Must be of the form http://111.222.333.444:5555

**auto-proxy (autoProxy):** PsychoPy should try to deduce the proxy automatically. If this is True and autoProxy is successful, then the above field should contain a valid proxy address.

**allow usage stats (allowUsageStats):** Allow PsychoPy to ping a website at when the application starts up. Please leave this set to True. The info sent is simply a string that gives the date, PsychoPy version and platform info. There is no cost to you: no data is sent that could identify you and PsychoPy will not be delayed in starting as a result. The aim is simple: if we can show that lots of people are using PsychoPy there is a greater chance of it being improved faster in the future.

**check for updates (checkForUpdates):** PsychoPy can (hopefully) automatically fetch and install updates. This will only work for minor updates and is still in a very experimental state (as of v1.51.00).

**timeout (timeout):** Maximum time in seconds to wait for a connection response.

## 2.4.6 Key bindings

There are many shortcut keys that you can use in PsychoPy. For instance did you realise that you can indent or outdent a block of code with Ctrl-[ and Ctrl-] ?

## 2.5 Data outputs

There are a number of different forms of output that PsychoPy can generate, depending on the study and your preferred analysis software. Multiple file types can be output from a single experiment (e.g. *Excel data file* for a quick browse, *Log file* to check for error messages and *PsychoPy data file (.psydat)* for detailed analysis)

### 2.5.1 Log file

Log files are actually rather difficult to use for data analysis but provide a chronological record of everything that happened during your study. The level of content in them depends on you. See *Logging data* for further information.

### 2.5.2 PsychoPy data file (.psydat)

This is actually a *TrialHandler* or *StairHandler* object that has been saved to disk with the python *cPickle* module.

These files are designed to be used by experienced users with previous experience of python and, probably, matplotlib. The contents of the file can be explored with *dir()*, as any other python object.

These files are ideal for batch analysis with a python script and plotting via *matplotlib*. They contain more information than the Excel or csv data files, and can even be used to (re)create those files.

**Of particular interest might be the attributes of the Handler:**

**extraInfo** the *extraInfo* dictionary provided to the Handler during its creation

**trialList** the list of dictionaries provided to the Handler during its creation

**data** a dictionary of 2D numpy arrays. Each entry in the dictionary represents a type of data (e.g. if you added 'rt' data during your experiment using `~psychopy.data.TrialHandler.addData` then 'rt' will be a key). For each of those entries the 2D array represents the condition number and repeat number (remember that these start at 0 in python, unlike Matlab(TM) which starts at 1)

For example, to open a psydat file and examine some of its contents with:

```
from psychopy.misc import fromFile
datFile = fromFile('fileName.psydat')
#get info (added when the handler was created)
print datFile.extraInfo
#get data
print datFile.data
#get list of conditions
conditions = datFile.trialList
for condN, condition in enumerate(conditions):
    print condition, datFile.data['response'][condN], numpy.mean(datFile.data[
↪ 'response'] [condN])
```

Ideally, we should provide a demo script here for fetching and plotting some data (feel free to *contribute*).

## 2.5.3 Long-wide data file

This form of data file is the default data output from Builder experiments as of v1.74.00. Rather than summarising data in a spreadsheet where one row represents all the data from a single condition (as in the summarised data format), in long-wide data files the data is not collapsed by condition, but written chronologically with one row representing one trial (hence it is typically longer than summarised data files). One column in this format is used for every single piece of information available in the experiment, even where that information might be considered redundant (hence the format is also ‘wide’).

Although these data files might not be quite as easy to read quickly by the experimenter, they are ideal for import and analysis under packages such as R, SPSS or Matlab.

## 2.5.4 Excel data file

Excel 2007 files (.xlsx) are a useful and flexible way to output data as a spreadsheet. The file format is open and supported by nearly all spreadsheet applications (including older versions of Excel and also OpenOffice). N.B. because .xlsx files are widely supported, the older Excel file format (.xls) is not likely to be supported by PsychoPy unless a user contributes the code to the project.

Data from PsychoPy are output as a table, with a header row. Each row represents one condition (trial type) as given to the *TrialHandler*. Each column represents a different type of data as given in the header. For some data, where there are multiple columns for a single entry in the header. This indicates multiple trials. For example, with a standard data file in which response time has been collected as ‘rt’ there will be a heading *rt\_raw* with several columns, one for each trial that occurred for the various trial types, and also an *rt\_mean* heading with just a single column giving the mean reaction time for each condition.

If you’re creating experiments by writing scripts then you can specify the sheet name as well as file name for Excel file outputs. This way you can store multiple sessions for a single subject (use the subject as the filename and a date-stamp as the sheetname) or a single file for multiple subjects (give the experiment name as the filename and the participant as the sheetname).

Builder experiments use the participant name as the file name and then create a sheet in the Excel file for each loop of the experiment. e.g. you could have a set of practice trials in a loop, followed by a set of main trials, and these would each receive their own sheet in the data file.

## 2.5.5 Delimited text files (.csv, .tsv, .txt)

For maximum compatibility, especially for legacy analysis software, you can choose to output your data as a delimited text file. Typically this would be comma-separated values (.csv file) or tab-delimited (.tsv file). The format of those files is exactly the same as the Excel file, but is limited by the file format to a single sheet.



## 2.6 Gamma correcting a monitor

Monitors typically don't have linear outputs; when you request luminance level of 127, it is not exactly half the luminance of value 254. For experiments that require the luminance values to be linear, a correction needs to be put in place for this nonlinearity which typically involves fitting a power law or gamma ( $\gamma$ ) function to the monitor output values. This process is often referred to as gamma correction.

PsychoPy can help you perform gamma correction on your monitor, especially if you have one of the supported photometers/spectroradiometers.

There are various different equations with which to perform gamma correction. The simple equation (2.1) is assumed by most hardware manufacturers and gives a reasonable first approximation to a linear correction. The full gamma correction equation (2.3) is more general, and likely more accurate especially where the lowest luminance value of the monitor is bright, but also requires more information. It can only be used in labs that do have access to a photometer or similar device.

### 2.6.1 Simple gamma correction

The simple form of correction (as used by most hardware and software) is this:

$$L(V) = a + kV^\gamma \quad (2.1)$$

where  $L$  is the final luminance value,  $V$  is the requested intensity (ranging 0 to 1),  $a$ ,  $k$  and  $\gamma$  are constants for the monitor.

This equation assumes that the luminance where the monitor is set to 'black' ( $V=0$ ) comes entirely from the surround and is therefore not subject to the same nonlinearity as the monitor. If the monitor itself contributes significantly to  $a$  then the function may not fit very well and the correction will be poor.

The advantage of this function is that the calibrating system (PsychoPy in this case) does not need to know anything more about the monitor than the gamma value itself (for each gun). For the full gamma equation (2.3), the system needs to know about several additional variables. The look-up table (LUT) values required to give a (roughly) linear luminance output can be generated by:

$$LUT(V) = V^{1/\gamma} \quad (2.2)$$

where  $V$  is the entry in the LUT, between 0 (black) and 1 (white).

### 2.6.2 Full gamma correction

For very accurate gamma correction PsychoPy uses a more general form of the equation above, which can separate the contribution of the monitor and the background to the lowest luminance level:

$$L(V) = a + (b + kV)^\gamma \quad (2.3)$$

This equation makes no assumption about the origin of the base luminance value, but requires that the system knows the values of  $b$  and  $k$  as well as  $\gamma$ .

The inverse values, required to build the LUT are found by:

$$LUT(V) = \frac{((1 - V)b^\gamma + V(b + k)^\gamma)^{1/\gamma} - b}{k} \quad (2.4)$$

This is derived below, for the interested reader. ;-)

And the associated luminance values for each point in the LUT are given by:

$$L(V) = a + (1 - V)b^\gamma + V(b + k)^\gamma$$

### 2.6.3 Deriving the inverse full equation

The difficulty with the full gamma equation (2.3) is that the presence of the  $b$  value complicates the issue of calculating the inverse values for the LUT. The simple inverse of (2.3) as a function of output luminance values is:

$$LUT(L) = \frac{((L - a)^{1/\gamma} - b)}{k} \quad (2.5)$$

To use this equation we need to first calculate the linear set of luminance values,  $L$ , that we are able to produce the current monitor and lighting conditions and *then* deduce the LUT value needed to generate that luminance value.

We need to insert into the LUT the values between 0 and 1 (to use the maximum range) that map onto the linear range from the minimum,  $m$ , to the maximum  $M$  possible luminance. From the parameters in (2.3) it is clear that:

$$\begin{aligned} m &= a + b^\gamma \\ M &= a + (b + k)^\gamma \end{aligned} \quad (2.6)$$

Thus, the luminance value,  $L$  at any given point in the LUT,  $V$ , is given by

$$\begin{aligned} L(V) &= m + (M - m)V \\ &= a + b^\gamma + (a + (b + k)^\gamma - a - b^\gamma)V \\ &= a + b^\gamma + ((b + k)^\gamma - b^\gamma)V \\ &= a + (1 - V)b^\gamma + V(b + k)^\gamma \end{aligned} \quad (2.7)$$

where  $V$  is the position in the LUT as a fraction.

Now, to generate the LUT as needed we simply take the inverse of (2.3):

$$LUT(L) = \frac{(L - a)^{1/\gamma} - b}{k} \quad (2.8)$$

and substitute our  $L(V)$  values from (2.7):

$$\begin{aligned} LUT(V) &= \frac{(a + (1 - V)b^\gamma + V(b + k)^\gamma - a)^{1/\gamma} - b}{k} \\ &= \frac{((1 - V)b^\gamma + V(b + k)^\gamma)^{1/\gamma} - b}{k} \end{aligned} \quad (2.9)$$

### 2.6.4 References

## 2.7 OpenGL and Rendering

All rendering performed by PsychoPy uses hardware-accelerated OpenGL rendering where possible. This means that, as much as possible, the necessary processing to calculate pixel values is performed by the graphics card *GPU* rather than by the *CPU*. For example, when an image is rotated the calculations to determine what pixel values should result, and any interpolation that is needed, are determined by the graphics card automatically.

In the double-buffered system, stimuli are initially drawn into a piece of memory on the graphics card called the ‘back buffer’, while the screen presents the ‘front buffer’. The back buffer initially starts blank (all pixels are set to the window’s defined color) and as stimuli are ‘rendered’ they are gradually added to this back buffer. The way in which stimuli are combined according to transparency rules is determined by the *blend mode* of the window. At some point in time, when we have rendered to this buffer all the objects that we wish to be presented, the buffers are ‘flipped’ such that the stimuli we have been drawing are presented simultaneously. The monitor updates at a very precise fixed rate and the flipping of the window will be synchronised to this monitor update if possible (see *Sync to VBL and wait for VBL*).

Each update of the window is referred to as a ‘frame’ and this ultimately determines the temporal resolution with which stimuli can be presented (you cannot present your stimulus for any duration other than a multiple of the frame duration). In addition to synchronising flips to the frame refresh rate, PsychoPy can optionally go a further step of not allowing the code to continue until a screen flip has occurred on the screen, which is useful in ascertaining exactly when the frame refresh occurred (and, thus, when your stimulus actually appeared to the subject). These timestamps are very precise on most computers. For further information about synchronising and waiting for the refresh see [Sync to VBL and wait for VBL](#).

If the code/processing required to render all your stimuli to the screen takes longer to complete than one screen refresh then you will ‘drop/skip a frame’. In this case the previous frame will be left on screen for a further frame period and the flip will only take effect on the following screen update. As a result, time-consuming operations such as disk accesses or execution of many lines of code, should be avoided while stimuli are being dynamically updated (if you care about the precise timing of your stimuli). For further information see the sections on [Detecting dropped frames](#) and [Reducing dropped frames](#).

### 2.7.1 Fast and slow functions

The fact that modern graphics processors are extremely powerful; they can carry out a great deal of processing from a very small number of commands. Consider, for instance, the PsychoPy Coder demo *elementArrayStim* in which several hundred Gabor patches are updated frame by frame. The graphics card has to blend a sinusoidal grating with a grey background, using a Gaussian profile, several hundred times each at a different orientation and location and it does this in less than one screen refresh on a good graphics card.

There are three things that are relatively slow and should be avoided at critical points in time (e.g. when rendering a dynamic or brief stimulus). These are:

1. disk accesses
2. passing large amounts of data to the graphics card
3. making large numbers of python calls.

Functions that are very fast:

1. Calls that move, resize, rotate your stimuli are likely to carry almost no overhead
2. Calls that alter the color, contrast or opacity of your stimulus will also have no overhead IF your graphics card supports *OpenGL Shaders*
3. Updating of stimulus parameters for `psychopy.visual.ElementArrayStim` is also surprisingly fast BUT you should try to update your stimuli using *numpy* arrays for the maths rather than *for... loops*

Notable slow functions in PsychoPy calls:

1. Calls to set the image or set the mask of a stimulus. This involves having to transfer large amounts of data between the computer’s main processor and the graphics card, which is a relatively time-consuming process.
2. Any of your own code that uses a Python *for... loop* is likely to be slow if you have a large number of cycles through the loop. Try to ‘vectorise’ your code using a *numpy* array instead.

### 2.7.2 Tips to render stimuli faster

1. Keep images as small as possible. This is meant in terms of **number of pixels**, not in terms of Mb on your disk. Reducing the size of the image on your disk might have been achieved by image compression such as using jpeg images but these introduce artefacts and do nothing to reduce the problem of send large amounts of data from the CPU to the graphics card. Keep in mind the size that the image will appear on your monitor and how many pixels it will occupy there. If you took your photo using a 10 megapixel camera that means the image is

represented by 30 million numbers (a red, green and blue) but your computer monitor will have, at most, around 2 megapixels (1960x1080).

2. Try to use square powers of two for your image sizes. This is efficient because computer memory is organised according to powers of two (did you notice how often numbers like 128, 512, 1024 seem to come up when you buy your computer?). Also several mathematical routines (anything involving Fourier maths, which is used a lot in graphics processing) are faster with power-of-two sequences. For the `psychopy.visual.GratingStim` a texture/mask of this size is **required** and if you don't provide one then your texture will be 'upsampled' to the next larger square-power-of-2, so you can save this interpolation step by providing it in the right shape initially.
3. Get a faster graphics card. Upgrading to a more recent card will cost around £30. If you're currently using an integrated Intel graphics chip then almost any graphics card will be an advantage. Try to get an nVidia or an ATI Radeon card.

### 2.7.3 OpenGL Shaders

You may have heard mention of 'shaders' on the users mailing list and wondered what that meant (or maybe you didn't wonder at all and just went for a donut!). OpenGL shader programs allow modern graphics cards to make changes to things during the rendering process (i.e. while the image is being drawn). To use this you need a graphics card that supports OpenGL 2.1 and PsychoPy will only make use of shaders if a specific OpenGL extension that allows floating point textures is also supported. Nowadays nearly all graphics cards support these features - even Intel chips from Intel!

One example of how such shaders are used is the way that PsychoPy colors greyscale images. If you provide a greyscale image as a 128x128 pixel texture and set its color to be red then, without shaders, PsychoPy needs to create a texture that contains the 3x128x128 values where each of the 3 planes is scaled according to the RGB values you require. If you change the color of the stimulus a new texture has to be generated with the new weightings for the 3 planes. However, with a shader program, that final step of scaling the texture value according to the appropriate RGB value can be done by the graphics card. That means we can upload just the 128x128 texture (taking 1/3 as much time to upload to the graphics card) and then we each time we change the color of the stimulus we just a new RGB triplet (only 3 numbers) without having to recalculate the texture. As a result, on graphics cards that support shaders, changing colors, contrasts and opacities etc. has almost zero overhead.

### 2.7.4 Blend Mode

A 'blend function' determines how the values of new pixels being drawn should be combined with existing pixels in the 'frame buffer'.

#### **blendMode = 'avg'**

This mode is exactly akin to the real-world scenario of objects with varying degrees of transparency being placed in front of each other; increasingly transparent objects allow increasing amounts of the underlying stimuli to show through. Opaque stimuli will simply occlude previously drawn objects. With each increasing semi-transparent object to be added, the visibility of the first object becomes increasingly weak. The order in which stimuli are rendered is very important since it determines the ordering of the layers. Mathematically, each pixel colour is constructed from  $\text{opacity} * \text{stimRGB} + (1 - \text{opacity}) * \text{backgroundRGB}$ . This was the only mode available before PsychoPy version 1.80 and remains the default for the sake of backwards compatibility.

#### **blendMode = 'add'**

If the window `blendMode` is set to 'add' then the value of the new stimulus does not in any way *replace* that of the existing stimuli that have been drawn; it is added to it. In this case the value of *opacity* still affects the weighting of

the new stimulus being drawn but the first stimulus to be drawn is never ‘occluded’ as such. The sum is performed using the signed values of the color representation in PsychoPy, with the mean grey being represented by zero. So a dark patch added to a dark background will get even darker. For grating stimuli this means that contrast is summed correctly.

This blend mode is ideal if you want to test, for example, the way that subjects perceive the sum of two potentially overlapping stimuli. It is also needed for rendering stereo/dichoptic stimuli to be viewed through colored anaglyph glasses.

If stimuli are combined in such a way that an impossible luminance value is requested of any of the monitor guns then that pixel will be out of bounds. In this case the pixel can either be clipped to provide the nearest possible colour, or can be artificially colored with noise, highlighting the problem if the user would prefer to know that this has happened.

### 2.7.5 Sync to VBL and wait for VBL

PsychoPy will always, if the graphics card allows it, synchronise the flipping of the window with the vertical blank interval (VBL aka VBI) of the screen. This prevents visual artefacts such as ‘tearing’ of moving stimuli. This does not, itself, indicate that the script also waits for the physical frame flip to occur before continuing. If the *waitBlanking* window argument is set to False then, although the window refreshes themselves will only occur in sync with the screen VBL, the *win.flip()* call will not actually wait for this to occur, such that preparations can continue immediately for the next frame. For rendering purposes this is actually optimal and will reduce the likelihood of frames being dropped during rendering.

By default the PsychoPy Window will also wait for the VBL (*waitBlanking=True*) . Although this is slightly less efficient for rendering purposes it is necessary if we need to know exactly when a frame flip occurred (e.g. to timestamp when the stimulus was physically presented). On most systems this will provide a very accurate measure of when the stimulus was presented (with a variance typically well below 1ms but this should be tested on your system).

## 2.8 Projects

As of version 1.84 PsychoPy connects directly with the Open Science Framework website (<http://OSF.io>) allowing you to search for existing projects and upload your own experiments and data.

**There are several reasons you may want to do this:**

- sharing files with collaborators
- sharing files with the rest of the scientific community
- maintaining historical evidence of your work
- providing yourself with a simple version control across your different machines

### 2.8.1 Sharing with collaborators

You may find it simple to share files with your collaborators using dropbox but that means your data are stored by a commercial company over which you have no control and with no interest in scientific integrity. Check with your ethics committee how they feel about your data (e.g. personal details of participants?) being stored on dropbox. OSF, by comparison, is designed for scientists to store their data securely and forever.

Once you’ve created a project on OSF you can add other contributors to it and when they log in via PsychoPy they will see the projects they share with you (as well as the project they have created themselves). Then they can sync with that project just like any other.

## 2.8.2 Sharing files/projects with others

Optionally, you can make your project (or subsets of it) publicly accessible so that others can view the files. This has various advantages, to the scientific field but also to you as a scientist.

### Good for open science:

- Sharing your work allows scientists to work out why one experiment gave a different result to another; there are often subtleties in the exact construction of a study that didn't get described fully in the methods section. By sharing the actual experiment, rather than just a description of it, we can reduce the failings of replications
- Sharing your work helps others get up and running quickly. That's good for the scientific community. We want science to progress faster and with fewer mistakes.

Some people feel that, having put in all that work to create their study, it would be giving up their advantage to let others simply use their work. Luckily, sharing is good for you as a scientist as well!

### Good for the scientist:

- When you create a study you want others to base their work on yours (we call that academic impact)
- By giving people the exact materials from your work you increase the chance that they will work on your topic and base their next study on something of yours
- By making your project publicly available on OSF (or other sharing repository) you raise visibility of your work

You don't need to decide to share immediately. Probably you want your work to be private until the experiment is complete and the paper is under review (or has been accepted even). That's fine. You can create your project and keep it private between you and your collaborators and then share it at a later date with the click of a button.

## 2.8.3 Maintaining a validated history of your work

In many areas of science researchers are very careful about maintaining a full documented history of what their work; what the

- you can “preregister” your plans for the next experiment (so that people can't later accuse you of “p-hacking”).
- all your files are timestamped so you can prove to others that they were collected on/by a certain date, removing any potential doubts about who collected data first
- your projects (and individual files) have a unique URL on OSF so you can cite/reference resources.

Additionally, “Registrations” (snapshots of your project at a fixed point in time) can be given a DOI, which guarantees they will exist permanently

## 2.8.4 Using PsychoPy to sync with OSF

PsychoPy doesn't currently have the facility to *create* user profiles or projects, so the first step is for you to do that yourself.

### Login to OSF

From the *Projects* menu you can log in to OSF with your username and password (this is never stored; see [Security](#)). This user will stay logged in while the PsychoPy application remains open, or until you switch to a different user. If

you select “Remember me” then your login will be stored and you can log in again without typing your password each time.

Projects that you have previously synchronised will try to use the stored details of the known users if possible and will revert to username and password if not. Project files (defining the details of the project to sync) can be stored wherever you choose; either in a private or shared location. User details are stored in the home space of the user currently logged in to the operating system so are not shared with other users by default.

## Security

When you log in with your username and password these details are not stored by PsychoPy in any way. They are sent immediately to OSF using a secure (https) connection. OSF sends back an “authorisation token” identifying you as a valid user with authorised credentials. This is stored locally for future log in attempts. By visiting your user profile at <http://OSF.io> you can see what applications/computers have retrieved authorisation tokens for your account (and revoke them if you choose).

The auth token is stored in plain text on your computer, but a malicious attacker with access to your computer could only use this to log in to OSF.io. They could not use it to work out your password.

All files are sent by secure connection (https) to the server.

## Searching for projects

Having logged in to OSF from the projects menu you can search for projects to work with using the *>Projects>Search* menu. This brings up a view that shows you all the current projects for the logged in user (owned or shared) and allows you to search for public projects using tags and/or words in the title.

When you select a project, either in your own projects or in the search box, then the details for that project come up on the right hand side, including a link to visit the project page on the web site.

On the web page for the project you can “fork” the project to your own username and then you can use PsychoPy to download/update/sync files with that project, just as with any other project. The project retains information about its history; the project from which it was forked gets its due credit.

## Synchronizing projects

Having found your project online you can then synchronize a local folder with that set of files.

### To do this the first time:

- select one of your projects in the project search window so the details appear on the right
- press the “Sync...” button
- the Project Sync dialog box will appear
- set the location/name for a project file, which will store information about the state of files on the last sync
- set the location of the (root) folder locally that you want to be synchronised with the remote files
- press sync

### The sync process and rules:

- on the first synchronisation all the files/folders will be merged: - the contents of the local folder will be uploaded to the server and vice versa - files that have the same name but different contents (irrespective of dates) will be flagged as conflicting (see below) and both copies kept



- on subsequent sync operations a two-way sync will be performed taking into account the previous state. **If you delete the files locally and then sync then they will be deleted remotely as well**
- files that are the same (according to an md5 checksum) and have the same location will be left as they are
- if a file is in conflict (it has been changed in both locations since the last sync) then both versions will be kept and will be tagged as conflicting
- if a file is deleted in one location but is also changed in the other (since the last sync) then it will be recreated on the side where it was deleted with the state of the side where it was not deleted.

Conflicting files will be labelled with their original filename plus the string “\_CONFLICT<timestamp>” Deletion conflicts will be labelled with their original filename plus the string “\_DELETED”

### Limitations

- PsychoPy does not directly allow you to create a new project yet, nor create a user account. To start with you need to go to <http://osf.io> to create your username and/or project. You also cannot currently fork public projects to your own user space yet from within PsychoPy. If you find a project that is useful to you then fork it from the website (the link is available in the details panel of the project search window)
- The synchronisation routines are fairly basic right now and will not cater for all possible eventualities. For example, if you create a file locally but your colleague created a folder with the same name and synced that with the server, it isn't clear what will (or should ideally) happen when you now sync your project. You should be careful with this tool and always back up your data by an independent means in case damage to your files is caused
- This functionality is new and may well have bugs. **User beware!**

## 2.9 Timing Issues and synchronisation

One of the key requirements of experimental control software is that it has good temporal precision. PsychoPy aims to be as precise as possible in this domain and can achieve excellent results depending on your experiment and hardware. It also provides you with a precise log file of your experiment to allow you to check the precision with which things occurred. Some general considerations are discussed here and there are links with *Specific considerations for specific designs*.

Something that people seem to forget (not helped by the software manufacturers that keep talking about their sub-millisecond precision) is that the monitor, keyboard and human participant DO NOT have anything like this sort of precision. Your monitor updates every 10-20ms depending on frame rate. If you use a CRT screen then the top is drawn before the bottom of the screen by several ms. If you use an LCD screen the whole screen can take around 20ms to switch from one image to the next. Your keyboard has a latency of 4-30ms, depending on brand and system.

So, yes, PsychoPy's temporal precision is as good as most other equivalent applications, for instance the duration for which stimuli are presented can be synchronised precisely to the frame, but the overall accuracy is likely to be severely limited by your experimental hardware. To get **very** precise timing of responses etc., you need to use specialised hardware like button boxes and you need to think carefully about the physics of your monitor.

**Warning:** The information about timing in PsychoPy assumes that your graphics card is capable of synchronising with the monitor frame rate. For integrated Intel graphics chips (e.g. GMA 945) under Windows, this is not true and the use of those chips is not recommended for serious experimental use as a result. Desktop systems can have a moderate graphics card added for around £30 which will be vastly superior in performance.



## 2.9.1 Specific considerations for specific designs

### Non-slip timing for imaging

For most behavioural/psychophysics studies timing is most simply controlled by setting some timer (e.g. a `Clock()`) to zero and waiting until it has reached a certain value before ending the trial. We might call this a ‘relative’ timing method, because everything is timed from the start of the trial/epoch. In reality this will cause an overshoot of some fraction of one screen refresh period (10ms, say). For imaging (EEG/MEG/fMRI) studies adding 10ms to each trial repeatedly for 10 minutes will become a problem, however. After 100 stimulus presentations your stimulus and scanner will be de-synchronised by 1 second.

There are two ways to get around this:

1. *Time by frames* If you are confident that you *aren't dropping frames* then you could base your timing on frames instead to avoid the problem.
2. *Non-slip (global) clock timing* The other way, which for imaging is probably the most sensible, is to arrange timing based on a global clock rather than on a relative timing method. At the start of each trial you add the (known) duration that the trial will last to a *global* timer and then wait until that timer reaches the necessary value. To facilitate this, the PsychoPy `Clock()` was given a new `add()` method as of version 1.74.00 and a `CountdownTimer()` was also added.

The non-slip method can only be used in cases where the trial is of a known duration at its start. It cannot, for example, be used if the trial ends when the subject makes a response, as would occur in most behavioural studies.

### Non-slip timing from the Builder

(new feature as of version 1.74.00)

When creating experiments in the *Builder*, PsychoPy will attempt to identify whether a particular *Routine* has a known endpoint in seconds. If so then it will use non-slip timing for this Routine based on a global countdown timer called *routineTimer*. Routines that are able to use this non-slip method are shown in green in the *Flow*, whereas Routines using relative timing are shown in red. So, if you are using PsychoPy for imaging studies then make sure that all the Routines within your loop of epochs are showing as green. (Typically your study will also have a Routine at the start waiting for the first scanner pulse and this will use relative timing, which is appropriate).

### Detecting dropped frames

Occasionally you will drop frames if you:

- try to do too much drawing
- do it in an inefficient manner (write poor code)
- have a poor computer/graphics card

Things to avoid:

- recreating textures for stimuli
- building new stimuli from scratch (create them once at the top of your script

and then change them using `stim.setOri(ori)()`, `stim.setPos([x,y]...)`

### Turn on frame time recording

The key sometimes is *knowing* if you are dropping frames. PsychoPy can help with that by keeping track of frame durations. By default, frame time tracking is turned off because many people don't need it, but it can be turned on any time after *Window* creation:

```
from psychopy import visual
win = visual.Window([800,600])
win.recordFrameIntervals = True
```

Since there are often dropped frames just after the system is initialised, it makes sense to start off with a fixation period, or a ready message and don't start recording frame times until that has ended. Obviously if you aren't refreshing the window at some point (e.g. waiting for a key press with an unchanging screen) then you should turn off the recording of frame times or it will give spurious results.

### Warn me if I drop a frame

The simplest way to check if a frame has been dropped is to get PsychoPy to report a warning if it thinks a frame was dropped:

```
from __future__ import division, print_function

from psychopy import visual, logging
win = visual.Window([800,600])

win.recordFrameIntervals = True

# By default, the threshold is set to 120% of the estimated refresh
# duration, but arbitrary values can be set.
#
# I've got 85Hz monitor and want to allow 4 ms tolerance; any refresh that
# takes longer than the specified period will be considered a "dropped"
# frame and increase the count of win.nDroppedFrames.
win.refreshThreshold = 1/85 + 0.004

# Set the log module to report warnings to the standard output window
# (default is errors only).
logging.console.setLevel(logging.WARNING)

print('Overall, %i frames were dropped.' % win.nDroppedFrames)
```

### Show me all the frame times that I recorded

While recording frame times, these are simply appended, every frame to win.frameIntervals (a list). You can simply plot these at the end of your script using matplotlib:

```
import matplotlib.pyplot as plt
plt.plot(win.frameIntervals)
plt.show()
```

Or you could save them to disk. A convenience function is provided for this:

```
win.saveFrameIntervals(fileName=None, clear=True)
```

The above will save the currently stored frame intervals (using the default filename, 'lastFrameIntervals.log') and then clears the data. The saved file is

a simple text file.

At any time you can also retrieve the time of the /last/ frame flip using `win.lastFrameT` (the time is synchronised with `logging.defaultClock` so it will match any logging commands that your script uses).

### 'Blocking' on the VBI

As of version 1.62 PsychoPy 'blocks' on the vertical blank interval meaning that, once `Window.flip()` has been called, no code will be executed until that flip actually takes place. The timestamp for the above frame interval measurements is taken immediately after the flip occurs. Run the `timeByFrames` demo in `Coder` to see the precision of these measurements on your system. They should be within 1ms of your mean frame interval.

Note that Intel integrated graphics chips (e.g. GMA 945) under win32 do not sync to the screen at all and so blocking on those machines is not possible.

### Reducing dropped frames

There are many things that can affect the speed at which drawing is achieved on your computer. These include, but are probably not limited to; your graphics card, CPU, operating system, running programs, stimuli, and your code itself. Of these, the CPU and the OS appear to make rather little difference. To determine whether you are actually dropping frames see *Detecting dropped frames*.

### Things to change on your system:

1. make sure you have a good graphics card. Avoid integrated graphics chips, especially Intel integrated chips and especially on laptops (because on these you don't get to change your mind so easily later). In particular, try to make sure that your card supports OpenGL 2.0
2. **shut down as many programs, including background processes. Although modern processors are fast and often have multiple cores, they are still limited by the amount of RAM and the speed of the hard drive.**
  - anti-virus auto-updating (if you're allowed)
  - email checking software
  - file indexing software
  - backup solutions (e.g. TimeMachine)
  - Dropbox
  - Synchronisation software

### Writing optimal scripts

1. run in full-screen mode (rather than simply filling the screen with your window). This way the OS doesn't have to spend time working out what application is currently getting keyboard/mouse events.
2. don't generate your stimuli when you need them. Generate them in advance and then just modify them later with the methods like `setContrast()`, `setOrientation()` etc...
3. **calls to the following functions are comparatively slow; they require more CPU time than most other functions and then have to wait for the next frame to be drawn.**

- (a) `GratingStim.setTexture()`
  - (b) `RadialStim.setTexture()`
  - (c) `TextStim.setText()`
4. if you don't have OpenGL 2.0 then calls to `setContrast`, `setRGB` and `setOpacity` will also be slow, because they also make a call to `setTexture()`. If you have shader support then this call is not necessary and a large speed increase will result.
  5. avoid loops in your python code (use numpy arrays to do maths with lots of elements)
  6. if you need to create a large number (e.g. greater than 10) similar stimuli, then try the `ElementArrayStim`

### Possible good ideas

It isn't clear that these actually make a difference, but they might).

1. disconnect the internet cable (to prevent programs performing auto-updates?)
2. on Macs you can actually shut down the Finder. It might help. See Alex Holcombe's page [here](#)
3. use a single screen rather than two (probably there is some graphics card overhead in managing double the number of pixels?)

### Comparing Operating Systems under PsychoPy

This is an attempt to quantify the ability of PsychoPy draw without dropping frames on a variety of hardware/software. The following tests were conducted using the script at the bottom of the page. Note, of course that the hardware fully differs between the Mac and Linux/Windows systems below, but that both are standard off-the-shelf machines.

**All of the below tests were conducted with 'normal' systems rather than anything that had been specifically optimised:**

- the machines were connected to network
- did not have anti-virus turned off (except Ubuntu had no anti-virus)
- they even all had dropbox clients running
- Linux was the standard (not 'realtime' kernel)

No applications were actively being used by the operator while tests were run.

**In order to test drawing under a variety of processing loads the test stimulus was one of:**

- a single drifting Gabor
- 500 random dots continuously updating
- 750 random dots continuously updating
- 1000 random dots continuously updating

**Common settings:**

- Monitor was a CRT 1024x768 100Hz
- all tests were run in full screen mode with mouse hidden

**System Differences:**

- the iMac was lower spec than the Windows/Linux box and running across two monitors (necessary in order to connect to the CRT)

- the Windows/Linux box ran off a single monitor

Each run below gives the number of dropped frames out of a run of 10,000 (2.7 mins at 100Hz).

—	Windows XP	Windows 7	Mac OS X 10.6	Ubuntu 11.10
—	(SP3)	Enterprise	Snow Leopard	
Gabor	0	5	0	0
500-dot RDK	0	5	54	3
750-dot RDK	21	7	aborted	1174
1000-dot RDK	776	aborted	aborted	aborted
GPU	Radeon 5400	Radeon 5400	Radeon 2400	Radeon 5400
GPU driver	Catalyst 11.11	Catalyst 11.11		Catalyst 11.11
CPU	Core Duo 3GHz	Core Duo 3GHz	Core Duo 2.4GHz	Core Duo 3GHz
RAM	4GB	4GB	2GB	4GB

I'll gradually try to update these tests to include:

- longer runs (one per night!)
- a faster Mac
- a real-time Linux kernel

## 2.9.2 Other questions about timing

### Can PsychoPy deliver millisecond precision?

The simple answer is 'yes', given some additional hardware. The clocks that PsychoPy uses do have sub-millisecond precision but your keyboard has a latency of 4-25ms depending on your platform and keyboard. You could buy a response pad (e.g. a [Cedrus Response Pad](#)) and use PsychoPy's serial port commands to retrieve information about responses and timing with a precision of around 1ms.

**Before conducting your experiment in which effects might be on the order of 1 ms, do consider that;**

- your screen has a temporal resolution of ~10 ms
- your visual system has a similar upper limit (or you would notice the flickering screen)
- human response times are typically in the range 200-400 ms and very variable
- USB keyboard latencies are variable, in the range 20-30ms

That said, PsychoPy does aim to give you as high a temporal precision as possible, and is likely not to be the limiting factor of your experiment.

### Computer monitors

Monitors have fixed refresh rates, typically 60 Hz for a flat-panel display, higher for a CRT (85-100 Hz are common, up to 200 Hz is possible). For a refresh rate of 85 Hz there is a gap of 11.7 ms between frames and this limits the timing of stimulus presentation. You cannot have your stimulus appear for 100 ms, for instance; on an 85Hz monitor it can appear for either 94 ms (8 frames) or 105 ms (9 frames). There are further, less obvious, limitations however.

For "CRT (cathode ray tube) screens", the lines of pixels are drawn sequentially from the top to the bottom and once the bottom line has been drawn the screen is finished and the line returns to the top (the Vertical Blank Interval, VBI). Most of your frame interval is spent drawing the lines with 1-2ms being left for the VBI. This means that the pixels at the bottom are drawn "up to 10 ms later" than the pixels at the top of the screen. At what point are you going to say your stimulus 'appeared' to the participant? For flat panel displays, or (or LCD projectors) your image will be

presented simultaneously all over the screen, but it takes up to 20 ms(!) for your pixels to go all the way from black to white (manufacturers of these panels quote values of 3 ms for the fastest panels, but they certainly don't mean 3 ms white-to-black, I assume they mean 3 ms half-life).




Fig. 1: Figure 1: photodiode trace at top of screen. The image above shows the luminance trace of a CRT recorded by a fast photo-sensitive diode at the top of the screen when a stimulus is requested (shown by the square wave). The square wave at the bottom is from a parallel port that indicates when the stimulus was flipped to the screen. Note that on a CRT the screen at any point is actually black for the majority of the time and just briefly bright. The visual system integrates over a large enough time window not to notice this. On the next frame after the stimulus 'presentation time' the luminance of the screen flash increased.

**Warning:** If you're using a regular computer display, *you have a hardware-limited temporal precision of 10 ms irrespective of your response box or software clocks etc...* and should bear that in mind when looking for effect sizes of less than that.

### Can I have my stimulus to appear with a very precise rate?

Yes. Generally to do that you should time your stimulus (its onset/offset, its rate of change...) using the frame refresh rather than a clock. e.g. you should write your code to say 'for 20 frames present this stimulus' rather than 'for 300ms present this stimulus'. Provided your graphics card is set to synchronise page-flips with the vertical blank, and provided that you aren't *dropping frames* the frame rate will always be absolutely constant.




Fig. 2: Figure 2: photodiode trace of the same large stimulus at bottom of screen. The image above shows comes from exactly the same script as the above but the photodiode is positioned at the bottom of the screen. In this case, after the stimulus is 'requested' the current frame (which is dark) finishes drawing and then, 10ms later than the above image, the screen goes bright at the bottom.

## 2.10 Glossary

- Adaptive staircase** An experimental method whereby the choice of stimulus parameters is not pre-determined but based on previous responses. For example, the difficulty of a task might be varied trial-to-trial based on the participant's responses. These are often used to find psychophysical thresholds. Contrast this with the *method of constants*.
- CPU Central Processing Unit** is the main processor of your computer. This has a lot to do, so we try to minimise the amount of processing that is needed, especially during a trial, when time is tight to get the stimulus presented on every screen refresh.
- CRT Cathode Ray Tube** 'Traditional' computer monitor (rather than an LCD or plasma flat screen).
- csv Comma-Separated Value files** Type of basic text file with 'comma-separated values'. This type of file can be opened with most spreadsheet packages (e.g. MS Excel) for easy reading and manipulation.
- GPU Graphics Processing Unit** is the processor on your graphics card. The GPUs of modern computers are incredibly powerful and it is by allowing the GPU to do a lot of the work of rendering that PsychoPy is able to achieve good timing precision despite being written in an interpreted language
- Method of constants** An experimental method whereby the parameters controlling trials are predetermined at the beginning of the experiment, rather than determined on each trial. For example, a stimulus may be presented for 3 pre-determined time periods (100, 200, 300ms) on different trials, and then repeated a number of times. The order of presentation of the different conditions can be randomised or sequential (in a fixed order). Contrast this method with the *adaptive staircase*.
- VBI (Vertical Blank Interval**, aka the Vertical Retrace, or Vertical Blank, VBL). The period in-between video frames and can be used for synchronising purposes. On a CRT display the screen is black during the VBI and the display beam is returned to the top of the display.
- VBI blocking** The setting whereby all functions are synced to the VBI. After a call to `psychopy.visual.Window.flip()` nothing else occurs until the VBI has occurred. This is optimal and allows very precise timing, because as soon as the flip has occurred a very precise time interval is known to have occurred.
- VBI syncing** (aka vsync) The setting whereby the video drawing commands are synced to the VBI. When `psychopy.visual.Window.flip()` is called, the current back buffer (where drawing commands are being executed) will be held and drawn on the next VBI. This does not necessarily entail *VBI blocking* (because the system may return and continue executing commands) but does guarantee a fixed interval between frames being drawn.
- xlsx Excel OpenXML file format**. A spreadsheet data format developed by Microsoft but with an open (published) format. This is the native file format for Excel (2007 or later) and can be opened by most modern spreadsheet applications including OpenOffice (3.0+), google docs, Apple iWork 08.



## INSTALLATION

### 3.1 Download

For the easiest installation download and install the Standalone package.

**For all versions** see the [PsychoPy releases on github](#)

### 3.2 Manual installations

See below for options if you don't want to use the Standalone releases:

- *pip install*
- *Linux*
- *Anaconda and Miniconda*
- *Developers install*

#### 3.2.1 pip install

Now that most python libraries can be install using *pip* it's relatively easy to manually install PsychoPy and all it's dependencies to your own installation of Python.

The steps are to fetch Python. This method should work on any version of Python but we recommend Python 3.6 for now.

You can install PsychoPy and its dependencies (more than you'll strictly need) by:

```
pip install psychopy
```

If you prefer *not* to install *all* the dependencies then you could do:

```
pip install psychopy --no-deps
```

and then install them manually.

#### 3.2.2 Linux

There used to be neurodebian and Gentoo packages for PsychoPy but these are both badly outdated. We'd recommend you do:

```
# with --no-deps flag if you want to install dependencies manually
pip install psychopy
```

Then fetch a wxPython wheel for your platform from:

<https://extras.wxpython.org/wxPython4/extras/linux/gtk3/>

and having downloaded the right wheel you can then install it with something like:

```
pip install path/to/your/wxpython.whl
```

wxPython>4.0 and doesn't have universal wheels yet which is why you have to find and install the correct wheel for your particular flavor of linux.

### 3.2.3 Anaconda and Miniconda

With Python 3.5:

```
conda create -n psypy3 python=3.5
conda activate psypy3
conda install numpy scipy matplotlib pandas pyopengl pillow lxml openpyxl xlrd_
↳configobj pyyaml gevent greenlet msgpack-python psutil pytables requests[security]_
↳cffi seaborn wxpython cython pyzmq pyserial
conda install -c conda-forge pyglet pysoundfile python-bidi moviepy pyosf
pip install zmq json-tricks pyparallel sounddevice pygame pysoundcard psychopy_ext_
↳psychopy
```

### 3.2.4 Developers install

Ensure you have Python 3.6 and the latest version of pip installed:

```
python --version
pip --version
```

Next, follow instructions [here](#) to fork and fetch the latest version of the PsychoPy repository.

From the directory where you cloned the latest PsychoPy repository (i.e., where setup.py resides), run:

```
pip install -e .
```

This will install all PsychoPy dependencies to your default Python distribution (which should be Python 3.6). Next, you should create a new PsychoPy shortcut linking your newly installed dependencies to your current version of PsychoPy in the cloned repository. To do this, simply create a new .BAT file containing:

```
"C:\PATH_TO_PYTHON3.6\python.exe C:\PATH_TO_CLONED_PSYCHOPY_
↳REPO\psychopy\app\psychopyApp.py"
```

Alternatively, you can run the psychopyApp.py from the command line:

```
python C:\PATH_TO_CLONED_PSYCHOPY_REPO\psychopy\app\psychopyApp
```

## 3.3 Recommended hardware

The minimum requirement for PsychoPy is a computer with a graphics card that supports OpenGL. Many newer graphics cards will work well. Ideally the graphics card should support OpenGL version 2.0 or higher. Certain visual functions run much faster if OpenGL 2.0 is available, and some require it (e.g. ElementArrayStim).

If you already have a computer, you can install PsychoPy and the Configuration Wizard will auto-detect the card and drivers, and provide more information. It is inexpensive to upgrade most desktop computers to an adequate graphics card. High-end graphics cards can be very expensive but are only needed for very intensive use.

Generally NVIDIA and ATI (AMD) graphics chips have higher performance than Intel graphics chips so try and get one of those instead.

### 3.3.1 Notes on OpenGL drivers


On Windows, if you get an error saying “**pyglet.gl.ContextException: Unable to share contexts**” then the most likely cause is that you need OpenGL drivers and your built-in Windows only has limited support for OpenGL (or possibly you have an Intel graphics card that isn’t very good). Try installing new drivers for your graphics card **from its manufacturer’s web page**, not from Microsoft. For example, NVIDIA provides drivers for its cards here: <https://www.nvidia.com/Download/index.aspx>



## GETTING STARTED

As an application, PsychoPy has two main views: the *Builder* view, and the *Coder* view. It also has a underlying *API* that you can call directly.

1. *Builder*. You can generate a wide range of experiments easily from the Builder using its intuitive, graphical user interface (GUI). This might be all you ever need to do. But you can always compile your experiment into a python script for fine-tuning, and this is a quick way for experienced programmers to explore some of PsychoPy's libraries and conventions.



1. *Coder*. For those comfortable with programming, the Coder view provides a basic code editor with syntax highlighting, code folding, and so on. Importantly, it has its own output window and Demo menu. The demos illustrate how to do specific tasks or use specific features; they are not whole experiments. The *Coder tutorials* should help get you going, and the *API reference* will give you the details.

The Builder and Coder views are the two main aspects of the PsychoPy application. If you've installed the StandAlone version of PsychoPy on **MS Windows** then there should be an obvious link to PsychoPy in your > Start > Programs. If you installed the StandAlone version on **macOS** then the application is where you put it (!). On these two platforms you can open the Builder and Coder views from the View menu and the default view can be set from the preferences. **On Linux**, you can start PsychoPy from a command line, or make a launch icon (which can depend on the desktop and distro). If the PsychoPy app is started with flags `—coder` (or `-c`), or `—builder` (or `-b`), then the preferences will be overridden and that view will be created as the app opens.

For experienced python programmers, it's possible to use PsychoPy without ever opening the Builder or Coder. Install the PsychoPy libraries and dependencies, and use your favorite IDE instead of the Coder.

The screenshot shows the PsychoPy2 application window. The title bar indicates the path to the script: `/Applications/PsychoPy2.app/Contents/Resources/lib/python2.6/psychopy/demos/coder/gabor.py - Ps...`. The window contains a code editor with the following Python code:

```

1  #!/usr/bin/env python
2  from psychopy import core, visual, event
3
4  #create a window to draw in
5  myWin = visual.Window([400,400.0], allowGUI=False)
6
7  #INITIALISE SOME STIMULI
8  gabor = visual.PatchStim(myWin, tex="sin", mask="gauss", texRes=256,
9  .....size=[1.0,1.0], sf=[4,0], ori = 0, name='gabor1')
10  gabor.setAutoDraw(True)
11  message = visual.TextStim(myWin, pos=(0.0,-0.9), text="Hit Q to quit")
12  trialClock = core.Clock()
13
14  #repeat drawing for each frame
15  while trialClock.getTime() < 20:
16  .....gabor.setPhase(0.01, '+')
17  .....message.draw()
18  .....#handle key presses each frame
19  for keys in event.getKeys(timeStamped=True):
20  .....if keys[0] in ['escape', 'q']:
21  .....myWin.close()
22  .....core.quit()
23

```

Below the code editor is an "Output" window. It displays the following text:

```

Welcome to PsychoPy2!
v1.63.00

```

## 4.1 Builder


When learning a new computer language, the classic first program is simply to print or display “Hello world!”. Lets do it.

### 4.1.1 A first program

Start PsychoPy, and be sure to be in the Builder view.

- If you have poked around a bit in the Builder already, be sure to start with a clean slate. To get a new Builder view, type *Ctrl-N* on Windows or Linux, or *Cmd-N* on Mac.
- Click on a Text component






and a Text Properties dialog will pop up.

- In the *Text* field, replace the default text with your message. When you run the program, the text you type here will be shown on the screen.
- Click OK (near the bottom of the dialog box). (Properties dialogs have a link to online help—an icon at the bottom, near the OK button.)
- Your text component now resides in a routine called *trial*. You can click on it to view or edit it. (Components, Routines, and other Builder concepts are explained in the [Builder documentation](#).)
- Back in the main Builder, type *Ctrl-R* (Windows, Linux) or *Cmd-R* (Mac), or use the mouse to click the *Run* icon.



Assuming you typed in “Hello world!”, your screen should have looked like this (briefly):





If nothing happens or it looks wrong, recheck all the steps above; be sure to start from a new Builder view.

What if you wanted to display your cheerful greeting for longer than the default time?

- Click on your Text component (the existing one, not a new one).
- Edit the *Stop duration (s)* to be 3.2; times are in seconds.
- Click OK.
- And finally *Run*.

When running an experiment, you can quit by pressing the *escape* key (this can be configured or disabled). You can quit PsychoPy from the File menu, or typing *Ctrl-Q / Cmd-Q*.

### 4.1.2 Getting beyond Hello

To do more, you can try things out and see what happens. You may want to consult the [Builder documentation](#). Many people find it helpful to explore the Builder demos, in part to see what is possible, and especially to see how different things are done.

A good way to develop your own first PsychoPy experiment is to base it on the Builder demo that seems closest. Copy it, and then adapt it step by step to become more and more like the program you have in mind. Being familiar with the Builder demos can only help this process.

You could stop here, and just use the Builder for creating your experiments. It provides a lot of the key features that people need to run a wide variety of studies. But it does have its limitations. When you want to have more complex designs or features, you'll want to investigate the Coder. As a segue to the Coder, let's start from the Builder, and see how Builder programs work.

## 4.2 Builder-to-coder

Whenever you run a Builder experiment, PsychoPy will first translate it into python code, and then execute that code.

To get a better feel for what was happening “behind the scenes” in the Builder program above:

- In the Builder, load or recreate your “hello world” program.
- Instead of running the program, explicitly convert it into python: Type *F5*, or click the *Compile* icon:



The view will automatically switch to the Coder, and display the python code. If you then save and run this code, it would look the same as running it directly from the Builder.

It is always possible to go from the Builder to python code in this way. You can then edit that code and run it as a python program. However, you cannot go from code back to a Builder representation.

To switch quickly between Builder and Coder views, you can type *Ctrl-L / Cmd-L*.

## 4.3 Coder

Being able to inspect Builder-generated code is nice, but it's possible to write code yourself, directly. With the Coder and various libraries, you can do virtually anything that your computer is capable of doing, using a full-featured modern programming language (python).

For variety, lets say hello to the Spanish-speaking world. PsychoPy knows Unicode (UTF-8).

If you are not in the Coder, switch to it now.

- Start a new code document: *Ctrl-N / Cmd-N*.
- Type (or copy & paste) the following:

```
from psychopy import visual, core

win = visual.Window()
msg = visual.TextStim(win, text=u"\u00A1Hola mundo!")

msg.draw()
win.flip()
core.wait(1)
win.close()
```

- Save the file (the same way as in Builder).
- Run the script.

Note that the same events happen on-screen with this code version, despite the code being much simpler than the code generated by the Builder. (The Builder actually does more, such as prompt for a subject number.)

### Coder Shell

The shell provides an interactive python interpreter, which means you can enter commands here to try them out. This provides yet another way to send your salutations to the world. By default, the Coder's output window is shown at the bottom of the Coder window. Click on the Shell tab, and you should see python's interactive prompt, `>>>`:

```
PyShell in PsychoPy - type some commands!

Type "help", "copyright", "credits" or "license" for more information.
>>>
```

At the prompt, type:

```
>>> print u"\u00A1Hola mundo!"
```

You can do more complex things, such as type in each line from the Coder example directly into the Shell window, doing so line by line:

```
>>> from psychopy import visual, core
```

and then:

```
>>> win = visual.Window()
```

**and so on—watch what happens each line::**

```
>>> msg = visual.TextStim(win, text=u"\u00A1Hola mundo!")
>>> msg.draw()
>>> win.flip()
```

and so on. This lets you try things out and see what happens line-by-line (which is how python goes through your program).



## BUILDER


### *Building experiments in a GUI*

You can now see a [youtube PsychoPy tutorial](#) showing you how to build a simple experiment in the Builder interface

---

**Note:** The Builder view is now (at version 1.75) fairly well-developed and should be able to construct a wide variety of studies. But you should still check carefully that the stimuli and response collection are as expected.

---



Contents:

## 5.1 Builder concepts

### 5.1.1 Routines and Flow

The Builder view of the PsychoPy application is designed to allow the rapid development of a wide range of experiments for experimental psychology and cognitive neuroscience experiments.

The Builder view comprises two main panels for viewing the experiment's *Routines* (upper left) and another for viewing the *Flow* (lower part of the window).

An experiment can have any number of *Routines*, describing the timing of stimuli, instructions and responses. These are portrayed in a simple track-based view, similar to that of video-editing software, which allows stimuli to come on go off repeatedly and to overlap with each other.

The way in which these *Routines* are combined and/or repeated is controlled by the *Flow* panel. All experiments have exactly one *Flow*. This takes the form of a standard flowchart allowing a sequence of routines to occur one after another, and for loops to be inserted around one or more of the *Routines*. The loop also controls variables that change between repetitions, such as stimulus attributes.

### 5.1.2 Example 1 - a reaction time experiment

For a simple reaction time experiment there might be 3 *Routines*, one that presents instructions and waits for a keypress, one that controls the trial timing, and one that thanks the participant at the end. These could then be combined in the *Flow* so that the instructions come first, followed by *trial*, followed by the *thanks Routine*, and a loop could be inserted so that the *Routine* repeated 4 times for each of 6 stimulus intensities.

### 5.1.3 Example 2 - an fMRI block design

Many fMRI experiments present a sequence of stimuli in a *block*. For this there are multiple ways to create the experiment:

- We could create a single *Routine* that contained a number of stimuli and presented them sequentially, followed by a long blank period to give the inter-epoch interval, and surround this single *Routine* by a loop to control the blocks.
- Alternatively we could create a pair of *Routines* to allow presentation of a) a single stimulus (for 1 sec) and b) a blank screen, for the prolonged period. With these *Routines* we could insert pair of loops, one to repeat the stimulus *Routine* with different images, followed by the blank *Routine*, and another to surround this whole set and control the blocks.

### 5.1.4 Demos

There are a couple of demos included with the package, that you can find in their own special menu. When you load these the first thing to do is make sure the experiment settings specify the same resolution as your monitor, otherwise the screen can appear off-centred and strangely scaled.

#### Stroop demo

This runs a digital demonstration of the Stroop effect<sup>1</sup>. The experiment presents a series of coloured words written in coloured 'inks'. Subjects have to report the colour of the letters for each word, but find it harder to do so when the letters are spelling out a different (incongruous) colour. Reaction times for the congruent trials (where letter colour matches the written word) are faster than for the incongruent trials.

**From this demo you should note:**

- How to setup a trial list in a .csv or .xlsx file
- How to record key presses and reaction times (using the *resp* Component in *trial Routine*)

---

<sup>1</sup> Stroop, J.R. (1935). "Studies of interference in serial verbal reactions". Journal of Experimental Psychology 18: 643-662.

- How to change a stimulus parameter on each repetition of the loop. The text and rgb values of the *word* Component are based on *thisTrial*, which represents a single iteration of the *trials* loop. They have been set to change every repeat (don't forget that step!)
- How to present instructions: just have a long-lasting *TextStim* and then force end of the *Routine* when a key is pressed (but don't bother storing the key press).

## Psychophysics Staircase demo

This is a mini psychophysics experiment, designed to find the contrast detection threshold of a gabor i.e. find the contrast where the observer can just see the stimulus.

### From this demo you should note:

- The opening dialog box requires the participant to enter the orientation of the stimulus, the required fields here are determined by 'Experiment Info' in 'Preferences' which is a python dictionary. This information is then entered into the stimulus parameters using '\$expInfo['ori']'
- The phase of the stimulus is set to change every frame and its value is determined by the value of *trialClock.getTime()\*2*. Every *Routine* has a clock associated with it that gets reset at the beginning of the iteration through the *Routine*. There is also a *globalClock* that can be used in the same way. The phase of a *Patch Component* ranges 0-1 (and wraps to that range if beyond it). The result in this case is that the grating drifts at a rate of 2Hz.
- The contrast of the stimulus is determined using an *adaptive staircase*. The *Staircase methods* are different to those used for a loop which uses predetermined values. An important thing to note is that you must define the correct answer.

## 5.2 Routines

An experiment consists of one or more Routines. A Routine might specify the timing of events within a trial or the presentation of instructions or feedback. Multiple Routines can then be combined in the *Flow*, which controls the order in which these occur and the way in which they repeat.

To create a new Routine, use the Experiment menu. The display size of items within a routine can be adjusted (see the View menu).

Within a Routine there are a number of components. These components determine the occurrence of a stimulus, or the recording of a response. Any number of components can be added to a Routine. Each has its own line in the Routine view that shows when the component starts and finishes in time, and these can overlap.

For now the time axis of the Routines panel is fixed, representing seconds (one line is one second). This will hopefully change in the future so that units can also be number of frames (more precise) and can be scaled up or down to allow very long or very short Routines to be viewed easily. That's on the wishlist...

## 5.3 Flow

In the Flow panel a number of *Routines* can be combined to form an experiment. For instance, your study may have a *Routine* that presented initial instructions and waited for a key to be pressed, followed by a *Routine* that presented one trial which should be repeated 5 times with various different parameters set. All of this is achieved in the Flow panel. You can adjust the display size of the Flow panel (see View menu).

### 5.3.1 Adding Routines

The *Routines* that the Flow will use should be generated first (although their contents can be added or altered at any time). To insert a *Routine* into the Flow click the appropriate button in the left of the Flow panel or use the Experiment menu. A dialog box will appear asking which of your *Routines* you wish to add. To select the location move the mouse to the section of the flow where you wish to add it and click on the black disk.

### 5.3.2 Loops

Loops control the repetition of *Routines* and the choice of stimulus parameters for each. PsychoPy can generate the next trial based on the *method of constants* or using an *adaptive staircase*. To insert a loop use the button on the left of the Flow panel, or the item in the Experiment menu of the Builder. The start and end of a loop is set in the same way as the location of a *Routine* (see above). Loops can encompass one or more *Routines* and other loops (i.e. they can be nested).

As with components in *Routines*, the loop must be given a name, which must be unique and made up of only alpha-numeric characters (underscores are allowed). I would normally use a plural name, since the loop represents multiple repeats of something. For example, *trials*, *blocks* or *epochs* would be good names for your loops.

It is usually best to use trial information that is contained in an external file (.xlsx or .csv). When inserting a *loop* into the *flow* you can browse to find the file you wish to use for this. An example of this kind of file can be found in the Stroop demo (trialTypes.xlsx). The column names are turned into variables (in this case text, letterColor, corrAns and congruent), these can be used to define parameters in the loop by putting a \$ sign before them e.g. \$text.

As the column names from the input file are used in this way they must have legal variable names i.e. they must be unique, have no punctuation or spaces (underscores are ok) and must not start with a digit.

The parameter *Is trials* exists because some loops are not there to indicate trials *per se* but a set of stimuli within a trial, or a set of blocks. In these cases we don't want the data file to add an extra line with each pass around the loop. This parameter can be unchecked to improve (hopefully) your data file outputs. [Added in v1.81.00]

#### Method of Constants

Selecting a loop type of *random*, *sequential*, or *fullRandom* will result in a *method of constants* experiment, whereby the types of trials that can occur are predetermined. That is, the trials cannot vary depending on how the subject has responded on a previous trial. In this case, a file must be provided that describes the parameters for the repeats. This should be an Excel 2007 (*xlsx*) file or a comma-separated-value (*csv*) file in which columns refer to parameters that are needed to describe stimuli etc. and rows one for each type of trial. These can easily be generated from a spreadsheet package like Excel. (Note that csv files can also be generated using most text editors, as long as they allow you to save the file as "plain text"; other output formats will *not* work, including "rich text".) The top row should be a row of headers: text labels describing the contents of the respective columns. (Headers must also not include spaces or other characters other than letters, numbers or underscores and must not be the same as any variable names used elsewhere in your experiment.) For example, a file containing the following table:

ori	text	corrAns
0	aaa	left
90	aaa	left
0	bbb	right
90	bbb	right

would represent 4 different conditions (or trial types, one per line). The header line describes the parameters in the 3 columns: ori, text and corrAns. It's really useful to include a column called corrAns that shows what the correct key press is going to be for this trial (if there is one).

If the loop type is *sequential* then, on each iteration through the *Routines*, the next row will be selected in the order listed in the file. Under a *random* order, the next row will be selected at random (without replacement); it can only be



selected again after all the other rows have also been selected. *nReps* determines how many repeats will be performed (for all conditions). The total number of trials will be the number of conditions (= number of rows in the file, not counting the header row) times the number of repetitions, *nReps*. With the *fullRandom* option, the entire list of trials including repetitions is used in random order, allowing the same item to appear potentially many times in a row, and to repeat without necessarily having done all of the other trials. For example, with 3 repetitions, a file of trial types like this:

```
letter
a
b
c
```

could result in the following possible sequences. *sequential* could only ever give one sequence with this order: [a b c a b c a b c]. *random* will give one of 216 different orders ( $= 3! * 3! * 3! = nReps * (nTrials!)$ ), for example: [b a c a b c c a b]. Here the letters are effectively in sets of (abc) (abc) (abc), and randomization is only done within each set, ensuring (for example) that there are at least two a's before the subject sees a 3rd b. Finally, *fullRandom* will return one of 362,880 different orders ( $= 9! = (nReps * nTrials!)$ ), such as [b b c a a c c a b], which *random* never would. There are no longer mini-blocks or “sets of trials” within the longer run. This means that, by chance, it would also be possible to get a very un-random-looking sequence like [a a a b b b c c c].

It is possible to achieve any sequence you like, subject to any constraints that are logically possible. To do so, in the file you specify every trial in the desired order, and then for the loop select *sequential* order and *nReps*=1.

### Selecting a subset of conditions

In the standard *Method of Constants* you would use all the rows/conditions within your conditions file. However there are often times when you want to select a subset of your trials before randomising and repeating.

The parameter *Select rows* allows this. You can specify which rows you want to use by inserting values here:

- 0,2,5 gives the 1st, 3rd and 5th entry of a list - Python starts with index zero)
- *random(4)\*10* gives 4 indices from 0 to 10 (so selects 4 out of 11 conditions)
- 5:10 selects the 6th to 9th rows
- *\$myIndices* uses a variable that you've already created

Note in the last case that 5:8 isn't valid syntax for a variable so you cannot do:

```
myIndices = 5:8
```

but you can do:

```
myIndices = slice(5,8) #python object to represent a slice
myIndices = "5:8" #a string that PsychoPy can then parse as a slice later
myIndices = "5:8:2" #as above but
```

Note that PsychoPy uses Python's built-in slicing syntax (where the first index is zero and the last entry of a slice doesn't get included). You might want to check the outputs of your selection in the Python shell (bottom of the Coder view) like this:

```
>>> range(100)[5:8] #slice 5:8 of a standard set of indices
[5, 6, 7]
>>> range(100)[5:10:2] #slice 5:8 of a standard set of indices
[5, 7, 9, 11, 13, 15, 17, 19]
```

Check that the conditions you wanted to select are the ones you intended!

## Staircase methods

The loop type *staircase* allows the implementation of adaptive methods. That is, aspects of a trial can depend on (or “adapt to”) how a subject has responded earlier in the study. This could be, for example, simple up-down staircases where an intensity value is varied trial-by-trial according to certain parameters, or a stop-signal paradigm to assess impulsivity. For this type of loop a ‘correct answer’ must be provided from something like a *Keyboard Component*. Various parameters for the staircase can be set to govern how many trials will be conducted and how many correct or incorrect answers make the staircase go up or down.

## Accessing loop parameters from components

The parameters from your loops are accessible to any component enclosed within that loop. The simplest (and default) way to address these variables is simply to call them by the name of the parameter, prepended with \$ to indicate that this is the name of a variable. For example, if your Flow contains a loop with the above table as its input trial types file then you could give one of your stimuli an orientation *\$ori* which would depend on the current trial type being presented. Example scenarios:

1. You want to loop randomly over some conditions in a loop called *trials*. Your conditions are stored in a csv file with headings ‘ori’, ‘text’, ‘corrAns’ which you provide to this loop. You can then access these values from any component using *\$ori*, *\$text*, and *\$corrAns*
2. You create a random loop called *blocks* and give it an Excel file with a single column called *movieName* listing filenames to be played. On each repeat you can access this with *\$movieName*
3. You create a staircase loop called *stairs*. On each trial you can access the current value in the staircase with *\$thisStair*

---

**Note:** When you set a component to use a parameter that will change (e.g on each repeat through the loop) you should **remember to change the component parameter from ‘constant’ to ‘set every repeat’ or ‘set every frame’** or it won’t have any effect!

---

## Reducing namespace clutter (advanced)

The downside of the above approach is that the names of trial parameters must be different between every loop, as well as not matching any of the predefined names in python, numpy and PsychoPy. For example, the stimulus called *movie* cannot use a parameter also called *movie* (so you need to call it *movieName*). An alternative method can be used without these restrictions. If you set the Builder preference *unclutteredNamespace* to True you can then access the variables by referring to parameter as an attribute of the singular name of the loop prepended with *this*. For example, if you have a loop called *trials* which has the above file attached to it, then you can access the stimulus ori with *\$thisTrial.ori*. If you have a loop called *blocks* you could use *\$thisBlock.corrAns*.

Now, although the name of the loop must still be valid and unique, the names of the parameters of the file do not have the same requirements (they must still not contain spaces or punctuation characters).

## 5.4 Blocks of trials and counterbalancing


Many people ask how to create blocks of trials, how to randomise them, and how to counterbalance their order. This isn’t all that hard, although it does require a bit of thinking!

### 5.4.1 Blocking

The key thing to understand is that you should not create different Routines for different trials in your blocks (if at all possible). Try to define your trials with a single Routine. For instance, let's imagine you're trying to create an experiment that presents a block of pictures of houses or a block of faces. It would be tempting to create a Routine called *presentFace* and another called *presentHouse* but you actually want just one called *presentStim* (or just *trial*) and then set that to differ as needed across different stimuli.

This example is included in the Builder demos, as of PsychoPy 1.85.

You can add a loop around your trials, as normal, to control the trials within a block (e.g. randomly selecting a number of images) but then you will have a second loop around this to define how the blocks change. You can also have additional Routines like something to inform participants that the next block is about to start.



So, how do you get the block to change from one set of images to another? To do this create three spreadsheets, one for each block, determining the filenames within that block, and then another to control which block is being used:

- facesBlock.xlsx
- housesBlock.xlsx
- chooseBlocks.xlsx

**Setting up the basic conditions.** The facesBlock, and housesBlock, files look more like your usual conditions files. In this example we can just use a variable *stimFile* with values like *stims/face01.jpg* and *stims/face02.jpg* while the housesBlock file has *stims/house01.jpg* and *stims/house02.jpg*. In a real experiment you'd probably also have response keys and suchlike as well.

**So, how to switch between these files?** That's the trick and that's what the other file is used for. In the *chooseBlocks.xlsx* file you set up a variable called something like *condsFile* and that has values of *facesBlock.xlsx* and *housesBlock.xlsx*. In the outer (blocks) loop you set up the conditions file to be *chooseBlocks.xlsx* which creates a variable *condsFile*. Then, in the inner (trials) loop you set the conditions file not to be any file directly but simply *\$condsFile*. Now, when PsychoPy starts this loop it will find the current value of *condsFile* and insert the appropriate thing, which will be the name of an conditions file and we're away!

Your *chooseBlocks.xlsx* can contain other values as well, such as useful identifiers. In this demo you could add a value *readyText* that says "Ready for some houses", and "Ready for some faces" and use this in your get ready Routine.

Variables that are defined in the loops are available anywhere within those. In this case, of course, the values in the outer loop are changing less often than the values in the inner loop.

### 5.4.2 Counterbalancing

Counterbalancing is simply an extension of blocking. Usually with a block design you would set the order of blocks to be set randomly. In the example above the blocks are set to occur randomly, but note that they could also be set to occur more than once if you want 2 repeats of the 2 blocks for a total of 4.

In a counterbalanced design you want to control the order explicitly and you want to provide a different order for different groups of participants. Maybe group A always gets faces first, then houses, and group B always gets houses first, then faces.

Now we need to create further conditions files, to specify the exact orders we want, so we'd have something like *groupA.xlsx*:

condsFile
housesBlock.xlsx
facesBlock.xlsx

and *groupB.xlsx*:

condsFile
facesBlock.xlsx
housesBlock.xlsx

In this case the last part of the puzzle is how to assign participants to groups. For this you *could* write a Code Component that would generate a variable for you (if...: *groupFile* = "*groupB.xlsx*") but the easiest thing is probably that you, the experimenter, chooses this outside of PsychoPy and simply tells PsychoPy which group to assign to each participant.

The easiest way to do that is to add the field *group* to the initial dialog box, maybe with the default value of A. If you set the conditions file for the *blocks* loop to be `` $"group"+expInfo['group']+".xlsx" `` then this variable will be used from the dialog box to create the filename for the blocks file and you.

Also, if you're doing this, remember to set the *blocks* loop to use "sequential" rather than "random" sorting. Your inner loop still probably wants to be random (to shuffle the image order within a block) but your outer loop should now be using exactly the order that you specified in the blocks condition file.

## 5.5 Components

Routines in the Builder contain any number of components, which typically define the parameters of a stimulus or an input/output device.

The following components are available, as at version 1.65, but further components will be added in the future including Parallel/Serial ports and other visual stimuli (e.g. GeometricStim).

### 5.5.1 Aperture Component

This component can be used to filter the visual display, as if the subject is looking at it through an opening. Currently only circular apertures are supported. Moreover, only one aperture is enabled at a time. You can't "double up": a second aperture takes precedence.

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** [float or integer] The time that the aperture should start having its effect. See [Defining the onset/duration of components](#) for details.

**stop** : When the aperture stops having its effect. See [Defining the onset/duration of components](#) for details.

**pos** [[X,Y]] The position of the centre of the aperture, in the units specified by the stimulus or window.

**size** [integer] The size controls how big the aperture will be, in pixels, default = 120

**units** [pix] What units to use (currently only pix).

**See also:**

API reference for [Aperture](#)

## 5.5.2 Brush Component

The Brush component is a freehand drawing tool.

### Properties

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** [int, float] The time that the stimulus should first appear.

**Stop** [int, float] Governs the duration for which the stimulus is presented.

**line settings:** Control color and width of the line. The line width is always specified in pixels - it does not honour the *units* parameter.

**opacity :** Vary the transparency, from 0.0 = invisible to 1.0 = opaque

**See also:**

API reference for [Brush](#)

## 5.5.3 Cedrus Button Box Component

This component allows you to connect to a Cedrus Button Box to collect key presses.

*Note that there is a limitation currently that a button box can only be used in a single Routine. Otherwise PsychoPy tries to initialise it twice which raises an error. As a workaround, you need to insert the start-routine and each-frame code from the button box into a code component for a second routine.*

### Properties

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start :** The time that the button box is first read. See [Defining the onset/duration of components](#) for details.

**Stop :** Governs the duration for which the button box is first read. See [Defining the onset/duration of components](#) for details.

**Force end of Routine** [true/false] If this is checked, the first response will end the routine.

**Allowed keys** [None, or an integer, list, or tuple of integers 0-7] This field lets you specify which buttons (None, or some or all of 0 through 7) to listen to.

**Store** [(choice of: first, last, all, nothing)] Which button events to save in the data file. Events and the response times are saved, with RT being recorded by the button box (not by PsychoPy).

**Store correct** [true/false] If selected, a correctness value will be saved in the data file, based on a match with the given correct answer.

**Correct answer: button** The correct answer, used by Store correct.

**Discard previous** [true/false] If selected, any previous responses will be ignored (typically this is what you want).

## Advanced

**Device number: integer** This is only needed if you have multiple Cedrus devices connected and you need to specify which to use.

**Use box timer** [true/false] Set this to True to use the button box timer for timing information (may give better time resolution)

**See also:**

API reference for *iolab*

## 5.5.4 Code Component

The *Code Component* can be used to insert short pieces of python code into your experiments. This might be create a variable that you want for another *Component*, to manipulate images before displaying them, to interact with hardware for which there isn't yet a pre-packaged component in *PsychoPy* (e.g. writing code to interact with the serial/parallel ports). See *code uses* below.

Be aware that the code for each of the components in your *Routine* are executed in the order they appear on the *Routine* display (from top to bottom). If you want your *Code Component* to alter a variable to be used by another component immediately, then it needs to be above that component in the view. You may want the code not to take effect until next frame however, in which case put it at the bottom of the *Routine*. You can move *Components* up and down the *Routine* by right-clicking on their icons.

**Within your code you can use other variables and modules from the script. For example, all routines have a stopwatch-style *clock***

```
currentT = trialClock.getTime()
```

To see what other variables you might want to use, and also what terms you need to avoid in your chunks of code, *compile your script* before inserting the code object and take a look at the contents of that script.

Note that this page is concerned with *Code Components* specifically, and not all cases in which you might use python syntax within the Builder. It is also possible to put code into a non-code input field (such as the duration or text of a *Text Component*). The syntax there is slightly different (requiring a \$ to trigger the special handling, or \ \$ to avoid triggering special handling). The syntax to use within a *Code Component* is always regular python syntax.

## Parameters

The parameters of the *Code Component* simply specify the code that will get executed at 5 different points within the experiment. You can use as many or as few of these as you need for any *Code Component*:

**Begin Experiment:** Things that need to be done just once, like importing a supporting module, initialising a variable for later use.

**Begin Routine:** Certain things might need to be done just once at the start of a *Routine* e.g. at the beginning of each trial you might decide which side a stimulus will appear

**Each Frame:** Things that need to be updated constantly, throughout the experiment. Note that these will be executed exactly once per video frame (on the order of every 10ms), to give dynamic displays. Static displays do not need to be updated every frame.

**End Routine:** At the end of the *Routine* (e.g. the trial) you may need to do additional things, like checking if the participant got the right answer

**End Experiment:** Use this for things like saving data to disk, presenting a graph(?), or resetting hardware to its original state.

## Example code uses

### 1. Set a random location for your target stimulus

There are many ways to do this, but you could add the following to the *Begin Routine* section of a *Code Component* at the top of your *Routine*. Then set your stimulus position to be *\$targetPos* and set the correct answer field of a *Keyboard Component* to be *\$corrAns* (set both of these to update on every repeat of the Routine).:

```
if random()>0.5:
    targetPos=[-2.0, 0.0]#on the left
    corrAns='left'
else:
    targetPos=[+2.0, 0.0]#on the right
    corrAns='right'
```

### 2. Create a patch of noise

As with the above there are many different ways to create noise, but a simple method would be to add the following to the *Begin Routine* section of a *Code Component* at the top of your *Routine*. Then set the image as *\$noiseTexture*.:

```
noiseTexture = random.rand((128,128)) * 2.0 - 1
```

### 3. Send a feedback message at the end of the experiment

Make a new routine, and place it at the end of the flow (i.e., the end of the experiment). Create a *Code Component* with this in the *Begin Experiment* field:

```
expClock = core.Clock()
```

and put this in the *Begin routine* field:

```
msg = "Thanks for participating - that took %.2f minutes in total" %(expClock.
↳getTime()/60.0)
```

Next, add a *Text Component* to the routine, and set the text to *\$msg*. Be sure that the text field's updating is set to "Set every repeat" (and not "Constant").

### 4. End a loop early.

Code components can also be used to control the end of a loop. See examples in *Recipes:builderTerminateLoops*.

## What variables are available to use?

The most complete way to find this out for your particular script is to *compile it* and take a look at what's in there. Below are some options that appear in nearly all scripts. Remember that those variables are Python objects and can have attributes of their own. You can find out about those attributes using:

```
dir(myObject)
```

Common PsychoPy variables:

- `expInfo`: This is a Python Dictionary containing the information from the starting dialog box. e.g. That generally includes the ‘participant’ identifier. You can access that in your experiment using `exp['participant']`
- `t`: the current time (in seconds) measured from the start of this Routine
- `frameN`: the number of /completed/ frames since the start of the Routine (=0 in the first frame)
- `win`: the *Window* that the experiment is using

Your own variables:

- anything you’ve created in a Code Component is available for the rest of the script. (Sometimes you might need to define it at the beginning of the experiment, so that it will be available throughout.)
- the name of any other stimulus or the parameters from your file also exist as variables.
- most Components have a *status* attribute, which is useful to determine whether a stimulus has *NOT\_STARTED*, *STARTED* or *FINISHED*. For example, to play a tone at the end of a Movie Component (of unknown duration) you could set start of your tone to have the ‘condition’

```
myMovieName.status==FINISHED
```

Selected contents of [the numpy library](#) and [numpy.random](#) are imported by default. The entire numpy library is imported as *np*, so you can use a several hundred maths functions by prepending things with ‘np.’:

- `random()`, `randint()`, `normal()`, `shuffle()` options for creating arrays of random numbers.
- `sin()`, `cos()`, `tan()`, and `pi`: For geometry and trig. By default angles are in radians, if you want the cosine of an angle specified in degrees use `cos(angle*180/pi)`, or use numpy’s conversion functions, `rad2deg(angle)` and `deg2rad(angle)`.
- `linspace()`: Create an array of linearly spaced values.
- `log()`, `log10()`: The natural and base-10 log functions, respectively. (It is a lowercase-L in log).
- `sum()`, `len()`: For the sum and length of a list or array. To find an average, it is better to use `average()` (due to the potential for integer division issues with `sum()/len()`).
- `average()`, `sqrt()`, `std()`: For average (mean), square root, and standard deviation, respectively. **Note:** Be sure that the numpy standard deviation formula is the one you want!
- `np._____`: Many math-related features are available through the complete numpy libraries, which are available within psychopy builder scripts as ‘np.’. For example, you could use `np.hanning(3)` or `np.random.poisson(10, 10)` in a code component.

### 5.5.5 Dots (RDK) Component

The Dots Component allows you to present a Random Dot Kinematogram (RDK) to the participant of your study. These are fields of dots that drift in different directions and subjects are typically required to identify the ‘global motion’ of the field.

There are many ways to define the motion of the signal and noise dots. In PsychoPy the way the dots are configured follows [Scase, Braddick & Raymond \(1996\)](#). Although Scase et al (1996) show that the choice of algorithm for your dots actually makes relatively little difference there are some **potential** gotchas. Think carefully about whether each of these will affect your particular case:

- **limited dot lifetimes**: as your dots drift in one direction they go off the edge of the stimulus and are replaced randomly in the stimulus field. This could lead to a higher density of dots in the direction of motion providing subjects with an alternative cue to direction. Keeping dot lives relatively short prevents this.



- **noiseDots='direction'**: some groups have used noise dots that appear in a random location on each frame (noiseDots='location'). This has the disadvantage that the noise dots not only have a random direction but also a random speed (whereas signal dots have a constant speed and constant direction)
- **signalDots='same'**: on each frame the dots constituting the signal could be the same as on the previous frame or different. If 'different', participants could follow a single dot for a long time and calculate its average direction of motion to get the 'global' direction, because the dots would sometimes take a random direction and sometimes take the signal direction.

As a result of these, the defaults for PsychoPy are to have signalDots that are from a 'different' population, noise dots that have random 'direction' and a dot life of 3 frames.

## Parameters

**name** : Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : Governs the duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**units** [None, 'norm', 'cm', 'deg' or 'pix'] If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

**nDots** [int] number of dots to be generated

**fieldPos** [(x,y) or [x,y]] specifying the location of the centre of the stimulus.

**fieldSize** [a single value, specifying the diameter of the field] Sizes can be negative and can extend beyond the window.

**fieldShape** : Defines the shape of the field in which the dots appear. For a circular field the nDots represents the *average* number of dots per frame, but on each frame this may vary a little.

**dotSize** Always specified in pixels

**dotLife** [int] Number of frames each dot lives for (-1=infinite)

**dir** [float (degrees)] Direction of the signal dots

**speed** [float] Speed of the dots (in *units* per frame)

**signalDots** : If 'same' then the signal and noise dots are constant. If different then the choice of which is signal and which is noise gets randomised on each frame. This corresponds to Scase et al's (1996) categories of RDK.

**noiseDots** ['direction', 'position' or 'walk'] Determines the behaviour of the noise dots, taken directly from Scase et al's (1996) categories. For 'position', noise dots take a random position every frame. For 'direction' noise dots follow a random, but constant direction. For 'walk' noise dots vary their direction every frame, but keep a constant speed.

**See also:**

API reference for *DotStim*

## 5.5.6 Form Component

The Form component enables Psychopy to be used as a questionnaire tool, where participants can be presented with a series of questions requiring responses. Form items, defined as questions and response pairs, are presented simultaneously onscreen with a scrollable viewing window.

## Properties

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** [int, float] The time that the stimulus should first appear.

**Stop** [int, float] Governs the duration for which the stimulus is presented.

**Items** [List of dicts or csv / xlsx file] A list of dicts or csv file should have the following key, value pairs / column headers: *:index*: The item index as a number *:questionText*: item question string *:questionWidth*: question width between 0:1 *:type*: type of rating e.g., 'radio', 'rating', 'slider' *:responseWidth*: question width between 0:1 *:options*: A sequence of tick labels for options e.g., yes, no *:layout*: Response object layout e.g., 'horiz' or 'vert'

Missing column headers will be replaced by default entries. The default entries are: *:index*: 0 (increments for each item) *:questionText*: Default question *:questionWidth*: 0.7 *:type*: rating *:responseWidth*: 0.3 *:options*: Yes, No *:layout*: horiz

**Text height** [float] Text height of the Form elements (i.e., question and response text).

**Size** [[X,Y]] Size of the stimulus, to be specified in 'height' units.

**Pos** [[X,Y]] The position of the centre of the stimulus, to be specified in 'height' units.

**Item padding** [float] Space or padding between Form elements (i.e., question and response text), to be specified in 'height' units.

**Data format** [menu] Choose whether to store items data by column or row in your datafile.

**randomize** [bool] Randomize order of Form elements

**See also:**

API reference for `Form`

## 5.5.7 Grating Component

The Grating stimulus allows a texture to be wrapped/cycled in 2 dimensions, optionally in conjunction with a mask (e.g. Gaussian window). The texture can be a bitmap image from a variety of standard file formats, or a synthetic texture such as a sinusoidal grating. The mask can also be derived from either an image, or mathematical form such as a Gaussian.

When using gratings, if you want to use the *spatial frequency* setting then create just a single cycle of your texture and allow PsychoPy to handle the repetition of that texture (do not create the cycles you're expecting within the texture).

Gratings can have their position, orientation, size and other settings manipulated on a frame-by-frame basis. There is a performance advantage (in terms of milliseconds) to using images which are square and powers of two (32, 64, 128, etc.), however this is slight and would not be noticed in the majority of experiments.

## Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** : The time that the stimulus should first appear. See [Defining the onset/duration of components](#) for details.

**Stop** : Governs the duration for which the stimulus is presented. See [Defining the onset/duration of components](#) for details.

**Color** : See [Color spaces](#)

**Color space** [rgb, dkl or lms] See *Color spaces*

**Opacity** [0-1] Can be used to create semi-transparent gratings

**Orientation** [degrees] The orientation of the entire patch (texture and mask) in degrees.

**Position** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**Size** [[size<sub>x</sub>, size<sub>y</sub>] or a single value (applied to x and y)] The size of the stimulus in the given units of the stimulus/window. If the mask is a Gaussian then the size refers to width at 3 standard deviations on either side of the mean (i.e.  $sd=size/6$ )

**Units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

## Advanced Settings

**Texture: a filename, a standard name (sin, sqr) or a variable giving a numpy array** This specifies the image that will be used as the *texture* for the visual patch. The image can be repeated on the patch (in either x or y or both) by setting the spatial frequency to be high (or can be stretched so that only a subset of the image appears by setting the spatial frequency to be low). Filenames can be relative or absolute paths and can refer to most image formats (e.g. tif, jpg, bmp, png, etc.). If this is set to none, the patch will be a flat colour.

**Mask** [a filename, a standard name (gauss, circle, raisedCos) or a numpy array of dimensions NxNx1] The mask can define the shape (e.g. circle will make the patch circular) or something which overlays the patch e.g. noise.

**Interpolate :** If *linear* is selected then linear interpolation will be applied when the image is rescaled to the appropriate size for the screen. *Nearest* will use a nearest-neighbour rule.

**Phase** [single float or pair of values [X,Y]] The position of the texture within the mask, in both X and Y. If a single value is given it will be applied to both dimensions. The phase has units of cycles (rather than degrees or radians), wrapping at 1. As a result, setting the phase to 0,1,2... is equivalent, causing the texture to be centered on the mask. A phase of 0.25 will cause the image to shift by half a cycle (equivalent to  $\pi$  radians). The advantage of this is that if you set the phase according to time it is automatically in Hz.

**Spatial Frequency** [[SF<sub>x</sub>, SF<sub>y</sub>] or a single value (applied to x and y)] The spatial frequency of the texture on the patch. The units are dependent on the specified units for the stimulus/window; if the units are *deg* then the SF units will be *cycles/deg*, if units are *norm* then the SF units will be cycles per stimulus. If this is set to none then only one cycle will be displayed.

**Texture Resolution** [an integer (power of two)] Defines the size of the resolution of the texture for standard textures such as *sin*, *sqr* etc. For most cases a value of 256 pixels will suffice, but if stimuli are going to be very small then a lower resolution will use less memory.

See also:

API reference for *GratingStim*

## 5.5.8 Image Component

The Image stimulus allows an image to be presented, which can be a bitmap image from a variety of standard file formats, with an optional transparency mask that can effectively control the shape of the image. The mask can also be derived from an image file, or mathematical form such as a Gaussian.

**It is a really good idea to get your image in roughly the size (in pixels) that it will appear on screen to save memory. If you leave the resolution at 12 megapixel camera, as taken from your camera, but then present it on a standard screen at 1680x1050 (=1.6 megapixels) then PsychoPy and your graphics card have to do an awful lot of unnecessary work.** There is a performance advantage (in terms of milliseconds) to using images which are square and powers of two (32, 64, 128, etc.), but this is slight and would not be noticed in the majority of experiments.

Images can have their position, orientation, size and other settings manipulated on a frame-by-frame basis.

### Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**Stop** : Governs the duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**Image** [a filename or a standard name (sin, sqr)] Filenames can be relative or absolute paths and can refer to most image formats (e.g. tif, jpg, bmp, png, etc.). If this is set to none, the patch will be a flat colour.

**Position** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**Size** [[sizex, sizey] or a single value (applied to x and y)] The size of the stimulus in the given units of the stimulus/window. If the mask is a Gaussian then the size refers to width at 3 standard deviations on either side of the mean (i.e.  $sd=size/6$ ) Set this to be blank to get the image in its native size.

**Orientation** [degrees] The orientation of the entire patch (texture and mask) in degrees.

**Opacity** [value from 0 to 1] If opacity is reduced then the underlying images/stimuli will show through

**Units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

### Advanced Settings

**Color** [Colors can be applied to luminance-only images (not to rgb images)] See *Color spaces*

**Color space** [to be used if a color is supplied] See *Color spaces*

**Mask** [a filename, a standard name (gauss, circle, raisedCos) or a numpy array of dimensions NxNx1] The mask can define the shape (e.g. circle will make the patch circular) or something which overlays the patch e.g. noise.

**Interpolate** : If *linear* is selected then linear interpolation will be applied when the image is rescaled to the appropriate size for the screen. *Nearest* will use a nearest-neighbour rule.

**Texture Resolution**: This is only needed if you use a synthetic texture (e.g. sinusoidal grating) as the image.

**See also:**

API reference for *ImageStim*

## 5.5.9 ioLab Systems buttonbox Component

A button box is a hardware device that is used to collect participant responses with high temporal precision, ideally with true ms accuracy.

Both the response (which button was pressed) and time taken to make it are returned. The time taken is determined by a clock on the device itself. This is what makes it capable (in theory) of high precision timing.

Check the log file to see how long it takes for PsychoPy to reset the button box's internal clock. If this takes a while, then the RT timing values are not likely to be high precision. It might be possible for you to obtain a correction factor for your computer + button box set up, if the timing delay is highly reliable.

The ioLabs button box also has a built-in voice-key, but PsychoPy does not have an interface for it. Use a microphone component instead.

## Properties

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : The duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**Force end of Routine** [checkbox] If this is checked, the first response will end the routine.

**Active buttons** [None, or an integer, list, or tuple of integers 0-7] The ioLabs box lets you specify a set of active buttons. Responses on non-active buttons are ignored by the box, and never sent to PsychoPy. This field lets you specify which buttons (None, or some or all of 0 through 7).

**Lights** : If selected, the lights above the active buttons will be turned on.

Using code components, it is possible to turn on and off specific lights within a trial. See the API for *iolab*.

**Store** [(choice of: first, last, all, nothing)] Which button events to save in the data file. Events and the response times are saved, with RT being recorded by the button box (not by PsychoPy).

**Store correct** [checkbox] If selected, a correctness value will be saved in the data file, based on a match with the given correct answer.

**Correct answer: button** The correct answer, used by Store correct.

**Discard previous** [checkbox] If selected, any previous responses will be ignored (typically this is what you want).

**Lights off** [checkbox] If selected, all lights will be turned off at the end of each routine.

**See also:**

API reference for *iolab*

## 5.5.10 JoyButtons Component

The JoyButtons component can be used to collect gamepad/joystick button responses from a participant.

By not storing the button number pressed and checking the *forceEndTrial* box it can be used simply to end a *Routine*. If no gamepad/joystick is installed the keyboard can be used to simulate button presses by pressing 'ctrl' + 'alt' + digit(0-9).

### Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** [float or integer] The time that joyButtons should first get checked. See *Defining the onset/duration of components* for details.

**Stop** [float or integer] When joyButtons should no longer get checked. See *Defining the onset/duration of components* for details.

**Force end routine** : If this box is checked then the *Routine* will end as soon as one of the *allowed* buttons is pressed.

**Allowed buttons** : A list of allowed buttons can be specified here, e.g. [0,1,2,3], or the name of a variable holding such a list. If this box is left blank then any button that is pressed will be read. Only *allowed buttons* count as having been pressed; any other button will not be stored and will not force the end of the Routine. Note that button numbers (0, 1, 2, 3, ...), should be separated by commas.

**Store :** Which button press, if any, should be stored; the first to be pressed, the last to be pressed or all that have been pressed. If the button press is to force the end of the trial then this setting is unlikely to be necessary, unless two buttons happen to be pressed in the same video frame. The response time will also be stored if a button press is recorded. This time will be taken from the start of joyButtons checking (e.g. if the joyButtons was initiated 2 seconds into the trial and a button was pressed 3.2s into the trials the response time will be recorded as 1.2s).

**Store correct :** Check this box if you wish to store whether or not this button press was correct. If so then fill in the next box that defines what would constitute a correct answer e.g. 1 or *\$corrAns* (note this should not be in inverted commas). This is given as Python code that should return True (1) or False (0). Often this correct answer will be defined in the settings of the *Loops*.

## Advanced Settings

**Device number** [integer] Which gamepad/joystick device number to use. The first device found is numbered 0.

### 5.5.11 Joystick Component

The Joystick component can be used to collect responses from a participant. The coordinates of the joystick location are given in the same coordinates as the Window, with (0,0) in the centre. Coordinates are correctly scaled for 'norm' and 'height' units. User defined scaling can be set by updating joystick.xFactor and joystick.yFactor to the desired values. Joystick.device.getX() and joystick.device.getY() always return 'norm' units. Joystick.getX() and joystick.getY() are scaled by xFactor or yFactor

No cursor is drawn to represent the joystick current position, but this is easily provided by updating the position of a partially transparent '.png' image on each screen frame using the joystick coordinates: joystick.getX() and joystick.getY(). To ensure that the cursor image is drawn on top of other images it should be the last image in the trial.

**Joystick Emulation** If no joystick device is found, the mouse and keyboard are used to emulate a joystick device. Joystick position corresponds to mouse position and mouse buttons correspond to joystick buttons (0,1,2). Other buttons can be simulated with key chords: 'ctrl' + 'alt' + digit(0..9).

## Scenarios

This can be used in various ways. Here are some scenarios (email the list if you have other uses for your joystick):

Use the joystick to record the location of a button press

**Use the joystick to control stimulus parameters** Imagine you want to use your joystick to make your 'patch' \_ bigger or smaller and save the final size. Call your *joystickComponent* 'joystick', set it to save its state at the end of the trial and set the button press to end the Routine. Then for the size setting of your Patch stimulus insert *\$joystick.getX()* to use the x position of the joystick to control the size or *\$joystick.getY()* to use the y position.

Tracking the entire path of the joystick during a period

## Parameters Basic

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start :** The time that the joystick should first be checked. See *Defining the onset/duration of components* for details.

**stop :** When the joystick is no longer checked. See *Defining the onset/duration of components* for details.

**Force End Routine on Press** If this box is checked then the *Routine* will end as soon as one of the joystick buttons is pressed.

**Save Joystick State** How often do you need to save the state of the joystick? Every time the subject presses a joystick button, at the end of the trial, or every single frame? Note that the text output for cases where you store the joystick data repeatedly per trial (e.g. every press or every frame) is likely to be very hard to interpret, so you may then need to analyse your data using the psydat file (with python code) instead. Hopefully in future releases the output of the text file will be improved.

**Time Relative To** Whenever the joystick state is saved (e.g. on button press or at end of trial) a time is saved too. Do you want this time to be relative to start of the *Routine*, or the start of the whole experiment?

**Clickable Stimulus** A comma-separated list of your stimulus names that ‘can be “clicked” by the participant. e.g. target, foil.

**Store params for clicked** The params (e.g. name, text), for which you want to store the current value, for the stimulus that was “clicked” by the joystick. Make sure that all the clickable objects have all these params.

## Parameters Advanced

**Device Number** If you have multiple joystick/gamepad devices which one do you want (0, 1, 2, ...).

**Allowed Buttons** Joystick buttons accepted for input (blank for any) numbers separated by ‘commas’.

**See also:**

API reference for `Joystick`

## 5.5.12 Keyboard Component

The Keyboard component can be used to collect responses from a participant.

By not storing the key press and checking the *forceEndTrial* box it can be used simply to end a *Routine*

### Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** [float or integer] The time that the keyboard should first get checked. See *Defining the onset/duration of components* for details.

**Stop** : When the keyboard is no longer checked. See *Defining the onset/duration of components* for details.

**Force end routine** If this box is checked then the *Routine* will end as soon as one of the *allowed keys* is pressed.

**Allowed keys** A list of allowed keys can be specified here, e.g. ['m','z','1','2'], or the name of a variable holding such a list. If this box is left blank then any key that is pressed will be read. Only *allowed keys* count as having been pressed; any other key will not be stored and will not force the end of the Routine. Note that key names (even for number keys) should be given in single quotes, separated by commas. Cursor control keys can be accessed with ‘up’, ‘down’, and so on; the space bar is ‘space’. To find other special keys, run the Coder Input demo, “what\_key.py”, press the key, and check the Coder output window.

**Store** Which key press, if any, should be stored; the first to be pressed, the last to be pressed or all that have been pressed. If the key press is to force the end of the trial then this setting is unlikely to be necessary, unless two keys happen to be pressed in the same video frame. The response time will also be stored if a keypress is recorded. This time will be taken from the start of keyboard checking (e.g. if the keyboard was initiated 2 seconds into the trial and a key was pressed 3.2s into the trials the response time will be recorded as 1.2s).



**Store correct** Check this box if you wish to store whether or not this key press was correct. If so then fill in the next box that defines what would constitute a correct answer e.g. left, 1 or *\$corrAns* (note this should not be in inverted commas). This is given as Python code that should return True (1) or False (0). Often this correct answer will be defined in the settings of the *Loops*.

**Discard previous** Check this box to ensure that only key presses that occur during this keyboard checking period are used. If this box is not checked a keyboard press that has occurred before the start of the checking period will be interpreted as the first keyboard press. For most experiments this box should be checked.

**See also:**

API reference for *psychopy.event*

### 5.5.13 Microphone Component

Please note: This is a new component, and is subject to change.

The microphone component provides a way to record sound during an experiment. To do so, specify the starting time relative to the start of the routine (see *start* below) and a stop time (= duration in seconds). A blank duration evaluates to recording for 0.000s.

The resulting sound files are saved in .wav format (at 48000 Hz, 16 bit), one file per recording. The files appear in a new folder within the data directory (the subdirectory name ends in *\_wav*). The file names include the unix (epoch) time of the onset of the recording with milliseconds, e.g., *mic-1346437545.759.wav*.

It is possible to stop a recording that is in progress by using a code component. Every frame, check for a condition (such as key 'q', or a mouse click), and call the *.stop()* method of the microphone component. The recording will end at that point and be saved. For example, if *mic* is the name of your microphone component, then in the code component, do this on **Each frame**:

```
if event.getKeys(['q']):
    mic.stop()
```

#### Parameters

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** [float or integer] The time that the stimulus should first play. See *Defining the onset/duration of components* for details.

**stop (duration):** The length of time (sec) to record for. An *expected duration* can be given for visualisation purposes. See *Defining the onset/duration of components* for details; note that only seconds are allowed.

**See also:**

API reference for *AdvAudioCapture*

### 5.5.14 Mouse Component

The Mouse component can be used to collect responses from a participant. The coordinates of the mouse location are given in the same coordinates as the Window, with (0,0) in the centre.



## Scenarios

This can be used in various ways. Here are some scenarios (email the list if you have other uses for your mouse):

Use the mouse to record the location of a button press

**Use the mouse to control stimulus parameters** Imagine you want to use your mouse to make your ‘patch’ bigger or smaller and save the final size. Call your *mouse* ‘mouse’, set it to save its state at the end of the trial and set the button press to end the Routine. Then for the size setting of your Patch stimulus insert `$mouse.getPos()[0]` to use the x position of the mouse to control the size or `$mouse.getPos()[1]` to use the y position.

Tracking the entire path of the mouse during a period

## Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the mouse should first be checked. See *Defining the onset/duration of components* for details.

**stop** : When the mouse is no longer checked. See *Defining the onset/duration of components* for details.

**Force End Routine on Press** If this box is checked then the *Routine* will end as soon as one of the mouse buttons is pressed.

**Save Mouse State** How often do you need to save the state of the mouse? Every time the subject presses a mouse button, at the end of the trial, or every single frame? Note that the text output for cases where you store the mouse data repeatedly per trial (e.g. every press or every frame) is likely to be very hard to interpret, so you may then need to analyse your data using the psydat file (with python code) instead. Hopefully in future releases the output of the text file will be improved.

**Time Relative To** Whenever the mouse state is saved (e.g. on button press or at end of trial) a time is saved too. Do you want this time to be relative to start of the *Routine*, or the start of the whole experiment?

**See also:**

API reference for *Mouse*

### 5.5.15 Movie Component

The Movie component allows movie files to be played from a variety of formats (e.g. mpeg, avi, mov).

The movie can be positioned, rotated, flipped and stretched to any size on the screen (using the *Units for the window and stimuli* given).

## Parameters

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : Governs the duration for which the stimulus is presented (if you want to cut a movie short). Usually you can leave this blank and insert the *Expected* duration just for visualisation purposes. See *Defining the onset/duration of components* for details.

**movie** [string] The filename of the movie, including the path. The path can be absolute or relative to the location of the experiment (.psyexp) file.

**pos** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**ori** [degrees] Movies can be rotated in real-time too! This specifies the orientation of the movie in degrees.

**size** [[sizex, sizey] or a single value (applied to both x and y)] The size of the stimulus in the given units of the stimulus/window.

**units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

**See also:**

API reference for *MovieStim*

### 5.5.16 Parallel Port Out Component

This component allows you to send triggers to a parallel port or to a LabJack device.

An example usage would be in EEG experiments to set the port to 0 when no stimuli are present and then set it to an identifier value for each stimulus synchronised to the start/stop of that stimulus. In that case you might set the *Start data* to be *\$ID* (with ID being a column in your conditions file) and set the *Stop Data* to be 0.

#### Properties

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start :** The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**Stop :** Governs the duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**Port address** [select the appropriate option] You need to know the address of the parallel port you wish to write to. The options that appear in this drop-down list are determined by the application preferences. You can add your particular port there if you prefer.

**Start data** [0-255] When the start time/condition occurs this value will be sent to the parallel port. The value is given as a byte (a value from 0-255) controlling the 8 data pins of the parallel port.

**Stop data** [0-255] As with start data but sent at the end of the period.

**Sync to screen** [boolean] If true then the parallel port will be sent synchronised to the next screen refresh, which is ideal if it should indicate the onset of a visual stimulus. If set to False then the data will be set on the parallel port immediately.

**See also:**

API reference for *iolab*

### 5.5.17 Patch (image) Component

The Patch stimulus allows images to be presented in a variety of forms on the screen. It allows the combination of an image, which can be a bitmap image from a variety of standard file formats, or a synthetic repeating texture such as a sinusoidal grating. A transparency mask can also be control the shape of the image, and this can also be derived from either a second image, or mathematical form such as a Gaussian.

Patches can have their position, orientation, size and other settings manipulated on a frame-by-frame basis. There is a performance advantage (in terms of milliseconds) to using images which are square and powers of two (32, 64, 128, etc.), however this is slight and would not be noticed in the majority of experiments.

## Parameters

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : Governs the duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**image** [a filename, a standard name ('sin', 'sqr') or a numpy array of dimensions NxNx1 or NxNx3] This specifies the image that will be used as the *texture* for the visual patch. The image can be repeated on the patch (in either x or y or both) by setting the spatial frequency to be high (or can be stretched so that only a subset of the image appears by setting the spatial frequency to be low). Filenames can be relative or absolute paths and can refer to most image formats (e.g. tif, jpg, bmp, png, etc.). If this is set to none, the patch will be a flat colour.

**mask** [a filename, a standard name ('gauss', 'circle') or a numpy array of dimensions NxNx1] The mask can define the shape (e.g. circle will make the patch circular) or something which overlays the patch e.g. noise.

**ori** [degrees] The orientation of the entire patch (texture and mask) in degrees.

**pos** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**size** [[size<sub>x</sub>, size<sub>y</sub>] or a single value (applied to x and y)] The size of the stimulus in the given units of the stimulus/window. If the mask is a Gaussian then the size refers to width at 3 standard deviations on either side of the mean (i.e.  $sd = size/6$ )

**units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

## Advanced Settings

**colour** : See *Color spaces*

**colour space** [rgb, dkl or lms] See *Color spaces*

**SF** [[SF<sub>x</sub>, SF<sub>y</sub>] or a single value (applied to x and y)] The spatial frequency of the texture on the patch. The units are dependent on the specified units for the stimulus/window; if the units are *deg* then the SF units will be *cycles/deg*, if units are *norm* then the SF units will be cycles per stimulus. If this is set to none then only one cycle will be displayed.

**phase** [single float or pair of values [X,Y]] The position of the texture within the mask, in both X and Y. If a single value is given it will be applied to both dimensions. The phase has units of cycles (rather than degrees or radians), wrapping at 1. As a result, setting the phase to 0,1,2... is equivalent, causing the texture to be centered on the mask. A phase of 0.25 will cause the image to shift by half a cycle (equivalent to  $\pi$  radians). The advantage of this is that if you set the phase according to time it is automatically in Hz.

**Texture Resolution** [an integer (power of two)] Defines the size of the resolution of the texture for standard textures such as *sin*, *sqr* etc. For most cases a value of 256 pixels will suffice, but if stimuli are going to be very small then a lower resolution will use less memory.

**interpolate** : If *linear* is selected then linear interpolation will be applied when the image is rescaled to the appropriate size for the screen. *Nearest* will use a nearest-neighbour rule.

See also:

API reference for *PatchStim*

## 5.5.18 Polygon (shape) Component

(added in version 1.78.00)

The Polygon stimulus allows you to present a wide range of regular geometric shapes. The basic control comes from setting the

- 2 vertices give a line
- 3 give a triangle
- 4 give a rectangle etc.
- a large number will approximate a circle/ellipse

The size parameter takes two values. For a line only the first is used (then use *ori* to specify the orientation). For triangles and rectangles the size specifies the height and width as expected. Note that for pentagons upwards, however, the size determines the width/height of the ellipse on which the vertices will fall, rather than the width/height of the vertices themselves (slightly smaller typically).

### Parameters

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**nVertices** : integer

The number of vertices for your shape (2 gives a line, 3 gives a triangle,... a large number results in a circle/ellipse). It is not (currently) possible to vary the number of vertices dynamically.

**fill settings:**

Control the color inside the shape. If you set this to *None* then you will have a transparent shape (the line will remain)

**line settings:**

Control color and width of the line. The line width is always specified in pixels - it does not honour the *units* parameter.

**size** [[w,h]] See note above

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : Governs the duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**ori** [degrees] The orientation of the entire patch (texture and mask) in degrees.

**pos** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

**See also:**

API reference for *Polygon* API reference for *Rect* API reference for *ShapeStim* #for arbitrary vertices

## 5.5.19 Pump Component

This component allows you to deliver liquid stimuli using a Cetoni neMESYS syringe pump.

Please specify the name of the pump configuration to use in the PsychoPy preferences under Hardware / Qmix pump configuration. See the [readme file](#) of the pyqmix project for details on how to set up your computer and create the configuration file.

## Properties

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**Start** : The time that the stimulus should first appear.

**Stop** : Governs the duration for which the stimulus is presented.

**Pump index** [int] The index of the pump: The first pump's index is 0, the second pump's index is 1, etc. You may insert the name of a variable here to adjust this value dynamically.

**Syringe type** [select the appropriate option] Currently, 25 mL and 50 mL glass syringes are supported. This setting ensures that the pump will operate at the correct flow rate.

**Pump action** [aspirate or dispense] Whether to fill (aspirate) or to empty (dispense) the syringe.

**Flow rate** [float] The flow rate in the selected flow rate units.

**Flow rate unit** [mL/s or mL/min] The unit in which the flow rate values are supplied.

**Switch valve after dosing** [bool] Whether to switch the valve position after the pump operation has finished. This can be used to ensure a sharp(er) stimulus offset.

**Sync to screen** [bool] Whether to synchronize the pump operations (starting, stopping) to the screen refresh. This ensures better synchronization with visual stimuli.

## 5.5.20 RatingScale Component

A rating scale is used to collect a numeric rating or a choice from a few alternatives, via the mouse, the keyboard, or both. Both the response and time taken to make it are returned.

A given routine might involve an image (patch component), along with a rating scale to collect the response. A routine from a personality questionnaire could have text plus a rating scale.

**Three common usage styles are enabled on the first settings page:** 'visual analog scale': the subject uses the mouse to position a marker on an unmarked line

'category choices': choose among verbal labels (categories, e.g., "True, False" or "Yes, No, Not sure")

'scale description': used for numeric choices, e.g., 1 to 7 rating

Complete control over the display options is available as an advanced setting, 'customize\_everything'.

## Properties

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : The duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**visualAnalogScale** [checkbox] If this is checked, a line with no tick marks will be presented using the 'glow' marker, and will return a rating from 0.00 to 1.00 (quasi-continuous). This is intended to bias people away from thinking in terms of numbers, and focus more on the visual bar when making their rating. This supersedes either choices or scaleDescription.

**category choices** [string] Instead of a numeric scale, you can present the subject with words or phrases to choose from. Enter all the words as a string. (Probably more than 6 or so will not look so great on the screen.) Spaces

are assumed to separate the words. If there are any commas, the string will be interpreted as a list of words or phrases (possibly including spaces) that are separated by commas.

**scaleDescription** : Brief instructions, reminding the subject how to interpret the numerical scale, default = “1 = not at all ... extremely = 7”

**low** [str] The lowest number (bottom end of the scale), default = 1. If it’s not an integer, it will be converted to lowAnchorText (see Advanced).

**high** [str] The highest number (top end of the scale), default = 7. If it’s not an integer, it will be converted to highAnchorText (see Advanced).

### Advanced settings

**single click** : If this box is checked the participant can only click the scale once and their response will be stored. If this box is not checked the participant must accept their rating before it is stored.

**startTime** [float or integer] The time (relative to the beginning of this Routine) that the rating scale should first appear.

**forceEndTrial** : If checked, when the subject makes a rating the routine will be ended.

**size** [float] The size controls how big the scale will appear on the screen. (Same as “displaySizeFactor”.) Larger than 1 will be larger than the default, smaller than 1 will be smaller than the default.

**pos** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window. Default is centered left-right, and somewhat lower than the vertical center (0, -0.4).

**duration** : The maximum duration in seconds for which the stimulus is presented. See duration for details. Typically, the subject’s response should end the trial, not a duration. A blank or negative value means wait for a very long time.

**storeRatingTime**: Save the time from the beginning of the trial until the participant responds.

**storeRating**: Save the rating that was selected

**lowAnchorText** [str] Custom text to display at the low end of the scale, e.g., “0%”; overrides ‘low’ setting

**highAnchorText** [str] Custom text to display at the low end of the scale, e.g., “100%”; overrides ‘high’ setting

**customize\_everything** [str] If this is not blank, it will be used when initializing the rating scale just as it would be in a code component (see [RatingScale](#)). This allows access to all the customizable aspects of a rating scale, and supersedes all of the other RatingScale settings in the dialog panel. (This does not affect: startTime, forceEndTrial, duration, storeRatingTime, storeRating.)

See also:

API reference for [RatingScale](#)

## 5.5.21 Sound Component

### Parameters

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start** [float or integer] The time that the stimulus should first play. See [Defining the onset/duration of components](#) for details.

**stop** : For sounds loaded from a file leave this blank and then give the *Expected duration* below for visualisation purposes. See [Defining the onset/duration of components](#) for details.

**sound :** This sound can be described in a variety of ways:

- a number can specify the frequency in Hz (e.g. 440)
- a letter gives a note name (e.g. “C”) and sharp or flat can also be added (e.g. “Csh” “Bf”)
- a filename, which can be a relative or absolute path (mid, wav, and ogg are supported).

**volume** [float or integer] The volume with which the sound should be played. It’s a normalized value between 0 (minimum) and 1 (maximum).

**See also:**

API reference for `SoundPyo`

## 5.5.22 Static Component

(Added in Version 1.78.00)

The Static Component allows you to have a period where you can preload images or perform other time-consuming operations that not be possible while the screen is being updated.

Typically a static period would be something like an inter-trial or inter-stimulus interval (ITI/ISI). During this period you should not have any other objects being presented that are being updated (this isn’t checked for you - you have to make that check yourself), but you can have components being presented that are themselves static. For instance a fixation point never changes and so it can be presented during the static period (it will be presented and left on-screen while the other updates are being made).

Any stimulus updates can be made to occur during any static period defined in the experiment (it does not have to be in the same Routine). This is done in the updates selection box- once a static period exists it will show up here as well as the standard options of *constant* and *every repeat* etc. Many parameter updates (e.g. orientation are made so quickly that using the static period is of no benefit but others, most notably the loading of images from disk, can take substantial periods of time and these should always be performed during a static period to ensure good timing.

If the updates that have been requested were not completed by the end of the static period (i.e. there was a timing overshoot) then you will receive a warning to that effect. In this case you either need a longer static period to perform the actions or you need to reduce the time required for the action (e.g. use an image with fewer pixels).

### Parameters

**name :** Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).

**start :** The time that the static period begins. See [Defining the onset/duration of components](#) for details.

**stop :** The time that the static period ends. See [Defining the onset/duration of components](#) for details.

**custom code :** After running the component updates (which are defined in each component, not here) any code inserted here will also be run

**See also:**

API reference for `StaticPeriod`

## 5.5.23 Text Component

This component can be used to present text to the participant, either instructions or stimuli.

**name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces).



**start** : The time that the stimulus should first appear. See *Defining the onset/duration of components* for details.

**stop** : The duration for which the stimulus is presented. See *Defining the onset/duration of components* for details.

**color** : See *Color spaces*

**color space** [rgb, dkl or lms] See *Color spaces*

**ori** [degrees] The orientation of the stimulus in degrees.

**pos** [[X,Y]] The position of the centre of the stimulus, in the units specified by the stimulus or window

**height** [integer or float] The height of the characters in the given units of the stimulus/window. Note that nearly all actual letters will occupy a smaller space than this, depending on font, character, presence of accents etc. The width of the letters is determined by the aspect ratio of the font.

**units** [deg, cm, pix, norm, or inherit from window] See *Units for the window and stimuli*

**opacity** : Vary the transparency, from 0.0 = invisible to 1.0 = opaque

**flip** : Whether to mirror-reverse the text: 'horiz' for left-right mirroring, 'vert' for up-down mirroring. The flip can be set dynamically on a per-frame basis by using a variable, e.g., \$mirror, as defined in a code component or conditions file and set to either 'horiz' or 'vert'.

**See also:**

API reference for *TextStim*

### 5.5.24 Variable Component

A variable can hold quantities or values in memory that can be referenced using a variable name. You can store values in a variable to use in your experiments.

#### Parameters

**Name** [string] Everything in a PsychoPy experiment needs a unique name. The name should contain only letters, numbers and underscores (no punctuation marks or spaces). The variable name references the value stored in memory, so that your stored values can be used in your experiments.

**Start** [int, float or bool] The time or condition from when you want your variable to be defined. The default value is None, and so will be defined at the beginning of the experiment, trial or frame. See *Defining the onset/duration of components* for details.

**Stop** [int, float or bool] The duration for which the variable is defined/updated. See *Defining the onset/duration of components* for details.

**Experiment start value: any** The variable can take any value at the beginning of the experiment, so long as you define you variables using literals or existing variables.

**Routine start value** [any] The variable can take any value at the beginning of a routine/trial, and can remain a constant, or be defined/updated on every routine.

**Frame start value** [any] The variable can take any value at the beginning of a frame, or during a condition bases on Start and/or Stop.

**Save exp start value** [bool] Choose whether or not to save the experiment start value to your data file.

**Save routine start value** [bool] Choose whether or not to save the routine start value to your data file.

**Save frame value** [bool and drop=down menu] Frame values are contained within a list for each trial, and discarded at the end of each trial. Choose whether or not to take the first, last or average variable values from the frame container, and save to your data file.



**Save routine start value** [bool] Choose whether or not to save the routine end value to your data file.

**Save exp start value** [bool] Choose whether or not to save the experiment end value to your data file.

### 5.5.25 Entering parameters

Most of the entry boxes for Component parameters simply receive text or numeric values or lists (sequences of values surrounded by square brackets) as input. In addition, the user can insert variables and code into most of these, which will be interpreted either at the beginning of the experiment or at regular intervals within it.

To indicate to PsychoPy that the value represents a variable or python code, rather than literal text, it should be preceded by a \$. For example, inserting *intensity* into the text field of the Text Component will cause that word literally to be presented, whereas *\$intensity* will cause python to search for the variable called intensity in the script.

Variables associated with *Loops* can also be entered in this way (see [Accessing loop parameters from components](#) for further details). But it can also be used to evaluate arbitrary python code.

For example:

- `$random(2)` will generate a pair of random numbers
- `$"yn"[randint(2)]` will randomly choose the first or second character (y or n)
- `$globalClock.getTime()` will insert the current time in secs of the globalClock object
- `$(sin(angle), cos(angle))` will insert the sin and cos of an angle (e.g. into the x,y coords of a stimulus)

### 5.5.26 How often to evaluate the variable/code

If you do want the parameters of a stimulus to be evaluated by code in this way you need also to decide how often it should be updated. By default, the parameters of Components are set to be *constant*; the parameter will be set at the beginning of the experiment and will remain that way for the duration. Alternatively, they can be set to change either on *every repeat* in which case the parameter will be set at the beginning of the Routine on each repeat of it. Lastly many parameters can even be set *on every frame*, allowing them to change constantly on every refresh of the screen.

## 5.6 Experiment settings

The settings menu can be accessed by clicking the icon at the top of the window. It allows the user to set various aspects of the experiment, such as the size of the window to be used or what information is gathered about the subject and determine what outputs (data files) will be generated.

### 5.6.1 Settings

#### Basic settings

**Experiment name:** A name that will be stored in the metadata of the data file.

**Show info dlg:** If this box is checked then a dialog will appear at the beginning of the experiment allowing the *Experiment Info* to be changed.

**Experiment Info:** This information will be presented in a dialog box at the start and will be saved with any data files and so can be used for storing information about the current run of the study. The information stored here can also be used within the experiment. For example, if the *Experiment Info* included a field called *ori* then Builder [Components](#) could access `expInfo['ori']` to retrieve the orientation set here. Obviously this is a useful way to run essentially the same experiment, but with different conditions set at run-time.

**Enable escape:** If ticked then the *Esc* key can be used to exit the experiment at any time (even without a keyboard component)

### Data settings

**Data filename: (new in version 1.80.00):** A *formatted string* to control the base filename and path, often based on variables such as the date and/or the participant. This base filename will be given the various extensions for the different file types as needed. Examples:

```
# all in data folder: data/JWP_memoryTask_2014_Feb_15_1648
'data/%s_%s_%s' %(expInfo['participant'], expName, expInfo['date'])

# group by participant folder: data/JWP/memoryTask-2014_Feb_15_1648
'data/%s/%s-%s' %(expInfo['participant'], expName, expInfo['date'])

# put into dropbox: ~/dropbox/data/memoryTask/JWP-2014_Feb_15_1648
# on Windows you may need to replace ~ with your home directory
'~/dropbox/data/%s/%s-%s' %(expName, expInfo['participant'], expInfo['date'])
```

**Save Excel file:** If this box is checked an Excel data file (.xlsx) will be stored.

**Save csv file:** If this box is checked a comma separated variable (.csv) will be stored.

**Save psydat file:** If this box is checked a *PsychoPy data file (.psydat)* will be stored. This is a Python specific format (pickle files) which contains more information than .xlsx or .csv files that can be used with data analysis and plotting scripts written in Python. Whilst you may not wish to use this format it is recommended that you always save a copy as it contains a complete record of the experiment at the time of data collection.

**Save log file** A log file provides a record of what occurred during the experiment in chronological order, including information about any errors or warnings that may have occurred.

**Logging level** How much detail do you want to be output to the log file, if it is being saved. The lowest level is *error*, which only outputs error messages; *warning* outputs warnings and errors; *info* outputs all info, warnings and errors; *debug* outputs all info that can be logged. This system enables the user to get a great deal of information while generating their experiments, but then reducing this easily to just the critical information needed when actually running the study. If your experiment is not behaving as you expect it to, this is an excellent place to begin to work out what the problem is.

### Screen settings

**Monitor** The name of the monitor calibration. Must match one of the monitor names from *Monitor Center*.

**Screen:** If multiple screens are available (and if the graphics card is *not* an intel integrated graphics chip) then the user can choose which screen they use (e.g. 1 or 2).

**Full-screen window:** If this box is checked then the experiment window will fill the screen (overriding the window size setting and using the size that the screen is currently set to in the operating system settings).

**Window size:** The size of the window in pixels, if this is not to be a full-screen window.

**Units** The default units of the window (see *Units for the window and stimuli*). These can be overridden by individual *Components*.

## 5.7 Defining the onset/duration of components

As of version 1.70.00, the onset and offset times of stimuli can be defined in several ways.

Start and stop times can be entered in terms of seconds (*time (s)*), by frame number (*frameN*) or in relation to another stimulus (*condition*). *Condition* would be used to make *Components* start or stop depending on the status of something else, for example when a sound has finished. Duration can also be varied using a *Code Component*.

If you need very precise timing (particularly for very brief stimuli for instance) then it is best to control your on-set/duration by specifying the number of frames the stimulus will be presented for.

Measuring duration in seconds (or milliseconds) is not very precise because it doesn't take into account the fact that your monitor has a fixed frame rate. For example if the screen has a refresh rate of 60Hz you cannot present your stimulus for 120ms; the frame rate would limit you to 116.7ms (7 frames) or 133.3ms (8 frames). The duration of a frame (in seconds) is simply 1/refresh rate in Hz.

*Condition* would be used to make *Components* start or stop depending on the status of something else, for example when a movie has finished. Duration can also be varied using a code component.

In cases where PsychoPy cannot determine the start/endpoint of your Component (e.g. because it is a variable) you can enter an 'Expected' start/duration. This simply allows components with variable durations to be drawn in the Routine window. If you do not enter the approximate duration it will not be drawn, but this will not affect experimental performance.

For more details of how to achieve good temporal precision see *Timing Issues and synchronisation*

### 5.7.1 Examples

- Use *time(s)* or *frameN* and simply enter numeric values into the start and duration boxes.
- Use *time(s)* or *frameN* and enter a numeric value into the start time and set the duration to a variable name by preceeding it with a \$ as described *here*. Then set *expected time* to see an approximation in your *routine*
- Use *condition* to cause the stimulus to start immediately after a movie component called myMovie, by entering `$myMovie.status==FINISHED` into the *start* time.

## 5.8 Generating outputs (datafiles)

There are 4 main forms of *output* file from PsychoPy:

- Excel 2007 files (.xlsx) see *Excel Data Files* for more details
- text data files (.csv, .tsv, or .txt) see *Delimited Text Files* for more details
- binary data files (.psydat) see *PsychoPy Data Files* for more details
- log files (.log) see *Log Files* for more details

## 5.9 Common Mistakes (aka Gotcha's)

### 5.9.1 General Advice

- Python and therefore PsychoPy is CASE SENSITIVE
- To use a dollar sign (\$) for anything other than to indicate a code snippet for example in a text, precede it with a backslash \ (the backslash won't be printed)
- Have you entered your the settings for your *monitor*? If you are using degrees as a unit of measurement and have not entered your monitor settings, the size of stimuli will not be accurate.

- If your experiment is not behaving in the way that you expect. Have you looked at the *log file*? This can point you in the right direction. Did you know you can change the type of information that is stored in the log file in preferences by changing the *logging level*.
- Have you tried compiling the script and running it. Does this produce a particular error message that points you at a particular problem area? You can also change things in a more detailed way in the coder view and if you are having problems, reading through the script can highlight problems. Reading a compiled script can also help with the creation of a *Code Component*

## 5.9.2 My stimulus isn't appearing, there's only the grey background

- Have you checked the size of your stimulus? If it is 0.5x0.5 pixels you won't be able to see it!
- Have you checked the position of your stimulus? Is it positioned off the screen?

## 5.9.3 The loop isn't using my Excel spreadsheet

- Have you remembered to specify the file you want to use when setting up the loop?
- Have you remembered to add the variables preceded by the \$ symbol to your stimuli?

## 5.9.4 I just want a plain square, but it's turning into a grating

- If you don't want your stimulus to have a texture, you need Image to be None

## 5.9.5 The code snippet I've entered doesn't do anything

- Have you remembered to put a \$ symbol at the beginning (this isn't necessary, and should be avoided in a *Code Component*)?
- A dollar sign as the first character of a line indicates to PsychoPy that the rest of the line is code. It does not indicate a variable name (unlike in perl or php). This means that if you are, for example, using variables to determine position, enter `$(x,y)`. The temptation is to use `[$x,$y]`, which will not work.

## 5.9.6 My stimulus isn't changing as I progress through the loop

- Have you changed the setting for the variable that you want to change to 'change every repeat' (or 'change every frame')?

## 5.9.7 I'm getting the error message `AttributeError: 'unicode object has no attribute 'XXXX'`

- This type of error is usually caused by a naming conflict. Whilst we have made every attempt to make sure that these conflicts produce a warning message it is possible that they may still occur.
- The most common source of naming conflicts in an external file which has been imported to be used in a loop i.e. `.xlsx`, `.csv`.
- Check to make sure that all of the variable names are unique. There can be no repeated variable names anywhere in your experiment.

### 5.9.8 The window opens and immediately closes

- Have you checked all of your variable entries are accepted commands e.g. gauss but not Gauss
- If you compile your experiment and run it from the coder window what does the error message say? Does it point you towards a particular variable which may be incorrectly formatted?

If you are having problems getting the application to run please see [Troubleshooting](#)

## 5.10 Compiling a Script

If you click the *compile script* icon this will display the script for your experiment in the *Coder* window.

This can be used for debugging experiments, entering small amounts of code and learning a bit about writing scripts amongst other things.

The code is fully commented and so this can be an excellent introduction to writing your own code.

## 5.11 Set up your monitor properly

It's a really good idea to tell PsychoPy about the set up of your monitor, especially the size in cm and pixels and its distance, so that PsychoPy can present your stimuli in units that will be consistent in another lab with a different set up (e.g. cm or degrees of visual angle).

You should do this in *Monitor Center* which can be opened from Builder by clicking on the icon that shows two monitors. In *Monitor Center* you can create settings for multiple configurations, e.g. different viewing distances or different physical devices and then select the appropriate one by name in your experiments or scripts.

Having set up your monitor settings you should then tell PsychoPy which of your monitor setups to use for this experiment by going to the *Experiment settings* dialog.

## 5.12 Future developments

The new big feature, which we're really excited about is that Builder experiments are going to web-enabled very soon! Make sure you watch for new posts in the [PsychoPy forum Announcements](#) category so you get updates of when this is available.



---

**Note:** These do not teach you about Python *per se*, and you are recommended also to learn about that (Python has many excellent tutorials for programmers and non-programmers alike). In particular, dictionaries, lists and numpy arrays are used a great deal in most PsychoPy experiments.

---

You can learn to use the scripting interface to PsychoPy in several ways, and you should probably follow a combination of them:

- *Basic Concepts*: some of the logic of PsychoPy scripting
- *PsychoPy Tutorials*: walk you through the development of some semi-complete experiments
- demos: in the demos menu of Coder view. Many and varied
- use the *Builder* to *compile a script* and see how it works
- check the *Reference Manual (API)* for further details
- ultimately go into PsychoPy and start examining the source code. It's just regular python!

## 6.1 Basic Concepts

### 6.1.1 Presenting Stimuli

---

**Note:** Before you start, tell PsychoPy about your monitor(s) using the *Monitor Center*. That way you get to use units (like degrees of visual angle) that will transfer easily to other computers.

---

#### Stimulus objects

Python is an 'object-oriented' programming language, meaning that most stimuli in PsychoPy are represented by python objects, with various associated methods and information.

Typically you should create your stimulus with the initial desired attributes once, at the beginning of the script, and then change select attributes later (see section below on setting stimulus attributes). For instance, create your text and then change its color any time you like:

```
from psychopy import visual, core
win = visual.Window([400,400])
message = visual.TextStim(win, text='hello')
```

(continues on next page)

(continued from previous page)

```
message.autoDraw = True # Automatically draw every frame
win.flip()
core.wait(2.0)
message.text = 'world' # Change properties of existing stim
win.flip()
core.wait(2.0)
```

## Setting stimulus attributes

**Stimulus attributes are typically set using either**

- a string, which is just some characters (as *message.text* = 'world' above)
- a scalar (a number; see below)
- an x,y-pair (two numbers; see below)

**x,y-pair:** PsychoPy is very flexible in terms of input. You can specify the widely used x,y-pairs using these types:

- A Tuple (x, y) with two elements
- A List [x, y] with two elements
- A numpy array([x, y]) with two elements

However, PsychoPy always converts the x,y-pairs to numpy arrays internally. For example, all three assignments of pos are equivalent here:

```
stim.pos = (0.5, -0.2) # Right and a bit up from the center
print stim.pos # array([0.5, -0.2])

stim.pos = [0.5, -0.2]
print stim.pos # array([0.5, -0.2])

stim.pos = numpy.array([0.5, -0.2])
print stim.pos # array([0.5, -0.2])
```

Choose your favorite :-) However, you can't assign elementwise:

```
stim.pos[1] = 4 # has no effect
```

**Scalar:** Int or Float.

Mostly, scalars are no-brainers to understand. E.g.:

```
stim.ori = 90 # Rotate stimulus 90 degrees
stim.opacity = 0.8 # Make the stimulus slightly transparent.
```

However, scalars can also be used to assign x,y-pairs. In that case, both x and y get the value of the scalar. E.g.:

```
stim.size = 0.5
print stim.size # array([0.5, 0.5])
```

**Operations on attributes:** Operations during assignment of attributes are a handy way to smoothly alter the appearance of your stimuli in loops.

Most scalars and x,y-pairs support the basic operations:



```
stim.attribute += value # addition
stim.attribute -= value # subtraction
stim.attribute *= value # multiplication
stim.attribute /= value # division
stim.attribute %= value # modulus
stim.attribute **= value # power
```

They are easy to use and understand on scalars:

```
stim.ori = 5 # 5.0, set rotation
stim.ori += 3.8 # 8.8, rotate clockwise
stim.ori -= 0.8 # 8.0, rotate counterclockwise
stim.ori /= 2 # 4.0, home in on zero
stim.ori **= 3 # 64.0, exponential increase in rotation
stim.ori %= 10 # 4.0, modulus 10
```

However, they can also be used on x,y-pairs in very flexible ways. Here you can use both scalars and x,y-pairs as operators. In the latter case, the operations are element-wise:

```
stim.size = 5 # array([5.0, 5.0]), set quadratic size
stim.size += 2 # array([7.0, 7.0]), increase size
stim.size /= 2 # array([3.5, 3.5]), downscale size
stim.size += (0.5, 2.5) # array([4.0, 6.0]), a little wider and much taller
stim.size *= (2, 0.25) # array([8.0, 1.5]), upscale horizontal and downscale
↪vertical
```

Operations are not meaningful for strings.

## Timing

There are various ways to measure and control timing in PsychoPy:

- using frame refresh periods (most accurate, least obvious)
- checking the time on Clock objects
- using `core.wait()` commands (most obvious, least flexible/accurate)

Using `core.wait()`, as in the above example, is clear and intuitive in your script. But it can't be used while something is changing. For more flexible timing, you could use a `Clock()` object from the `core` module:

```
from psychopy import visual, core

# Setup stimulus
win = visual.Window([400, 400])
gabor = visual.GratingStim(win, tex='sin', mask='gauss', sf=5, name='gabor')
gabor.autoDraw = True # Automatically draw every frame
gabor.autoLog = False # Or we'll get many messages about phase change

# Let's draw a stimulus for 2s, drifting for middle 0.5s
clock = core.Clock()
while clock.getTime() < 2.0: # Clock times are in seconds
    if 0.5 <= clock.getTime() < 1.0:
        gabor.phase += 0.1 # Increment by 10th of cycle
    win.flip()
```

Clocks are accurate to around 1ms (better on some platforms), but using them to time stimuli is not very accurate because it fails to account for the fact that one frame on your monitor has a fixed frame rate. In the above, the stimulus

does not actually get drawn for exactly 0.5s (500ms). If the screen is refreshing at 60Hz (16.7ms per frame) and the `getTime()` call reports that the time has reached 1.999s, then the stimulus will draw again for a frame, in accordance with the `while` loop statement and will ultimately be displayed for 2.0167s. Alternatively, if the time has reached 2.001s, there will not be an extra frame drawn. So using this method you get timing accurate to the nearest frame period but with little consistent precision. An error of 16.7ms might be acceptable to long-duration stimuli, but not to a brief presentation. It also might also give the false impression that a stimulus can be presented for any given period. At 60Hz refresh you can not present your stimulus for, say, 120ms; the frame period would limit you to a period of 116.7ms (7 frames) or 133.3ms (8 frames).

As a result, the most precise way to control stimulus timing is to present them for a specified number of frames. The frame rate is extremely precise, much better than ms-precision. Calls to `Window.flip()` will be synchronised to the frame refresh; the script will not continue until the flip has occurred. As a result, on most cards, as long as frames are not being ‘dropped’ (see [Detecting dropped frames](#)) you can present stimuli for a fixed, reproducible period.

---

**Note:** Some graphics cards, such as Intel GMA graphics chips under win32, don’t support frame sync. Avoid integrated graphics for experiment computers wherever possible.

---

Using the concept of fixed frame periods and `flip()` calls that sync to those periods we can time stimulus presentation extremely precisely with the following:

```
from psychopy import visual, core

# Setup stimulus
win = visual.Window([400, 400])
gabor = visual.GratingStim(win, tex='sin', mask='gauss', sf=5,
    name='gabor', autoLog=False)
fixation = visual.GratingStim(win, tex=None, mask='gauss', sf=0, size=0.02,
    name='fixation', autoLog=False)

# Let's draw a stimulus for 200 frames, drifting for frames 50:100
for frameN in range(200):    # For exactly 200 frames
    if 10 <= frameN < 150:    # Present fixation for a subset of frames
        fixation.draw()
    if 50 <= frameN < 100:    # Present stim for a different subset
        gabor.phase += 0.1    # Increment by 10th of cycle
        gabor.draw()
    win.flip()
```

## Using autoDraw

Stimuli are typically drawn manually on every frame in which they are needed, using the `draw()` function. You can also set any stimulus to start drawing every frame using `stim.autoDraw = True` or `stim.autoDraw = False`. If you use these commands on stimuli that also have `autoLog=True`, then these functions will also generate a log message on the frame when the first drawing occurs and on the first frame when it is confirmed to have ended.

### 6.1.2 Logging data

TrialHandler and StairHandler can both generate data outputs in which responses are stored, in relation to the stimulus conditions. In addition to those data outputs, PsychoPy can create detailed chronological log files of events during the experiment.

## Log levels and targets

**Log messages have various levels of severity:** ERROR, WARNING, DATA, EXP, INFO and DEBUG

Multiple *targets* can also be created to receive log messages. Each target has a particular critical level and receives all logged messages greater than that. For example, you could set the console (visual output) to receive only warnings and errors, have a central log file that you use to store warning messages across studies (with file mode *append*), and another to create a detailed log of data and events within a single study with *level=INFO*:

```
from psychopy import logging
logging.console.setLevel(logging.WARNING)
# overwrite (filemode='w') a detailed log of the last run in this dir
lastLog = logging.LogFile("lastRun.log", level=logging.INFO, filemode='w')
# also append warnings to a central log file
centralLog = logging.LogFile("C:\\psychopyExps.log", level=logging.WARNING, filemode=
    ↪ 'a')
```

## Updating the logs

For performance purposes log files are not actually written when the log commands are ‘sent’. They are stored in a list and processed automatically when the script ends. You might also choose to force a *flush* of the logged messages manually during the experiment (e.g. during an inter-trial interval):

```
from psychopy import logging

...

logging.flush()    # write messages out to all targets
```

This should only be necessary if you want to see the logged information as the experiment progresses.

## AutoLogging

### New in version 1.63.00

Certain events will log themselves automatically by default. For instance, visual stimuli send log messages every time one of their parameters is changed, and when autoDraw is toggled they send a message that the stimulus has started/stopped. All such log messages are timestamped with the frame flip on which they take effect. To avoid this logging, for stimuli such as fixation points that might not be critical to your analyses, or for stimuli that change constantly and will flood the logging system with messages, the autoLogging can be turned on/off at initialisation of the stimulus and can be altered afterwards with *.setAutoLog(True/False)*

## Manual methods

In addition to a variety of automatic logging messages, you can create your own, of various levels. These can be timestamped immediately:

```
from psychopy import logging
logging.log(level=logging.WARN, msg='something important')
logging.log(level=logging.EXP, msg='something about the conditions')
logging.log(level=logging.DATA, msg='something about a response')
logging.log(level=logging.INFO, msg='something less important')
```

There are additional convenience functions for the above: `logging.warn('a warning')` etc.

For stimulus changes you probably want the log message to be timestamped based on the frame flip (when the stimulus is next presented) rather than the time that the log message is sent:

```
from psychopy import logging, visual
win = visual.Window([400,400])
win.flip()
logging.log(level=logging.EXP, msg='sent immediately')
win.logOnFlip(level=logging.EXP, msg='sent on actual flip')
win.flip()
```

### Using a custom clock for logs

#### New in version 1.63.00

By default times for log files are reported as seconds after the very beginning of the script (often it takes a few seconds to initialise and import all modules too). You can set the logging system to use any given `core.Clock` object (actually, anything with a `getTime()` method):

```
from psychopy import core, logging
globalClock = core.Clock()
logging.setDefaultClock(globalClock)
```

## 6.1.3 Handling Trials and Conditions

### TrialHandler

This is what underlies the random and sequential loop types in *Builder*, they work using the *method of constants*. The `TrialHandler` presents a predetermined list of conditions in either a sequential or random (without replacement) order.

see `TrialHandler` for more details.

### StairHandler

This generates the next trial using an *adaptive staircase*. The conditions are not predetermined and are generated based on the participant's responses.

Staircases are predominately used in psychophysics to measure the discrimination and detection thresholds. However they can be used in any experiment which varies a numeric value as a result of a 2 alternative forced choice (2AFC) response.

The `StairHandler` systematically generates numbers based on staircase parameters. These can then be used to define a stimulus parameter e.g. spatial frequency, stimulus presentation duration. If the participant gives the incorrect response the number generated will get larger and if the participant gives the correct response the number will get smaller.

see `StairHandler` for more details

## 6.1.4 Global Event Keys

Global event keys are single keys (or combinations of a single key and one or more “modifier” keys such as Ctrl, Alt, etc.) with an associated Python callback function. This function will be executed if the key (or key/modifiers combination) was pressed.

---

**Note:** Global event keys only work with the *pyglet* backend, which is the default.

---

PsychoPy fully automatically monitors and processes key presses during most portions of the experimental run, for example during *core.wait()* periods, or when calling *win.flip()*. If a global event key press is detected, the specified function will be run immediately. You are not required to manually poll and check for key presses. This can be particularly useful to implement a global “shutdown” key, or to trigger laboratory equipment on a key press when testing your experimental script – without cluttering the code. But of course the application is not limited to these two scenarios. In fact, you can associate any Python function with a global event key.

All active global event keys are stored in *event.globalKeys*.

### Adding a global event key (simple)

First, let’s ensure no global event keys are currently set by calling `func:event.globalKeys.clear`.

```
>>> from psychopy import event
>>> event.globalKeys.clear()
```

To add a new global event key, you need to invoke `func:event.globalKeys.add`. This function has two required arguments: the key name, and the function to associate with that key.

```
>>> key = 'a'
>>> def myfunc():
...     pass
...
>>> event.globalKeys.add(key=key, func=myfunc)
```

Look at *event.globalKeys*, we can see that the global event key has indeed been created.

```
>>> event.globalKeys
<_GlobalEventKeys :
  [A] -> 'myfunc' <function myfunc at 0x10669ba28>
>
```

Your output should look similar. You may happen to spot We can take a closer look at the specific global key event we added.

```
>>> event.globalKeys['a']
_GlobalEvent(func=<function myfunc at 0x10669ba28>, func_args=(), func_kwargs={},
↳name='myfunc')
```

This output tells us that

- our key *a* is associated with our function *myfunc*
- *myfunc* will be called without passing any positional or keyword arguments (*func\_args* and *func\_kwargs*, respectively)
- the event name was automatically set to the name of the function.

---

**Note:** Pressing the key won’t do anything unless a *psychopy.visual.Window* is created and its `:func:~‘psychopy.visual.Window.flip’` method or *psychopy.core.wait()* are called.

---

### Adding a global event key (advanced)

We are going to associate a function with a more complex calling signature (with positional and keyword arguments) with a global event key. First, let's create the dummy function:

```
>>> def myfunc2(*args, **kwargs):  
...     pass  
...
```

Next, compile some positional and keyword arguments and a custom name for this event. Positional arguments must be passed as tuples or uples, and keyword arguments as dictionaries.

```
>>> args = (1, 2)  
>>> kwargs = dict(foo=3, bar=4)  
>>> name = 'my name'
```

---

**Note:** Even when intending to pass only a single positional argument, *args* must be a list or tuple, e.g., *args = [1]* or *args = (1,)*.

---

Finally, specify the key and a combination of modifiers. While key names are just strings, modifiers are lists or tuples of modifier names.

```
>>> key = 'b'  
>>> modifiers = ['ctrl', 'alt']
```

---

**Note:** Even when specifying only a single modifier key, *modifiers* must be a list or tuple, e.g., *modifiers = ['ctrl']* or *modifiers = ('ctrl',)*.

---

We are now ready to create the global event key.

```
>>> event.globalKeys.add(key=key, modifiers=modifiers,  
... func=myfunc2, func_args=args, func_kwargs=kwargs,  
... name=name)
```

Check that the global event key was successfully added.

```
>>> event.globalKeys  
<_GlobalEventKeys :  
  [A] -> 'myfunc' <function myfunc at 0x10669ba28>  
  [CTRL] + [ALT] + [B] -> 'my name' <function myfunc2 at 0x112eecb90>  
>
```

The key combination *[CTRL] + [ALT] + [B]* is now associated with the function *myfunc2*, which will be called in the following way:

```
myfunc2(1, 2, foo=2, bar=4)
```

### Indexing

*event.globalKeys* can be accessed like an ordinary dictionary. The index keys are (*key*, *modifiers*) namedtuples.

```
>>> event.globalKeys.keys()
[_IndexKey(key='a', modifiers=()), _IndexKey(key='b', modifiers=('ctrl', 'alt'))]
```

To access the global event associated with the key combination *[CTRL] + [ALT] + [B]*, we can do

```
>>> event.globalKeys['b', ['ctrl', 'alt']]
_GlobalEvent(func=<function myfunc2 at 0x112eecb90>, func_args=(1, 2), func_kwargs={
↳ 'foo': 3, 'bar': 4}, name='my name')
```

To make access more convenient, specifying the modifiers is optional in case none were passed to `psychopy.event.globalKeys.add()` when the global event key was added, meaning the following commands are identical.

```
>>> event.globalKeys['a', ()]
_GlobalEvent(func=<function myfunc at 0x10669ba28>, func_args=(), func_kwargs={},
↳ name='myfunc')
>>> event.globalKeys['a']
_GlobalEvent(func=<function myfunc at 0x10669ba28>, func_args=(), func_kwargs={},
↳ name='myfunc')
```

All elements of a global event can be accessed directly.

```
>>> index = ('b', ['ctrl', 'alt'])
>>> event.globalKeys[index].func
<function myfunc2 at 0x112eecb90>
>>> event.globalKeys[index].func_args
(1, 2)
>>> event.globalKeys[index].func_kwargs
{'foo': 3, 'bar': 4}
>>> event.globalKeys[index].name
'my name'
```

## Number of active event keys

The number of currently active event keys can be retrieved by passing `event.globalKeys` to the `len()` function.

```
>>> len(event.globalKeys)
2
```

## Removing global event keys

There are three ways to remove global event keys:

- using `psychopy.event.globalKeys.remove()`,
- using `del`, and
- using `psychopy.event.globalKeys.pop()`.

### `psychopy.event.globalKeys.remove()`

To remove a single key, pass the key name and modifiers (if any) to `psychopy.event.globalKeys.remove()`.

```
>>> event.globalKeys.remove(key='a')
```

A convenience method to quickly delete *all* global event keys is to pass *key='all'*

```
>>> event.globalKeys.remove(key='all')
```

### *del*

Like with other dictionaries, items can be removed from *event.globalKeys* by using the *del* statement. The provided index key must be specified as described in [Indexing](#).

```
>>> index = ('b', ['ctrl', 'alt'])
>>> del event.globalKeys[index]
```

### `psychopy.event.globalKeys.pop()`

Again, as other dictionaries, *event.globalKeys* provides a *pop* method to retrieve an item and remove it from the dict. The first argument to *pop* is the index key, specified as described in [Indexing](#). The second argument is optional. Its value will be returned in case no item with the matching indexing key could be found, for example if the item had already been removed previously.

```
>>> r = event.globalKeys.pop('a', None)
>>> print(r)
_GlobalEvent(func=<function myfunc at 0x10669ba28>, func_args=(), func_kwargs={},
↳name='myfunc')
>>> r = event.globalKeys.pop('a', None)
>>> print(r)
None
```

### Global shutdown key

The PsychoPy preferences for *shutdownKey* and *shutdownKeyModifiers* (both unset by default) will be used to automatically create a global shutdown key. To demonstrate this automated behavior, let us first change the preferences programmatically (these changes will be lost when quitting the current Python session).

```
>>> from psychopy.preferences import prefs
>>> prefs.general['shutdownKey'] = 'q'
```

We can now check if a global shutdown key has been automatically created.

```
>>> from psychopy import event
>>> event.globalKeys
<_GlobalEventKeys :
  [Q] -> 'shutdown (auto-created from prefs)' <function quit at 0x10c171938>
>
```

And indeed, it worked!

What happened behind the scenes? When importing the *psychopy.event* module, the initialization of *event.globalKeys* checked for valid shutdown key preferences and automatically initialized a shutdown key accordingly. This key is associated with the `:func:~'psychopy.core.quit'` function, which will shut down PsychoPy.



```
>>> from psychopy.core import quit
>>> event.globalKeys['q'].func == quit
True
```

Of course you can very easily add a global shutdown key manually, too. You simply have to associate a key with `:func=~'psychopy.core.quit'`.

```
>>> from psychopy import core, event
>>> event.globalKeys.add(key='q', func=core.quit, name='shutdown')
```

That's it!

## A working example

In the above code snippets, our global event keys were not actually functional, as we didn't create a window, which is required to actually collect the key presses. Our working example will thus first create a window and then add global event keys to change the window color and quit the experiment, respectively.

```
#!/usr/bin/env python
# -*- coding: utf-8 -*-

from __future__ import print_function
from psychopy import core, event, visual

def change_color(win, log=False):
    win.color = 'blue' if win.color == 'gray' else 'gray'
    if log:
        print('Changed color to %s' % win.color)

win = visual.Window(color='gray')
text = visual.TextStim(win,
                        text='Press C to change color,\n CTRL + Q to quit.')

# Global event key to change window background color.
event.globalKeys.add(key='c',
                     func=change_color,
                     func_args=[win],
                     func_kwargs=dict(log=True),
                     name='change window color')

# Global event key (with modifier) to quit the experiment ("shutdown key").
event.globalKeys.add(key='q', modifiers=['ctrl'], func=core.quit)

while True:
    text.draw()
    win.flip()
```

## 6.2 PsychoPy Tutorials

### 6.2.1 Tutorial 1: Generating your first stimulus

A tutorial to get you going with your first stimulus display.

### Know your monitor

PsychoPy has been designed to handle your screen calibrations for you. It is also designed to operate (if possible) in the final experimental units that you like to use e.g. degrees of visual angle.

In order to do this PsychoPy needs to know a little about your monitor. There is a GUI to help with this (select MonitorCenter from the tools menu of PsychoPyIDE or run ...site-packages/monitors/MonitorCenter.py).

In the MonitorCenter window you can create a new monitor name, insert values that describe your monitor and run calibrations like gamma corrections. For now you can just stick to the `[testMonitor]` but give it correct values for your screen size in number of pixels and width in cm.

Now, when you create a window on your monitor you can give it the name 'testMonitor' and stimuli will know how they should be scaled appropriately.

### Your first stimulus

Building stimuli is extremely easy. All you need to do is create a *Window*, then some stimuli. Draw those stimuli, then update the window. PsychoPy has various other useful commands to help with timing too. Here's an example. Type it into a coder window, save it somewhere and press run.

```
1 from psychopy import visual, core # import some libraries from PsychoPy
2
3 #create a window
4 mywin = visual.Window([800,600], monitor="testMonitor", units="deg")
5
6 #create some stimuli
7 grating = visual.GratingStim(win=mywin, mask="circle", size=3, pos=[-4,0], sf=3)
8 fixation = visual.GratingStim(win=mywin, size=0.5, pos=[0,0], sf=0, rgb=-1)
9
10 #draw the stimuli and update the window
11 grating.draw()
12 fixation.draw()
13 mywin.update()
14
15 #pause, so you get a chance to see it!
16 core.wait(5.0)
```

---

**Note: For those new to Python.** Did you notice that the grating and the fixation stimuli both call *GratingStim* but have different arguments? One of the nice features about python is that you can select which arguments to set. GratingStim has over 15 arguments that can be set, but the others just take on default values if they aren't needed.

---

That's a bit easy though. Let's make the stimulus move, at least! To do that we need to create a loop where we change the phase (or orientation, or position...) of the stimulus and then redraw. Add this code in place of the drawing code above:

```
for frameN in range(200):
    grating.setPhase(0.05, '+') # advance phase by 0.05 of a cycle
    grating.draw()
    fixation.draw()
    mywin.update()
```

That ran for 200 frames (and then waited 5 seconds as well). Maybe it would be nicer to keep updating until the user hits a key instead. That's easy to add too. In the first line add `event` to the list of modules you'll import. Then replace the line:

```
for frameN in range(200):
```

with the line:

```
while True: #this creates a never-ending loop
```

Then, within the loop (make sure it has the same indentation as the other lines) add the lines:

```
    if len(event.getKeys())>0:
        break
    event.clearEvents()
```

the first line counts how many keys have been pressed since the last frame. If more than zero are found then we break out of the never-ending loop. The second line clears the event buffer and should always be called after you've collected the events you want (otherwise it gets full of events that we don't care about like the mouse moving around etc...).

Your finished script should look something like this:

```
1 from psychopy import visual, core, event #import some libraries from PsychoPy
2
3 #create a window
4 mywin = visual.Window([800,600],monitor="testMonitor", units="deg")
5
6 #create some stimuli
7 grating = visual.GratingStim(win=mywin, mask='circle', size=3, pos=[-4,0], sf=3)
8 fixation = visual.GratingStim(win=mywin, size=0.2, pos=[0,0], sf=0, rgb=-1)
9
10 #draw the stimuli and update the window
11 while True: #this creates a never-ending loop
12     grating.setPhase(0.05, '+') #advance phase by 0.05 of a cycle
13     grating.draw()
14     fixation.draw()
15     mywin.flip()
16
17     if len(event.getKeys())>0:
18         break
19     event.clearEvents()
20
21 #cleanup
22 mywin.close()
23 core.quit()
```

There are several more simple scripts like this in the demos menu of the Coder and Builder views and many more to download. If you're feeling like something bigger then go to [Tutorial 2: Measuring a JND using a staircase procedure](#) which will show you how to build an actual experiment.

## 6.2.2 Tutorial 2: Measuring a JND using a staircase procedure

This tutorial builds an experiment to test your just-noticeable-difference (JND) to orientation, that is it determines the smallest angular deviation that is needed for you to detect that a gabor stimulus isn't vertical (or at some other reference orientation). The method presents a pair of stimuli at once with the observer having to report with a key press whether the left or the right stimulus was at the reference orientation (e.g. vertical).

You can download the [full code here](#). Note that the entire experiment is constructed of less than 100 lines of code, including the initial presentation of a dialogue for parameters, generation and presentation of stimuli, running the trials, saving data and outputting a simple summary analysis for feedback. Not bad, eh?

There are a great many modifications that can be made to this code, however this example is designed to demonstrate how much can be achieved with very simple code. Modifying existing is an excellent way to begin writing your own scripts, for example you may want to try changing the appearance of the text or the stimuli.

### Get info from the user

The first lines of code import the necessary libraries. We need lots of the PsychoPy modules for a full experiment, as well as *numpy* (which handles various numerical/mathematical functions):

```
1 """measure your JND in orientation using a staircase method"""
2 from psychopy import core, visual, gui, data, event
3 from psychopy.tools.filetools import fromFile, toFile
4 import numpy, random
```

Also note that there are two ways to insert comments in Python (and you should do this often!). Using triple quotes, as in `"""Here's my comment"""`, allows you to write a comment that can span several lines. Often you need that at the start of your script to leave yourself a note about the implementation and history of what you've written. For single-line comments, as you'll see below, you can use a simple `#` to indicate that the rest of the line is a comment.

The `try:...except:...`  lines allow us to try and load a parameter file from a previous run of the experiment. If that fails (e.g. because the experiment has never been run) then create a default set of parameters. These are easy to store in a python dictionary that we'll call *expInfo*:

```
6 try: # try to get a previous parameters file
7     expInfo = fromFile('lastParams.pickle')
8 except: # if not there then use a default set
9     expInfo = {'observer':'jwp', 'refOrientation':0}
10 expInfo['dateStr'] = data.getDateStr() # add the current time
```

The last line adds the current date to the information, whether we loaded from a previous run or created default values.

So having loaded those parameters, let's allow the user to change them in a dialogue box (which we'll call *dlg*). This is the simplest form of dialogue, created directly from the dictionary above. the dialogue will be presented immediately to the user and the script will wait until they hit *OK* or *Cancel*.

If they hit *OK* then `dlg.OK=True`, in which case we'll use the updated values and save them straight to a parameters file (the one we try to load above).

If they hit *Cancel* then we'll simply quit the script and not save the values.

```
11 # present a dialogue to change params
12 dlg = gui.DlgFromDict(expInfo, title='simple JND Exp', fixed=['dateStr'])
13 if dlg.OK:
14     toFile('lastParams.pickle', expInfo) # save params to file for next time
15 else:
16     core.quit() # the user hit cancel so exit
```

### Setup the information for trials

We'll create a file to which we can output some data as text during each trial (as well as *outputting a binary file* at the end of the experiment). PsychoPy actually has supporting functions to do this automatically, but here we're showing you the manual way to do it.

We'll create a filename from the subject+date+`".csv"` (note how easy it is to concatenate strings in python just by 'adding' them). *csv* files can be opened in most spreadsheet packages. Having opened a text file for writing, the last line shows how easy it is to send text to this target document.

```

18 # make a text file to save data
19 fileName = expInfo['observer'] + expInfo['dateStr']
20 dataFile = open(fileName+'.csv', 'w') # a simple text file with 'comma-separated-
    ↳ values'
21 dataFile.write('targetSide,oriIncrement,correct\n')

```

PsychoPy allows us to set up an object to handle the presentation of stimuli in a staircase procedure, the *StairHandler*. This will define the increment of the orientation (i.e. how far it is from the reference orientation). The staircase can be configured in many ways, but we'll set it up to begin with an increment of 20deg (very detectable) and home in on the 80% threshold value. We'll step up our increment every time the subject gets a wrong answer and step down if they get three right answers in a row. The step size will also decrease after every 2 reversals, starting with an 8dB step (large) and going down to 1dB steps (smallish). We'll finish after 50 trials.

```

23 # create the staircase handler
24 staircase = data.StairHandler(startVal = 20.0,
25                               stepType = 'db', stepSizes=[8,4,4,2],
26                               nUp=1, nDown=3, # will home in on the 80% threshold
27                               nTrials=1)

```

## Build your stimuli

Now we need to create a window, some stimuli and timers. We need a *~psychopy.visual.Window* in which to draw our stimuli, a fixation point and two *~psychopy.visual.GratingStim* stimuli (one for the target probe and one as the foil). We can have as many timers as we like and reset them at any time during the experiment, but I generally use one to measure the time since the experiment started and another that I reset at the beginning of each trial.

```

29 # create window and stimuli
30 win = visual.Window([800,600],allowGUI=True,
31                     monitor='testMonitor', units='deg')
32 foil = visual.GratingStim(win, sf=1, size=4, mask='gauss',
33                            ori=expInfo['refOrientation'])
34 target = visual.GratingStim(win, sf=1, size=4, mask='gauss',
35                              ori=expInfo['refOrientation'])
36 fixation = visual.GratingStim(win, color=-1, colorSpace='rgb',
37                                tex=None, mask='circle', size=0.2)
38 # and some handy clocks to keep track of time
39 globalClock = core.Clock()
40 trialClock = core.Clock()

```

Once the stimuli are created we should give the subject a message asking if they're ready. The next two lines create a pair of messages, then draw them into the screen and then update the screen to show what we've drawn. Finally we issue the command `event.waitKeys()` which will wait for a keypress before continuing.

```

42 # display instructions and wait
43 message1 = visual.TextStim(win, pos=[0,+3],text='Hit a key when ready.')
44 message2 = visual.TextStim(win, pos=[0,-3],
45                             text="Then press left or right to identify the %.1f deg probe." %expInfo[
    ↳ 'refOrientation'])
46 message1.draw()
47 message2.draw()
48 fixation.draw()
49 win.flip() #to show our newly drawn 'stimuli'
50 #pause until there's a keypress
51 event.waitKeys()

```

## Control the presentation of the stimuli

OK, so we have everything that we need to run the experiment. The following uses a for-loop that will iterate over trials in the experiment. With each pass through the loop the `staircase` object will provide the new value for the intensity (which we will call `thisIncrement`). We will randomly choose a side to present the target stimulus using `numpy.random.random()`, setting the position of the target to be there and the foil to be on the other side of the fixation point.

```
53 for thisIncrement in staircase: # will continue the staircase until it terminates!
54     # set location of stimuli
55     targetSide= random.choice([-1,1]) # will be either +1(right) or -1(left)
56     foil.setPos([-5*targetSide, 0])
57     target.setPos([5*targetSide, 0]) # in other location
```

Then set the orientation of the foil to be the reference orientation plus `thisIncrement`, draw all the stimuli (including the fixation point) and update the window.

```
59     # set orientation of probe
60     foil.setOri(expInfo['refOrientation'] + thisIncrement)
61
62     # draw all stimuli
63     foil.draw()
64     target.draw()
65     fixation.draw()
66     win.flip()
```

Wait for presentation time of 500ms and then blank the screen (by updating the screen after drawing just the fixation point).

```
68     # wait 500ms; but use a loop of x frames for more accurate timing
69     core.wait(0.5)
```

(This is not the most precise way to time your stimuli - you'll probably overshoot by one frame - but its easy to understand. PsychoPy allows you to present a stimulus for acertain number of screen refreshes instead which is better for short stimuli.)

## Get input from the subject

Still within the for-loop (note the level of indentation is the same) we need to get the response from the subject. The method works by starting off assuming that there hasn't yet been a response and then waiting for a key press. For each key pressed we check if the answer was correct or incorrect and assign the response appropriately, which ends the trial. We always have to clear the event buffer if we're checking for key presses like this

```
75     # get response
76     thisResp=None
77     while thisResp==None:
78         allKeys=event.waitKeys()
79         for thisKey in allKeys:
80             if thisKey=='left':
81                 if targetSide== -1: thisResp = 1 # correct
82                 else: thisResp = -1 # incorrect
83             elif thisKey=='right':
84                 if targetSide== 1: thisResp = 1 # correct
85                 else: thisResp = -1 # incorrect
86             elif thisKey in ['q', 'escape']:
```

(continues on next page)

(continued from previous page)

```
87         core.quit() # abort experiment
88         event.clearEvents() # clear other (eg mouse) events - they clog the buffer
```

Now we must tell the staircase the result of this trial with its `addData()` method. Then it can work out whether the next trial is an increment or decrement. Also, on each trial (so still within the for-loop) we may as well save the data as a line of text in that .csv file we created earlier.

```
90         # add the data to the staircase so it can calculate the next level
91         staircase.addData(thisResp)
92         dataFile.write('%i,%.3f,%i\n' % (targetSide, thisIncrement, thisResp))
93         core.wait(1)
```

## Output your data and clean up

OK! We're basically done! We've reached the end of the for-loop (which occurred because the staircase terminated) which means the trials are over. The next step is to close the text data file and also save the staircase as a binary file (by 'pickling' the file in Python speak) which maintains a lot more info than we were saving in the text file.

```
95 # staircase has ended
96 dataFile.close()
97 staircase.saveAsPickle(fileName) # special python binary file to save all the info
```

While we're here, it's quite nice to give some immediate feedback to the user. Let's tell them the intensity values at the all the reversals and give them the mean of the last 6. This is an easy way to get an estimate of the threshold, but we might be able to do a better job by trying to reconstruct the psychometric function. To give that a try see the staircase analysis script of *Tutorial 3*.

Having saved the data you can give your participant some feedback and quit!

```
99 # give some output to user in the command line in the output window
100 print('reversals:')
101 print(staircase.reversalIntensities)
102 approxThreshold = numpy.average(staircase.reversalIntensities[-6:])
103 print('mean of final 6 reversals = %.3f' % (approxThreshold))
104
105 # give some on-screen feedback
106 feedback1 = visual.TextStim(
107     win, pos=[0,+3],
108     text='mean of final 6 reversals = %.3f' % (approxThreshold))
109
110 feedback1.draw()
111 fixation.draw()
112 win.flip()
113 event.waitKeys() # wait for participant to respond
114
115 win.close()
116 core.quit()
```

## 6.2.3 Tutorial 3: Analysing data in Python

You could simply output your data as tab- or comma-separated text files and analyse the data in some spreadsheet package. But the `matplotlib` library in Python also allows for very neat and simple creation of publication-quality plots.

This script shows you how to use a couple of functions from PsychoPy to open some data files (*psychopy.gui.fileOpenDlg()*) and create a psychometric function out of some staircase data (*psychopy.data.functionFromStaircase()*).

Matplotlib is then used to plot the data.

---

**Note:** **Matplotlib** and **pylab**. Matplotlib is a python library that has similar command syntax to most of the plotting functions in Matlab(tm). It can be imported in different ways; the `import pylab` line at the beginning of the script is the way to import matplotlib as well as a variety of other scientific tools (that aren't strictly to do with plotting *per se*).

---

```
1  from __future__ import print_function
2
3  #This analysis script takes one or more staircase datafiles as input
4  #from a GUI. It then plots the staircases on top of each other on
5  #the left and a combined psychometric function from the same data
6  #on the right
7
8  from psychopy import data, gui, core
9  from psychopy.tools.filetools import fromFile
10 import pylab
11
12 #Open a dialog box to select files from
13 files = gui.fileOpenDlg('.')
14 if not files:
15     core.quit()
16
17 #get the data from all the files
18 allIntensities, allResponses = [],[]
19 for thisFileName in files:
20     thisDat = fromFile(thisFileName)
21     allIntensities.append( thisDat.intensities )
22     allResponses.append( thisDat.data )
23
24 #plot each staircase
25 pylab.subplot(121)
26 colors = 'brgkcmbrgkcm'
27 lines, names = [],[]
28 for fileN, thisStair in enumerate(allIntensities):
29     #lines.extend(pylab.plot(thisStair))
30     #names = files[fileN]
31     pylab.plot(thisStair, label=files[fileN])
32 #pylab.legend()
33
34 #get combined data
35 combinedInten, combinedResp, combinedN = \
36     data.functionFromStaircase(allIntensities, allResponses, 5)
37 #fit curve - in this case using a Weibull function
38 fit = data.FitWeibull(combinedInten, combinedResp, guess=[0.2, 0.5])
39 smoothInt = pylab.arange(min(combinedInten), max(combinedInten), 0.001)
40 smoothResp = fit.eval(smoothInt)
41 thresh = fit.inverse(0.8)
42 print(thresh)
43
44 #plot curve
45 pylab.subplot(122)
```

(continues on next page)



(continued from previous page)

```

46 pylab.plot(smoothInt, smoothResp, '-')
47 pylab.plot([thresh, thresh], [0, 0.8], '--'); pylab.plot([0, thresh], \
48 [0.8, 0.8], '--')
49 pylab.title('threshold = %0.3f' % (thresh))
50 #plot points
51 pylab.plot(combinedInten, combinedResp, 'o')
52 pylab.ylim([0, 1])
53
54 pylab.show()

```



## RUNNING STUDIES ONLINE


In 2016 we wrote a proof-of-principle that PsychoPy could generate studies for online use. In January 2018 we began a [Wellcome Trust](#) grant to develop it fully. This is what we call PsychoPy3 - the 3rd major phase of PsychoPy's development.

The key steps to this are basically to:

- export your experiment to JavaScript, ready to run online
- upload it to Pavlovia.org to be launched
- distribute the web address (URL) needed to run the study

Information on how to carry out those steps is below, as well as technical information regarding the precision, about how the project actually works, and about the status of the work.

### *So you want to run an online experiment?*



## 7.1 Creating an account on Pavlovia

To create and log in to your account on [Pavlovia](#), you will need an active internet connection. If you have not created your account, you can either 1) go to [Pavlovia](#) and create your account, or 2) click the login button highlighted in Figure 1, and create an account through the dialog box. Once you have an account on [Pavlovia](#), check to see that you are logged in via Builder by clicking button (4) highlighted below, in Figure 1.




Figure 1. PsychoPy 3 Builder icons for building and running online studies

## 7.2 Creating projects and uploading to Pavlovia.org

Creating your project repository is your first step to running your experiment from [Pavlovia](#). To create your project, first make sure that you have an internet connection and are logged in to [Pavlovia](#). Once you are logged in create your project repository by syncing your project with the server using button (1) in Figure 1.

A dialog box will appear, informing you that your .psyexp file does not belong to an existing project. Click “Create a project” if you wish to create a project, or click “Cancel” if you wish to return to your experiment in Builder. See Figure 2.




Figure 2. The dialog that appears when an online project does not exist.

If you clicked the “Create a project” button, another window will appear. This window is designed to collect important metadata about your project, see Figure 3 below.

Figure 3. Dialog for creating your project on Pavlovia.org

Use this window to add information to store your project on Pavlovia:

**Name:** This is the name of your project on Pavlovia

**Group/Owner:** The user or group to upload the project

A screenshot of a software dialog box for creating a project. The dialog has a title bar with a close button (X) in the top right corner. The main area contains several input fields and buttons. At the top, there is a 'Name:' label followed by a text input field. Below it is a 'Group/owner:' label followed by a dropdown menu. The next field is 'Local folder:' with a text input showing 'C:\Users\' and a 'Browse...' button to its right. Below that is a 'Description:' label followed by a large text area. At the bottom left, there is a 'Tags (comma separated):' label followed by a text input containing 'PsychoPy, Builder, Coder, Stroop'. Below the tags is a 'Public:' label followed by an unchecked checkbox. At the bottom right, there are two buttons: 'Create project on Pavlovia' and 'Cancel'.

Name:

Group/owner:

Local folder:

Description:

Tags (comma separated):

Public: ☐

**Local folder:** The (local) project path on your computer. Use the Browse button to find your local directory, if required.

**Description:** Describe your experiment – similar to the readme files used for describing PsychoPy experiments.

**Tags (comma separated):** The tag will be used to filter and search for experiments by key words.

**Public:** Tick this box if you would like to make your repository public, for anyone to see.

When you have completed all fields in the Project window, click “Create project on Pavlovia” button to push your experiment up to the online repository. Click “Cancel” if you wish to return to your experiment in Builder.

## 7.3 Viewing your experiment on Pavlovia.org

After you have uploaded your project to Pavlovia via Builder, you can go and have a look at your project online. To view your project, go to [www.pavlovia.org](https://www.pavlovia.org). From the Pavlovia home page, you can explore your own existing projects, or other users public projects that have been made available to all users. To find your study, click the Explore tab on the home page (see Figure 4)




Figure 4. The Pavlovia home page

When exploring studies online, you are presented with a series of thumbnail images for all of the projects on Pavlovia. See Figure 5.




Figure 5. Exploring projects on Pavlovia

From the “Explore” page, you can filter projects by setting the filter buttons to a) Public or Private, B) Active or Inactive, and C) sort by number of forks, name, date and number of stars. The default sorting method is Stars. You can also search for projects using the search tool using key words describing your area of interest, e.g., Stroop, or attention.

When you have found your project, you have several options (see Figure 6).

- 1) Run your task from the Pavlovia server
- 2) Activate or deactivate your experiment
- 3) view your project code and resources on the Pavlovia repository via Gitlab repository.




Figure 6. Projects on Pavlovia

## 7.4 Running your experiment on Pavlovia.org from Builder

If you wish to run your experiment online, in a web-browser, you have two options. You can run your experiment directly from pavlovia.org, as described above, or you can run your experiment directly from Builder. (There is also the option to send your experiment URL – more on that later in Recruitment Pools).


To run your experiment on Pavlovia via Builder, you must first ensure you have a valid internet connection, are logged in, and have created a repository for your project on Pavlovia. Once you have completed these steps, simply click button (2) in the Builder frame, as shown in Figure 1 above.

## 7.5 Searching for experiments from Builder

If you wish to search for your own existing projects on Pavlovia, or other users public projects, you can do this via the Builder interface. To search for a project, click button (3) on the Builder Frame in Figure 1. Following this, a search dialog will appear, see Figure 7. The search dialog presents several options that allow users to search, fork and synchronize projects.

Figure 7. The search dialog in Builder





**To search for a project** (see Fig 7, Box A), type in search terms in the text box and click the “Search” button to find related projects on Pavlovia. Use the search filters (e.g., “My group”, “Public” etc) above the text box to filter the search output. The output of your search will be listed in the search panel below the search button, where you can select your project of interest.

**To fork and sync a project** is to take your own copy of a project from [Pavlovia](#) (*fork*) and copy a version to your local desktop or laptop computer (*sync*). To fork a project, select the local folder to download the project using the “Browse” button, and then click “Sync” when you are ready - (see Fig 7, Box B). You should now have a local copy of the project from [Pavlovia](#) ready to run in PsychoPy!

Now you can run your synced project online from [Pavlovia](#)!

Contents:

**maxdepth 1**

fromBuilder

**maxdepth 1**

**status** tech psychojsCode cautions

## REFERENCE MANUAL (API)

Contents:

### 8.1 `psychopy.core` - basic functions (clocks etc.)

Basic functions, including timing, `rush` (imported), `quit`

`psychopy.core.getTime()`

Get the current time since `psychopy.core` was loaded.

Version Notes: Note that prior to PsychoPy 1.77.00 the behaviour of `getTime()` was platform dependent (on OSX and linux it was equivalent to `psychopy.core.getAbsTime()` whereas on windows it returned time since loading of the module, as now)

`psychopy.core.getAbsTime()`

Return unix time (i.e., whole seconds elapsed since Jan 1, 1970).

This uses the same clock-base as the other timing features, like `getTime()`. The time (in seconds) ignores the time-zone (like `time.time()` on linux). To take the timezone into account, use `int(time.mktime(time.gmtime()))`.

Absolute times in seconds are especially useful to add to generated file names for being unique, informative (= a meaningful time stamp), and because the resulting files will always sort as expected when sorted in chronological, alphabetical, or numerical order, regardless of locale and so on.

Version Notes: This method was added in PsychoPy 1.77.00

`psychopy.core.wait(secs, hogCPUperiod=0.2)`

Wait for a given time period.

If `secs=10` and `hogCPU=0.2` then for 9.8s python's `time.sleep` function will be used, which is not especially precise, but allows the cpu to perform housekeeping. In the final `hogCPUperiod` the more precise method of constantly polling the clock is used for greater precision.

If you want to obtain key-presses during the wait, be sure to use `pyglet` and to `hogCPU` for the entire time, and then call `psychopy.event.getKeys()` after calling `wait()`

If you want to suppress checking for `pyglet` events during the wait, do this once:

```
core.checkPygletDuringWait = False
```

and from then on you can do:

```
core.wait(sec)
```

This will preserve terminal-window focus during command line usage.

### **class** psychopy.core.Clock

A convenient class to keep track of time in your experiments. You can have as many independent clocks as you like (e.g. one to time responses, one to keep track of stimuli...)

This clock is identical to the *MonotonicClock* except that it can also be reset to 0 or another value at any point.

#### **add** (t)

Add more time to the clock's 'start' time (t0).

Note that, by adding time to t0, you make the current time appear less. Can have the effect that getTime() returns a negative number that will gradually count back up to zero.

e.g.:

```
timer = core.Clock()
timer.add(5)
while timer.getTime() < 0:
    # do something
```

#### **reset** (newT=0.0)

Reset the time on the clock. With no args time will be set to zero. If a float is received this will be the new time on the clock

### **class** psychopy.core.CountdownTimer (start=0)

Similar to a *Clock* except that time counts down from the time of last reset

Typical usage:

```
timer = core.CountdownTimer(5)
while timer.getTime() > 0: # after 5s will become negative
    # do stuff
```

#### **getTime** ()

Returns the current time left on this timer in secs (sub-ms precision)

#### **reset** (t=None)

Reset the time on the clock. With no args time will be set to zero. If a float is received this will be the new time on the clock

### **class** psychopy.core.MonotonicClock (start\_time=None)

A convenient class to keep track of time in your experiments using a sub-millisecond timer.

Unlike the *Clock* this cannot be reset to arbitrary times. For this clock t=0 always represents the time that the clock was created.

Don't confuse this *class* with *core.monotonicClock* which is an *instance* of it that got created when PsychoPy.core was imported. That clock instance is deliberately designed always to return the time since the start of the study.

Version Notes: This class was added in PsychoPy 1.77.00

#### **getLastResetTime** ()

Returns the current offset being applied to the high resolution timebase used by Clock.

#### **getTime** ()

Returns the current time on this clock in secs (sub-ms precision)

### **class** psychopy.core.StaticPeriod (screenHz=None, win=None, name='StaticPeriod')

A class to help insert a timing period that includes code to be run.

Typical usage:

```
fixation.draw()
win.flip()
ISI = StaticPeriod(screenHz=60)
ISI.start(0.5) # start a period of 0.5s
stim.image = 'largeFile.bmp' # could take some time
ISI.complete() # finish the 0.5s, taking into account one 60Hz frame

stim.draw()
win.flip() # the period takes into account the next frame flip
# time should now be at exactly 0.5s later than when ISI.start()
# was called
```

### Parameters

- **screenHz** – the frame rate of the monitor (leave as None if you don't want this accounted for)
- **win** – if a visual.Window is given then StaticPeriod will also pause/restart frame interval recording
- **name** – give this StaticPeriod a name for more informative logging messages

### complete()

Completes the period, using up whatever time is remaining with a call to wait()

**Returns** 1 for success, 0 for fail (the period overran)

### start(duration)

Start the period. If this is called a second time, the timer will be reset and starts again

**Parameters** **duration** – The duration of the period, in seconds.

## 8.2 psychopy.visual - many visual stimuli

*Window* to display all stimuli below.

### 8.2.1 Aperture

**class** psychopy.visual.**Aperture** (*win, size=1, pos=(0, 0), ori=0, nVert=120, shape='circle', inverted=False, units=None, name=None, autoLog=None*)

Restrict a stimulus visibility area to a basic shape or list of vertices.

When enabled, any drawing commands will only operate on pixels within the Aperture. Once disabled, subsequent draw operations affect the whole screen as usual.

If shape is 'square' or 'triangle' then that is what will be used If shape is 'circle' or *None* then a polygon with nVerts will be used

(120 for a rough circle)

**If shape is a list or numpy array (Nx2) then it will be used directly** as the vertices to a *ShapeStim*

**If shape is a filename then it will be used to load and image as a *ImageStim*.** Note that transparent parts in the image (e.g. in a PNG file) will not be included in the mask shape. The color of the image will be ignored.

See demos/stimuli/aperture.py for example usage

**Author** 2011, Yuri Spitsyn 2011, Jon Peirce added units options,

Jeremy Gray added shape & orientation

2014, Jeremy Gray added .contains() option 2015, Thomas Emmerling added ImageStim option

**mro** () → list

return a type's method resolution order

## 8.2.2 BufferImageStim

### Attributes

<i>BufferImageStim</i> (win[, buffer, rect, ...])	Take a “screen-shot”, save as an ImageStim (RGBA object).
<i>BufferImageStim.win</i>	The <i>Window</i> object in which the
<i>BufferImageStim.buffer</i>	
<i>BufferImageStim.rect</i>	
<i>BufferImageStim.stim</i>	
<i>BufferImageStim.mask</i>	The alpha mask that can be used to control the outer shape of the stimulus
<i>BufferImageStim.units</i>	None, ‘norm’, ‘cm’, ‘deg’, ‘degFlat’, ‘degFlatPos’, or ‘pix’
<i>BufferImageStim.pos</i>	The position of the center of the stimulus in the stimulus <i>units</i>
<i>BufferImageStim.ori</i>	The orientation of the stimulus (in degrees).
<i>BufferImageStim.size</i>	The size (width, height) of the stimulus in the stimulus <i>units</i>
<i>BufferImageStim.contrast</i>	A value that is simply multiplied by the color
<i>BufferImageStim.color</i>	Color of the stimulus
<i>BufferImageStim.colorSpace</i>	The name of the color space currently being used
<i>BufferImageStim.opacity</i>	Determines how visible the stimulus is relative to background
<i>BufferImageStim.interpolate</i>	Whether to interpolate (linearly) the texture in the stimulus
<i>BufferImageStim.name</i>	String or None.
<i>BufferImageStim.autoLog</i>	Whether every change in this stimulus should be auto logged.
<i>BufferImageStim.draw</i> ([win])	Draws the BufferImage on the screen, similar to <i>ImageStim.draw</i> ().
<i>BufferImageStim.autoDraw</i>	Determines whether the stimulus should be automatically drawn on every frame flip.

### Details

```
class psychopy.visual.BufferImageStim(win, buffer='back', rect=(-1, 1, 1, -1),
sqPower2=False, stim=(), interpolate=True,
flipHoriz=False, flipVert=False, mask='None',
pos=(0, 0), name=None, autoLog=None)
```

Take a “screen-shot”, save as an ImageStim (RGBA object).

The screen-shot is a single collage image composed of static elements that you can treat as being a single

stimulus. The screen-shot can be of the visible screen (front buffer) or hidden (back buffer).

BufferImageStim aims to provide fast rendering, while still allowing dynamic orientation, position, and opacity. It's fast to draw but slower to init (same as an ImageStim).

You specify the part of the screen to capture (in norm units), and optionally the stimuli themselves (as a list of items to be drawn). You get a screenshot of those pixels. If your OpenGL does not support arbitrary sizes, the image will be larger, using square powers of two if needed, with the excess image being invisible (using alpha). The aim is to preserve the buffer contents as rendered.

Checks for OpenGL 2.1+, or uses square-power-of-2 images.

#### Example:

```
# define lots of stimuli, make a list:
mySimpleImageStim = ...
myTextStim = ...
stimList = [mySimpleImageStim, myTextStim]

# draw stim list items & capture (slow; see EXP log for times):
screenshot = visual.BufferImageStim(myWin, stim=stimList)

# render to screen (very fast, except for the first draw):
while <conditions>:
    screenshot.draw() # fast; can vary .ori, .pos, .opacity
    other_stuff.draw() # dynamic
    myWin.flip()
```

See coder Demos > stimuli > bufferImageStim.py for a demo, with timing stats.

#### Author

- 2010 Jeremy Gray, with on-going fixes

#### Parameters

**buffer** : the screen buffer to capture from, default is 'back' (hidden). 'front' is the buffer in view after win.flip()

**rect** : a list of edges [left, top, right, bottom] defining a screen rectangle which is the area to capture from the screen, given in norm units. default is fullscreen: [-1, 1, 1, -1]

**stim** : a list of item(s) to be drawn to the back buffer (in order). The back buffer is first cleared (without the win being flip(ed)), then stim items are drawn, and finally the buffer (or part of it) is captured. Each item needs to have its own .draw() method, and have the same window as win.

**interpolate** : whether to use interpolation (default = True, generally good, especially if you change the orientation)

#### sqPower2 :

- False (default) = use rect for size if OpenGL = 2.1+
- True = use square, power-of-two image sizes

**flipHoriz** : horizontally flip (mirror) the captured image, default = False

**flipVert** : vertically flip (mirror) the captured image; default = False

#### `_calcPosRendered()`

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

**\_calcSizeRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`

**\_createTexture** (*tex, id, pixFormat, stim, res=128, maskParams=None, forcePOW2=True, dataType=None, wrapping=True*)

**Params**

**id:** is the texture ID

**pixFormat:** GL.GL\_ALPHA, GL.GL\_RGB

**useShaders:** bool

**interpolate:** bool (determines whether texture will use GL\_LINEAR or GL\_NEAREST)

**res:** the resolution of the texture (unless a bitmap image is used)

**dataType:** None, GL.GL\_UNSIGNED\_BYTE, GL\_FLOAT. Only affects image files (numpy arrays will be float)

For grating stimuli (anything that needs multiple cycles) `forcePOW2` should be set to be `True`. Otherwise the wrapping of the texture will not work.

**\_getDesiredRGB** (*rgb, colorSpace, contrast*)

Convert color to RGB while adding contrast. Requires `self.rgb`, `self.colorSpace` and `self.contrast`

**\_getPolyAsRendered()**

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow** (*win*)

Switch drawing to the specified window. Calls the window's `_setCurrent()` method which handles the switch.

**\_set** (*attrib, val, op="", log=None*)

DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

**\_updateList()**

The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

**\_updateListNoShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command.

**\_updateListShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**\_updateVertices()**

Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

**autoDraw**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**autoLog**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every



frame) and you want to avoid swamping the log file with messages that aren't likely to be useful.

#### **clearTextures ()**

Clear all textures associated with the stimulus.

As of v1.61.00 this is called automatically during garbage collection of your stimulus, so doesn't need calling explicitly by the user.

#### **color**

Color of the stimulus

**Value should be one of:**

- string: to specify a *Colors by name*. Any of the standard html/X11 *color names* <[http://www.w3schools.com/html/html\\_colornames.asp](http://www.w3schools.com/html/html_colornames.asp)> can be used.
- *Colors by hex value*
- **numerically: (scalar or triplet) for DKL, RGB or other *Color spaces***. For these, *operations* are supported.

When color is specified using numbers, it is interpreted with respect to the stimulus' current colorSpace. If color is given as a single value (scalar) then this will be applied to all 3 channels.

**Examples::** # ... for whatever stim you have: stim.color = 'white' stim.color = 'RoyalBlue' # (the case is actually ignored) stim.color = '#DDA0DD' # DDA0DD is hexadecimal for plum stim.color = [1.0, -1.0, -1.0] # if stim.colorSpace='rgb':

# a red color in rgb space

**stim.color = [0.0, 45.0, 1.0] # if stim.colorSpace='dkl':** # DKL space with elev=0, azimuth=45

**stim.color = [0, 0, 255] # if stim.colorSpace='rgb255':** # a blue stimulus using rgb255 space

**stim.color = 255 # interpreted as (255, 255, 255)** # which is white in rgb255.

*Operations* work as normal for all numeric colorSpaces (e.g. 'rgb', 'hsv' and 'rgb255') but not for strings, like named and hex. For example, assuming that colorSpace='rgb':

```
stim.color += [1, 1, 1] # increment all guns by 1 value
stim.color *= -1 # multiply the color by -1 (which in this
                 # space inverts the contrast)
stim.color *= [0.5, 0, 1] # decrease red, remove green, keep blue
```

You can use *setColor* if you want to set color and colorSpace in one line. These two are equivalent:

```
stim.setColor((0, 128, 255), 'rgb255')
# ... is equivalent to
stim.colorSpace = 'rgb255'
stim.color = (0, 128, 255)
```

#### **colorSpace**

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default colorSpace for the stimulus is used (defined during initialisation).

Please note that changing colorSpace does not change stimulus parameters. Thus you usually want to specify colorSpace before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                       color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'

# Make it light green again
stim.color = (128, 255, 128)
```

**contains** (*x, y=None, units=None*)

Returns True if a point x,y is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a `getPos()` method that returns x,y, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (*pos*), and orientation (*ori*) settings (and by the vertices for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

**contrast**

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

**depth**

DEPRECATED. Depth is now controlled simply by drawing order.

**draw** (*win=None*)

Draws the *BufferImage* on the screen, similar to *ImageStim.draw()*. Allows dynamic position, size, rotation, mirroring, and opacity. Limitations / bugs: not sure what happens with shaders and `self._updateList()`

#### **flipHoriz**

If set to True then the image will be flipped horizontally (left-to-right). Note that this is relative to the original image, not relative to the current state.

#### **flipVert**

If set to True then the image will be flipped vertically (left-to-right). Note that this is relative to the original image, not relative to the current state.

#### **image**

The image file to be presented (most formats supported).

#### **interpolate**

Whether to interpolate (linearly) the texture in the stimulus

If set to False then nearest neighbour will be used when needed, otherwise some form of interpolation will be used.

#### **mask**

The alpha mask that can be used to control the outer shape of the stimulus

- **None**, 'circle', 'gauss', 'raisedCos'
- or the name of an image file (most formats supported)
- or a numpy array (1xN or NxN) ranging -1:1

#### **maskParams**

Various types of input. Default to None.

This is used to pass additional parameters to the mask if those are needed.

- **For 'gauss' mask, pass dict {'sd': 5} to control** standard deviation.
- **For the 'raisedCos' mask, pass a dict: {'fringeWidth':0.2}**, where 'fringeWidth' is a parameter (float, 0-1), determining the proportion of the patch that will be blurred by the raised cosine edge.

#### **name**

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called "unnamed <type>", e.g. visual.TextStim(win) will be called "unnamed TextStim" in the logs.

#### **opacity**

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

#### **ori**

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

#### **overlaps** (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, `shapeContains.py`

## pos

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
    Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
    Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix posPix = posToPix(stim)
```

## setAutoDraw (value, log=None)

Sets `autoDraw`. Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method to suppress the log message.

## setAutoLog (value=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

## setColor (color, colorSpace=None, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message and/or set `colorSpace` simultaneously.

## setContrast (newContrast, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

## setDKL (newDKL, operation="")

DEPRECATED since v1.60.05: Please use the *color* attribute

## setDepth (newDepth, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

## setFlipHoriz (newVal=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

## setFlipVert (newVal=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

## setImage (value, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

## setLMS (newLMS, operation="")

DEPRECATED since v1.60.05: Please use the *color* attribute

**setMask** (*value*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setOpacity** (*newOpacity*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPos** (*newPos*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation=*”, *log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSize** (*newSize*, *operation=*”, *units=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setUseShaders** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**size**

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or None (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

**texRes**

Power-of-two int. Sets the resolution of the mask and texture. texRes is overridden if an array or image is provided as mask.

*Operations* supported.

**units**

None, ‘norm’, ‘cm’, ‘deg’, ‘degFlat’, ‘degFlatPos’, or ‘pix’

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don’t change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5))
```

(continues on next page)

(continued from previous page)

```
# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

### useShaders

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

### verticesPix

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

### win

The *Window* object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (win1, win2 and stim):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw()    # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw()    # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
                             # monitor update
win2.flip()    # wait for vertical blanking.
```

Note that this just changes *default* window *for* stimulus.  
You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

## 8.2.3 Circle

**class** psychopy.visual.Circle (win, radius=0.5, edges=32, *\*\*kwargs*)

Creates a Circle with a given radius as a special case of a *ShapeStim*

(New in version 1.72.00)

Circle accepts all input parameters that *~psychopy.visual.ShapeStim* accept, except for vertices and closeShape.

**mro** () → list

return a type's method resolution order

## 8.2.4 CustomMouse

**class** psychopy.visual.CustomMouse (win, newPos=None, visible=True, leftLimit=None, topLimit=None, rightLimit=None, bottomLimit=None, showLimitBox=False, clickOnUp=False, pointer=None, name=None, autoLog=None)

Class for more control over the mouse, including the pointer graphic and bounding box.

Seems to work with pyglet or pygame. Not completely tested.

Known limitations: - only norm units are working - getRel() always returns [0,0] - mouseMoved() is always False; maybe due to

```
self.mouse.visible == False -> held at [0,0]
```

- no idea if clickReset() works

Author: Jeremy Gray, 2011

Class for customizing the appearance and behavior of the mouse.

Use a custom mouse for extra control over the pointer appearance and function. It's probably slower to render than the regular system mouse. Create your *visual.Window* before creating a CustomMouse.

#### Parameters

**win** [required, *visual.Window*] the window to which this mouse is attached

**visible** [**True** or False] makes the mouse invisible if necessary

**newPos** [**None** or [x,y]] gives the mouse a particular starting position

**leftLimit** : left edge of a virtual box within which the mouse can move

**topLimit** : top edge of virtual box

**rightLimit** : right edge of virtual box

**bottomLimit** : lower edge of virtual box

**showLimitBox** [default is False] display the boundary within which the mouse can move.

**pointer** : The visual display item to use as the pointer; must have .draw() and setPos() methods. If your item has .setOpacity(), you can alter the mouse's opacity.

**clickOnUp** [when to count a mouse click as having occurred] default is False, record a click when the mouse is first pressed down. True means record a click when the mouse button is released.

**Note** CustomMouse is a new feature, and subject to change. *setPos()* does not work yet. *getRel()* returns [0,0] and *mouseMoved()* always returns False. *clickReset()* may not be working.

**mro** () → list  
return a type's method resolution order

## 8.2.5 DotStim

```
class psychopy.visual.DotStim(win, units='', nDots=1, coherence=0.5, fieldPos=(0.0, 0.0),
                               fieldSize=(1.0, 1.0), fieldShape='sqr', dotSize=2.0, dotLife=3,
                               dir=0.0, speed=0.5, rgb=None, color=(1.0, 1.0, 1.0), colorSpace='rgb',
                               opacity=1.0, contrast=1.0, depth=0, element=None, signalDots='same',
                               noiseDots='direction', name=None, autoLog=None)
```

This stimulus class defines a field of dots with an update rule that determines how they change on every call to the .draw() method.

This single class can be used to generate a wide variety of dot motion types. For a review of possible types and their pros and cons see Scase, Braddick & Raymond (1996). All six possible motions they describe can be generated with appropriate choices of the signalDots (which determines whether signal dots are the 'same' or 'different' on each frame), noiseDots (which determines the locations of the noise dots on each frame) and the dotLife (which determines for how many frames the dot will continue before being regenerated).

The default settings (as of v1.70.00) is for the noise dots to have identical velocity but random direction and signal dots remain the ‘same’ (once a signal dot, always a signal dot).

For further detail about the different configurations see [Dots \(RDK\) Component](#) in the Builder Components section of the documentation.

If further customisation is required, then the DotStim should be subclassed and its `_update_dotsXY` and `_newDotsXY` methods overridden.

#### Parameters

**fieldSize** [(x,y) or [x,y] or single value (applied to both] dimensions). Sizes can be negative and can extend beyond the window.

**mro** () → list  
return a type’s method resolution order

### 8.2.6 ElementArrayStim

```
class psychopy.visual.ElementArrayStim(win, units=None, fieldPos=(0.0, 0.0), fieldSize=(1.0, 1.0), fieldShape='circle', nElements=100, sizes=2.0, xys=None, rgbs=None, colors=(1.0, 1.0, 1.0), colorSpace='rgb', opacities=1.0, depths=0, fieldDepth=0, oris=0, sfs=1.0, contrs=1, phases=0, elementTex='sin', elementMask='gauss', texRes=48, interpolate=True, name=None, autoLog=None, maskParams=None)
```

This stimulus class defines a field of elements whose behaviour can be independently controlled. Suitable for creating ‘global form’ stimuli or more detailed random dot stimuli.

This stimulus can draw thousands of elements without dropping a frame, but in order to achieve this performance, uses several OpenGL extensions only available on modern graphics cards (supporting OpenGL2.0). See the ElementArray demo.

#### Parameters

**win** : a [Window](#) object (required)

**units** [None, ‘height’, ‘norm’, ‘cm’, ‘deg’ or ‘pix’] If None then the current units of the [Window](#) will be used. See [Units for the window and stimuli](#) for explanation of other options.

**nElements** : number of elements in the array.

**mro** () → list  
return a type’s method resolution order

### 8.2.7 GratingStim

#### Attributes

<code>GratingStim(win[, tex, mask, units, pos, ...])</code>	Stimulus object for drawing arbitrary bitmaps that can repeat (cycle) in either dimension.
<code>GratingStim.win</code>	The <a href="#">Window</a> object in which the
<code>GratingStim.tex</code>	Texture to used on the stimulus as a grating (aka carrier)
<code>GratingStim.mask</code>	The alpha mask (forming the shape of the image)

Continued on next page



Table 2 – continued from previous page

<code>GratingStim.units</code>	None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'
<code>GratingStim.sf</code>	Spatial frequency of the grating texture
<code>GratingStim.pos</code>	The position of the center of the stimulus in the stimulus <i>units</i>
<code>GratingStim.ori</code>	The orientation of the stimulus (in degrees).
<code>GratingStim.size</code>	The size (width, height) of the stimulus in the stimulus <i>units</i>
<code>GratingStim.contrast</code>	A value that is simply multiplied by the color
<code>GratingStim.color</code>	Color of the stimulus
<code>GratingStim.colorSpace</code>	The name of the color space currently being used
<code>GratingStim.opacity</code>	Determines how visible the stimulus is relative to background
<code>GratingStim.interpolate</code>	Whether to interpolate (linearly) the texture in the stimulus
<code>GratingStim.texRes</code>	Power-of-two int.
<code>GratingStim.name</code>	String or None.
<code>GratingStim.autoLog</code>	Whether every change in this stimulus should be auto logged.
<code>GratingStim.draw([win])</code>	Draw the stimulus in its relevant window.
<code>GratingStim.autoDraw</code>	Determines whether the stimulus should be automatically drawn on every frame flip.

## Details

```
class psychopy.visual.GratingStim(win, tex='sin', mask='none', units="", pos=(0.0,
0.0), size=None, sf=None, ori=0.0, phase=(0.0, 0.0),
texRes=128, rgb=None, dkl=None, lms=None, color=(1.0,
1.0, 1.0), colorSpace='rgb', contrast=1.0, opacity=1.0,
depth=0, rgbPedestal=(0.0, 0.0, 0.0), interpolate=False,
blendmode='avg', name=None, autoLog=None, auto-
Draw=False, maskParams=None)
```

Stimulus object for drawing arbitrary bitmaps that can repeat (cycle) in either dimension.

One of the main stimuli for PsychoPy.

Formally GratingStim is just a texture behind an optional transparency mask (an 'alpha mask'). Both the texture and mask can be arbitrary bitmaps and their combination allows an enormous variety of stimuli to be drawn in realtime.

### Examples:

```
myGrat = GratingStim(tex='sin', mask='circle') # circular grating
myGabor = GratingStim(tex='sin', mask='gauss') # gives a 'Gabor'
```

A GratingStim can be rotated scaled and shifted in position, its texture can be drifted in X and/or Y and it can have a spatial frequency in X and/or Y (for an image file that simply draws multiple copies in the patch).

Also since transparency can be controlled two GratingStims can combine e.g. to form a plaid.

### Using GratingStim with images from disk (jpg, tif, png, ...)

Ideally texture images to be rendered should be square with 'power-of-2' dimensions e.g. 16 x 16, 128 x 128. Any image that is not will be upsampled (with linear interpolation) to the nearest such texture by PsychoPy. The size of the stimulus should be specified in the normal way using the appropriate units (deg, pix, cm, ...). Be sure to get the aspect ratio the same as the image (if you don't want it stretched!).

**\_calcPosRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

**\_calcSizeRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`

**\_createTexture** (*tex, id, pixFormat, stim, res=128, maskParams=None, forcePOW2=True, dataType=None, wrapping=True*)

**Params**

**id:** is the texture ID

**pixFormat:** GL.GL\_ALPHA, GL.GL\_RGB

**useShaders:** bool

**interpolate:** bool (determines whether texture will use GL\_LINEAR or GL\_NEAREST

**res:** the resolution of the texture (unless a bitmap image is used)

**dataType:** None, GL.GL\_UNSIGNED\_BYTE, GL\_FLOAT. Only affects image files (numpy arrays will be float)

For grating stimuli (anything that needs multiple cycles) forcePOW2 should be set to be True. Otherwise the wrapping of the texture will not work.

**\_getDesiredRGB** (*rgb, colorSpace, contrast*)

Convert color to RGB while adding contrast. Requires `self.rgb`, `self.colorSpace` and `self.contrast`

**\_getPolyAsRendered()**

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow** (*win*)

Switch drawing to the specified window. Calls the window's `_setCurrent()` method which handles the switch.

**\_set** (*attrib, val, op="", log=None*)

DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

**\_updateList()**

The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

**\_updateListNoShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**\_updateListShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**\_updateVertices()**

Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

**autoDraw**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**autoLog**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every

frame) and you want to avoid swamping the log file with messages that aren't likely to be useful.

#### **blendmode**

The OpenGL mode in which the stimulus is draw

Can be 'avg' or 'add'. Average (avg) places the new stimulus over the old one with a transparency given by its opacity. Opaque stimuli will hide other stimuli transparent stimuli won't. Add performs the arithmetic sum of the new stimulus and the ones already present.

#### **clearTextures ()**

Clear all textures associated with the stimulus.

As of v1.61.00 this is called automatically during garbage collection of your stimulus, so doesn't need calling explicitly by the user.

#### **color**

Color of the stimulus

**Value should be one of:**

- string: to specify a *Colors by name*. Any of the standard html/X11 *color names* <[http://www.w3schools.com/html/html\\_colornames.asp](http://www.w3schools.com/html/html_colornames.asp)> can be used.
- *Colors by hex value*
- **numerically: (scalar or triplet) for DKL, RGB or other *Color spaces***. For these, *operations* are supported.

When color is specified using numbers, it is interpreted with respect to the stimulus' current colorSpace. If color is given as a single value (scalar) then this will be applied to all 3 channels.

**Examples::** # ... for whatever stim you have: stim.color = 'white' stim.color = 'RoyalBlue' # (the case is actually ignored) stim.color = '#DDA0DD' # DDA0DD is hexadecimal for plum stim.color = [1.0, -1.0, -1.0] # if stim.colorSpace='rgb':

# a red color in rgb space

**stim.color = [0.0, 45.0, 1.0] # if stim.colorSpace='dkl':** # DKL space with elev=0, azimuth=45

**stim.color = [0, 0, 255] # if stim.colorSpace='rgb255':** # a blue stimulus using rgb255 space

**stim.color = 255 # interpreted as (255, 255, 255)** # which is white in rgb255.

*Operations* work as normal for all numeric colorSpaces (e.g. 'rgb', 'hsv' and 'rgb255') but not for strings, like named and hex. For example, assuming that colorSpace='rgb':

```
stim.color += [1, 1, 1] # increment all guns by 1 value
stim.color *= -1 # multiply the color by -1 (which in this
                 # space inverts the contrast)
stim.color *= [0.5, 0, 1] # decrease red, remove green, keep blue
```

You can use *setColor* if you want to set color and colorSpace in one line. These two are equivalent:

```
stim.setColor((0, 128, 255), 'rgb255')
# ... is equivalent to
stim.colorSpace = 'rgb255'
stim.color = (0, 128, 255)
```

### colorSpace

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default colorSpace for the stimulus is used (defined during initialisation).

Please note that changing colorSpace does not change stimulus parameters. Thus you usually want to specify colorSpace before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                       color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'

# Make it light green again
stim.color = (128, 255, 128)
```

### contains (x, y=None, units=None)

Returns True if a point x,y is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a getPos() method that returns x,y, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (pos), and orientation (ori) settings (and by the vertices for shape stimuli).

See Coder demos: shapeContains.py See Coder demos: shapeContains.py

### contrast

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

### depth

DEPRECATED. Depth is now controlled simply by drawing order.

### draw (win=None)

Draw the stimulus in its relevant window. You must call this method after every `MyWin.flip()` if you want the stimulus to appear on that frame and then update the screen again.

### interpolate

Whether to interpolate (linearly) the texture in the stimulus

If set to False then nearest neighbour will be used when needed, otherwise some form of interpolation will be used.

### mask

The alpha mask (forming the shape of the image)

**This can be one of various options:**

- 'circle', 'gauss', 'raisedCos', 'cross'
- **None** (resets to default)
- the name of an image file (most formats supported)
- a numpy array (1xN or NxN) ranging -1:1

### maskParams

Various types of input. Default to None.

This is used to pass additional parameters to the mask if those are needed.

- **For 'gauss' mask, pass dict {'sd': 5} to control** standard deviation.
- **For the 'raisedCos' mask, pass a dict: {'fringeWidth':0.2}**, where 'fringeWidth' is a parameter (float, 0-1), determining the proportion of the patch that will be blurred by the raised cosine edge.

### name

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called "unnamed <type>", e.g. `visual.TextStim(win)` will be called "unnamed TextStim" in the logs.

### opacity

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

### ori

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

### overlaps (polygon)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, `shapeContains.py`

### phase

Phase of the stimulus in each dimension of the texture.

Should be an *x,y-pair* or *scalar*

**NB** phase has modulus 1 (rather than 360 or  $2\pi$ ) This is a little unconventional but has the nice effect that setting `phase=t*n` drifts a stimulus at *n* Hz

### pos

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
# Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
# Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix
posPix = posToPix(stim)
```

### setAutoDraw (value, log=None)

Sets `autoDraw`. Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method to suppress the log message.

### setAutoLog (value=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

### setBlendmode (value, log=None)

DEPRECATED. Use ‘`stim.parameter = value`’ syntax instead

### setColor (color, colorSpace=None, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message and/or set `colorSpace` simultaneously.

### setContrast (newContrast, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

### setDKL (newDKL, operation="")

DEPRECATED since v1.60.05: Please use the *color* attribute

### setDepth (newDepth, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

### setLMS (newLMS, operation="")

DEPRECATED since v1.60.05: Please use the *color* attribute

**setMask** (*value*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setOpacity** (*newOpacity*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPhase** (*value*, *operation=*”, *log=None*)

DEPRECATED. Use ‘stim.parameter = value’ syntax instead

**setPos** (*newPos*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation=*”, *log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSF** (*value*, *operation=*”, *log=None*)

DEPRECATED. Use ‘stim.parameter = value’ syntax instead

**setSize** (*newSize*, *operation=*”, *units=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setTex** (*value*, *log=None*)

DEPRECATED. Use ‘stim.parameter = value’ syntax instead

**setUseShaders** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**sf**

Spatial frequency of the grating texture

Should be a *x,y-pair* or *scalar* or None. If *units* == ‘deg’ or ‘cm’ units are in cycles per deg or cm as appropriate.

If *units* == ‘norm’ then *sf* units are in cycles per stimulus (and so SF scales with stimulus size).

If texture is an image loaded from a file then *sf=None* defaults to 1/*stimSize* to give one cycle of the image.

**size**

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or None (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

#### **tex**

Texture to used on the stimulus as a grating (aka carrier)

**This can be one of various options:**

- **'sin'**, **'sqr'**, **'saw'**, **'tri'**, **None** (resets to default)
- the name of an image file (most formats supported)
- a numpy array (1xN or NxN) ranging -1:1

If specifying your own texture using an image or numpy array you should ensure that the image has square power-of-two dimesnions (e.g. 256 x 256). If not then PsychoPy will upsample your stimulus to the next larger power of two.

#### **texRes**

Power-of-two int. Sets the resolution of the mask and texture. *texRes* is overridden if an array or image is provided as mask.

*Operations* supported.

#### **units**

None, **'norm'**, **'cm'**, **'deg'**, **'degFlat'**, **'degFlatPos'**, or **'pix'**

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don't change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5)

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

#### **useShaders**

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

#### **verticesPix**

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

#### **win**

**The *Window* object in which the** stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (*win1*, *win2* and *stim*):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw()    # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw()    # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
                             # monitor update
```

(continues on next page)



(continued from previous page)

```
win2.flip() # wait for vertical blanking.
```

Note that this just changes **\*\*default\*\*** window **for** stimulus.  
You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

## 8.2.8 Helper functions

`psychopy.visual.helpers.pointInPolygon(x, y, poly)`

Determine if a point is inside a polygon; returns True if inside.

(x, y) is the point to test. *poly* is a list of 3 or more vertices as (x,y) pairs. If given an object, such as a *ShapeStim*, will try to use its vertices and position as the polygon.

Same as the `.contains()` method elsewhere.

`psychopy.visual.helpers.polygonsOverlap(poly1, poly2)`

Determine if two polygons intersect; can fail for very pointy polygons.

Accepts two polygons, as lists of vertices (x,y) pairs. If given an object with with (vertices + pos), will try to use that as the polygon.

Checks if any vertex of one polygon is inside the other polygon. Same as the `.overlaps()` method elsewhere.

### Notes

We implement special handling for the *Line* stimulus as it is not a proper polygon. We do not check for class instances because this would require importing of *visual.Line*, creating a circular import. Instead, we assume that a “polygon” with only two vertices is meant to specify a line. Pixels between the endpoints get interpolated before testing for overlap.

`psychopy.visual.helpers.groupFlipVert(flipList, yReflect=0)`

Reverses the vertical mirroring of all items in list `flipList`.

Reverses the `.flipVert` status, vertical (y) positions, and angular rotation (`.ori`). Flipping preserves the relations among the group’s visual elements. The parameter `yReflect` is the y-value of an imaginary horizontal line around which to reflect the items; default = 0 (screen center).

Typical usage is to call once prior to any display; call again to un-flip. Can be called with a list of all stim to be presented in a given routine.

Will flip a) all `psychopy.visual.xyzStim` that have a `setFlipVert` method, b) the y values of `.vertices`, and c) items in `n x 2` lists that are mutable (i.e., list, `np.array`, no tuples): `[[x1, y1], [x2, y2], ...]`

## 8.2.9 ImageStim

As of PsychoPy version 1.79.00 *some* of the properties for this stimulus can be set using the syntax:

```
stim.pos = newPos
```

others need to be set with the older syntax:

```
stim.setImage(newImage)
```

## Attributes

<code>ImageStim(win[, image, mask, units, pos, ...])</code>	Display an image on a <a href="#"><i>psychopy.visual.Window</i></a>
<code>ImageStim.win</code>	The <a href="#"><i>Window</i></a> object in which the
<code>ImageStim.setImage(value[, log])</code>	Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.
<code>ImageStim.setMask(value[, log])</code>	Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.
<code>ImageStim.units</code>	None, ‘norm’, ‘cm’, ‘deg’, ‘degFlat’, ‘degFlatPos’, or ‘pix’
<code>ImageStim.pos</code>	The position of the center of the stimulus in the stimulus <a href="#"><i>units</i></a>
<code>ImageStim.ori</code>	The orientation of the stimulus (in degrees).
<code>ImageStim.size</code>	The size (width, height) of the stimulus in the stimulus <a href="#"><i>units</i></a>
<code>ImageStim.contrast</code>	A value that is simply multiplied by the color
<code>ImageStim.color</code>	Color of the stimulus
<code>ImageStim.colorSpace</code>	The name of the color space currently being used
<code>ImageStim.opacity</code>	Determines how visible the stimulus is relative to background
<code>ImageStim.interpolate</code>	Whether to interpolate (linearly) the texture in the stimulus
<code>ImageStim.contains(x[, y, units])</code>	Returns True if a point x,y is inside the stimulus’ border.
<code>ImageStim.overlaps(polygon)</code>	Returns <i>True</i> if this stimulus intersects another one.
<code>ImageStim.name</code>	String or None.
<code>ImageStim.autoLog</code>	Whether every change in this stimulus should be auto logged.
<code>ImageStim.draw([win])</code>	Draw.
<code>ImageStim.autoDraw</code>	Determines whether the stimulus should be automatically drawn on every frame flip.
<code>ImageStim.clearTextures()</code>	Clear all textures associated with the stimulus.

## Details

```
class psychopy.visual.ImageStim(win, image=None, mask=None, units="", pos=(0.0, 0.0),
                                size=None, ori=0.0, color=(1.0, 1.0, 1.0), colorSpace='rgb',
                                contrast=1.0, opacity=1.0, depth=0, interpolate=False,
                                flipHoriz=False, flipVert=False, texRes=128, name=None,
                                autoLog=None, maskParams=None)
```

Display an image on a [\*psychopy.visual.Window\*](#)

`_calcPosRendered()`

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

`_calcSizeRendered()`

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`

`_createTexture(tex, id, pixFormat, stim, res=128, maskParams=None, forcePOW2=True,
 dataType=None, wrapping=True)`

### Params

**id:** is the texture ID

**pixFormat:** GL.GL\_ALPHA, GL.GL\_RGB

**useShaders:** bool

**interpolate:** bool (determines whether texture will use GL\_LINEAR or GL\_NEAREST

**res:** the resolution of the texture (unless a bitmap image is used)

**dataType:** None, GL.GL\_UNSIGNED\_BYTE, GL\_FLOAT. Only affects image files (numpy arrays will be float)

For grating stimuli (anything that needs multiple cycles) forcePOW2 should be set to be True. Otherwise the wrapping of the texture will not work.

**\_getDesiredRGB** (*rgb, colorSpace, contrast*)

Convert color to RGB while adding contrast. Requires self.rgb, self.colorSpace and self.contrast

**\_getPolyAsRendered** ()

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow** (*win*)

Switch drawing to the specified window. Calls the window's \_setCurrent() method which handles the switch.

**\_set** (*attrib, val, op=", log=None*)

DEPRECATED since 1.80.04 + 1. Use setAttribute() and val2array() instead.

**\_updateList** ()

The user shouldn't need this method since it gets called after every call to .set() Chooses between using and not using shaders each call.

**\_updateListNoShaders** ()

The user shouldn't need this method since it gets called after every call to .set() Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the .set() command.

**\_updateListShaders** ()

The user shouldn't need this method since it gets called after every call to .set() Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the .set() command

**\_updateVertices** ()

Sets Stim.verticesPix and .\_borderPix from pos, size, ori, flipVert, flipHoriz

**autoDraw**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**autoLog**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every

frame) and you want to avoid swamping the log file with

messages that aren't likely to be useful.

**clearTextures** ()

Clear all textures associated with the stimulus.

As of v1.61.00 this is called automatically during garbage collection of your stimulus, so doesn't need calling explicitly by the user.

## color

Color of the stimulus

Value should be one of:

- string: to specify a *Colors by name*. Any of the standard html/X11 *color names* <[http://www.w3schools.com/html/html\\_colornames.asp](http://www.w3schools.com/html/html_colornames.asp)> can be used.
- *Colors by hex value*
- **numerically: (scalar or triplet) for DKL, RGB or other *Color spaces*.** For these, *operations* are supported.

When color is specified using numbers, it is interpreted with respect to the stimulus' current colorSpace. If color is given as a single value (scalar) then this will be applied to all 3 channels.

**Examples::** # ... for whatever stim you have: stim.color = 'white' stim.color = 'RoyalBlue' # (the case is actually ignored) stim.color = '#DDA0DD' # DDA0DD is hexadecimal for plum stim.color = [1.0, -1.0, -1.0] # if stim.colorSpace='rgb':

# a red color in rgb space

**stim.color = [0.0, 45.0, 1.0] # if stim.colorSpace='dkl':** # DKL space with elev=0, azimuth=45

**stim.color = [0, 0, 255] # if stim.colorSpace='rgb255':** # a blue stimulus using rgb255 space

**stim.color = 255 # interpreted as (255, 255, 255)** # which is white in rgb255.

*Operations* work as normal for all numeric colorSpaces (e.g. 'rgb', 'hsv' and 'rgb255') but not for strings, like named and hex. For example, assuming that colorSpace='rgb':

```
stim.color += [1, 1, 1] # increment all guns by 1 value
stim.color *= -1 # multiply the color by -1 (which in this
                 # space inverts the contrast)
stim.color *= [0.5, 0, 1] # decrease red, remove green, keep blue
```

You can use *setColor* if you want to set color and colorSpace in one line. These two are equivalent:

```
stim.setColor((0, 128, 255), 'rgb255')
# ... is equivalent to
stim.colorSpace = 'rgb255'
stim.color = (0, 128, 255)
```

## colorSpace

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default colorSpace for the stimulus is used (defined during initialisation).

Please note that changing colorSpace does not change stimulus parameters. Thus you usually want to specify colorSpace before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                      color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'
```

(continues on next page)

(continued from previous page)

```
# Make it light green again
stim.color = (128, 255, 128)
```

**contains** (*x, y=None, units=None*)

Returns True if a point x,y is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a getPos() method that returns x,y, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (*pos*), and orientation (*ori*) settings (and by the vertices for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

**contrast**

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

**depth**

DEPRECATED. Depth is now controlled simply by drawing order.

**draw** (*win=None*)

Draw.

**image**

The image file to be presented (most formats supported).

**interpolate**

Whether to interpolate (linearly) the texture in the stimulus

If set to False then nearest neighbour will be used when needed, otherwise some form of interpolation will be used.

### mask

The alpha mask that can be used to control the outer shape of the stimulus

- **None**, 'circle', 'gauss', 'raisedCos'
- or the name of an image file (most formats supported)
- or a numpy array (1xN or NxN) ranging -1:1

### maskParams

Various types of input. Default to None.

This is used to pass additional parameters to the mask if those are needed.

- **For 'gauss' mask, pass dict {'sd': 5} to control** standard deviation.
- **For the 'raisedCos' mask, pass a dict: {'fringeWidth':0.2}**, where 'fringeWidth' is a parameter (float, 0-1), determining the proportion of the patch that will be blurred by the raised cosine edge.

### name

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called "unnamed <type>", e.g. visual.TextStim(win) will be called "unnamed TextStim" in the logs.

### opacity

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

### ori

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

### overlaps (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, shapeContains.py

### pos

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
# Is now (1.0, -1.0)
```

(continues on next page)

(continued from previous page)

```
stim.pos *= 0.2 # Move stim towards the center.
            Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix posPix = posToPix(stim)
```

**setAutoDraw** (*value*, *log=None*)

Sets autoDraw. Usually you can use ‘stim.attribute = value’ syntax instead, but use this method to suppress the log message.

**setAutoLog** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setColor** (*color*, *colorSpace=None*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message and/or set colorSpace simultaneously.

**setContrast** (*newContrast*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setDKL** (*newDKL*, *operation=*”)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setDepth** (*newDepth*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setImage** (*value*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setLMS** (*newLMS*, *operation=*”)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setMask** (*value*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setOpacity** (*newOpacity*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPos** (*newPos*, *operation=*”, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation=*”, *log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSize** (*newSize*, *operation=*”, *units=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setUseShaders** (*value=True, log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**size**

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or None (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

**texRes**

Power-of-two int. Sets the resolution of the mask and texture. texRes is overridden if an array or image is provided as mask.

*Operations* supported.

**units**

None, ‘norm’, ‘cm’, ‘deg’, ‘degFlat’, ‘degFlatPos’, or ‘pix’

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don’t change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5))

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

**useShaders**

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to True is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

**verticesPix**

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

**win**

The *Window* object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (win1, win2 and stim):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw() # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
```

(continues on next page)



(continued from previous page)

```
stim.draw() # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
# monitor update
win2.flip() # wait for vertical blanking.
```

Note that this just changes **\*\*default\*\*** window **for** stimulus.  
You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

## 8.2.10 Line

**class** psychopy.visual.**Line** (win, start=(-0.5, -0.5), end=(0.5, 0.5), **\*\*kwargs**)

Creates a Line between two points.

(New in version 1.72.00)

Line accepts all input parameters, that *ShapeStim* accepts, except for vertices, closeShape and fillColor.

### Notes

The *contains* method always return False because a line is not a proper (2D) polygon.

**mro** () → list  
return a type's method resolution order

## 8.2.11 MovieStim

### Attributes

<i>MovieStim</i> (win[, filename, units, size, pos, ...])	A stimulus class for playing movies (mpeg, avi, etc...) in PsychoPy.
<i>MovieStim.win</i>	The <i>Window</i> object in which the
<i>MovieStim.units</i>	None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'
<i>MovieStim.pos</i>	The position of the center of the stimulus in the stimulus <i>units</i>
<i>MovieStim.ori</i>	The orientation of the stimulus (in degrees).
<i>MovieStim.size</i>	The size (width, height) of the stimulus in the stimulus <i>units</i>
<i>MovieStim.opacity</i>	Determines how visible the stimulus is relative to background
<i>MovieStim.name</i>	String or None.
<i>MovieStim.autoLog</i>	Whether every change in this stimulus should be auto logged.
<i>MovieStim.draw</i> ([win])	Draw the current frame to a particular visual.Window.
<i>MovieStim.autoDraw</i>	Determines whether the stimulus should be automatically drawn on every frame flip.
<i>MovieStim.loadMovie</i> (filename[, log])	Load a movie from file
<i>MovieStim.play</i> ([log])	Continue a paused movie from current position.

Continued on next page

Table 4 – continued from previous page

<code>MovieStim.seek(timestamp[, log])</code>	Seek to a particular timestamp in the movie.
<code>MovieStim.pause([log])</code>	Pause the current point in the movie (sound will stop, current frame will not advance).
<code>MovieStim.stop([log])</code>	Stop the current point in the movie.
<code>MovieStim.setFlipHoriz([newVal, log])</code>	If set to True then the movie will be flipped horizontally (left-to-right).
<code>MovieStim.setFlipVert([newVal, log])</code>	If set to True then the movie will be flipped vertically (top-to-bottom).

## Details

```
class psychopy.visual.MovieStim(win, filename="", units='pix', size=None, pos=(0.0, 0.0),
                                ori=0.0, flipVert=False, flipHoriz=False, color=(1.0, 1.0, 1.0),
                                colorSpace='rgb', opacity=1.0, volume=1.0, name=None,
                                loop=False, autoLog=None, depth=0.0)
```

A stimulus class for playing movies (mpeg, avi, etc...) in PsychoPy.

### Example:

```
mov = visual.MovieStim(myWin, 'testMovie.mp4', flipVert=False)
print(mov.duration)
# give the original size of the movie in pixels:
print(mov.format.width, mov.format.height)

mov.draw() # draw the current frame (automagically determined)
```

See MovieStim.py for demo.

### Parameters

**filename** : a string giving the relative or absolute path to the movie. Can be any movie that AVbin can read (e.g. mpeg, DivX)

**flipVert** [True or False] If True then the movie will be top-bottom flipped

**flipHoriz** [True or False] If True then the movie will be right-left flipped

**volume** : The nominal level is 1.0, and 0.0 is silence, see pyglet.media.Player

**loop** [bool, optional] Whether to start the movie over from the beginning if draw is called and the movie is done.

**\_calcPosRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

**\_calcSizeRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`

**\_getPolyAsRendered()**

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow(win)**

Switch drawing to the specified window. Calls the window's `_setCurrent()` method which handles the switch.

**\_set(attrib, val, op="", log=None)**

DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

#### **`_updateList()`**

The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

#### **`_updateVertices()`**

Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

#### **`autoDraw`**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

#### **`autoLog`**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every

frame) and you want to avoid swamping the log file with messages that aren't likely to be useful.

#### **`contains(x, y=None, units=None)`**

Returns True if a point `x,y` is inside the stimulus' border.

#### **Can accept variety of input options:**

- two separate args, `x` and `y`
- one arg (list, tuple or array) containing two vals (`x,y`)
- **an object with a `getPos()` method that returns `x,y`, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the *size*, *position (pos)*, and *orientation (ori)* settings (and by the *vertices* for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

#### **`depth`**

DEPRECATED. Depth is now controlled simply by drawing order.

#### **`draw(win=None)`**

Draw the current frame to a particular visual.Window.

Draw to the default win for this object if not specified. The current position in the movie will be determined automatically.

This method should be called on every frame that the movie is meant to appear.

#### **`loadMovie(filename, log=None)`**

Load a movie from file

#### **Parameters**

**filename: string** The name of the file, including path if necessary

Brings up a warning if `avbin` is not found on the computer. After the file is loaded `MovieStim.duration` is updated with the movie duration (in seconds).

#### **name**

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called “unnamed <type>”, e.g. `visual.TextStim(win)` will be called “unnamed TextStim” in the logs.

#### **opacity**

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

#### **ori**

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

#### **overlaps** (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, `shapeContains.py`

#### **pause** (*log=None*)

Pause the current point in the movie (sound will stop, current frame will not advance). If `play()` is called again both will restart.

#### **play** (*log=None*)

Continue a paused movie from current position.

#### **pos**

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
# Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
# Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix
posPix = posToPix(stim)
```

#### **seek** (*timestamp, log=None*)

Seek to a particular timestamp in the movie.

NB this does not seem very robust as at version 1.62, may crash!

**setAutoDraw** (*val*, *log=None*)

Add or remove a stimulus from the list of stimuli that will be automatically drawn on each flip

#### Parameters

- **val: True/False** True to add the stimulus to the draw list, False to remove it

**setAutoLog** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setContrast** ()

Not yet implemented for MovieStim.

**setDKL** (*newDKL*, *operation=""*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setDepth** (*newDepth*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setFlipHoriz** (*newVal=True*, *log=None*)

If set to True then the movie will be flipped horizontally (left-to-right). Note that this is relative to the original, not relative to the current state.

**setFlipVert** (*newVal=True*, *log=None*)

If set to True then the movie will be flipped vertically (top-to-bottom). Note that this is relative to the original, not relative to the current state.

**setLMS** (*newLMS*, *operation=""*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setMovie** (*filename*, *log=None*)

See `~MovieStim.loadMovie` (the functions are identical). This form is provided for syntactic consistency with other visual stimuli.

**setOpacity** (*newOpacity*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPos** (*newPos*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation=""*, *log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSize** (*newSize*, *operation=""*, *units=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setUseShaders** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**size**

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or *None* (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

**stop** (*log=None*)

Stop the current point in the movie.

The sound will stop, current frame will not advance. Once stopped the movie cannot be restarted - it must be loaded again. Use *pause()* if you may need to restart the movie.

**units**

*None*, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'

If *None* then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don't change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5))

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

**useShaders**

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

**verticesPix**

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

**win**

The *Window* object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (*win1*, *win2* and *stim*):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw() # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw() # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
# monitor update
win2.flip() # wait for vertical blanking.
```

Note that this just changes *\*\*default\*\** window for stimulus.

(continues on next page)

(continued from previous page)

You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

## 8.2.12 NoiseStim

### Attributes

### Details

```
class psychopy.visual.NoiseStim(win, mask='none', units="", pos=(0.0, 0.0), size=None,
                                sf=None, ori=0.0, phase=(0.0, 0.0), noiseType='none',
                                noiseElementSize='16', noiseBaseSf='1', noiseBW='1',
                                noiseBWO='30', noiseOri='0', noiseFractalPower='0.0',
                                noiseFilterUpper='50', noiseFilterLower='0', noise-
                                FilterOrder='0.0', noiseClip='1', noiseImage='None', image-
                                Component='Phase', filter='None', texRes=128, rgb=None,
                                dkl=None, lms=None, color=(1.0, 1.0, 1.0), colorSpace='rgb',
                                contrast=0.5, opacity=1.0, depth=0, rgbPedestal=(0.0, 0.0,
                                0.0), interpolate=False, blendmode='avg', name=None,
                                autoLog=None, autoDraw=False, maskParams=None)
```

A stimulus with 2 textures: a random noise sample and a mask

### Example:

```
noise1 = noise = visual.NoiseStim(
```

```
    win=win, name='noise', units='pix', noiseImage='testImg.jpg', mask='circle', ori=1.0,
    pos=(0, 0), size=(512, 512), sf=None, phase=0, color=[1,1,1], colorSpace='rgb',
    opacity=1, blendmode='add', contrast=1.0, texRes=512, filter='None', imageComp-
    onent='Phase' noiseType='Gabor', noiseElementSize=4, noiseBaseSf=32.0/512, noiseBW=1.0,
    noiseBWO=30, noiseFractalPower=-1, noiseFilterLower=3/512, noiseFilterUpper=8.0/512.0,
    noiseFilterOrder=3.0, noiseClip=3.0, filter=False, interpolate=False, depth=-1.0)
```

# gives a circular patch of noise made up of scattered Gabor elements with peak frequency = 32.0/512 cycles per pixel, # orientation = 0, frequency bandwidth = 1 octave and orientation bandwidth 30 degrees

**Types of noise available** Binary, Normal, Uniform - pixel based noise samples drawn from a binary (blank and white), normal or uniform distribution respectively. Binary noise is always exactly zero mean, Normal and Uniform are approximately so.

**Parameters - noiseElementSize** - (can be a tuple) defines the size of the noise elements in the components units.

**noiseClip** the values in normally distributed noise are divided by noiseClip to limit excessively high or low values

However, values can still go out of range -1 to 1 which will throw a soft error message high values of noiseClip are recommended if using 'Normal'

**Gabor, Isotropic** - Effectively a dense scattering of Gabor elements with random amplitude and fixed orientation for Gabor

**Parameters - noiseBaseSf** - centre spatial frequency in the component units. noiseBW - spatial frequency bandwidth full width half height in octaves. ori - center orientation for Gabor noise (works as for gratingStim so twists the final image at render time). noiseBWO - orientation bandwidth for Gabor

noise full width half height in degrees. noiseOri - alternative center orientation for Gabor which sets the orientation during the image build rather than at render time.

useful for setting the orientation of a filter to be applied to some other noise type with a different base orientation.

In practice the desired amplitude spectrum for the noise is built in Fourier space with a random phase spectrum. DC term is set to zero - ie zero mean.

**Filtered - A white noise sample that has been filtered with a low, high or bandpass Butterworth filter. The initial sample contrast is 1.0**

The contrast of the noise falls by half its maximum (3dB) at the cutoff frequencies. Parameters - noiseFilterLower - lower cutoff frequency - if greater than texRes/2 cycles per image low pass filter used.

noiseFilterUpper - upper cutoff frequency - if greater than texRes/2 cycles per image low pass filter used. noiseFilterOrder - The order of the filter controls the steepness of the falloff outside the passband is zero no filter is applied. noiseFractalPower - spectrum =  $f^{\text{noiseFractalPower}}$  - determines the spatial frequency bias of the initial noise sample. 0 = flat spectrum, negative = low frequency bias, positive = high frequency bias, -1 = fractal or brownian noise. noiseClip - determines clipping values and rescaling factor such that final rms contrast is close to that requested by contrast parameter while keeping pixel values in range -1, 1.

**White - A short cut to obtain noise with a flat, unfiltered spectrum**

noiseClip - determines clipping values and rescaling factor such that final rms contrast is close to that requested by contrast parameter while keeping pixel values in range -1, 1.

In practice the desired amplitude spectrum is built in the Fourier Domain with a random phase spectrum. DC term is set to zero - ie zero mean Note despite name the noise contains all grey levels.

**Image - A noise sample whose spatial frequency spectrum is taken from the supplied image.**

**Parameters - noiseImage name of nparray or image file from which to take spectrum - should be same size as largest texture**

**imageComponent: 'Phase' randomizes the phase spectrum leaving the amplitude spectrum untouched.**

'Amplitude' randomizes the amplitude spectrum leaving the phase spectrum untouched - retains spatial structure of image. 'Neither' keeps the image as is - but you can now apply a spatial filter to the image.

noiseClip - determines clipping values and rescaling factor such that final rms contrast is close to that requested by contrast parameter while keeping pixel values in range -1, 1.

In practice the desired amplitude spectrum is taken from the image and paired with a random phase spectrum. DC term is set to zero - ie zero mean

**\*\*filter parameter** If the filter parameter = Butterworth then the a spectral filter defined by the filtered noise parameters will be applied to the other noise types. If the filter parameter = Gabor then the a spectral filter defined by the Gabor noise parameters will be applied to the other noise types. If the filter parameter = Isotropic then the a spectral filter defined by the Isotropic noise parameters will be applied to the other noise types.

**Updating noise samples and timing** The noise is rebuilt at next call of the draw function whenever a parameter starting 'noise' is notionally changed even if the value does not actually change every time. eg. setting a parameter to update every frame will cause a new noise sample on every frame but see below. A rebuild can also be forced at any time using the buildNoise() function. The updateNoise() function can be used at any time to produce a new random sample of noise without doing a full build. ie it is quicker than a full build. Both buildNoise and updateNoise can be slow for large samples. Samples of Binary, Normal or Uniform noise can usually be made at frame rate using noiseUpdate. Updating or building other noise types at frame rate may result in dropped frames. An alternative is to build a large sample of noise at the start of the routine and place it off the screen then cut a samples out of this at random locations and feed that as a numpy array into the texture of a visible gratingStim.



**Notes on size** If units = pix and noiseType = Binary, Normal or Uniform will make noise sample of requested size. If units = pix and noiseType is Gabor, Isotropic, Filtered, White, Coloured or Image will make square noise sample with side length equal that of the largest dimetions requested. if units is not pix will make square noise sample with side length equal to texRes then rescale to present.

**Notes on interpolation** For pixel based noise interpolation = nearest is usually best. For other noise types linear is better if the size of the noise sample does not match the final size of the image well.

**Notes on frequency** Frequencies for cutoffs etc are converted between units for you but can be counter intuitive. 1/size is always 1 cycle per image. For the sf (final spatial frequency) parameter itself 1/size (or None for units pix) will faithfully represent the image without further scaling.

Filter cutoff and Gabor/Isotropic base frequencies should not be too high you should aim to keep them below 0.5 c/pixel on the screen. The function will produce an error when it can't draw the stimulus in the buffer but it may still be wrong when displayed.

**Notes on orientation and phase** The ori parameter twists the final image so the samples in noiseType Binary, Normal or Uniform will no longer be aligned to the sides of the monitor if ori is not a multiple of 90. Most other noise types look broadly the same for all values of ori but the specific sample shown can be made to rotate by changing ori. The dominant orientation for Gabor noise is determined by ori at render time, not before.

The phase parameter similarly shifts the sample around within the display window at render time and will not choose new random phases for the noise sample.

**mro** () → list  
return a type's method resolution order

### 8.2.13 PatchStim (deprecated)

**class** psychopy.visual.PatchStim(\*args, \*\*kwargs)  
Deprecated (as of version 1.74.00): please use the *GratingStim* or the *ImageStim* classes.

The GratingStim has identical abilities to the PatchStim (but possibly different initial values) whereas the ImageStim is designed to be use for non-cyclic images (photographs, not gratings).

**mro** () → list  
return a type's method resolution order

### 8.2.14 Polygon

**class** psychopy.visual.Polygon(win, edges=3, radius=0.5, \*\*kwargs)

Creates a regular polygon (triangles, pentagrams, ...). A special case of a *ShapeStim*.

(New in version 1.72.00)

Polygon accepts all input parameters that *ShapeStim* accepts, except for vertices and closeShape.

**mro** () → list  
return a type's method resolution order

### 8.2.15 RadialStim

#### Attributes

<code>RadialStim(win[, tex, mask, units, pos, ...])</code>	Stimulus object for drawing radial stimuli.
<code>RadialStim.win</code>	The <i>Window</i> object in which the
<code>RadialStim.tex</code>	Texture to used on the stimulus as a grating (aka carrier)
<code>RadialStim.mask</code>	The alpha mask that forms the shape of the resulting image.
<code>RadialStim.units</code>	None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'
<code>RadialStim.pos</code>	The position of the center of the stimulus in the stimulus <i>units</i>
<code>RadialStim.ori</code>	The orientation of the stimulus (in degrees).
<code>RadialStim.size</code>	The size (width, height) of the stimulus in the stimulus <i>units</i>
<code>RadialStim.contrast</code>	A value that is simply multiplied by the color
<code>RadialStim.color</code>	Color of the stimulus
<code>RadialStim.colorSpace</code>	The name of the color space currently being used
<code>RadialStim.opacity</code>	Determines how visible the stimulus is relative to background
<code>RadialStim.interpolate</code>	Whether to interpolate (linearly) the texture in the stimulus
<code>RadialStim.setAngularCycles(value[, ...])</code>	Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message
<code>RadialStim.setAngularPhase(value[, ...])</code>	Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message
<code>RadialStim.setRadialCycles(value[, ...])</code>	Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message
<code>RadialStim.setRadialPhase(value[, ...])</code>	Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message
<code>RadialStim.name</code>	String or None.
<code>RadialStim.autoLog</code>	Whether every change in this stimulus should be auto logged.
<code>RadialStim.draw([win])</code>	Draw the stimulus in its relevant window.
<code>RadialStim.autoDraw</code>	Determines whether the stimulus should be automatically drawn on every frame flip.
<code>RadialStim.clearTextures()</code>	Clear all textures associated with the stimulus.

## Details

```
class psychopy.visual.RadialStim(win, tex='sqrXsqr', mask='none', units="", pos=(0.0,
0.0), size=(1.0, 1.0), radialCycles=3, angularCycles=4,
radialPhase=0, angularPhase=0, ori=0.0, texRes=64, angularRes=100, visibleWedge=(0, 360), rgb=None, color=(1.0,
1.0, 1.0), colorSpace='rgb', dkl=None, lms=None, contrast=1.0, opacity=1.0, depth=0, rgbPedestal=(0.0, 0.0,
0.0), interpolate=False, name=None, autoLog=None, maskParams=None)
```

Stimulus object for drawing radial stimuli.

Examples: annulus, rotating wedge, checkerboard.

Ideal for fMRI retinotopy stimuli!

Many of the capabilities are built on top of the GratingStim.

This stimulus is still relatively new and I'm finding occasional glitches. It also takes longer to draw than a typical GratingStim, so not recommended for tasks where high frame rates are needed.

**\_calcPosRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

**\_calcSizeRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`

**\_createTexture**(*tex, id, pixFormat, stim, res=128, maskParams=None, forcePOW2=True, dataType=None, wrapping=True*)

#### Params

**id:** is the texture ID

**pixFormat:** GL.GL\_ALPHA, GL.GL\_RGB

**useShaders:** bool

**interpolate:** bool (determines whether texture will use GL\_LINEAR or GL\_NEAREST

**res:** the resolution of the texture (unless a bitmap image is used)

**dataType:** None, GL.GL\_UNSIGNED\_BYTE, GL\_FLOAT. Only affects image files (numpy arrays will be float)

For grating stimuli (anything that needs multiple cycles) forcePOW2 should be set to be True. Otherwise the wrapping of the texture will not work.

**\_getDesiredRGB**(*rgb, colorSpace, contrast*)

Convert color to RGB while adding contrast. Requires `self.rgb`, `self.colorSpace` and `self.contrast`

**\_getPolyAsRendered()**

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow**(*win*)

Switch drawing to the specified window. Calls the window's `_setCurrent()` method which handles the switch.

**\_set**(*attrib, val, op="", log=None*)

DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

**\_setRadialAttribute**(*attr, value*)

Internal helper function to reduce redundancy

**\_updateEverything()**

Internal helper function for `angularRes` and `visibleWedge` (and `init`)

**\_updateList()**

The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

**\_updateListNoShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**\_updateListShaders()**

The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the

OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**`_updateMaskCoords ()`**

calculate mask coords

**`_updateTextureCoords ()`**

calculate texture coordinates if `angularCycles` or `Phase` change

**`_updateVertices ()`**

Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

**`_updateVerticesBase ()`**

Update the base vertices if angular resolution changes.

These will be multiplied by the size and rotation matrix before rendering.

**`angularCycles`**

Float (but Int is prettiest). Set the number of cycles going around the stimulus. i.e. it controls the number of ‘spokes’.

*Operations* supported.

**`angularPhase`**

Float. Set the angular phase (like orientation) of the texture (wraps 0-1).

This is akin to setting the orientation of the texture around the stimulus in radians. If possible, it is more efficient to rotate the stimulus using its *ori* setting instead.

*Operations* supported.

**`angularRes`**

The number of triangles used to make the sti.

*Operations* supported.

**`autoDraw`**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**`autoLog`**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every

frame) and you want to avoid swamping the log file with

messages that aren’t likely to be useful.

**`blendmode`**

The OpenGL mode in which the stimulus is draw

Can be ‘avg’ or ‘add’. Average (avg) places the new stimulus over the old one with a transparency given by its opacity. Opaque stimuli will hide other stimuli transparent stimuli won’t. Add performs the arithmetic sum of the new stimulus and the ones already present.

**`clearTextures ()`**

Clear all textures associated with the stimulus.

As of v1.61.00 this is called automatically during garbage collection of your stimulus, so doesn’t need calling explicitly by the user.

## color

Color of the stimulus

Value should be one of:

- string: to specify a *Colors by name*. Any of the standard html/X11 *color names* <[http://www.w3schools.com/html/html\\_colornames.asp](http://www.w3schools.com/html/html_colornames.asp)> can be used.
- *Colors by hex value*
- **numerically: (scalar or triplet) for DKL, RGB or other Color spaces.** For these, *operations* are supported.

When color is specified using numbers, it is interpreted with respect to the stimulus' current colorSpace. If color is given as a single value (scalar) then this will be applied to all 3 channels.

**Examples::** # ... for whatever stim you have: stim.color = 'white' stim.color = 'RoyalBlue' # (the case is actually ignored) stim.color = '#DDA0DD' # DDA0DD is hexadecimal for plum stim.color = [1.0, -1.0, -1.0] # if stim.colorSpace='rgb':

# a red color in rgb space

**stim.color = [0.0, 45.0, 1.0] # if stim.colorSpace='dkl':** # DKL space with elev=0, azimuth=45

**stim.color = [0, 0, 255] # if stim.colorSpace='rgb255':** # a blue stimulus using rgb255 space

**stim.color = 255 # interpreted as (255, 255, 255)** # which is white in rgb255.

*Operations* work as normal for all numeric colorSpaces (e.g. 'rgb', 'hsv' and 'rgb255') but not for strings, like named and hex. For example, assuming that colorSpace='rgb':

```
stim.color += [1, 1, 1] # increment all guns by 1 value
stim.color *= -1 # multiply the color by -1 (which in this
                 # space inverts the contrast)
stim.color *= [0.5, 0, 1] # decrease red, remove green, keep blue
```

You can use *setColor* if you want to set color and colorSpace in one line. These two are equivalent:

```
stim.setColor((0, 128, 255), 'rgb255')
# ... is equivalent to
stim.colorSpace = 'rgb255'
stim.color = (0, 128, 255)
```

## colorSpace

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default colorSpace for the stimulus is used (defined during initialisation).

Please note that changing colorSpace does not change stimulus parameters. Thus you usually want to specify colorSpace before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                      color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'
```

(continues on next page)

(continued from previous page)

```
# Make it light green again
stim.color = (128, 255, 128)
```

**contains** (*x, y=None, units=None*)

Returns True if a point x,y is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a getPos() method that returns x,y, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (*pos*), and orientation (*ori*) settings (and by the vertices for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

**contrast**

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

**depth**

DEPRECATED. Depth is now controlled simply by drawing order.

**draw** (*win=None*)

Draw the stimulus in its relevant window. You must call this method after every *win.flip()* if you want the stimulus to appear on that frame and then update the screen again.

If *win* is specified then override the normal window of this stimulus.

**interpolate**

Whether to interpolate (linearly) the texture in the stimulus

If set to False then nearest neighbour will be used when needed, otherwise some form of interpolation will be used.

### mask

The alpha mask that forms the shape of the resulting image.

Value should be one of:

- ‘circle’, ‘gauss’, ‘raisedCos’, **None** (resets to default)
- or the name of an image file (most formats supported)
- or a numpy array (1xN) ranging -1:1

Note that the mask for *RadialStim* is somewhat different to the mask for *ImageStim*. For *RadialStim* it is a 1D array specifying the luminance profile extending outwards from the center of the stimulus, rather than a 2D array

### maskParams

Various types of input. Default to None.

This is used to pass additional parameters to the mask if those are needed.

- **For ‘gauss’ mask, pass dict {‘sd’: 5} to control** standard deviation.
- **For the ‘raisedCos’ mask, pass a dict: {‘fringeWidth’:0.2},** where ‘fringeWidth’ is a parameter (float, 0-1), determining the proportion of the patch that will be blurred by the raised cosine edge.

### name

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called “unnamed <type>”, e.g. visual.TextStim(win) will be called “unnamed TextStim” in the logs.

### opacity

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

### ori

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

### overlaps (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, shapeContains.py

### phase

Phase of the stimulus in each dimension of the texture.

Should be an *x,y-pair* or *scalar*

**NB** phase has modulus 1 (rather than 360 or  $2\pi$ ) This is a little unconventional but has the nice effect that setting `phase=t*n` drifts a stimulus at  $n$  Hz

#### **pos**

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix
posPix = posToPix(stim)
```

#### **radialCycles**

Float (but Int is prettiest). Set the number of texture cycles from centre to periphery, i.e. it controls the number of ‘rings’.

*Operations* supported.

#### **radialPhase**

Float. Set the radial phase of the texture (wraps 0-1). This is the phase of the texture from the centre to the perimeter of the stimulus (in radians). Can be used to drift concentric rings out/inwards.

*Operations* supported.

#### **setAngularCycles** (*value*, *operation*=”, *log*=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

#### **setAngularPhase** (*value*, *operation*=”, *log*=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

#### **setAutoDraw** (*value*, *log*=None)

Sets `autoDraw`. Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method to suppress the log message.

#### **setAutoLog** (*value*=True, *log*=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

#### **setBlendmode** (*value*, *log*=None)

DEPRECATED. Use ‘`stim.parameter = value`’ syntax instead

#### **setColor** (*color*, *colorSpace*=None, *operation*=”, *log*=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message and/or set `colorSpace` simultaneously.

#### **setContrast** (*newContrast*, *operation*=”, *log*=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

#### **setDKL** (*newDKL*, *operation*=”)

DEPRECATED since v1.60.05: Please use the *color* attribute



**setDepth** (*newDepth*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setLMS** (*newLMS*, *operation*=")

DEPRECATED since v1.60.05: Please use the *color* attribute

**setMask** (*value*, *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setOpacity** (*newOpacity*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setPhase** (*value*, *operation*=", *log*=None)

DEPRECATED. Use 'stim.parameter = value' syntax instead

**setPos** (*newPos*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation*=", *log*=None)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setRadialCycles** (*value*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setRadialPhase** (*value*, *operation*=", *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setSF** (*value*, *operation*=", *log*=None)

DEPRECATED. Use 'stim.parameter = value' syntax instead

**setSize** (*newSize*, *operation*=", *units*=None, *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**setTex** (*value*, *log*=None)

DEPRECATED. Use 'stim.parameter = value' syntax instead

**setUseShaders** (*value*=True, *log*=None)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**sf**

Spatial frequency of the grating texture

Should be a *x,y-pair* or *scalar* or None. If *units* == 'deg' or 'cm' units are in cycles per deg or cm as appropriate.

If *units* == 'norm' then *sf* units are in cycles per stimulus (and so SF scales with stimulus size).

If texture is an image loaded from a file then *sf*=None defaults to 1/stimSize to give one cycle of the image.

### size

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or None (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

### tex

Texture to used on the stimulus as a grating (aka carrier)

**This can be one of various options:**

- ‘sin’, ‘sqr’, ‘saw’, ‘tri’, None (resets to default)
- the name of an image file (most formats supported)
- a numpy array (1xN or NxN) ranging -1:1

If specifying your own texture using an image or numpy array you should ensure that the image has square power-of-two dimesnions (e.g. 256 x 256). If not then PsychoPy will upsample your stimulus to the next larger power of two.

### texRes

Power-of-two int. Sets the resolution of the mask and texture. texRes is overridden if an array or image is provided as mask.

*Operations* supported.

### units

None, ‘norm’, ‘cm’, ‘deg’, ‘degFlat’, ‘degFlatPos’, or ‘pix’

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don’t change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5)

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

### useShaders

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

### verticesPix

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

### **visibleWedge**

tuple (start, end) in degrees. Determines visible range.

(0, 360) is full visibility.

*Operations* supported.

### **win**

The **Window** object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (win1, win2 and stim):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw()    # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw()    # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
                             # monitor update
win2.flip()    # wait for vertical blanking.
```

Note that this just changes **default** window **for** stimulus.

You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

## 8.2.16 RatingScale

```
class psychopy.visual.RatingScale(win, scale='<default>', choices=None, low=1,
                                   high=7, precision=1, labels=(), tickMarks=None, tick-
                                   Height=1.0, marker='triangle', markerStart=None, mark-
                                   erColor=None, markerExpansion=1, singleClick=False,
                                   disappear=False, textSize=1.0, textColor='LightGray',
                                   textFont='Helvetica Bold', showValue=True, showAc-
                                   cept=True, acceptKeys='return', acceptPreText='key,
                                   click', acceptText='accept?', acceptSize=1.0, left-
                                   Keys='left', rightKeys='right', respKeys=(), line-
                                   Color='White', skipKeys='tab', mouseOnly=False,
                                   noMouse=False, size=1.0, stretch=1.0, pos=None,
                                   minTime=0.4, maxTime=0.0, flipVert=False, depth=0,
                                   name=None, autoLog=True, **kwargs)
```

A class for obtaining ratings, e.g., on a 1-to-7 or categorical scale.

A RatingScale instance is a re-usable visual object having a `draw()` method, with customizable appearance and response options. `draw()` displays the rating scale, handles the subject's mouse or key responses, and updates the display. When the subject accepts a selection, `.noResponse` goes False (i.e., there is a response).

You can call the `getRating()` method anytime to get a rating, `getRT()` to get the decision time, or `getHistory()` to obtain the entire set of (rating, RT) pairs.

There are five main elements of a rating scale: the *scale* (text above the line intended to be a reminder of how to use the scale), the *line* (with tick marks), the *marker* (a moveable visual indicator on the line), the *labels* (text below the line that label specific points), and the *accept* button. The appearance and function of elements can be customized by the experimenter; it is not possible to orient a rating scale to be vertical. Multiple scales can be displayed at the same time, and continuous real-time ratings can be obtained from the history.

The Builder RatingScale component gives a restricted set of options, but also allows full control over a RatingScale via the 'customize\_everything' field.

A RatingScale instance has no idea what else is on the screen. The experimenter has to draw the item to be rated, and handle *escape* to break or quit, if desired. The subject can use the mouse or keys to respond. Direction keys (left, right) will move the marker in the smallest available increment (e.g., 1/10th of a tick-mark if precision = 10).

#### Example 1:

A basic 7-point scale:

```
ratingScale = visual.RatingScale(win)
item = <statement, question, image, movie, ...>
while ratingScale.noResponse:
    item.draw()
    ratingScale.draw()
    win.flip()
rating = ratingScale.getRating()
decisionTime = ratingScale.getRT()
choiceHistory = ratingScale.getHistory()
```

#### Example 2:

For fMRI, sometimes only a keyboard can be used. If your response box sends keys 1-4, you could specify left, right, and accept keys, and not need a mouse:

```
ratingScale = visual.RatingScale(
    win, low=1, high=5, markerStart=4,
    leftKeys='1', rightKeys = '2', acceptKeys='4')
```

#### Example 3:

Categorical ratings can be obtained using choices:

```
ratingScale = visual.RatingScale(
    win, choices=['agree', 'disagree'],
    markerStart=0.5, singleClick=True)
```

For other examples see Coder Demos -> stimuli -> ratingScale.py.

#### Authors

- 2010 Jeremy Gray: original code and on-going updates
- 2012 Henrik Singmann: tickMarks, labels, ticksAboveLine
- 2014 Jeremy Gray: multiple API changes (v1.80.00)

#### Parameters

**win** : A *Window* object (required).

**choices** : A list of items which the subject can choose among. *choices* takes precedence over *low*, *high*, *precision*, *scale*, *labels*, and *tickMarks*.

**low** : Lowest numeric rating (integer), default = 1.

**high** : Highest numeric rating (integer), default = 7.

**precision** : Portions of a tick to accept as input [1, 10, 60, 100]; default = 1 (a whole tick). Pressing a key in *leftKeys* or *rightKeys* will move the marker by one portion of a tick. *precision*=60 is intended to support ratings of time-based quantities, with seconds being frac-

tional minutes (or minutes being fractional hours). The display uses a colon (min:sec, or hours:min) to signal this to participants. The value returned by `getRating()` will be a proportion of a minute (e.g., 1:30 -> 1.5, or 59 seconds ->  $59/60 = 0.98333$ ). hours:min:sec is not supported.

**scale** : Optional reminder message about how to respond or rate an item, displayed above the line; default = '<low>=not at all, <high>=extremely'. To suppress the scale, set `scale=None`.

**labels** : Text to be placed at specific tick marks to indicate their value. Can be just the ends (if given 2 labels), ends + middle (if given 3 labels), or all points (if given the same number of labels as points).

**tickMarks** : List of positions at which tick marks should be placed from low to high. The default is to space tick marks equally, one per integer value.

**tickHeight** : The vertical height of tick marks: 1.0 is the default height (above line), -1.0 is below the line, and 0.0 suppresses the display of tickmarks. `tickHeight` is purely cosmetic, and can be fractional, e.g., 1.2.

**marker** : The moveable visual indicator of the current selection. The predefined styles are 'triangle', 'circle', 'glow', 'slider', and 'hover'. A slider moves smoothly when there are enough screen positions to move through, e.g., `low=0`, `high=100`. Hovering requires a set of choices, and allows clicking directly on individual choices; dwell-time is not recorded. Can also be set to a custom marker stimulus: any object with a `.draw()` method and `.pos` will work, e.g., `visual.TextStim(win, text='[]', units='norm')`.

**markerStart** : The location or value to be pre-selected upon initial display, either numeric or one of the choices. Can be fractional, e.g., midway between two options.

**markerColor** : Color to use for a predefined marker style, e.g., 'DarkRed'.

**markerExpansion** : Only affects the *glow* marker: How much to expand or contract when moving rightward; 0=none, negative shrinks.

**singleClick** : Enable a mouse click to both select and accept the rating, default = `False`. A legal key press will also count as a `singleClick`. The 'accept' box is visible, but clicking it has no effect.

**pos** [tuple (x, y)] Position of the rating scale on the screen. The midpoint of the line will be positioned at (x, y); default = (0.0, -0.4) in norm units

**size** : How much to expand or contract the overall rating scale display. Default size = 1.0. For larger than the default, set `size > 1`; for smaller, set `< 1`.

**stretch**: Like `size`, but only affects the horizontal direction.

**textSize** : The size of text elements, relative to the default size (i.e., a scaling factor, not points).

**textColor** : Color to use for labels and scale text; default = 'LightGray'.

**textFont** : Name of the font to use; default = 'Helvetica Bold'.

**showValue** : Show the subject their current selection default = `True`. Ignored if `singleClick` is `True`.

**showAccept** : Show the button to click to accept the current value by using the mouse; default = `True`.

**acceptPreText** : The text to display before any value has been selected.

**acceptText** : The text to display in the 'accept' button after a value has been selected.

**acceptSize** : The width of the accept box relative to the default (e.g., 2 is twice as wide).

- acceptKeys** : A list of keys that are used to accept the current response; default = 'return'.
- leftKeys** : A list of keys that each mean “move leftwards”; default = 'left'.
- rightKeys** : A list of keys that each mean “move rightwards”; default = 'right'.
- respKeys** : A list of keys to use for selecting choices, in the desired order. The first item will be the left-most choice, the second item will be the next choice, and so on.
- skipKeys** : List of keys the subject can use to skip a response, default = 'tab'. To require a response to every item, set `skipKeys=None`.
- lineColor** : The RGB color to use for the scale line, default = 'White'.
- mouseOnly** : Require the subject to use the mouse (any keyboard input is ignored), default = `False`. Can be used to avoid competing with other objects for keyboard input.
- noMouse** : Require the subject to use keys to respond; disable and hide the mouse. *markerStart* will default to the left end.
- minTime** : Seconds that must elapse before a response can be accepted, default = 0.4.
- maxTime** : Seconds after which a response cannot be accepted. If `maxTime <= minTime`, there's no time limit. Default = 0.0 (no time limit).
- disappear** : Whether the rating scale should vanish after a value is accepted. Can be useful when showing multiple scales.
- flipVert** : Whether to mirror-reverse the rating scale in the vertical direction.

### 8.2.17 Rect

**class** `psychopy.visual.Rect` (*win, width=0.5, height=0.5, autoLog=None, \*\*kwargs*)

Creates a rectangle of given width and height as a special case of a *ShapeStim*

(New in version 1.72.00)

Rect accepts all input parameters, that *~psychopy.visual.ShapeStim* accept, except vertices and `closeShape`.

**mro** () → list  
return a type's method resolution order

### 8.2.18 Rift

#### Attributes

<i>Rift</i> ([fovType, trackingOriginType, ...])	Class provides a display and peripheral interface for the Oculus Rift (see: <a href="https://www.oculus.com/">https://www.oculus.com/</a> ) head-mounted display.
<i>Rift.productName</i>	Get the HMD's product name.
<i>Rift.manufacturer</i>	Get the connected HMD's manufacturer.
<i>Rift.serialNumber</i>	Get the connected HMD's unique serial number.
<i>Rift.firmwareVersion</i>	Get the firmware version of the active HMD.
<i>Rift.resolution</i>	Get the HMD's raster display size.
<i>Rift.displayRefreshRate</i>	Get the HMD's display refresh rate.
<i>Rift.trackingOriginType</i>	Current tracking origin type.
<i>Rift.getTrackingOriginType</i> ()	Get the current tracking origin type.

Continued on next page

Table 6 – continued from previous page

<code>Rift.setTrackinOrigin([origin_type, recenter])</code>	Set the tracking origin type.
<code>Rift.recenterTrackingOrigin()</code>	Recenter the tracking origin.
<code>Rift.shouldQuit</code>	Check if the user requested the application should quit through the headset's interface.
<code>Rift.isVisible</code>	Check if the app has focus in the HMD and is visible to the viewer.
<code>Rift.isHmdMounted</code>	Check if the HMD is mounted on the user's head.
<code>Rift.isHmdPresent</code>	Check if the HMD is present.
<code>Rift.shouldRecenter</code>	Check if the user requested the origin be recentered through the headset's interface.
<code>Rift.setBuffer(buffer[, clear])</code>	Set the active stereo draw buffer.
<code>Rift.absTime</code>	Get the absolute time for this frame.
<code>Rift.viewMatrix</code>	Get the view matrix for the current buffer.
<code>Rift.projectionMatrix</code>	Get the projection matrix for the current buffer.
<code>Rift.headLocked</code>	Enable/disable head locking.
<code>Rift.pollControllers()</code>	Update all connected controller states.
<code>Rift.flip([clearBuffer])</code>	Submit view buffer images to the HMD's compositor for display at next V-SYNC.
<code>Rift.multiplyViewMatrixGL()</code>	Multiply the local eye pose transformation matrix obtained from the SDK using <code>glMultMatrixf()</code> .
<code>Rift.multiplyProjectionMatrixGL()</code>	Multiply the current projection matrix obtained from the SDK using <code>glMultMatrixf()</code> .
<code>Rift.setRiftView([clearDepth])</code>	Set head-mounted display view.
<code>Rift.setDefaultView([clearDepth])</code>	Return to default projection.
<code>Rift.controllerConnected([controller])</code>	Check if a given device is connected to the Haptics engine.
<code>Rift.getConectedControllers()</code>	Get a list of connected input devices (controllers) managed by the LibOVR runtime.
<code>Rift.getThumbstickValues([controller, dead-zone])</code>	Get a list of tuples containing the displacement values (with deadzone) for each thumbstick on a specified controller.
<code>Rift.getIndexTriggerValues([controller, ...])</code>	Get the values of the index triggers representing the amount they are being displaced.
<code>Rift.getHandTriggerValues([controller, dead-zone])</code>	Get the values of the hand triggers representing the amount they are being displaced.
<code>Rift.getButtons(buttonNames[, controller, ...])</code>	Returns True if any of the buttons in <code>button_list</code> are held down.
<code>Rift.getTouches(touchNames[, edgeTrigger])</code>	Returns True if any buttons are touched using sensors.
<code>Rift.isIndexPointing([hand])</code>	Check if the user is doing a pointing gesture with the given hand, or if the index finger is not touching the controller.
<code>Rift.isThumbUp([hand])</code>	Check if the user's thumb is pointing upwards with a given hand, or if not touching the controller.
<code>Rift.raycastSphere(originPose, targetPose[, ...])</code>	Project an invisible ray of finite or infinite length from the <code>originPose</code> in <code>rayDirection</code> and check if it intersects with the <code>targetPose</code> bounding sphere.

## Details

**class** psychopy.visual.Rift (*fovType='recommended', trackingOriginType='eye', texelsPerPixel=1.0, headLocked=False, highQuality=True, nearClip=0.1, farClip=100.0, monoscopic=False, samples=1, mirrorRes=None, legacyOpenGL=True, warnAppFrameDropped=True, \*args, \*\*kwargs*)

Class provides a display and peripheral interface for the Oculus Rift (see: <https://www.oculus.com/>) head-mounted display.

### Parameters

- **fovType** (*str*) – Field-of-view (FOV) configuration type. Using 'recommended' auto-configures the FOV using the recommended parameters computed by the runtime. Using 'symmetric' forces a symmetric FOV using optimal parameters from the SDK.
- **trackingOriginType** (*str*) – Specify the HMD origin type. If 'floor', the height of the user is added to the head tracker by LibOVR.
- **texelsPerPixel** (*float*) – Texture pixels per display pixel at FOV center. A value of 1.0 results in 1:1 mapping. A fractional value results in a lower resolution draw buffer which may increase performance.
- **headLocked** (*bool*) – Lock the head position to the world origin. This cancels out any translation and rotation from the headset. Note, hand poses are NOT transformed accordingly (this will be addressed eventually).
- **highQuality** (*bool*) – Configure the compositor to use anisotropic texture sampling (4x). This reduces aliasing artifacts resulting from high frequency details particularly in the periphery.
- **nearClip** (*float*) – Location of the near clipping plane in GL units (meters by default) from the viewer.
- **farClip** (*float*) – Location of the far clipping plane in GL units (meters by default) from the viewer.
- **monoscopic** (*bool*) – Enable monoscopic rendering mode which presents the same image to both eyes. Eye poses used will be both centered at the HMD origin. Monoscopic mode uses a separate rendering pipeline which reduces VRAM usage. When in monoscopic mode, you do not need to call 'setBuffer' prior to rendering (doing so will do have no effect).
- **samples** (*int*) – Specify the number of samples for anti-aliasing. When >1, multi-sampling logic is enabled in the rendering pipeline. If 'max' is specified, the largest number of samples supported by the platform is used. If floating point textures are used, MSAA sampling is disabled. Must be power of two value.
- **legacyOpenGL** (*bool*) – Disable 'immediate mode' OpenGL calls in the rendering pipeline. Specifying False maintains compatibility with existing PsychoPy stimuli drawing routines. Use True when computing transformations using some other method and supplying shaders matrices directly.
- **mirrorRes** (*list of int*) – Resolution of the mirror texture. If None, the resolution will match the window size.
- **warnAppFrameDropped** (*bool*) – Log a warning if the application drops a frame. This occurs when the application fails to submit a frame to the compositor on-time. Application frame drops can have many causes, such as running routines in your application loop that take too long to complete. However, frame drops can happen sporadically due to driver bugs and running background processes (such as Windows Update). Use the performance HUD to help diagnose the causes of frame drops.



**`_prepareMonoFrame (clear=True)`**

Prepare a frame for monoscopic rendering. This is called automatically after ‘startHmdFrame’ if monoscopic rendering is enabled.

**`_resolveMSAA ()`**

Resolve multisample anti-aliasing (MSAA). If MSAA is enabled, drawing operations are diverted to a special multisample render buffer. Pixel data must be ‘resolved’ by blitting it to the swap chain texture. If not, the texture will be blank.

NOTE: You cannot perform operations on the default FBO (at frameBuffer) when MSAA is enabled. Any changes will be over-written when ‘flip’ is called.

**Returns**

**Return type** `None`

**`_setupFrameBuffer ()`**

Override the default framebuffer init code in window.Window to use the HMD swap chain. The HMD’s swap texture and render buffer are configured here.

If multisample anti-aliasing (MSAA) is enabled, a secondary render buffer is created. Rendering is diverted to the multi-sample buffer when drawing, which is then resolved into the HMD’s swap chain texture prior to committing it to the chain. Consequently, you cannot pass the texture attached to the FBO specified by frameBuffer until the MSAA buffer is resolved. Doing so will result in a blank texture.

**Returns**

**Return type** `None`

**`_startHmdFrame ()`**

Prepare to render an HMD frame. This must be called every frame before flipping or setting the view buffer.

This function will wait until the HMD is ready to begin rendering before continuing. The current frame texture from the swap chain are pulled from the SDK and made available for binding.

**Returns**

**Return type** `None`

**`_startOfFlip ()`**

Custom \_startOfFlip for HMD rendering. This finalizes the HMD texture before diverting drawing operations back to the on-screen window. This allows ‘flip()’ to swap the on-screen and HMD buffers when called. This function always returns True.

**Returns**

**Return type** `True`

**`_updatePerformanceStats ()`**

Run profiling routines. This just reports if the application drops a frame. Nothing too fancy yet.

**`_updateProjectionMatrix ()`**

Update or re-calculate projection matrices based on the current render descriptor configuration.

**Returns**

**Return type** `None`

**`_updateTrackingState ()`**

Update the tracking state and calculate new eye poses.

The absolute display time is updated when called and used when computing new head, eye and hand poses.

**Returns**

**Return type** `None`

**absTime**

Get the absolute time for this frame.

**controllerConnected** (*controller='xbox'*)

Check if a given device is connected to the Haptics engine.

**Parameters** **controller** (*str*) – Name of the controller to check if connected.

**Returns** True if specified controller connected, else False.

**Return type** `boolean`

**displayLost**

Check if the display has been lost.

**Returns**

**Return type** `bool`

**displayRefreshRate**

Get the HMD's display refresh rate. This rate is independent of the monitor display rate.

**Returns** Refresh rate in Hz.

**Return type** `float`

**firmwareVersion**

Get the firmware version of the active HMD. Returns a tuple containing the major and minor version.

**Returns** Firmware major and minor version.

**Return type** `tuple (int, int)`

**flip** (*clearBuffer=True*)

Submit view buffer images to the HMD's compositor for display at next V-SYNC. This must be called every frame.

**Parameters** **clearBuffer** (*boolean*) – Clear the frame after flipping.

**Returns**

**Return type** `None`

**getButtons** (*buttonNames, controller='xbox', edgeTrigger='continuous'*)

Returns True if any of the buttons in `button_list` are held down. All buttons are ORed together and tested. Edge triggering can be enabled by specifying either 'rising' or 'falling' to `edge_trigger`. When enabled, True is returned only when a button's state changes. If `button_list` is empty, will return True when no buttons are pressed.

Valid button values are 'A', 'B', 'RThumb', 'X', 'Y', 'LThumb', 'LShoulder', 'Up', 'Down', 'Left', 'Right', 'Enter', 'Back', 'VolUp', 'VolDown', 'Home', 'RMask' and 'LMask'.

**Returns**

**Return type** `bool`

## Examples

```
# check if the 'Enter' button on the Oculus remote was released
isPressed = getButtons(['Enter'], 'remote', 'falling')
```

#### **getConectedControllers ()**

Get a list of connected input devices (controllers) managed by the LibOVR runtime. Valid names are 'xbox', 'remote', 'left\_touch', 'right\_touch' and 'touch'.

**Returns** List of connected controller names.

**Return type** `list`

#### **getHandTriggerValues (controller='xbox', deadzone=False)**

Get the values of the hand triggers representing the amount they are being displaced.

##### **Parameters**

- **controller** (`str`) – Name of the controller to get hand trigger values.
- **deadzone** (`bool`) – Apply the deadzone to hand trigger values.

**Returns** Left and right index trigger values.

**Return type** `tuple`

#### **getIndexTriggerValues (controller='xbox', deadzone=False)**

Get the values of the index triggers representing the amount they are being displaced.

##### **Parameters**

- **controller** (`str`) – Name of the controller to get index trigger values.
- **deadzone** (`bool`) – Apply the deadzone to index trigger values.

**Returns** Left and right index trigger values.

**Return type** `tuple`

#### **getThumbstickValues (controller='xbox', deadzone=False)**

Get a list of tuples containing the displacement values (with deadzone) for each thumbstick on a specified controller.

Axis displacements are represented in each tuple by a floats ranging from -1.0 (full left/down) to 1.0 (full right/up). The SDK library pre-filters stick input to apply a dead-zone where 0.0 will be returned if the sticks return a displacement within -0.2746 to 0.2746. Index 0 of the returned tuple contains the X,Y displacement values of the left thumbstick, and the right thumbstick values at index 1.

Possible values for 'controller' are 'xbox' and 'touch'; the only devices with thumbsticks the SDK manages.

##### **Parameters**

- **controller** (`str`) – Name of the controller to get thumbstick values.
- **deadzone** (`bool`) – Apply the deadzone to thumbstick values.

**Returns** Left and right, X and Y thumbstick values.

**Return type** `tuple`

#### **getTouches (touchNames, edgeTrigger='continuous')**

Returns True if any buttons are touched using sensors. This feature is used to estimate finger poses and can be used to read gestures. An example of a possible use case is a pointing task, where responses are only valid if the user's index finger is extended away from the index trigger button.

Currently, this feature is only available with the Oculus Touch controllers.

**Returns**

**Return type** `None`

**getTrackingOriginType()**

Get the current tracking origin type.

**Returns**

**Return type** `str`

**hasInputFocus**

Check if the application currently has input focus.

**Returns**

**Return type** `bool`

**headLocked**

Enable/disable head locking.

**isHmdMounted**

Check if the HMD is mounted on the user's head.

**Returns** True if the HMD is being worn, otherwise False.

**Return type** `bool`

**isHmdPresent**

Check if the HMD is present.

**Returns** True if the HMD is present, otherwise False.

**Return type** `bool`

**isIndexPointing** (*hand='right'*)

Check if the user is doing a pointing gesture with the given hand, or if the index finger is not touching the controller. Only applicable when using Oculus Touch controllers.

**Returns**

**Return type** `None`

**isThumbUp** (*hand='right'*)

Check if the user's thumb is pointing upwards with a given hand, or if not touching the controller. Only applicable when using Oculus Touch controllers.

**Returns**

**Return type** `None`

**isVisible**

Check if the app has focus in the HMD and is visible to the viewer.

**Returns** True if app has focus and is visible in the HMD, otherwise False.

**Return type** `bool`

**manufacturer**

Get the connected HMD's manufacturer.

**Returns** UTF-8 encoded string containing the manufacturer name.

**Return type** `str`

**multiplyProjectionMatrixGL()**

Multiply the current projection matrix obtained from the SDK using `glMultMatrixf()`. The matrix used depends on the current eye buffer set by `'setBuffer()'`.

**Returns**

**Return type** `None`

**multiplyViewMatrixGL()**

Multiply the local eye pose transformation matrix obtained from the SDK using `glMultMatrixf()`. The matrix used depends on the current eye buffer set by `'setBuffer()'`.

**Returns**

**Return type** `None`

**overlayPresent**

**pollControllers()**

Update all connected controller states. This should be called at least once per frame.

**Returns**

**Return type** `None`

**productName**

Get the HMD's product name.

**Returns** UTF-8 encoded string containing the product name.

**Return type** `str`

**projectionMatrix**

Get the projection matrix for the current buffer.

**raycastSphere** (*originPose, targetPose, targetRadius=0.5, rayDirection=None, maxRange=None*)

Project an invisible ray of finite or infinite length from the `originPose` in `rayDirection` and check if it intersects with the `targetPose` bounding sphere.

Specifying `maxRange` as `>0.0` casts a ray of finite length in world units. The distance between the target and ray origin position are checked prior to casting the ray; automatically failing if the ray can never reach the edge of the bounding sphere centered about `targetPose`. This avoids having to do the costly transformations required for picking.

This raycast implementation can only determine if contact is being made with the object's bounding sphere, not where on the object the ray intersects. This method might not work for irregular or elongated objects since bounding spheres may not approximate those shapes well. In such cases, one may use multiple spheres at different locations and radii to pick the same object.

:param `originPose ovrPosef`: Origin pose of the ray. :param `targetPose ovrPosef` or: Pose of the target. :type `targetPose ovrPosef` or: `obj:ovrVector3f` :param `targetRadius :obj:'float'`: The radius of the target. :param `rayDirection ovrVector3f`: Vector indicating the direction for the ray. If `None` is specified,

then `-Z` is used.

**Parameters** `maxRange` – The maximum range of the ray. Ray testing will fail automatically if the target is out of range. The ray has infinite length if `None` is specified.

**Returns** True if the ray intersects anywhere on the bounding sphere, False in every other condition.

**Return type** `bool`

## Examples

```
# raycast from the head pose to a target headPose = hmd.headPose targetPos = rift.math.ovrVector3f(0.0, 0.0, -5.0) # 5 meters front
isLooking = hmd.raycast(headPose, targetPos)
```

```
# now with touch controller positions rightHandPose = hmd.getHandPose(1) # 1 = right hand fingerLength
= 0.10 # 10 cm pointing = hmd.raycast(rightHandPose, targetPos, maxRange=fingerLength)
```

**recenterTrackingOrigin()**

Recenter the tracking origin.

**Returns**

**Return type** `None`

**resolution**

Get the HMD's raster display size.

**Returns** Width and height in pixels.

**Return type** `tuple(int, int)`

**serialNumber**

Get the connected HMD's unique serial number. Use this to identify a particular unit if you own many.

**Returns** UTF-8 encoded string containing the devices serial number.

**Return type** `str`

**setBuffer(buffer, clear=True)**

Set the active stereo draw buffer.

Warning! The window.Window.size property will return the buffer's dimensions in pixels instead of the window's when setBuffer is set to 'left' or 'right'.

**Parameters**

- **buffer** (`str`) – View buffer to divert successive drawing operations to, can be either 'left' or 'right'.
- **clear** (`boolean`) – Clear the color, stencil and depth buffer.

**Returns**

**Return type** `None`

**setDefaultView(clearDepth=True)**

Return to default projection. Call this before drawing PsychoPy's 2D stimuli after a stereo projection change.

Note: This only has an effect if using Rift in legacy immediate mode OpenGL mode by setting `~Rift.legacy_opengl=True`.

**Parameters** **clearDepth** (`boolean`) – Clear the depth buffer prior after configuring the view parameters.

**Returns**

**Return type** `None`

**setHudMode(mode='Off')**

**setRiftView(clearDepth=True)**

Set head-mounted display view. Gets the projection and view matrices from the HMD and applies them.

Note: This only has an effect if using Rift in legacy immediate mode OpenGL mode by setting `~Rift.legacy_opengl=True`.

**Parameters** **clearDepth** (`boolean`) – Clear the depth buffer prior after configuring the view parameters.

**Returns**

**Return type** `None`

**setSize** (*value*, *log=True*)

**setTrackingOrigin** (*origin\_type='floor'*, *recenter=False*)

Set the tracking origin type. Can either be 'floor' or 'eye'. The effect of changing types is immediate.

**Parameters**

- **origin\_type** (*str*) – Tracking origin type to use, can be either 'floor' or 'eye'.
- **recenter** (*boolean*) – If True, the tracking origin is applied immediately.

**Returns**

**Return type** `None`

**shouldQuit**

Check if the user requested the application should quit through the headset's interface.

**Returns** True if user requested the application quit via some menu in the HMD, otherwise False.

**Return type** `bool`

**shouldRecenter**

Check if the user requested the origin be recentered through the headset's interface.

**Returns** True if user requested the application recenter itself to reposition the origin, else False.

**Return type** `bool`

**size**

Size property to get the dimensions of the view buffer instead of the window. If there are no view buffers, always return the dims of the window.

**trackingOriginType**

Current tracking origin type.

**viewMatrix**

Get the view matrix for the current buffer.

## 8.2.19 EnvelopeGrating

### Attributes

### Details

```
class psychopy.visual.EnvelopeGrating (win, carrier='noise', mask='none', envelope='sin',
                                         units="", pos=(0.0, 0.0), size=None, sf=None, envsf=None, ori=0.0, envori=0.0, phase=(0.0, 0.0),
                                         envphase=(0.0, 0.0), beat=False, texRes=128,
                                         rgb=None, dcl=None, lms=None, color=(1.0, 1.0, 1.0), colorSpace='rgb', contrast=0.5, moddepth=1.0,
                                         power=1.0, opacity=1.0, depth=0, rgbPedestal=(0.0, 0.0, 0.0), interpolate=False, blendmode='avg',
                                         name=None, autoLog=None, autoDraw=False,
                                         maskParams=None)
```

Second-order envelope stimuli with 3 textures; a carrier, an envelope and a mask

**Examples:**

**env1 = EnvelopeGrating(win,ori=0, carrier='sin', envelope='sin', mask = 'gauss', sf=24, envsf=4, size=1, contrast=0.5, moddepth=1.0, envori=0, pos=[-.5,.5],interpolate=0)** # gives a circular patch of high frequency carrier with a # low frequency envelope

**env2 = EnvelopeGrating(win,ori=0, carrier=noise, envelope='sin', mask = None, sf=1, envsf=4, size=1, contrast=0.5, moddepth=0.8, envori=0, pos=[-.5,.5],interpolate=0)** # If noise is some numpy array containing random values gives a # patch of noise with a low frequency sinewave envelope

**env4 = EnvelopeGrating(win,ori=90, carrier='sin', envelope='sin', mask = 'gauss', sf=24, envsf=4, size=1, contrast=0.5, moddepth=1.0, envori=0, pos=[.5,.5], beat=True, interpolate=0)** # Setting beat will create a second order beat stimulus which # critically contains no net energy at the carrier frequency # even though it appears to be present. In this case carrier # and envelope are at 90 degree to each other

With an EnvelopeStim the carrier and envelope can have different spatial frequencies, phases and orientations. Its position can be shifted as a whole.

contrast controls the contrast of the carrier and moddepth the modulation depth of the envelope. contrast and moddepth must work together, for moddepth=1 the max carrier contrast is 0.5 otherwise the displayable range will be exceeded. If moddepth < 1 higher contrasts can be accommodated.

Opacity controls the transparency of the whole stimulus.

Because orientation is implemented very differently for the carrier and envelope using this function without a broadly circular mask may produce unexpected results

#### Using EnvelopeStim with images from disk (jpg, tif, png, ...)

Ideally texture images to be rendered should be square with 'power-of-2' dimensions e.g. 16x16, 128x128. Any image that is not will be upsampled (with linear interpolation) to the nearest such texture by PsychoPy. The size of the stimulus should be specified in the normal way using the appropriate units (deg, pix, cm, ...). Be sure to get the aspect ratio the same as the image (if you don't want it stretched!).

**mro()** → list  
return a type's method resolution order

## 8.2.20 ShapeStim

### Attributes

<i>ShapeStim</i> (win[, units, lineWidth, ...])	A class for arbitrary shapes defined as lists of vertices (x,y).
<i>ShapeStim.win</i>	The <i>Window</i> object in which the
<i>ShapeStim.units</i>	None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'
<i>ShapeStim.vertices</i>	A list of lists or a numpy array (Nx2) specifying xy positions of each vertex, relative to the center of the field.
<i>ShapeStim.closeShape</i>	True or False Should the last vertex be automatically connected to the first?
<i>ShapeStim.pos</i>	The position of the center of the stimulus in the stimulus <i>units</i>
<i>ShapeStim.ori</i>	The orientation of the stimulus (in degrees).
<i>ShapeStim.size</i>	Int/Float or <i>x,y-pair</i> .
<i>ShapeStim.contrast</i>	A value that is simply multiplied by the color
<i>ShapeStim.lineColor</i>	Sets the color of the shape lines.
<i>ShapeStim.lineColorSpace</i>	Sets color space for line color.

Continued on next page



Table 7 – continued from previous page

<i>ShapeStim.fillColor</i>	Sets the color of the shape fill.
<i>ShapeStim.fillColorSpace</i>	Sets color space for fill color.
<i>ShapeStim.opacity</i>	Determines how visible the stimulus is relative to background
<i>ShapeStim.interpolate</i>	True or False If True the edge of the line will be antialiased.
<i>ShapeStim.name</i>	String or None.
<i>ShapeStim.autoLog</i>	Whether every change in this stimulus should be auto logged.
<i>ShapeStim.draw([win, keepMatrix])</i>	Draw the stimulus in the relevant window.
<i>ShapeStim.autoDraw</i>	Determines whether the stimulus should be automatically drawn on every frame flip.

## Details

```
class psychopy.visual.ShapeStim(win, units="", lineWidth=1.5, lineColor='white', line-
    ColorSpace='rgb', fillColor=None, fillColorSpace='rgb',
    vertices=(-0.5, 0), (0, 0.5), (0.5, 0)), windingRule=None,
    closeShape=True, pos=(0, 0), size=1, ori=0.0, opacity=1.0,
    contrast=1.0, depth=0, interpolate=True, name=None,
    autoLog=None, autoDraw=False)
```

A class for arbitrary shapes defined as lists of vertices (x,y).

Shapes can be lines, polygons (concave, convex, self-crossing), or have holes or multiple regions.

*vertices* is typically a list of points (x,y). By default, these are assumed to define a closed figure (polygon); set *closeShape=False* for a line. *closeShape* cannot be changed dynamically, but individual vertices can be changed on a frame-by-frame basis. The stimulus as a whole can be rotated, translated, or scaled dynamically (using *.ori*, *.pos*, *.size*).

Vertices can be a string, giving the name of a known set of vertices, although “cross” is the only named shape available at present.

Advanced shapes: *vertices* can also be a list of loops, where each loop is a list of points (x,y), e.g., to define a shape with a hole. Borders and *contains()* are not supported for multi-loop stimuli.

*windingRule* is an advanced feature to allow control over the GLU tessellator winding rule (default: GLU\_TESS\_WINDING\_ODD). This is relevant only for self-crossing or multi-loop shapes. Cannot be set dynamically.

See Coder demo > stimuli > shapes.py

Changed Nov 2015: v1.84.00. Now allows filling of complex shapes. This is almost completely backwards compatible (see changelog). The old version is accessible as *psychopy.visual.BaseShapeStim*.

**\_\_calcPosRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by *\_updateVertices()* and *verticesPix*.

**\_\_calcSizeRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by *\_updateVertices()* and *verticesPix*

**\_\_getDesiredRGB** (*rgb, colorSpace, contrast*)

Convert color to RGB while adding contrast. Requires *self.rgb*, *self.colorSpace* and *self.contrast*

**\_\_getPolyAsRendered()**

DEPRECATED. Return a list of vertices as rendered.

**\_selectWindow** (*win*)

Switch drawing to the specified window. Calls the window's `_setCurrent()` method which handles the switch.

**\_set** (*attrib, val, op="", log=None*)

DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

**\_tessellate** (*newVertices*)

Set the `.vertices` and `.border` to new values, invoking tessellation.

**\_updateList** ()

The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

**\_updateVertices** ()

Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

**autoDraw**

Determines whether the stimulus should be automatically drawn on every frame flip.

Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**autoLog**

Whether every change in this stimulus should be auto logged.

Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every

frame) and you want to avoid swamping the log file with

messages that aren't likely to be useful.

**closeShape**

True or False Should the last vertex be automatically connected to the first?

If you're using *Polygon*, *Circle* or *Rect*, `closeShape=True` is assumed and shouldn't be changed.

**color**

**colorSpace**

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default `colorSpace` for the stimulus is used (defined during initialisation).

Please note that changing `colorSpace` does not change stimulus parameters. Thus you usually want to specify `colorSpace` before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                      color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'

# Make it light green again
stim.color = (128, 255, 128)
```

**contains** (*x, y=None, units=None*)

Returns True if a point `x,y` is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a `getPos()` method that returns x,y, such as a `Mouse`.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (*pos*), and orientation (*ori*) settings (and by the vertices for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

### contrast

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

### depth

DEPRECATED. Depth is now controlled simply by drawing order.

### draw (win=None, keepMatrix=False)

Draw the stimulus in the relevant window. You must call this method after every `win.flip()` if you want the stimulus to appear on that frame and then update the screen again.

### fillColor

Sets the color of the shape fill.

See `psychopy.visual.GratingStim.color()` for further details of how to use colors.

Note that shapes where some vertices point inwards will usually not ‘fill’ correctly.

### fillColorSpace

Sets color space for fill color. See documentation for `fillColorSpace`

### interpolate

True or False If True the edge of the line will be antialiased.

### lineColor

Sets the color of the shape lines.

See `psychopy.visual.GratingStim.color()` for further details of how to use colors.

### **lineColorSpace**

Sets color space for line color. See documentation for lineColorSpace

### **lineWidth**

int or float specifying the line width in **pixels**

*Operations* supported.

### **name**

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called “unnamed <type>”, e.g. visual.TextStim(win) will be called “unnamed TextStim” in the logs.

### **opacity**

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

### **ori**

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

### **overlaps** (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, shapeContains.py

### **pos**

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
# Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
# Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix
posPix = posToPix(stim)
```

### **setAutoDraw** (*value*, *log=None*)

Sets autoDraw. Usually you can use ‘stim.attribute = value’ syntax instead, but use this method to suppress the log message.

**setAutoLog** (*value=True, log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setColor** (*color, colorSpace=None, operation="", log=None*)

Sets both the line and fill to be the same color

**setContrast** (*newContrast, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setDKL** (*newDKL, operation=""*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setDepth** (*newDepth, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setFillColor** (*color, colorSpace=None, operation="", log=None*)

Sets the color of the shape fill.

See [psychopy.visual.GratingStim.color\(\)](#) for further details.

Note that shapes where some vertices point inwards will usually not ‘fill’ correctly.

**setFillRGB** (*value, operation=""*)

DEPRECATED since v1.60.05: Please use [fillColor\(\)](#)

**setLMS** (*newLMS, operation=""*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setLineColor** (*color, colorSpace=None, operation="", log=None*)

Sets the color of the shape edge.

See [psychopy.visual.GratingStim.color\(\)](#) for further details.

**setLineRGB** (*value, operation=""*)

DEPRECATED since v1.60.05: Please use [lineColor\(\)](#)

**setLineWidth** (*value, operation="", log=None*)

**setOpacity** (*newOpacity, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPos** (*newPos, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB, operation="", log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSize** (*value, operation="", log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setUseShaders** (*value=True, log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setVertices** (*value=None, operation="", log=None*)

Usually you can use 'stim.attribute = value' syntax instead, but use this method if you need to suppress the log message

**size**

Int/Float or *x,y-pair*. Sets the size of the shape. Size is independent of the units of shape and will simply scale the shape's vertices by the factor given. Use a tuple or list of two values to scale asymmetrically.

*Operations* supported.

**units**

None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don't change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5)

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

**useShaders**

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

**vertices**

A list of lists or a numpy array (Nx2) specifying xy positions of each vertex, relative to the center of the field.

Assigning to vertices can be slow if there are many vertices.

*Operations* supported with *.setVertices()*.

**verticesPix**

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

**win**

The *Window* object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (win1, win2 and stim):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw() # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw() # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
# monitor update
win2.flip() # wait for vertical blanking.
```

Note that this just changes *\*\*default\*\** window **for** stimulus. You could also specify window-to-draw-to when drawing::

(continues on next page)

(continued from previous page)

```
stim.draw(win1)
stim.draw(win2)
```

### 8.2.21 SimpleImageStim

```
class psychopy.visual.SimpleImageStim(win, image="", units="", pos=(0.0, 0.0),
                                       flipHoriz=False, flipVert=False, name=None, autoLog=None)
```

A simple stimulus for loading images from a file and presenting at exactly the resolution and color in the file (subject to gamma correction if set).

Unlike the ImageStim, this type of stimulus cannot be rescaled, rotated or masked (although flipping horizontally or vertically is possible). Drawing will also tend to be marginally slower, because the image isn't preloaded to the graphics card. The slight advantage, however is that the stimulus will always be in its original aspect ratio, with no interpolation or other transformation, and it is slightly faster to load into PsychoPy.

**mro()** → list  
return a type's method resolution order

### 8.2.22 Slider

#### Attributes

<i>Slider</i> (win[, ticks, labels, pos, size, ...])	A class for obtaining ratings, e.g., on a 1-to-7 or categorical scale.
<i>Slider.getRating</i> ()	Get the current value of rating (or None if no response yet)
<i>Slider.getRT</i> ()	Get the RT for most recent rating (or None if no response yet)
<i>Slider.markerPos</i>	The position on the scale where the marker should be.
<i>Slider.setReadOnly</i> ([value, log])	When the rating scale is read only no responses can be made and the scale contrast is reduced
<i>Slider.contrast</i>	Set all elements of the Slider (labels, ticks, line) to a contrast
<i>Slider.style</i>	Sets some predefined styles or use these to create your own.
<i>Slider.getHistory</i> ()	Return a list of the subject's history as (rating, time) tuples.
<i>Slider.getMouseResponses</i> ()	Instructs the rating scale to check for valid mouse responses.
<i>Slider.reset</i> ()	Resets the slider to its starting state (so that it can be restarted on each trial with a new stimulus)

## Details

```
class psychopy.visual.Slider(win, ticks=(1, 2, 3, 4, 5), labels=None, pos=None, size=None,
                             units=None, flip=False, style='rating', granularity=0, read-
                             Only=False, color='LightGray', font='Helvetica Bold', depth=0,
                             name=None, labelHeight=None, labelWrapWidth=None, auto-
                             Draw=False, autoLog=True)
```

A class for obtaining ratings, e.g., on a 1-to-7 or categorical scale.

A simpler alternative to RatingScale, to be customised with code rather than with arguments.

A RatingScale instance is a re-usable visual object having a `draw()` method, with customizable appearance and response options. `draw()` displays the rating scale, handles the subject's mouse or key responses, and updates the display. When the subject accepts a selection, `.noResponse` goes `False` (i.e., there is a response).

You can call the `getRating()` method anytime to get a rating, `getRT()` to get the decision time, or `getHistory()` to obtain the entire set of (rating, RT) pairs.

For other examples see Coder Demos -> stimuli -> slider.py.

### Authors

- 2018: Jon Peirce

### Parameters

- **win** (`psychopy.visual.Window`) – Into which the scale will be rendered
- **ticks** (*list or tuple*) – A set of values for tick locations. If given a list of numbers then these determine the locations of the ticks (the first and last determine the endpoints and the rest are spaced according to their values between these endpoints).
- **labels** (*a list or tuple*) – The text to go with each tick (or spaced evenly across the ticks). If you give 3 labels but 5 tick locations then the end and middle ticks will be given labels. If the labels can't be distributed across the ticks then an error will be raised. If you want an uneven distribution you should include a list matching the length of ticks but with some values set to `None`
- **pos** (*XY pair (tuple, array or list)*) –
- **size** (*w,h pair (tuple, array or list)*) – The size for the scale defines the area taken up by the line and the ticks. This also controls whether the scale is horizontal or vertical.
- **units** (*the units to interpret the pos and size*) –
- **flip** (*bool*) – By default the labels will be below or left of the line. This puts them above (or right)
- **granularity** (*int or float*) – The smallest valid increments for the scale. 0 gives a continuous (e.g. “VAS”) scale. 1 gives a traditional likert scale. Something like 0.1 gives a limited fine-grained scale.
- **color** – Color of the line/ticks/labels according to the color space
- **font** (*font name*) –
- **autodraw** –
- **depth** –
- **name** –
- **autoLog** –



**\_granularRating** (*rating*)

Handle granularity for the rating

**\_setLabelLocs** ()

Calculates the locations of the line, tickLines and labels from the rating info

**\_setTickLocs** ()

Calculates the locations of the line, tickLines and labels from the rating info

**color**

Color of the line/ticks/labels according to the color space.

**contrast**

Set all elements of the Slider (labels, ticks, line) to a contrast

**Parameters contrast** –

**draw** ()

Draw the Slider, with all its constituent elements on this frame

**getHistory** ()

Return a list of the subject's history as (rating, time) tuples.

The history can be retrieved at any time, allowing for continuous ratings to be obtained in real-time. Both numerical and categorical choices are stored automatically in the history.

**getMouseResponses** ()

Instructs the rating scale to check for valid mouse responses.

This is usually done during the draw() method but can be done by the user as well at any point in time. The rating will be returned but will ALSO automatically be set as the current rating response.

While the mouse button is down we will alter self.markerPos but don't set a value for self.rating until button comes up

**Returns**

**Return type** A rating value or `None`

**getRT** ()

Get the RT for most recent rating (or None if no response yet)

**getRating** ()

Get the current value of rating (or None if no response yet)

**horiz**

(readonly) determines from self.size whether the scale is horizontal

**knownStyles** = ['slider', 'rating', 'radio', 'labels45', 'whiteOnBlack', 'triangleMarker']

**markerPos**

The position on the scale where the marker should be. Note that this does not alter the value of the reported rating, only its visible display. Also note that this position is in scale units, not in coordinates

**pos**

Set position of slider

**Parameters value** (*tuple*, *list*) – The new position of slider

**rating**

The most recent rating from the participant or None. Note that the position of the marker can be set using current without looking like a change in the marker position

**recordRating** (*rating*, *rt=None*, *log=None*)

Sets the current rating value

### **reset ()**

Resets the slider to its starting state (so that it can be restarted on each trial with a new stimulus)

### **setReadOnly (value=True, log=None)**

When the rating scale is read only no responses can be made and the scale contrast is reduced

#### **Parameters**

- **value** (*bool* (*True*)) – The value to which we should set the readOnly flag
- **log** (*bool* or *None*) – Force the autologging to occur or leave as default

### **size**

The size for the scale defines the area taken up by the line and the ticks.

### **style**

Sets some predefined styles or use these to create your own.

If you fancy creating and including your own styles that would be great!

**Parameters style** (*list of strings*) – Known styles currently include:

‘rating’: the marker is a circle ‘triangleMarker’: the marker is a triangle ‘slider’: looks more like an application slider control ‘whiteOnBlack’: a sort of color-inverse rating scale ‘labels45’ the text is rotated by 45 degrees

Styles can be combined in a list e.g. [*‘whiteOnBlack’, ‘labels45’*]

## 8.2.23 TextBox

### Attributes

<i>TextBox</i> ([window, text, font_name, bold, ...])	Similar to the visual.TextStim component, TextBox can be used to display text within a psychopy window.
---	---

**Note:** The following *set\_\_\_\_\_()* attributes all have equivalent *get\_\_\_\_\_()* attributes:

<i>TextBox.setText(text_source)</i>	Set the text to be displayed within the Textbox.
<i>TextBox.setPosition(pos)</i>	Set the (x,y) position of the TextBox on the Monitor.
<i>TextBox.setOri</i>	
<i>TextBox.setHorzAlign(v)</i>	Specify how the horizontal (x) component of the TextBox position is to be interpreted.
<i>TextBox.setVertAlign(v)</i>	Specify how the vertical (y) component of the TextBox position is to be interpreted.
<i>TextBox.setHorzJust(v)</i>	Specify how text within the TextBox should be aligned horizontally.
<i>TextBox.setVertJust(v)</i>	Specify how text within the TextBox should be aligned vertically.
<i>TextBox.setFontColor(c)</i>	Set the color to use when drawing text glyphs within the TextBox.
<i>TextBox.setBorderColor(c)</i>	Set the color to use for the border of the textBox.
<i>TextBox.setBackgroundColor(c)</i>	Set the fill color used to fill the rectangular area of the TextBox stim.

Continued on next page

Table 10 – continued from previous page

<code>TextBox.setTextGridLineColor(c)</code>	Set the color used when drawing text grid lines.
<code>TextBox.setTextGridLineWidth(c)</code>	Set the stroke width (in pixels) to use for the text grid character bounding boxes.
<code>TextBox.setInterpolated(interpolate)</code>	Specify whether interpolation should be enabled for the TextBox when it is drawn.
<code>TextBox.setOpacity(o)</code>	Sets the TextBox transparency level to use for color related attributes of the Textbox.
<code>TextBox.setAutoLog(v)</code>	Specify if changes to textBox attribute values should be logged automatically by PsychoPy.
<code>TextBox.draw()</code>	Draws the TextBox to the back buffer of the graphics card.

**Note:** TextBox also provides the following read-only functions:

<code>TextBox.getSize()</code>	Return the width,height of the TextBox, using the unit type being used by the stimulus.
<code>TextBox.getName()</code>	Same as the GetLabel method.
<code>TextBox.getDisplayedText()</code>	Return the text that fits within the TextBox and therefore is actually seen.
<code>TextBox.getValidStrokeWidths()</code>	Returns the stroke width range supported by the graphics card being used.
<code>TextBox.getLineSpacing()</code>	Return the additional spacing being applied between rows of text.
<code>TextBox.getGlyphPositionForTextIndex(char_index)</code>	FontManager provided char_index, which is the index of one character in
<code>TextBox.getTextGridCellPlacement()</code>	Returns a 3d numpy array containing position information for each text grid cell in the TextBox.

## Helper functions:

### getFontManager()

FontManager provides a simple API for finding and loading font files (.ttf) via the FreeType lib

The FontManager finds supported font files on the computer and initially creates a dictionary containing the information about available fonts. This can be used to quickly determine what font family names are available on the computer and what styles (bold, italic) are supported for each family.

This font information can then be used to create the resources necessary to display text using a given font family, style, size, color, and dpi.

The FontManager is currently used by the psychopy.visual.TextBox stim type. A user script can access the FontManager via:

```
font_mgr=visual.textbox.getFontManager()
```

Once a font of a given size and dpi has been created; it is cached by the FontManager and can be used by all TextBox instances created within the experiment.

## Details

```
class psychopy.visual.TextBox (window=None, text='Default Test Text.', font_name=None,
                                bold=False, italic=False, font_size=32, font_color=(0, 0,
0, 1), dpi=72, line_spacing=0, line_spacing_units='pix',
                                background_color=None, border_color=None, border_stroke_width=1,
                                size=None, textgrid_shape=None, pos=(0.0, 0.0), align_horz='center', align_vert='center',
                                units='norm', grid_color=None, grid_stroke_width=1,
                                color_space='rgb', opacity=1.0, grid_horz_justification='left',
                                grid_vert_justification='top', autoLog=True, interpolate=False,
                                name=None)
```

Similar to the visual.TextStim component, TextBox can be used to display text within a psychopy window. TextBox and TextStim each have different strengths and weaknesses. You should select the most appropriate text component type based on how it will be used within the experiment.

NOTE: As of PsychoPy 1.79, TextBox should be considered experimental. The two TextBox demo scripts provided have been tested on all PsychoPy supported OS's and run without exceptions. However there are very likely bugs in the existing TextBox code and the TextBox API will be further enhanced and improved (i.e. changed) over the next couple months.

- Text character placement is very well defined, useful when the exact positioning of each letter needs to be known.
- The text string that is displayed can be changed ( setText() ) and drawn ( win.draw() ) **very** quickly. See the TextBox vs. TextStim comparison table for details.
- Built-in font manager; providing easy access to the font family names and styles that are available on the computer being used.
- TextBox is a composite stimulus type, with the following graphical elements:
  - TextBox Border / Outline
  - TextBox Fill Area
  - Text Grid Cell Lines
  - Text Glyphs

Attributes for each of the TextBox graphical elements can be changed to control many aspects of how the TextBox is displayed.

- When using 'rgb' or 'rgb255' color spaces, colors can be specified as a list/tuple of 3 elements (red, green, blue), or with four elements (red, green, blue, alpha) which allows different elements of the TextBox to use different opacity settings if desired. For colors that include the alpha channel value, it will be applied instead of the opacity setting of the TextBox, effectively overriding the stimulus defined opacity for that part of the textbox graphics. Colors that do not include an alpha channel use the opacity setting as normal.
- Text Line Spacing can be controlled.
- Only Monospace Fonts are supported.
- TextBox component is not a completely **standard** psychopy visual stim and has the following functional difference:
  - TextBox attributes are never accessed directly; get\* and set\* methods are always used (this will be changed to use class properties in the future).
  - Setting an attribute of a TextBox only supports value replacement, ( textbox.setFontColor([1.0,1.0,1.0]) ) and does not support specifying operators.

- Some key word arguments supported by other stimulus types in general, or by TextStim itself, are not supported by TextBox. See the TextBox class definition for the arguments that are supported.
- When a new font, style, and size are used it takes about 1 second to load and process the font. This is a one time delay for a given font name, style, and size. After first being loaded, the same font style can be used or re-applied to multiple TextBox components with no significant delay.
- Auto logging or auto drawing is not currently supported.

Feature	TextBox	TextStim
Change text + redraw time^	1.513 msec	28.537 msec
No change + redraw time^	0.240 msec	0.931 msec
Initial Creation time^	0.927 msec	0.194 msec
MonoSpace Font Support	Yes	Yes
Non MonoSpace Font Support	No	Yes
Adjustable Line Spacing	Yes	No
Precise Text Pos. Info	Yes	No
Auto logging Support	No	Yes
Rotation Support	No	Yes
Word Wrapping Support	Yes	Yes

^ Times are in msec.usec format. Tested using the `textstim_vs_textbox.py` demo script provided with the PsychoPy distribution. Results are dependent on text length, video card, and OS. Displayed results are based on 120 character string with an average of 24 words. Test computer used Windows 7 64 bit, PsychoPy 1.79, with a i7 3.4 Ghz CPU, 8 GB RAM, and NVIDIA 480 GTX 2GB graphics card.

```

from psychopy import visual

win=visual.Window(...)

# A Textbox stim that will look similar to a TextStim component #
textstimlike=visual.TextBox(
    window=win, text='This textbox looks most like a textstim.', font_size=18,
    font_color=[-1,-1,1], color_space='rgb', size=(1.8,.1), pos=(0.0,.5), units='norm'
)

# A Textbox stim that uses more of the supported graphical features #
textboxloaded=visual.TextBox(
    window=win text='TextBox showing all supported graphical elements', font_size=32,
    font_color=[1,1,1], border_color=[-1,-1,1], # draw a blue border around stim
    border_stroke_width=4, # border width of 4 pix.
    background_color=[-1,-1,-1], # fill the stim
    background_grid_color=[1,-1,-1,0.5], # draw a red line around each
    # possible letter area, # 50% transparent
    grid_stroke_width=1, # with a width of 1 pix
    textgrid_shape=[20,2], # specify area of text
    box
    # by the number of cols x # number of rows of text to support # instead of by a
    screen # units width x height.
    pos=(0.0,-.5), # If the text string length < num rows * num cols in #
    textgrid_shape, how should text be justified? # grid_horz_justification='center',
    grid_vert_justification='center', )

textstimlike.draw() textboxloaded.draw() win.flip()

```

**draw()**

Draws the TextBox to the back buffer of the graphics card. Then call win.flip() to display the changes drawn. If draw() is not called prior to a call to win.flip(), the textBox will not be displayed for that retrace.

**getAutoLog()**

Indicates if changes to textBox attribute values should be logged automatically by PsychoPy. \*Currently not supported by TextBox.

**getBackgroundColor()**

Get the color used to fill the rectangular area of the TextBox stim. All other graphical elements of the TextBox are drawn on top of the background.

**getBorderColor()**

A border can be drawn around the perimeter of the TextBox. This method sets the color of that border.

**getBorderWidth()**

Get the stroke width of the optional TextBox area outline. This is always given in pixel units.

**getColorSpace()**

Returns the psychopy color space used when specifying colors for the TextBox. Supported values are:

- 'rgb'
- 'rbg255'
- 'norm'
- hex (implicit)
- html name (implicit)

See the Color Space section of the PsychoPy docs for details.

**getDisplayedText()**

Return the text that fits within the TextBox and therefore is actually seen. This is equal to:

```
text_length=len(self.getText()) cols,rows=self.getTextGridShape()
displayed_text=self.getText()[0:min(text_length,rows*cols)]
```

**getFontColor()**

Return the color used when drawing text glyphs.

**getGlyphPositionForTextIndex(char\_index)**

For the provided char\_index, which is the index of one character in the current text being displayed by the TextBox ( getDisplayedText() ), return the bounding box position, width, and height for the associated glyph drawn to the screen. This factors in the glyphs position within the textgrid cell it is being drawn in, so the returned bounding box is for the actual glyph itself, not the textgrid cell. For textgrid cell placement information, see the getTextGridCellPlacement() method.

The glyph position for the given text index is returned as a tuple (x,y,width,height), where x,y is the top left hand corner of the bounding box.

**Special Cases:**

- If the index provided is out of bounds for the currently displayed text, None is returned.
- For u' ' (space) characters, the full textgrid cell bounding box is returned.
- For u'

' ( new line ) characters,the textgrid cell bounding box is returned, but with the box width set to 0.

**getHorzAlign()**

Return what textbox x position should be interpreted as. Valid options are 'left', 'center', or 'right'.

**getHorzJust()**

Return how text should be laid out horizontally when the number of columns of each text grid row is greater than the number needed to display the text for that text row.

**getInterpolated()**

Returns whether interpolation is enabled for the TextBox when it is drawn. When True, GL\_LINE\_SMOOTH and GL\_POLYGON\_SMOOTH are enabled within OpenGL; otherwise they are disabled.

**getLabel()**

Return the label / name assigned to the textbox. This does not impact how the stimulus looks when drawn, and instead is used for internal purposes only.

**getLineSpacing()**

Return the additional spacing being applied between rows of text. The value is in units specified by the textbox getUnits() method.

**getName()**

Same as the GetLabel method.

**getOpacity()**

Get the default TextBox transparency level used for color related attributes. 0.0 equals fully transparent, 1.0 equals fully opaque.

**getPosition()**

Return the x,y position of the textbox, in getUnitType() coord space.

**getSize()**

Return the width,height of the TextBox, using the unit type being used by the stimulus.

**getText()**

Return the text to display.

**getTextGridCellForCharIndex(char\_index)**

**getTextGridCellPlacement()**

Returns a 3d numpy array containing position information for each text grid cell in the TextBox. The array has the shape (num\_cols,num\_rows,cell\_bounds), where num\_cols is the number of textgrid columns in the TextBox. num\_rows is the number of textgrid rows in the TextBox. cell\_bounds is a 4 element array containing the (x pos, y pos, width, height) data for the given cell. Position fields are for the top left hand corner of the cell box. Column and Row indices start at 0.

To get the shape of the textgrid in terms of columns and rows, use:

```
cell_pos_array=textbox.getTextGridCellPlacement() col_row_count=cell_pos_array.shape[:2]
```

To access the position, width, and height for textgrid cell at column 0 and row 0 (so the top left cell in the textgrid):

```
cell00=cell_pos_array[0,0,:]
```

For the cell at col 3, row 1 (so 4th cell on second row):

```
cell41=cell_pos_array[4,1,:]
```

**getTextGridLineColor()**

Return the color used when drawing the outline of the text grid cells. Each letter displayed in a TextBox populates one of the text cells defined by the shape of the TextBox text grid. Color value must be valid for the color space being used by the TextBox.

A value of None indicates drawing of the textgrid lines is disabled.

**getTextGridLineWidth ()**

Return the stroke width (in pixels) of the optional lines drawn around the text grid cell areas.

**getUnitType ()**

Returns which of the psychopy coordinate systems are used by the TextBox. Position and size related attributes must be specified relative to the unit type being used. Valid options are:

- pix
- norm
- cm

**getValidStrokeWidths ()**

Returns the stroke width range supported by the graphics card being used. If the TextBox is Interpolated, a tuple is returned using float values, with the following structure:

((min\_line\_width, max\_line\_width), line\_width\_granularity)

If Interpolation is disabled for the TextBox, the returned tuple elements are int values, with the following structure:

(min\_line\_width, max\_line\_width)

**getVertAlign ()**

Return what textbox y position should be interpreted as. Valid options are 'top', 'center', or 'bottom'.

**getVertJust ()**

Return how text should be laid out vertically when the number of text grid rows is greater than the number needed to display the current text

**getWindow ()**

Returns the psychopy window that the TextBox is associated with.

**setAutoLog (v)**

Specify if changes to TextBox attribute values should be logged automatically by PsychoPy. True enables auto logging; False disables it. \*Currently not supported by TextBox.

**setBackgroundColor (c)**

Set the fill color used to fill the rectangular area of the TextBox stim. Color value must be valid for the color space being used by the TextBox.

A value of None will disable drawing of the TextBox background.

**setBorderColor (c)**

Set the color to use for the border of the TextBox. The TextBox border is a rectangular outline drawn around the edges of the TextBox stim. Color value must be valid for the color space being used by the TextBox.

A value of None will disable drawing of the border.

**setBorderWidth (c)**

Set the stroke width (in pixels) to use for the border of the TextBox stim. Border values must be within the range of stroke widths supported by the OpenGL driver used by the graphics. Setting the width outside the valid range will result in the stroke width being clamped to the nearest end of the valid range.

Use the TextBox.getValidStrokeWidths() to access the minimum - maximum range of valid line widths.

**setFontColor (c)**

Set the color to use when drawing text glyphs within the TextBox. Color value must be valid for the color space being used by the TextBox. For 'rgb', 'rgb255', and 'norm' based colors, three or four element lists



are valid. Three element colors use the TextBox getOpacity() value to determine the alpha channel for the color. Four element colors use the value of the fourth element to set the alpha value for the color.

**setHorzAlign** (*v*)

Specify how the horizontal (x) component of the TextBox position is to be interpreted. left = x position is the left edge, right = x position is the right edge x position, and center = the x position is used to center the stim horizontally.

**setHorzJust** (*v*)

Specify how text within the TextBox should be aligned horizontally. For example, if a text grid has 10 columns, and the text being displayed is 6 characters in length, the horizontal justification determines if the text should be draw starting at the left of the text columns (left), or should be centered on the columns ('center', in this example there would be two empty text cells to the left and right of the text.), or should be drawn such that the last letter of text is drawn in the last column of the text row ('right').

**setInterpolated** (*interpolate*)

Specify whether interpolation should be enabled for the TextBox when it is drawn. When interpolate == True, GL\_LINE\_SMOOTH and GL\_POLYGON\_SMOOTH are enabled within OpenGL. When interpolate is set to False, GL\_POLYGON\_SMOOTH and GL\_LINE\_SMOOTH are disabled.

**setOpacity** (*o*)

Sets the TextBox transparency level to use for color related attributes of the Textbox. 0.0 equals fully transparent, 1.0 equals fully opaque.

If opacity is set to None, it is assumed to have a default value of 1.0.

When a color is defined with a 4th element in the colors element list, then this opacity value is ignored and the alpha value provided in the color itself is used for that TextGrid element instead.

**setPosition** (*pos*)

Set the (x,y) position of the TextBox on the Monitor. The position must be given using the unit coord type used by the stim.

The TextBox position is interpreted differently depending on the Horizontal and Vertical Alignment settings of the stim. See getHorzAlignment() and getVertAlignment() for more information.

For example, if the TextBox alignment is specified as left, top, then the position specifies the top left hand corner of where the stim will be drawn. An alignment of bottom,right indicates that the position value will define where the bottom right corner of the TextBox will be drawn. A horz., vert. alignment of center, center will place the center of the TextBox at pos.

**setText** (*text\_source*)

Set the text to be displayed within the Textbox.

Note that once a TextBox has been created, the number of character rows and columns is static. To change the size of a TextBox, a new TextBox stim must be created to replace the current Textbox stim. Therefore ensure that the textbox is large enough to display the largest length string to be presented in the TextBox. Characters that do not fit within the TextBox will not be displayed.

Color value must be valid for the color space being used by the TextBox.

**setTextGridLineColor** (*c*)

Set the color used when drawing text grid lines. These are lines that can be drawn which mark the bounding box for each character within the TextBox text grid. Color value must be valid for the color space being used by the TextBox.

Provide a value of None to disable drawing of textgrid lines.

**setTextGridLineWidth** (*c*)

Set the stroke width (in pixels) to use for the text grid character bounding boxes. Border values must be within the range of stroke widths supported by the OpenGL driver used by the computer graphics card.

Setting the width outside the valid range will result in the stroke width being clamped to the nearest end of the valid range.

Use the `TextBox.getGLLineRanges()` to access a dict containing some OpenGL parameters which provide the minimum, maximum, and resolution of valid line widths.

#### **setVertAlign** (*v*)

Specify how the vertical (*y*) component of the `TextBox` position is to be interpreted. `top` = *y* position is the top edge, `bottom` = *y* position is the bottom edge *y* position, and `center` = the *y* position is used to center the stim vertically.

#### **setVertJust** (*v*)

Specify how text within the `TextBox` should be aligned vertically. For example, if a text grid has 3 rows for text, and the text being displayed all fits on one row, the vertical justification determines if the text should be draw on the top row of the text grid (`top`), or should be centered on the rows (`'center'`, in this example there would be one row above and below the row used to draw the text), or should be drawn on the last row of the text grid, (`'bottom'`).

## 8.2.24 TextStim

```
class psychopy.visual.TextStim(win, text='Hello World', font="", pos=(0.0, 0.0), depth=0,
                                rgb=None, color=(1.0, 1.0, 1.0), colorSpace='rgb', opac-
                                ity=1.0, contrast=1.0, units="", ori=0.0, height=None, an-
                                tialias=True, bold=False, italic=False, alignHoriz='center',
                                alignVert='center', fontFiles=(), wrapWidth=None,
                                flipHoriz=False, flipVert=False, languageStyle='LTR',
                                name=None, autoLog=None)
```

Class of text stimuli to be displayed in a [Window](#)

**Performance OBS:** in general, `TextStim` is slower than many other visual stimuli, i.e. it takes longer to change some attributes. In general, it's the attributes that affect the shapes of the letters: `text`, `height`, `font`, `bold` etc. These make the next `.draw()` slower because that sets the text again. You can make the `draw()` quick by calling re-setting the text (`myTextStim.text = myTextStim.text`) when you've changed the parameters.

In general, other attributes which merely affect the presentation of unchanged shapes are as fast as usual. This includes `pos`, `opacity` etc.

The following attribute can only be set at initialization (see further down for a list of attributes which can be changed after initialization):

**languageStyle** Apply settings to correctly display content from some languages that are written right-to-left. Currently there are three (case- insensitive) values for this parameter: `'LTR'` is the default, for typical left-to-right, Latin-style languages. `'RTL'` will correctly display text in right-to-left languages

such as Hebrew. By applying the bidirectional algorithm, it allows mixing portions of left-to-right content (such as numbers or Latin script) within the string.

`'Arabic'` applies the bidirectional algorithm but additionally will `_reshape_` Arabic characters so they appear in the cursive, linked form that depends on neighbouring characters, rather than in their isolated form. May also be applied in other scripts, such as Farsi or Urdu, that use Arabic-style alphabets.

#### **Parameters**

#### **\_calcPosRendered()**

DEPRECATED in 1.80.00. This functionality is now handled by `_updateVertices()` and `verticesPix`.

**\_\_calcSizeRendered()**  
DEPRECATED in 1.80.00. This functionality is now handled by `__updateVertices()` and `verticesPix`

**\_\_getDesiredRGB(*rgb, colorSpace, contrast*)**  
Convert color to RGB while adding contrast. Requires `self.rgb`, `self.colorSpace` and `self.contrast`

**\_\_getPolyAsRendered()**  
DEPRECATED. Return a list of vertices as rendered.

**\_\_selectWindow(*win*)**  
Switch drawing to the specified window. Calls the window's `__setCurrent()` method which handles the switch.

**\_\_set(*attrib, val, op=*", log=None*)***  
DEPRECATED since 1.80.04 + 1. Use `setAttribute()` and `val2array()` instead.

**\_\_setTextNoShaders(*value=None*)**  
Set the text to be rendered using the current font

**\_\_setTextShaders(*value=None*)**  
Set the text to be rendered using the current font

**\_\_updateList()**  
The user shouldn't need this method since it gets called after every call to `.set()` Chooses between using and not using shaders each call.

**\_\_updateListNoShaders()**  
The user shouldn't need this method since it gets called after every call to `.set()` Basically it updates the OpenGL representation of your stimulus if some parameter of the stimulus changes. Call it if you change a property manually rather than using the `.set()` command

**\_\_updateListShaders()**  
Only used with pygame text - pygame handles all from the `draw()`

**\_\_updateVertices()**  
Sets `Stim.verticesPix` and `._borderPix` from `pos`, `size`, `ori`, `flipVert`, `flipHoriz`

**alignHoriz**  
The horizontal alignment ('left', 'right' or 'center')

**alignVert**  
The vertical alignment ('top', 'bottom' or 'center') Note that this will not necessarily center the particular characters you choose to draw. Instead, it likely centers the invisible bounding box (which is often spanned by the top of a 'T' to the bottom of a 'y') at the *pos*.

**antialias**  
Allow antialiasing the text (True or False). Sets `text`, `slow`.

**autoDraw**  
Determines whether the stimulus should be automatically drawn on every frame flip.  
Value should be: *True* or *False*. You do NOT need to set this on every frame flip!

**autoLog**  
Whether every change in this stimulus should be auto logged.  
Value should be: *True* or *False*. Set to *False* if your stimulus is updating frequently (e.g. updating its position every  
frame) and you want to avoid swamping the log file with  
messages that aren't likely to be useful.

### **bold**

Make the text bold (True, False) (better to use a bold font name).

### **boundingBox**

(read only) attribute representing the bounding box of the text (w,h). This differs from *width* in that the width represents the width of the margins, which might differ from the width of the text within them.

NOTE: currently always returns the size in pixels (this will change to return in stimulus units)

### **color**

Color of the stimulus

**Value should be one of:**

- string: to specify a *Colors by name*. Any of the standard html/X11 *color names* <[http://www.w3schools.com/html/html\\_colornames.asp](http://www.w3schools.com/html/html_colornames.asp)> can be used.
- *Colors by hex value*
- **numerically: (scalar or triplet) for DKL, RGB or other *Color spaces***. For these, *operations* are supported.

When color is specified using numbers, it is interpreted with respect to the stimulus' current colorSpace. If color is given as a single value (scalar) then this will be applied to all 3 channels.

**Examples::** # ... for whatever stim you have: stim.color = 'white' stim.color = 'RoyalBlue' # (the case is actually ignored) stim.color = '#DDA0DD' # DDA0DD is hexadecimal for plum stim.color = [1.0, -1.0, -1.0] # if stim.colorSpace='rgb':

# a red color in rgb space

**stim.color = [0.0, 45.0, 1.0] # if stim.colorSpace='dkl':** # DKL space with elev=0, azimuth=45

**stim.color = [0, 0, 255] # if stim.colorSpace='rgb255':** # a blue stimulus using rgb255 space

**stim.color = 255 # interpreted as (255, 255, 255)** # which is white in rgb255.

*Operations* work as normal for all numeric colorSpaces (e.g. 'rgb', 'hsv' and 'rgb255') but not for strings, like named and hex. For example, assuming that colorSpace='rgb':

```
stim.color += [1, 1, 1] # increment all guns by 1 value
stim.color *= -1 # multiply the color by -1 (which in this
                 # space inverts the contrast)
stim.color *= [0.5, 0, 1] # decrease red, remove green, keep blue
```

You can use *setColor* if you want to set color and colorSpace in one line. These two are equivalent:

```
stim.setColor((0, 128, 255), 'rgb255')
# ... is equivalent to
stim.colorSpace = 'rgb255'
stim.color = (0, 128, 255)
```

### **colorSpace**

The name of the color space currently being used

Value should be: a string or None

For strings and hex values this is not needed. If None the default colorSpace for the stimulus is used (defined during initialisation).

Please note that changing colorSpace does not change stimulus parameters. Thus you usually want to specify colorSpace before setting the color. Example:

```
# A light green text
stim = visual.TextStim(win, 'Color me!',
                       color=(0, 1, 0), colorSpace='rgb')

# An almost-black text
stim.colorSpace = 'rgb255'

# Make it light green again
stim.color = (128, 255, 128)
```

**contains** (*x, y=None, units=None*)

Returns True if a point x,y is inside the stimulus' border.

**Can accept variety of input options:**

- two separate args, x and y
- one arg (list, tuple or array) containing two vals (x,y)
- **an object with a `getPos()` method that returns x,y, such as a *Mouse*.**

Returns *True* if the point is within the area defined either by its *border* attribute (if one defined), or its *vertices* attribute if there is no *.border*. This method handles complex shapes, including concavities and self-crossings.

Note that, if your stimulus uses a mask (such as a Gaussian) then this is not accounted for by the *contains* method; the extent of the stimulus is determined purely by the size, position (*pos*), and orientation (*ori*) settings (and by the vertices for shape stimuli).

See Coder demos: `shapeContains.py` See Coder demos: `shapeContains.py`

**contrast**

A value that is simply multiplied by the color

**Value should be: a float between -1 (negative) and 1 (unchanged).** *Operations* supported.

Set the contrast of the stimulus, i.e. scales how far the stimulus deviates from the middle grey. You can also use the stimulus *opacity* to control contrast, but that cannot be negative.

Examples:

```
stim.contrast = 1.0 # unchanged contrast
stim.contrast = 0.5 # decrease contrast
stim.contrast = 0.0 # uniform, no contrast
stim.contrast = -0.5 # slightly inverted
stim.contrast = -1.0 # totally inverted
```

Setting contrast outside range -1 to 1 is permitted, but may produce strange results if color values exceeds the monitor limits.:

```
stim.contrast = 1.2 # increases contrast
stim.contrast = -1.2 # inverts with increased contrast
```

**depth**

DEPRECATED. Depth is now controlled simply by drawing order.

**draw** (*win=None*)

Draw the stimulus in its relevant window. You must call this method after every `MyWin.flip()` if you want the stimulus to appear on that frame and then update the screen again.

If win is specified then override the normal window of this stimulus.

**flipHoriz**

If set to True then the text will be flipped left-to-right. The flip is relative to the original, not relative to the current state.

**flipVert**

If set to True then the text will be flipped top-to-bottom. The flip is relative to the original, not relative to the current state.

**font**

String. Set the font to be used for text rendering. font should be a string specifying the name of the font (in system resources).

**fontFiles**

A list of additional files if the font is not in the standard system location (include the full path).

OBS: fonts are added every time this value is set. Previous are not deleted.

E.g.:

```
stim.fontFiles = ['SpringRage.ttf'] # load file(s)
stim.font = 'SpringRage' # set to font
```

**height**

The height of the letters (Float/int or None = set default).

Height includes the entire box that surrounds the letters in the font. The width of the letters is then defined by the font.

*Operations* supported.

**italic**

True/False. Make the text italic (better to use a italic font name).

**name**

String or None. The name of the object to be using during logged messages about this stim. If you have multiple stimuli in your experiment this really helps to make sense of log files!

If name = None your stimulus will be called “unnamed <type>”, e.g. visual.TextStim(win) will be called “unnamed TextStim” in the logs.

**opacity**

Determines how visible the stimulus is relative to background

The value should be a single float ranging 1.0 (opaque) to 0.0 (transparent). *Operations* are supported. Precisely how this is used depends on the *Blend Mode*.

**ori**

The orientation of the stimulus (in degrees).

Should be a single value (*scalar*). *Operations* are supported.

Orientation convention is like a clock: 0 is vertical, and positive values rotate clockwise. Beyond 360 and below zero values wrap appropriately.

**overlaps** (*polygon*)

Returns *True* if this stimulus intersects another one.

If *polygon* is another stimulus instance, then the vertices and location of that stimulus will be used as the polygon. Overlap detection is typically very good, but it can fail with very pointy shapes in a crossed-swords configuration.

Note that, if your stimulus uses a mask (such as a Gaussian blob) then this is not accounted for by the *overlaps* method; the extent of the stimulus is determined purely by the size, pos, and orientation settings (and by the vertices for shape stimuli).

See coder demo, `shapeContains.py`

### pos

The position of the center of the stimulus in the stimulus *units*

*value* should be an *x,y-pair*. *Operations* are also supported.

Example:

```
stim.pos = (0.5, 0) # Set slightly to the right of center
stim.pos += (0.5, -1) # Increment pos rightwards and upwards.
    Is now (1.0, -1.0)
stim.pos *= 0.2 # Move stim towards the center.
    Is now (0.2, -0.2)
```

Tip: If you need the position of stim in pixels, you can obtain it like this:

```
from psychopy.tools.monitorunittools import posToPix
posPix = posToPix(stim)
```

### posPix

This determines the coordinates in pixels of the position for the current stimulus, accounting for pos and units. This property should automatically update if *pos* is changed

### setAutoDraw (value, log=None)

Sets `autoDraw`. Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method to suppress the log message.

### setAutoLog (value=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

### setColor (color, colorSpace=None, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message and/or set `colorSpace` simultaneously.

### setContrast (newContrast, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

### setDKL (newDKL, operation="")

DEPRECATED since v1.60.05: Please use the *color* attribute

### setDepth (newDepth, operation="", log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

### setFlip (direction, log=None)

(used by Builder to simplify the dialog)

### setFlipHoriz (newVal=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message.

### setFlipVert (newVal=True, log=None)

Usually you can use ‘`stim.attribute = value`’ syntax instead, but use this method if you need to suppress the log message

**setFont** (*font*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setHeight** (*height*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setLMS** (*newLMS*, *operation=""*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setOpacity** (*newOpacity*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setOri** (*newOri*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setPos** (*newPos*, *operation=""*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setRGB** (*newRGB*, *operation=""*, *log=None*)

DEPRECATED since v1.60.05: Please use the *color* attribute

**setSize** (*newSize*, *operation=""*, *units=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**setText** (*text=None*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message.

**setUseShaders** (*value=True*, *log=None*)

Usually you can use ‘stim.attribute = value’ syntax instead, but use this method if you need to suppress the log message

**size**

The size (width, height) of the stimulus in the stimulus *units*

Value should be *x,y-pair*, *scalar* (applies to both dimensions) or None (resets to default). *Operations* are supported.

Sizes can be negative (causing a mirror-image reversal) and can extend beyond the window.

Example:

```
stim.size = 0.8 # Set size to (xsize, ysize) = (0.8, 0.8)
print(stim.size) # Outputs array([0.8, 0.8])
stim.size += (0.5, -0.5) # make wider and flatter: (1.3, 0.3)
```

Tip: if you can see the actual pixel range this corresponds to by looking at *stim.\_sizeRendered*

**text**

The text to be rendered. Use \n to make new lines.

Issues: May be slow, and pyglet has a memory leak when setting text. For these reasons, this function checks so that it only updates the text if it has changed. So scripts can safely set the text on every frame, with no need to check if it has actually altered.



### units

None, 'norm', 'cm', 'deg', 'degFlat', 'degFlatPos', or 'pix'

If None then the current units of the *Window* will be used. See *Units for the window and stimuli* for explanation of other options.

Note that when you change units, you don't change the stimulus parameters and it is likely to change appearance. Example:

```
# This stimulus is 20% wide and 50% tall with respect to window
stim = visual.PatchStim(win, units='norm', size=(0.2, 0.5)

# This stimulus is 0.2 degrees wide and 0.5 degrees tall.
stim.units = 'deg'
```

### useShaders

Should shaders be used to render the stimulus (typically leave as *True*)

If the system support the use of OpenGL shader language then leaving this set to *True* is highly recommended. If shaders cannot be used then various operations will be slower (notably, changes to stimulus color or contrast)

### verticesPix

This determines the coordinates of the vertices for the current stimulus in pixels, accounting for size, ori, pos and units

### win

The *Window* object in which the stimulus will be rendered by default. (required)

Example, drawing same stimulus in two different windows and display simultaneously. Assuming that you have two windows and a stimulus (win1, win2 and stim):

```
stim.win = win1 # stimulus will be drawn in win1
stim.draw()    # stimulus is now drawn to win1
stim.win = win2 # stimulus will be drawn in win2
stim.draw()    # it is now drawn in win2
win1.flip(waitBlanking=False) # do not wait for next
                             # monitor update
win2.flip()    # wait for vertical blanking.
```

Note that this just changes *\*\*default\*\** window **for** stimulus. You could also specify window-to-draw-to when drawing::

```
stim.draw(win1)
stim.draw(win2)
```

### wrapWidth

Int/float or None (set default). The width the text should run before wrapping.

*Operations* supported.

## 8.2.25 Window

A class representing a window for displaying one or more stimuli.

```
class psychopy.visual.Window(size=(800, 600), pos=None, color=(0, 0, 0), colorSpace='rgb',
                             rgb=None, dkl=None, lms=None, fullscr=None, allowGUI=None,
                             monitor=None, bitsMode=None, winType=None, units=None,
                             gamma=None, blendMode='avg', screen=0, viewScale=None,
                             viewPos=None, viewOri=0.0, waitBlanking=True, allowSten-
                             cil=False, multiSample=False, numSamples=2, stereo=False,
                             name='window1', checkTiming=True, useFBO=False,
                             useRetina=True, autoLog=True, *args, **kwargs)
```

Used to set up a context in which to draw objects, using either [pyglet](#), [pygame](#), or [glfw](#).

The pyglet backend allows multiple windows to be created, allows the user to specify which screen to use (if more than one is available, duh!) and allows movies to be rendered.

The GLFW backend is a new addition which provides most of the same features as pyglet, but provides greater flexibility for complex display configurations.

Pygame may still work for you but it's officially deprecated in this project (we won't be fixing pygame-specific bugs).

These attributes can only be set at initialization. See further down for a list of attributes which can be changed after initialization of the Window, e.g. color, colorSpace, gamma etc.

### Parameters

- **size** (*array-like of int*) – Size of the window in pixels [x, y].
- **pos** (*array-like of int*) – Location of the top-left corner of the window on the screen [x, y].
- **color** (*array-like of float*) – Color of background as [r, g, b] list or single value. Each gun can take values between -1.0 and 1.0.
- **fullscr** (*bool or None*) – Create a window in 'full-screen' mode. Better timing can be achieved in full-screen mode.
- **allowGUI** (*bool or None*) – If set to False, window will be drawn with no frame and no buttons to close etc., use *None* for value from preferences.
- **winType** (*str or None*) – Set the window type or back-end to use. If *None* then PsychoPy will revert to user/site preferences.
- **monitor** (*Monitor or None*) – The monitor to be used during the experiment. If *None* a default monitor profile will be used.
- **units** (*str or None*) – Defines the default units of stimuli drawn in the window (can be overridden by each stimulus). Values can be *None*, 'height' (of the window), 'norm' (normalised), 'deg', 'cm', 'pix'. See [Units for the window and stimuli](#) for explanation of options.
- **screen** (*int*) – Specifies the physical screen that stimuli will appear on ('pyglet' and 'glfw' *winType* only). Values can be >0 if more than one screen is present.
- **viewScale** (*array-like of float or None*) – Scaling factors [x, y] to apply custom scaling to the current units of the *Window* instance.
- **viewPos** (*array-like of float or None*) – If not *None*, redefines the origin within the window, in the units of the window. Values outside the borders will be clamped to lie on the border.
- **viewOri** (*float*) – A single value determining the orientation of the view in degrees.
- **waitBlanking** (*bool or None*) – After a call to [flip\(\)](#) should we wait for the blank before the script continues.
- **bitsMode** – DEPRECATED in 1.80.02. Use BitsSharp class from pycrsltd instead.

- **checkTiming** (*bool*) – Whether to calculate frame duration on initialization. Estimated duration is saved in *monitorFramePeriod*.
- **allowStencil** (*bool*) – When set to *True*, this allows operations that use the OpenGL stencil buffer (notably, allowing the *Aperture* to be used).
- **multiSample** (*bool*) – If *True* and your graphics driver supports multisample buffers, multiple color samples will be taken per-pixel, providing an anti-aliased image through spatial filtering. This setting cannot be changed after opening a window. Only works with ‘pyglet’ and ‘glfw’ *winTypes*, and *useFBO* is *False*.
- **numSamples** (*int*) – A single value specifying the number of samples per pixel if multi-sample is enabled. The higher the number, the better the image quality, but can delay frame flipping. The largest number of samples is determined by *GL\_MAX\_SAMPLES*, usually 16 or 32 on newer hardware, will crash if number is invalid.
- **stereo** (*bool*) – If *True* and your graphics card supports quad buffers then this will be enabled. You can switch between left and right-eye scenes for drawing operations using *setBuffer()*.
- **useRetina** (*bool*) – In PsychoPy >1.85.3 this should always be *True* as pyglet (or Apple) no longer allows us to create a non-retina display. NB when you use Retina display the initial win size request will be in the larger pixels but subsequent use of *units='pix'* should refer to the tiny Retina pixels. *Window.size* will give the actual size of the screen in Retina pixels.

## Notes

- Some parameters (e.g. *units*) can now be given default values in the user/site preferences and these will be used if *None* is given here. If you do specify a value here it will take precedence over preferences.

### size

*array-like(float)* – Dimensions of the window’s drawing area/buffer in pixels [w, h].

### monitorFramePeriod

*float* – Refresh rate of the display if *checkTiming=True* on window instantiation.

### applyEyeTransform (clearDepth=True)

Apply the current view and projection matrices.

Matrices specified by attributes *viewMatrix* and *projectionMatrix* are applied using ‘immediate mode’ OpenGL functions. Subsequent drawing operations will be affected until *flip()* is called.

All transformations in *GL\_PROJECTION* and *GL\_MODELVIEW* matrix stacks will be cleared (set to identity) prior to applying.

**Parameters** *clearDepth* (*bool*) – Clear the depth buffer. This may be required prior to rendering 3D objects.

### blendMode

Blend mode to use.

### callOnFlip (function, \*args, \*\*kwargs)

Call a function immediately after the next *flip()* command.

The first argument should be the function to call, the following args should be used exactly as you would for your normal call to the function (can use ordered arguments or keyword arguments as normal).

e.g. If you have a function that you would normally call like this:

```
pingMyDevice(portToPing, channel=2, level=0)
```

then you could call `callOnFlip()` to have the function call synchronized with the frame flip like this:

```
win.callOnFlip(pingMyDevice, portToPing, channel=2, level=0)
```

#### **clearBuffer()**

Clear the back buffer (to which you are currently drawing) without flipping the window. Useful if you want to generate movie sequences from the back buffer without actually taking the time to flip the window.

#### **close()**

Close the window (and reset the Bits++ if neces).

#### **color**

Set the color of the window.

This command sets the color that the blank screen will have on the next clear operation. As a result it effectively takes TWO `flip()` operations to become visible (the first uses the color to create the new screen, the second presents that screen to the viewer). For this reason, if you want to changed background color of the window “on the fly”, it might be a better idea to draw a `Rect` that fills the whole window with the desired `Rect.fillColor` attribute. That’ll show up on first flip.

See other stimuli (e.g. `GratingStim.color`) for more info on the color attribute which essentially works the same on all PsychoPy stimuli.

See [Color spaces](#) for further information about the ways to specify colors and their various implications.

#### **colorSpace**

Documentation for colorSpace is in the stimuli.

e.g. `GratingStim.colorSpace`

Usually used in conjunction with `color` like this:

```
win.colorSpace = 'rgb255' # changes colorSpace but not
                          # the value of win.color
win.color = [0, 0, 255]   # clear blue in rgb255
```

See [Color spaces](#) for further information about the ways to specify colors and their various implications.

#### **farClip**

Distance to the far clipping plane in meters.

#### **flip (clearBuffer=True)**

Flip the front and back buffers after drawing everything for your frame. (This replaces the `update()` method, better reflecting what is happening underneath).

**Parameters** `clearBuffer` (*bool, optional*) – Clear the draw buffer after flipping. Default is `True`.

**Returns** Wall-clock time in seconds the flip completed. Returns `None` if `waitBlanking` is `False`.

**Return type** `float` or `None`

#### **Notes**

- The time returned when `waitBlanking` is `True` corresponds to when the graphics driver releases the draw buffer to accept draw commands again. This time is usually close to the vertical sync signal of the display.

## Examples

Results in a clear screen after flipping:

```
win.flip(clearBuffer=True)
```

The screen is not cleared (so represent the previous screen):

```
win.flip(clearBuffer=False)
```

### **fps()**

Report the frames per second since the last call to this function (or since the window was created if this is first call)

### **fullscr**

Set whether fullscreen mode is *True* or *False* (not all backends can toggle an open window).

### **gamma**

Set the monitor gamma for linearization.

**Warning:** Don't use this if using a Bits++ or Bits#, as it overrides monitor settings.

### **gammaRamp**

Sets the hardware CLUT using a specified 3xN array of floats ranging between 0.0 and 1.0.

Array must have a number of rows equal to  $2^{\max(\text{bpc})}$ .

### **getActualFrameRate** (*nIdentical=10, nMaxFrames=100, nWarmUpFrames=10, threshold=1*)

Measures the actual frames-per-second (FPS) for the screen.

This is done by waiting (for a max of *nMaxFrames*) until *nIdentical* frames in a row have identical frame times (std dev below *threshold* ms).

#### Parameters

- **nIdentical** (*int, optional*) – The number of consecutive frames that will be evaluated. Higher → greater precision. Lower → faster.
- **nMaxFrames** (*int, optional*) – The maximum number of frames to wait for a matching set of *nIdentical*.
- **nWarmUpFrames** (*int, optional*) – The number of frames to display before starting the test (this is in place to allow the system to settle after opening the *Window* for the first time).
- **threshold** (*int, optional*) – The threshold for the std deviation (in ms) before the set are considered a match.

**Returns** Frame rate (FPS) in seconds. If there is no such sequence of identical frames a warning is logged and *None* will be returned.

**Return type** *float* or *None*

### **getMovieFrame** (*buffer='front'*)

Capture the current Window as an image.

Saves to stack for *saveMovieFrames()*. As of v1.81.00 this also returns the frame as a PIL image

This can be done at any time (usually after a *flip()* command).

Frames are stored in memory until a `saveMovieFrames()` command is issued. You can issue `getMovieFrame()` as often as you like and then save them all in one go when finished.

The back buffer will return the frame that hasn't yet been 'flipped' to be visible on screen but has the advantage that the mouse and any other overlapping windows won't get in the way.

The default front buffer is to be called immediately after a `flip()` and gives a complete copy of the screen at the window's coordinates.

**Parameters** `buffer` (*str*, *optional*) – Buffer to capture.

**Returns** Buffer pixel contents as a PIL/Pillow image object.

**Return type** Image

**getMsPerFrame** (*nFrames=60*, *showVisual=False*, *msg=""*, *msDelay=0.0*)

Assesses the monitor refresh rate (average, median, SD) under current conditions, over at least 60 frames.

Records time for each refresh (frame) for *n* frames (at least 60), while displaying an optional visual. The visual is just eye-candy to show that something is happening when assessing many frames. You can also give it text to display instead of a visual, e.g., `msg='(testing refresh rate...)'`; setting `msg` implies `showVisual == False`.

To simulate refresh rate under cpu load, you can specify a time to wait within the loop prior to doing the `flip()`. If  $0 < \text{msDelay} < 100$ , wait for that long in ms.

Returns timing stats (in ms) of:

- average time per frame, for all frames
- standard deviation of all frames
- median, as the average of 12 frame times around the median (~monitor refresh rate)

**Author**

- 2010 written by Jeremy Gray

**logOnFlip** (*msg*, *level*, *obj=None*)

Send a log message that should be time-stamped at the next `flip()` command.

**Parameters**

- `msg` (*str*) – The message to be logged.
- `level` (*int*) – The level of importance for the message.
- `obj` (*object*, *optional*) – The python object that might be associated with this message if desired.

**mouseVisible**

Sets the visibility of the mouse cursor.

If Window was initialized with `allowGUI=True` then the mouse is initially set to invisible, otherwise it will initially be visible.

Usage:

```
win.mouseVisible = False
win.mouseVisible = True
```

**nearClip**

Distance to the near clipping plane in meters.

### **projectionMatrix**

Projection matrix defined as a 4x4 numpy array.

### **recordFrameIntervals**

Record time elapsed per frame.

Provides accurate measures of frame intervals to determine whether frames are being dropped. The intervals are the times between calls to `flip()`. Set to *True* only during the time-critical parts of the script. Set this to *False* while the screen is not being updated, i.e., during any slow, non-frame-time-critical sections of your code, including `inter-trial-intervals`, `event.waitkeys()`, `core.wait()`, or `image.setImage()`.

## **Examples**

Enable frame interval recording, successive frame intervals will be stored:

```
win.recordFrameIntervals = True
```

Frame intervals can be saved by calling the `saveFrameIntervals` method:

```
win.saveFrameIntervals()
```

### **resetEyeTransform** (*clearDepth=True*)

Restore the default projection and view settings to PsychoPy defaults. Call this prior to drawing 2D stimuli objects (i.e. `GratingStim`, `ImageStim`, `Rect`, etc.) if any eye transformations were applied for the stimuli to be drawn correctly.

## **Notes**

- Calling `flip()` automatically resets the view and projection to defaults. So you don't need to call this unless you are mixing views.

### **saveFrameIntervals** (*fileName=None, clear=True*)

Save recorded screen frame intervals to disk, as comma-separated values.

#### **Parameters**

- **fileName** (*None* or *str*) – *None* or the filename (including path if necessary) in which to store the data. If *None* then 'lastFrameIntervals.log' will be used.
- **clear** (*bool*) – Clear buffer frames intervals were stored after saving. Default is *True*.

### **saveMovieFrames** (*fileName, codec='libx264', fps=30, clearFrames=True*)

Writes any captured frames to disk.

Will write any format that is understood by PIL (tif, jpg, png, ...)

#### **Parameters**

- **filename** (*str*) – Name of file, including path. The extension at the end of the file determines the type of file(s) created. If an image type (e.g. .png) is given, then multiple static frames are created. If it is .gif then an animated GIF image is created (although you will get higher quality GIF by saving PNG files and then combining them in dedicated image manipulation software, such as GIMP). On Windows and Linux .mpeg files can be created if *pymedia* is installed. On macOS .mov files can be created if the *pyobjc-frameworks-UIKit* is installed. Unfortunately the libs used for movie generation can be

flaky and poor quality. As for animated GIFs, better results can be achieved by saving as individual .png frames and then combining them into a movie using software like ffmpeg.

- **codec** (*str*, *optional*) – The codec to be used by **moviepy** for mp4/mpg/mov files. If *None* then the default will depend on file extension. Can be one of `libx264`, `mpeg4` for mp4/mov files. Can be `rawvideo`, `png` for avi files (not recommended). Can be `libvorbis` for ogv files. Default is `libx264`.
- **fps** (*int*, *optional*) – The frame rate to be used throughout the movie. **Only for quicktime (.mov) movies..** Default is `30`.
- **clearFrames** (*bool*, *optional*) – Set this to *False* if you want the frames to be kept for additional calls to `saveMovieFrames`. Default is *True*.

## Examples

Writes a series of static frames as `frame001.tif`, `frame002.tif` etc.:

```
myWin.saveMovieFrames('frame.tif')
```

As of PsychoPy 1.84.1 the following are written with **moviepy**:

```
myWin.saveMovieFrames('stimuli.mp4') # codec = 'libx264' or 'mpeg4'
myWin.saveMovieFrames('stimuli.mov')
myWin.saveMovieFrames('stimuli.gif')
```

**setBuffer** (*buffer*, *clear=True*)

Choose which buffer to draw to ('left' or 'right').

Requires the Window to be initialised with `stereo=True` and requires a graphics card that supports quad buffering (e.g nVidia Quadro series)

PsychoPy always draws to the back buffers, so 'left' will use `GL_BACK_LEFT` This then needs to be flipped once both eye's buffers have been rendered.

### Parameters

- **buffer** (*str*) – Buffer to draw to. Can either be 'left' or 'right'.
- **clear** (*bool*, *optional*) – Clear the buffer before drawing. Default is *True*.

## Examples

Stereoscopic rendering example using quad-buffers:

```
win = visual.Window(..., stereo=True)
while True:
    # clear may not actually be needed
    win.setBuffer('left', clear=True)
    # do drawing for left eye
    win.setBuffer('right', clear=True)
    # do drawing for right eye
    win.flip()
```

**setMouseType** (*name='arrow'*)

Change the appearance of the cursor for this window. Cursor types provide contextual hints about how to interact with on-screen objects.



The graphics used ‘standard cursors’ provided by the operating system. They may vary in appearance and hot spot location across platforms. The following names are valid on most platforms:

- `arrow` : Default pointer.
- `ibeam` : Indicates text can be edited.
- `crosshair` : Crosshair with hot-spot at center.
- `hand` : A pointing hand.
- `hresize` : Double arrows pointing horizontally.
- `vresize` : Double arrows pointing vertically.

**Parameters** `name` (*str*) – Type of standard cursor to use (see above). Default is `arrow`.

## Notes

- On Windows the `crosshair` option is negated with the background color. It will not be visible when placed over 50% grey fields.

**setPerspectiveView** (*applyTransform=True, \*\*kwargs*)

Set the projection and view matrix to render with perspective.

Matrices are computed using values specified in the monitor configuration with the scene origin on the screen plane. Calculations assume units are in meters.

Note that the values of *projectionMatrix* and *viewMatrix* will be replaced when calling this function.

### Parameters

- **applyTransform** (*bool*) – Apply transformations after computing them in immediate mode. Same as calling *applyEyeTransform()* afterwards.
- **\*\*kwargs** – Additional arguments for *applyEyeTransform()*.

**timeOnFlip** (*obj, attrib*)

Retrieves the time on the next flip and assigns it to the *attrib* for this *obj*.

### Parameters

- **obj** (*dict or object*) – A mutable object (usually a dict of class instance).
- **attrib** (*str*) – Key or attribute of *obj* to assign the flip time to.

## Examples

Assign time on flip to the `tStartRefresh` key of `myTimingDict`:

```
win.getTimeOnFlip(myTimingDict, 'tStartRefresh')
```

### units

*None*, ‘height’ (of the window), ‘norm’, ‘deg’, ‘cm’, ‘pix’ Defines the default units of stimuli initialized in the window. I.e. if you change units, already initialized stimuli won’t change their units.

Can be overridden by each stimulus, if units is specified on initialization.

See *Units for the window and stimuli* for explanation of options.

**viewMatrix**

View matrix defined as a 4x4 numpy array.

**viewPos**

The origin of the window onto which stimulus-objects are drawn.

The value should be given in the units defined for the window. NB: Never change a single component (x or y) of the origin, instead replace the viewPos-attribute in one shot, e.g.:

```
win.viewPos = [new_xval, new_yval] # This is the way to do it
win.viewPos[0] = new_xval # DO NOT DO THIS! Errors will result.
```

**waitBlanking**

After a call to `flip()` should we wait for the blank before the script continues.

## 8.2.26 `psychopy.visual.windowframepack` - Pack multiple monochrome images into RGB frame

Copyright (C) 2014 Allen Institute for Brain Science

This program is free software: you can redistribute it and/or modify it under the terms of the GNU General Public License Version 3 as published by the Free Software Foundation on 29 June 2007. This program is distributed WITHOUT WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OR ANY OTHER WARRANTY, EXPRESSED OR IMPLIED. See the GNU General Public License Version 3 for more details. You should have received a copy of the GNU General Public License along with this program. If not, see <http://www.gnu.org/licenses/>

**ProjectorFramePacker**

**class** `psychopy.visual.windowframepack.ProjectorFramePacker` (*win*)

Class which packs 3 monochrome images per RGB frame.

Allowing 180Hz stimuli with DLP projectors such as TI LightCrafter 4500.

The class overrides methods of the `visual.Window` class to pack a monochrome image into each RGB channel. PsychoPy is running at 180Hz. The display device is running at 60Hz. The output projector is producing images at 180Hz.

Frame packing can work with any projector which can operate in ‘structured light mode’ where each RGB channel is presented sequentially as a monochrome image. Most home and office projectors cannot operate in this mode, but projectors designed for machine vision applications typically will offer this feature.

Example usage to use `ProjectorFramePacker`:

```
from psychopy.visual.windowframepack import ProjectorFramePacker
win = Window(monitor='testMonitor', screen=1,
             fullscr=True, useFBO = True)
framePacker = ProjectorFramePacker (win)
```

**Parameters** *win* : Handle to the window.

**endOfFlip** (*clearBuffer*)

Mask RGB cyclically after each flip. We ignore `clearBuffer` and just auto-clear after each hardware flip.

**startOfFlip** ()

Return True if all channels of the RGB frame have been filled with monochrome images, and the associated window should perform a hardware flip

## 8.2.27 psychopy.visual.windowwarp - warping to spherical, cylindrical, or other projections

Copyright (C) 2014 Allen Institute for Brain Science

This program is free software: you can redistribute it and/or modify it under the terms of the GNU General Public License Version 3 as published by the Free Software Foundation on 29 June 2007. This program is distributed WITHOUT WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OR ANY OTHER WARRANTY, EXPRESSED OR IMPLIED. See the GNU General Public License Version 3 for more details. You should have received a copy of the GNU General Public License along with this program. If not, see <http://www.gnu.org/licenses/>

### Warper

**class** psychopy.visual.windowwarp.**Warper** (*win*, *warp=None*, *warpfile=None*, *warpGridsize=300*, *eyepoint=(0.5, 0.5)*, *flipHorizontal=False*, *flipVertical=False*)

Class to perform warps.

Supports spherical, cylindrical, warpfile, or None (disabled) warps

Warping is a final operation which can be optionally performed on each frame just before transmission to the display. It is useful for perspective correction when the eye to monitor distance is small (say, under 50 cm), or when projecting to domes or other non-planar surfaces.

These attributes define the projection and can be altered dynamically using the `changeProjection()` method.

**Parameters** *win* : Handle to the window.

**warp** ['spherical', 'cylindrical', 'warpfile' or *None*] This table gives the main properties of each projection

Warp	eyepoint modifies warp	verticals parallel	horizontal parallel	perspective correct
spherical	y	n	n	y
cylindrical	y	y	n	n
warpfile	n	?	?	?
None	n	y	y	n

**warpfile** [*None* or filename containing Blender and Paul Bourke] compatible warp definition. (see <http://paulbourke.net/dome/warpingfisheye/>)

**warpGridsize** [300] Defines the resolution of the warp in both X and Y when not using a warpfile. Typical values would be 64-300 trading off tolerance for jaggies for speed.

**eyepoint** [[0.5, 0.5] center of the screen] Position of the eye in X and Y as a fraction of the normalized screen width and height. [0,0] is the bottom left of the screen. [1,1] is the top right of the screen.

**flipHorizontal: True or False** Flip the entire output horizontally. Useful for back projection scenarios.

**flipVertical: True or False** Flip the entire output vertically. useful if projector is flipped upside down.

### Notes

1. The eye distance from the screen is initialized from the monitor definition.
2. The eye distance can be altered dynamically by changing 'warper.dist\_cm' and then calling `changeProjection()`.

Example usage to create a spherical projection:

```
from psychopy.visual.windowwarp import Warper
win = Window(monitor='testMonitor', screen=1,
             fullscr=True, useFBO = True)
warper = Warper(win,
                warp='spherical',
                warpfile = "",
                warpGridsize = 128,
                eyepoint = [0.5, 0.5],
                flipHorizontal = False,
                flipVertical = False)
```

**changeProjection** (*warp*, *warpfile*=None, *eyepoint*=(0.5, 0.5), *flipHorizontal*=False, *flipVertical*=False)

Allows changing the warp method on the fly. Uses the same parameter definitions as constructor.

Windows and display devices:

- *Window* is the main class to display objects
- *Warper* for non-flat projection screens
- *ProjectorFramePacker* for handling displays with 'structured light mode' to achieve high framerates
- *Rift* for Oculus Rift support (Windows 64bit only)

Commonly used:

- *ImageStim* to show images
- *TextStim* to show text
- *TextBox* rewrite of TextStim (faster/better but only monospace fonts)

Shapes (all special classes of *ShapeStim*):

- *ShapeStim* to draw shapes with arbitrary numbers of vertices
- *Rect* to show rectangles
- *Circle* to show circles
- *Polygon* to show polygons
- *Line* to show a line

Images and patterns:

- *ImageStim* to show images
- *SimpleImageStim* to show images without bells and whistles
- *GratingStim* to show gratings
- *RadialStim* to show annulus, a rotating wedge, a checkerboard etc
- *NoiseStim* to show filtered noise patterns of various forms
- *EnvelopeGrating* to generate second-order stimuli (gratings that can have a carrier and envelope)

Multiple stimuli:

- *ElementArrayStim* to show many stimuli of the same type
- *DotStim* to show and control movement of dots

Other stimuli:

- *MovieStim* to show movies
- *Slider* a new improved class to collect ratings
- *RatingScale* to collect ratings
- *CustomMouse* to change the cursor in windows with GUI. OBS: will be deprecated soon

Meta stimuli (stimuli that operate on other stimuli):

- *BufferImageStim* to make a faster-to-show “screenshot” of other stimuli
- *Aperture* to restrict visibility area of other stimuli

Helper functions:

- *filters* for creating grating textures and Gaussian masks etc.
- *visualhelperfunctions* for tests about whether one stimulus contains another
- *unittools* to convert deg<->radians
- *monitorunittools* to convert cm<->pix<->deg etc.
- *colorspacetools* to convert between supported color spaces
- *viewtools* to work with view projections
- *mathtools* to work with vectors, quaternions, and matrices

## 8.3 psychopy.clock - Clocks and timers

Created on Tue Apr 23 11:28:32 2013

Provides the high resolution timebase used by psychopy, and defines some time related utility Classes.

Moved functionality from core.py so a common code base could be used in core.py and logging.py; vs. duplicating the getTime and Clock logic.

@author: Sol @author: Jon

`psychopy.clock.getTime()`

Copyright (c) 2018 Mario Kleiner. Licensed under MIT license.

For detailed help on a subfunction SUBFUNCTIONNAME, type `GetSecs('SUBFUNCTIONNAME?')` ie. the name with a question mark appended. E.g., for detailed help on the subfunction called Version, type this: `GetSecs('Version?')`

`[GetSecsTime, WallTime, syncErrorSecs] = GetSecs('AllClocks' [, maxError=0.000020]);`

`psychopy.clock.getAbsTime()`

Return unix time (i.e., whole seconds elapsed since Jan 1, 1970).

This uses the same clock-base as the other timing features, like `getTime()`. The time (in seconds) ignores the time-zone (like `time.time()` on linux). To take the timezone into account, use `int(time.mktime(time.gmtime()))`.

Absolute times in seconds are especially useful to add to generated file names for being unique, informative (= a meaningful time stamp), and because the resulting files will always sort as expected when sorted in chronological, alphabetical, or numerical order, regardless of locale and so on.

Version Notes: This method was added in PsychoPy 1.77.00

`psychopy.clock.wait(secs, hogCPUperiod=0.2)`

Wait for a given time period.

If `secs=10` and `hogCPU=0.2` then for 9.8s python's `time.sleep` function will be used, which is not especially precise, but allows the cpu to perform housekeeping. In the final `hogCPUperiod` the more precise method of constantly polling the clock is used for greater precision.

If you want to obtain key-presses during the wait, be sure to use `pyglet` and to `hogCPU` for the entire time, and then call `psychopy.event.getKeys()` after calling `wait()`

If you want to suppress checking for `pyglet` events during the wait, do this once:

```
core.checkPygletDuringWait = False
```

and from then on you can do:

```
core.wait(sec)
```

This will preserve terminal-window focus during command line usage.

**class** `psychopy.clock.Clock`

A convenient class to keep track of time in your experiments. You can have as many independent clocks as you like (e.g. one to time responses, one to keep track of stimuli...)

This clock is identical to the `MonotonicClock` except that it can also be reset to 0 or another value at any point.

**add** (*t*)

Add more time to the clock's 'start' time (*t0*).

Note that, by adding time to *t0*, you make the current time appear less. Can have the effect that `getTime()` returns a negative number that will gradually count back up to zero.

e.g.:

```
timer = core.Clock()
timer.add(5)
while timer.getTime() < 0:
    # do something
```

**reset** (*newT=0.0*)

Reset the time on the clock. With no args time will be set to zero. If a float is received this will be the new time on the clock

**class** `psychopy.clock.CountdownTimer` (*start=0*)

Similar to a `Clock` except that time counts down from the time of last reset

Typical usage:

```
timer = core.CountdownTimer(5)
while timer.getTime() > 0: # after 5s will become negative
    # do stuff
```

**getTime** ()

Returns the current time left on this timer in secs (sub-ms precision)

**reset** (*t=None*)

Reset the time on the clock. With no args time will be set to zero. If a float is received this will be the new time on the clock

**class** psychopy.clock.MonotonicClock (start\_time=None)

A convenient class to keep track of time in your experiments using a sub-millisecond timer.

Unlike the `clock` this cannot be reset to arbitrary times. For this clock  $t=0$  always represents the time that the clock was created.

Don't confuse this *class* with `core.monotonicClock` which is an *instance* of it that got created when PsychoPy.core was imported. That clock instance is deliberately designed always to return the time since the start of the study.

Version Notes: This class was added in PsychoPy 1.77.00

**getLastResetTime** ()

Returns the current offset being applied to the high resolution timebase used by Clock.

**getTime** ()

Returns the current time on this clock in secs (sub-ms precision)

**class** psychopy.clock.StaticPeriod (screenHz=None, win=None, name='StaticPeriod')

A class to help insert a timing period that includes code to be run.

Typical usage:

```
fixation.draw()
win.flip()
ISI = StaticPeriod(screenHz=60)
ISI.start(0.5) # start a period of 0.5s
stim.image = 'largeFile.bmp' # could take some time
ISI.complete() # finish the 0.5s, taking into account one 60Hz frame

stim.draw()
win.flip() # the period takes into account the next frame flip
# time should now be at exactly 0.5s later than when ISI.start()
# was called
```

### Parameters

- **screenHz** – the frame rate of the monitor (leave as None if you don't want this accounted for)
- **win** – if a visual.Window is given then StaticPeriod will also pause/restart frame interval recording
- **name** – give this StaticPeriod a name for more informative logging messages

**complete** ()

Completes the period, using up whatever time is remaining with a call to wait()

**Returns** 1 for success, 0 for fail (the period overran)

**start** (duration)

Start the period. If this is called a second time, the timer will be reset and starts again

**Parameters** **duration** – The duration of the period, in seconds.

## 8.4 psychopy.data - functions for storing/saving/analysing data

### 8.4.1 ExperimentHandler

```
class psychopy.data.ExperimentHandler (name="", version="", extraInfo=None, runtime-
                                         Info=None, originPath=None, savePickle=True,
                                         saveWideText=True, dataFileName="", au-
                                         toLog=True, appendFiles=False)
```

A container class for keeping track of multiple loops/handlers

Useful for generating a single data file from an experiment with many different loops (e.g. interleaved staircases or loops within loops)

**Usage** exp = data.ExperimentHandler(name="Face Preference",version='0.1.0')

#### Parameters

**name** [a string or unicode] As a useful identifier later

**version** [usually a string (e.g. '1.1.0')] To keep track of which version of the experiment was run

**extraInfo** [a dictionary] Containing useful information about this run (e.g. {'participant':'jwp','gender':'m','orientation':90} )

**runtimeInfo** [*psychopy.info.RunTimeInfo*] Containining information about the system as detected at runtime

**originPath** [string or unicode] The path and filename of the originating script/experiment If not provided this will be determined as the path of the calling script.

**dataFileName** [string] This is defined in advance and the file will be saved at any point that the handler is removed or discarded (unless .abort() had been called in advance). The handler will attempt to populate the file even in the event of a (not too serious) crash!

savePickle : True (default) or False

saveWideText : True (default) or False

autoLog : True (default) or False

**\_getAllParamNames** ()

Returns the attribute names of loop parameters (trialN etc) that the current set of loops contain, ready to build a wide-format data file.

**\_getExtraInfo** ()

Get the names and vals from the extraInfo dict (if it exists)

**\_getLoopInfo** (loop)

Returns the attribute names and values for the current trial of a particular loop. Does not return data inputs from the subject, only info relating to the trial execution.

**abort** ()

Inform the ExperimentHandler that the run was aborted.

Experiment handler will attempt automatically to save data (even in the event of a crash if possible). So if you quit your script early you may want to tell the Handler not to save out the data files for this run. This is the method that allows you to do that.

**addData** (name, value)

Add the data with a given name to the current experiment.



Typically the user does not need to use this function; if you added your data to the loop and had already added the loop to the experiment then the loop will automatically inform the experiment that it has received data.

Multiple data name/value pairs can be added to any given entry of the data file and is considered part of the same entry until the `nextEntry()` call is made.

e.g.:

```
# add some data for this trial
exp.addData('resp.rt', 0.8)
exp.addData('resp.key', 'k')
# end of trial - move to next line in data output
exp.nextEntry()
```

**addLoop** (*loopHandler*)

Add a loop such as a *TrialHandler* or *StairHandler* Data from this loop will be included in the resulting data files.

**close** ()

**getAllEntries** ()

Fetches a copy of all the entries including a final (orphan) entry if that exists. This allows entries to be saved even if `nextEntry()` is not yet called.

**Returns** copy (not pointer) to entries

**loopEnded** (*loopHandler*)

Informs the experiment handler that the loop is finished and not to include its values in further entries of the experiment.

This method is called by the loop itself if it ends its iterations, so is not typically needed by the user.

**nextEntry** ()

Calling `nextEntry` indicates to the ExperimentHandler that the current trial has ended and so further `addData()` calls correspond to the next trial.

**saveAsPickle** (*fileName*, *fileCollisionMethod*='rename')

Basically just saves a copy of self (with data) to a pickle file.

This can be reloaded if necessary and further analyses carried out.

**Parameters** *fileCollisionMethod*: Collision method passed to `handleFileCollision()`

**saveAsWideText** (*fileName*, *delim*=None, *matrixOnly*=False, *appendFile*=None, *encoding*='utf-8-sig', *fileCollisionMethod*='rename', *sortColumns*=False)

Saves a long, wide-format text file, with one line representing the attributes and data for a single trial. Suitable for analysis in R and SPSS.

If *appendFile*=True then the data will be added to the bottom of an existing file. Otherwise, if the file exists already it will be overwritten

If *matrixOnly*=True then the file will not contain a header row, which can be handy if you want to append data to an existing file of the same format.

**Parameters**

**fileName**: if extension is not specified, '.csv' will be appended if the delimiter is ',', else '.tsv' will be appended. Can include path info.

**delim**: allows the user to use a delimiter other than the default tab ("," is popular with file extension ".csv")

**matrixOnly**: outputs the data with no header row.

**appendFile:** will add this output to the end of the specified file if it already exists.

**encoding:** The encoding to use when saving a the file. Defaults to *utf-8-sig*.

**fileCollisionMethod:** Collision method passed to `handleFileCollision()`

**sortColumns:** will sort columns alphabetically by header name if True

## 8.4.2 TrialHandler

```
class psychopy.data.TrialHandler (trialList, nReps, method='random', dataTypes=None, extraInfo=None, seed=None, originPath=None, name="", autoLog=True)
```

Class to handle trial sequencing and data storage.

Calls to `.next()` will fetch the next trial object given to this handler, according to the method specified (random, sequential, fullRandom). Calls will raise a `StopIteration` error if trials have finished.

See `demo_trialHandler.py`

The psydat file format is literally just a pickled copy of the TrialHandler object that saved it. You can open it with:

```
from psychopy.tools.filetools import fromFile
dat = fromFile(path)
```

Then you'll find that *dat* has the following attributes that

### Parameters

**trialList:** a simple list (or flat array) of dictionaries specifying conditions. This can be imported from an excel/csv file using `importConditions()`

**nReps:** number of repeats for all conditions

**method:** 'random', 'sequential', or 'fullRandom' 'sequential' obviously presents the conditions in the order they appear in the list. 'random' will result in a shuffle of the conditions on each repeat, but all conditions occur once before the second repeat etc. 'fullRandom' fully randomises the trials across repeats as well, which means you could potentially run all trials of one condition before any trial of another.

**dataTypes:** (optional) list of names for data storage. e.g. ['corr','rt','resp']. If not provided then these will be created as needed during calls to `addData()`

**extraInfo:** A dictionary This will be stored alongside the data and usually describes the experiment and subject ID, date etc.

**seed:** an integer If provided then this fixes the random number generator to use the same pattern of trials, by seeding its startpoint

**originPath:** a string describing the location of the script / experiment file path. The psydat file format will store a copy of the experiment if possible. If `originPath==None` is provided here then the TrialHandler will still store a copy of the script where it was created. If `OriginPath==None` then nothing will be stored.

### Attributes (after creation)

**.data** - a dictionary (or more strictly, a *DataHandler* subclass of a dictionary) of numpy arrays, one for each data type stored

**.trialList** - the original list of dicts, specifying the conditions

**.thisIndex** - the index of the current trial in the original conditions list

.nTotal - the total number of trials that will be run  
 .nRemaining - the total number of trials remaining  
 .thisN - total trials completed so far  
 .thisRepN - which repeat you are currently on  
 .thisTrialN - which trial number *within* that repeat  
**.thisTrial - a dictionary giving the parameters of the current trial**  
 .finished - True/False for have we finished yet  
 .extraInfo - the dictionary of extra info as given at beginning  
**.origin - the contents of the script or builder experiment that** created the handler

**\_createOutputArray** (*stimOut, dataOut, delim=None, matrixOnly=False*)  
 Does the leg-work for saveAsText and saveAsExcel. Combines stimOut with .\_parseDataOutput()

**\_createOutputArrayData** (*dataOut*)  
 This just creates the dataOut part of the output matrix. It is called by \_createOutputArray() which creates the header line and adds the stimOut columns

**\_createSequence** ()  
 Pre-generates the sequence of trial presentations (for non-adaptive methods). This is called automatically when the TrialHandler is initialised so doesn't need an explicit call from the user.  
 The returned sequence has form indices[stimN][repN] Example: sequential with 6 trialtypes (rows), 5 reps (cols), returns:

**[[0 0 0 0 0] [1 1 1 1 1] [2 2 2 2 2] [3 3 3 3 3] [4 4 4 4 4] [5 5 5 5 5]]**

**These 30 trials will be returned by .next() in the order:** 0, 1, 2, 3, 4, 5, 0, 1, 2, ... 3, 4, 5

To add a new type of sequence (as of v1.65.02): - add the sequence generation code here - adjust "if self.method in [ ... ]:" in both \_\_init\_\_ and .next() - adjust allowedVals in experiment.py -> shows up in DlgLoopProperties Note that users can make any sequence whatsoever outside of PsychoPy, and specify sequential order; any order is possible this way.

**\_makeIndices** (*inputArray*)  
 Creates an array of tuples the same shape as the input array where each tuple contains the indices to itself in the array.

Useful for shuffling and then using as a reference.

**\_terminate** ()  
 Remove references to ourself in experiments and terminate the loop

**addData** (*thisType, value, position=None*)  
 Add data for the current trial

**getEarlierTrial** (*n=-1*)  
 Returns the condition information from n trials previously. Useful for comparisons in n-back tasks. Returns 'None' if trying to access a trial prior to the first.

**getExp** ()  
 Return the ExperimentHandler that this handler is attached to, if any. Returns None if not attached

**getFutureTrial** (*n=1*)  
 Returns the condition for n trials into the future, without advancing the trials. A negative n returns a previous (past) trial. Returns 'None' if attempting to go beyond the last trial.

**getOriginPathAndFile** (*originPath=None*)

Attempts to determine the path of the script that created this data file and returns both the path to that script and its contents. Useful to store the entire experiment with the data.

If *originPath* is provided (e.g. from Builder) then this is used otherwise the calling script is the *originPath* (fine from a standard python script).

**next** ()

Advances to next trial and returns it. Updates attributes; *thisTrial*, *thisTrialN* and *thisIndex*. If the trials have ended this method will raise a *StopIteration* error. This can be handled with code such as:

```
trials = data.TrialHandler(.....)
for eachTrial in trials: # automatically stops when done
    # do stuff
```

or:

```
trials = data.TrialHandler(.....)
while True: # ie forever
    try:
        thisTrial = trials.next()
    except StopIteration: # we got a StopIteration error
        break #break out of the forever loop
    # do stuff here for the trial
```

**printAsText** (*stimOut=None*, *dataOut=('all\_mean', 'all\_std', 'all\_raw')*, *delim='\t'*, *matrixOnly=False*)

Exactly like *saveAsText*() except that the output goes to the screen instead of a file

**saveAsExcel** (*fileName*, *sheetName='rawData'*, *stimOut=None*, *dataOut=('n', 'all\_mean', 'all\_std', 'all\_raw')*, *matrixOnly=False*, *appendFile=True*, *fileCollisionMethod='rename'*)

Save a summary data file in Excel OpenXML format workbook (*xlsx*) for processing in most spreadsheet packages. This format is compatible with versions of Excel (2007 or greater) and with OpenOffice (>=3.0).

It has the advantage over the simpler text files (see *TrialHandler.saveAsText()*) that data can be stored in multiple named sheets within the file. So you could have a single file named after your experiment and then have one worksheet for each participant. Or you could have one file for each participant and then multiple sheets for repeated sessions etc.

The file extension *.xlsx* will be added if not given already.

### Parameters

**fileName: string** the name of the file to create or append. Can include relative or absolute path

**sheetName: string** the name of the worksheet within the file

**stimOut: list of strings** the attributes of the trial characteristics to be output. To use this you need to have provided a list of dictionaries specifying to *trialList* parameter of the *TrialHandler* and give here the names of strings specifying entries in that dictionary

**dataOut: list of strings** specifying the *dataType* and the analysis to be performed, in the form *dataType\_analysis*. The data can be any of the types that you added using *trialHandler.data.add()* and the analysis can be either 'raw' or most things in the numpy library, including 'mean', 'std', 'median', 'max', 'min'. e.g. *rt\_max* will give a column of max reaction times across the trials assuming that *rt* values have been stored. The default values will output the raw, mean and std of all datatypes found.

**appendFile: True or False** If False any existing file with this name will be overwritten. If True then a new worksheet will be appended. If a worksheet already exists with that name a number will be added to make it unique.

**fileCollisionMethod: string** Collision method passed to `handleFileCollision()`. This is ignored if `append` is True.

**saveAsJson** (*fileName=None, encoding='utf-8', fileCollisionMethod='rename'*)  
Serialize the object to the JSON format.

#### Parameters

- **fileName** (*string, or None*) – the name of the file to create or append. Can include a relative or absolute path. If *None*, will not write to a file, but return an in-memory JSON object.
- **encoding** (*string, optional*) – The encoding to use when writing the file.
- **fileCollisionMethod** (*string*) – Collision method passed to `handleFileCollision()`. Can be either of *'rename'*, *'overwrite'*, or *'fail'*.

#### Notes

Currently, a copy of the object is created, and the copy's `.origin` attribute is set to an empty string before serializing because loading the created JSON file would sometimes fail otherwise.

**saveAsPickle** (*fileName, fileCollisionMethod='rename'*)  
Basically just saves a copy of the handler (with data) to a pickle file.

This can be reloaded if necessary and further analyses carried out.

**Parameters** `fileCollisionMethod`: Collision method passed to `handleFileCollision()`

**saveAsText** (*fileName, stimOut=None, dataOut=('n', 'all\_mean', 'all\_std', 'all\_raw'), delim=None, matrixOnly=False, appendFile=True, summarised=True, fileCollisionMethod='rename', encoding='utf-8-sig'*)

Write a text file with the data and various chosen stimulus attributes

#### Parameters

**fileName**: will have `.tsv` appended and can include path info.

**stimOut**: the stimulus attributes to be output. To use this you need to use a list of dictionaries and give here the names of dictionary keys that you want as strings

**dataOut**: a list of strings specifying the `dataType` and the analysis to be performed, in the form `dataType_analysis`. The data can be any of the types that you added using `trialHandler.data.add()` and the analysis can be either *'raw'* or most things in the numpy library, including; *'mean', 'std', 'median', 'max', 'min'*... The default values will output the raw, mean and std of all datatypes found

**delim**: allows the user to use a delimiter other than tab ("`,`" is popular with file extension `".csv"`)

**matrixOnly**: outputs the data with no header row or extraInfo attached

**appendFile**: will add this output to the end of the specified file if it already exists

**fileCollisionMethod**: Collision method passed to `handleFileCollision()`

**encoding**: The encoding to use when saving a the file. Defaults to `utf-8-sig`.

**saveAsWideText** (*fileName*, *delim=None*, *matrixOnly=False*, *appendFile=True*, *encoding='utf-8-sig'*, *fileCollisionMethod='rename'*)

Write a text file with the session, stimulus, and data values from each trial in chronological order. Also, return a pandas DataFrame containing same information as the file.

**That is, unlike ‘saveAsText’ and ‘saveAsExcel’:**

- each row comprises information from only a single trial.
- no summarizing is done (such as collapsing to produce mean and standard deviation values across trials).

This ‘wide’ format, as expected by R for creating dataframes, and various other analysis programs, means that some information must be repeated on every row.

In particular, if the trialHandler’s ‘extraInfo’ exists, then each entry in there occurs in every row. In builder, this will include any entries in the ‘Experiment info’ field of the ‘Experiment settings’ dialog. In Coder, this information can be set using something like:

```
myTrialHandler.extraInfo = {'SubjID': 'Joan Smith',
                             'Group': 'Control'}
```

### Parameters

**fileName:** if extension is not specified, ‘.csv’ will be appended if the delimiter is ‘;’, else ‘.tsv’ will be appended. Can include path info.

**delim:** allows the user to use a delimiter other than the default tab (“,” is popular with file extension “.csv”)

**matrixOnly:** outputs the data with no header row.

**appendFile:** will add this output to the end of the specified file if it already exists.

**fileCollisionMethod:** Collision method passed to `handleFileCollision()`

**encoding:** The encoding to use when saving a the file. Defaults to *utf-8-sig*.

**setExp** (*exp*)

Sets the ExperimentHandler that this handler is attached to

Do NOT attempt to set the experiment using:

```
trials._exp = myExperiment
```

because it needs to be performed using the *weakref* module.

## 8.4.3 StairHandler

**class** psychopy.data.**StairHandler** (*startVal*, *nReversals=None*, *stepSizes=4*, *nTrials=0*, *nUp=1*, *nDown=3*, *applyInitialRule=True*, *extraInfo=None*, *method='2AFC'*, *stepType='db'*, *minVal=None*, *maxVal=None*, *originPath=None*, *name=""*, *autoLog=True*, *\*\*kwargs*)

Class to handle smoothly the selection of the next trial and report current values etc. Calls to `next()` will fetch the next object given to this handler, according to the method specified.

See Demos >> ExperimentalControl >> JND\_staircase\_exp.py

The staircase will terminate when *nTrials* AND *nReversals* have been exceeded. If *stepSizes* was an array and has been exceeded before *nTrials* is exceeded then the staircase will continue to reverse.

*nUp* and *nDown* are always considered as 1 until the first reversal is reached. The values entered as arguments are then used.

### Parameters

**startVal:** The initial value for the staircase.

**nReversals:** The minimum number of reversals permitted. If *stepSizes* is a list, but the minimum number of reversals to perform, *nReversals*, is less than the length of this list, PsychoPy will automatically increase the minimum number of reversals and emit a warning.

**stepSizes:** The size of steps as a single value or a list (or array). For a single value the step size is fixed. For an array or list the step size will progress to the next entry at each reversal.

**nTrials:** The minimum number of trials to be conducted. If the staircase has not reached the required number of reversals then it will continue.

**nUp:** The number of 'incorrect' (or 0) responses before the staircase level increases.

**nDown:** The number of 'correct' (or 1) responses before the staircase level decreases.

**applyInitialRule** [bool] Whether to apply a 1-up/1-down rule until the first reversal point (if *True*), before switching to the specified up/down rule.

**extraInfo:** A dictionary (typically) that will be stored along with collected data using *saveAsPickle()* or *saveAsText()* methods.

**stepType:** specifies whether each step will be a jump of the given size in 'db', 'log' or 'lin' units ('lin' means this intensity will be added/subtracted)

**method:** Not used and may be deprecated in future releases.

**stepType: 'db', 'lin', 'log'** The type of steps that should be taken each time. 'lin' will simply add or subtract that amount each step, 'db' and 'log' will step by a certain number of decibels or log units (note that this will prevent your value ever reaching zero or less)

**minVal: None, or a number** The smallest legal value for the staircase, which can be used to prevent it reaching impossible contrast values, for instance.

**maxVal: None, or a number** The largest legal value for the staircase, which can be used to prevent it reaching impossible contrast values, for instance.

Additional keyword arguments will be ignored.

### Notes

The additional keyword arguments *\*\*kwargs* might for example be passed by the *MultiStairHandler*, which expects a *label* keyword for each staircase. These parameters are to be ignored by the StairHandler.

**\_intensityDec()**

decrement the current intensity and reset counter

**\_intensityInc()**

increment the current intensity and reset counter

**\_terminate()**

Remove references to ourselves in experiments and terminate the loop

**addData(result, intensity=None)**

Deprecated since 1.79.00: This function name was ambiguous. Please use one of these instead:

.addResponse(result, intensity) .addOtherData('dataName', value')

**addOtherData** (*dataName, value*)

Add additional data to the handler, to be tracked alongside the result data but not affecting the value of the staircase

**addResponse** (*result, intensity=None*)

Add a 1 or 0 to signify a correct / detected or incorrect / missed trial

This is essential to advance the staircase to a new intensity level!

Supplying an *intensity* value here indicates that you did not use the recommended intensity in your last trial and the staircase will replace its recorded value with the one you supplied here.

**calculateNextIntensity** ()

Based on current intensity, counter of correct responses, and current direction.

**getExp** ()

Return the ExperimentHandler that this handler is attached to, if any. Returns None if not attached

**getOriginPathAndFile** (*originPath=None*)

Attempts to determine the path of the script that created this data file and returns both the path to that script and its contents. Useful to store the entire experiment with the data.

If originPath is provided (e.g. from Builder) then this is used otherwise the calling script is the originPath (fine from a standard python script).

**next** ()

Advances to next trial and returns it. Updates attributes; *thisTrial*, *thisTrialN* and *thisIndex*.

If the trials have ended, calling this method will raise a StopIteration error. This can be handled with code such as:

```
staircase = data.StairHandler(.....)
for eachTrial in staircase: # automatically stops when done
    # do stuff
```

or:

```
staircase = data.StairHandler(.....)
while True: # ie forever
    try:
        thisTrial = staircase.next()
    except StopIteration: # we got a StopIteration error
        break # break out of the forever loop
    # do stuff here for the trial
```

**printAsText** (*stimOut=None, dataOut=('all\_mean', 'all\_std', 'all\_raw'), delim='\t', matrixOnly=False*)

Exactly like saveAsText() except that the output goes to the screen instead of a file

**saveAsExcel** (*fileName, sheetName='data', matrixOnly=False, appendFile=True, fileCollision-Method='rename'*)

Save a summary data file in Excel OpenXML format workbook (*xlsx*) for processing in most spreadsheet packages. This format is compatible with versions of Excel (2007 or greater) and with OpenOffice (>=3.0).

It has the advantage over the simpler text files (see *TrialHandler.saveAsText()*) that data can be stored in multiple named sheets within the file. So you could have a single file named after your experiment and then have one worksheet for each participant. Or you could have one file for each participant and then multiple sheets for repeated sessions etc.

The file extension *.xlsx* will be added if not given already.



The file will contain a set of values specifying the staircase level ('intensity') at each reversal, a list of reversal indices (trial numbers), the raw staircase / intensity level on *every* trial and the corresponding responses of the participant on every trial.

#### Parameters

**fileName:** **string** the name of the file to create or append. Can include relative or absolute path

**sheetName:** **string** the name of the worksheet within the file

**matrixOnly:** **True or False** If set to True then only the data itself will be output (no additional info)

**appendFile:** **True or False** If False any existing file with this name will be overwritten. If True then a new worksheet will be appended. If a worksheet already exists with that name a number will be added to make it unique.

**fileCollisionMethod:** **string** Collision method passed to `handleFileCollision()`  
This is ignored if `append` is True.

**saveAsJson** (*fileName=None, encoding='utf-8', fileCollisionMethod='rename'*)

Serialize the object to the JSON format.

#### Parameters

- **fileName** (*string, or None*) – the name of the file to create or append. Can include a relative or absolute path. If *None*, will not write to a file, but return an in-memory JSON object.
- **encoding** (*string, optional*) – The encoding to use when writing the file.
- **fileCollisionMethod** (*string*) – Collision method passed to `handleFileCollision()`. Can be either of 'rename', 'overwrite', or 'fail'.

#### Notes

Currently, a copy of the object is created, and the copy's `.origin` attribute is set to an empty string before serializing because loading the created JSON file would sometimes fail otherwise.

**saveAsPickle** (*fileName, fileCollisionMethod='rename'*)

Basically just saves a copy of self (with data) to a pickle file.

This can be reloaded if necessary and further analyses carried out.

**Parameters** `fileCollisionMethod`: Collision method passed to `handleFileCollision()`

**saveAsText** (*fileName, delim=None, matrixOnly=False, fileCollisionMethod='rename', encoding='utf-8-sig'*)

Write a text file with the data

#### Parameters

**fileName:** **a string** The name of the file, including path if needed. The extension `.tsv` will be added if not included.

**delim:** **a string** the delimiter to be used (e.g. ' ' for tab-delimited, ',' for csv files)

**matrixOnly:** **True/False** If True, prevents the output of the *extraInfo* provided at initialisation.

**fileCollisionMethod:** Collision method passed to `handleFileCollision()`

**encoding:** The encoding to use when saving a the file. Defaults to *utf-8-sig*.

**setExp** (*exp*)

Sets the ExperimentHandler that this handler is attached to

Do NOT attempt to set the experiment using:

```
trials._exp = myExperiment
```

because it needs to be performed using the *weakref* module.

## 8.4.4 MultiStairHandler

**class** psychopy.data.**MultiStairHandler** (*stairType='simple', method='random', conditions=None, nTrials=50, originPath=None, name="", autoLog=True*)

A Handler to allow easy interleaved staircase procedures (simple or QUEST).

Parameters for the staircases, as used by the relevant *StairHandler* or *QuestHandler* (e.g. the *startVal*, *minVal*, *maxVal*...) should be specified in the *conditions* list and may vary between each staircase. In particular, the conditions /must/ include the a *startVal* (because this is a required argument to the above handlers) a *label* to tag the staircase and a *startValSd* (only for QUEST staircases). Any parameters not specified in the conditions file will revert to the default for that individual handler.

If you need to custom the behaviour further you may want to look at the recipe on *Coder - interleave staircases*.

### Params

**stairType: 'simple' or 'quest'** Use a *StairHandler* or *QuestHandler*

**method: 'random' or 'sequential'** The stairs are shuffled in each repeat but not randomised more than that (so you can't have 3 repeats of the same staircase in a row unless it's the only one still running)

**conditions: a list of dictionaries specifying conditions** Can be used to control parameters for the different staircases. Can be imported from an Excel file using *psychopy.data.importConditions* MUST include keys providing, 'startVal', 'label' and 'startValSd' (QUEST only). The 'label' will be used in data file saving so should be unique. See Example Usage below.

**nTrials=50** Minimum trials to run (but may take more if the staircase hasn't also met its minimal reversals. See *StairHandler*

Example usage:

```
conditions=[
    {'label':'low', 'startVal': 0.1, 'ori':45},
    {'label':'high','startVal': 0.8, 'ori':45},
    {'label':'low', 'startVal': 0.1, 'ori':90},
    {'label':'high','startVal': 0.8, 'ori':90},
]
stairs = data.MultiStairHandler(conditions=conditions, nTrials=50)

for thisIntensity, thisCondition in stairs:
    thisOri = thisCondition['ori']

    # do something with thisIntensity and thisOri

    stairs.addResponse(correctIncorrect) # this is ESSENTIAL

# save data as multiple formats
```

(continues on next page)

(continued from previous page)

```
stairs.saveDataAsExcel(fileName) # easy to browse
stairs.saveAsPickle(fileName)   # contains more info
```

#### **\_startNewPass()**

Create a new iteration of the running staircases for this pass.

This is not normally needed by the user - it gets called at `__init__` and every time that `next()` runs out of trials for this pass.

#### **\_terminate()**

Remove references to ourself in experiments and terminate the loop

#### **addData(result, intensity=None)**

Deprecated 1.79.00: It was ambiguous whether you were adding the response (0 or 1) or some other data concerning the trial so there is now a pair of explicit methods:

**addResponse(corr,intensity)** #some data that alters the next trial value

**addOtherData('RT', reactionTime)** #some other data that won't control staircase

#### **addOtherData(name, value)**

Add some data about the current trial that will not be used to control the staircase(s) such as reaction time data

#### **addResponse(result, intensity=None)**

Add a 1 or 0 to signify a correct / detected or incorrect / missed trial

This is essential to advance the staircase to a new intensity level!

#### **getExp()**

Return the ExperimentHandler that this handler is attached to, if any. Returns None if not attached

#### **getOriginPathAndFile(originPath=None)**

Attempts to determine the path of the script that created this data file and returns both the path to that script and its contents. Useful to store the entire experiment with the data.

If originPath is provided (e.g. from Builder) then this is used otherwise the calling script is the originPath (fine from a standard python script).

#### **next()**

Advances to next trial and returns it.

This can be handled with code such as:

```
staircase = data.MultiStairHandler(...)
for eachTrial in staircase: # automatically stops when done
    # do stuff here for the trial
```

or:

```
staircase = data.MultiStairHandler(...)
while True: # ie forever
    try:
        thisTrial = staircase.next()
    except StopIteration: # we got a StopIteration error
        break # break out of the forever loop
    # do stuff here for the trial
```

#### **printAsText(delim='\n', matrixOnly=False)**

Write the data to the standard output stream

### Parameters

**delim:** a string the delimiter to be used (e.g. ‘ ‘ for tab-delimited, ‘,’ for csv files)

**matrixOnly: True/False** If True, prevents the output of the *extraInfo* provided at initialisation.

**saveAsExcel** (*fileName*, *matrixOnly=False*, *appendFile=False*, *fileCollisionMethod='rename'*)

Save a summary data file in Excel OpenXML format workbook (*xlsx*) for processing in most spreadsheet packages. This format is compatible with versions of Excel (2007 or greater) and with OpenOffice (>=3.0).

It has the advantage over the simpler text files (see *TrialHandler.saveAsText()*) that the data from each staircase will be save in the same file, with the sheet name coming from the ‘label’ given in the dictionary of conditions during initialisation of the Handler.

The file extension *.xlsx* will be added if not given already.

The file will contain a set of values specifying the staircase level (‘intensity’) at each reversal, a list of reversal indices (trial numbers), the raw staircase/intensity level on *every* trial and the corresponding responses of the participant on every trial.

### Parameters

**fileName: string** the name of the file to create or append. Can include relative or absolute path

**matrixOnly: True or False** If set to True then only the data itself will be output (no additional info)

**appendFile: True or False** If False any existing file with this name will be overwritten. If True then a new worksheet will be appended. If a worksheet already exists with that name a number will be added to make it unique.

**fileCollisionMethod: string** Collision method passed to *handleFileCollision()*. This is ignored if *append* is True.

**saveAsJson** (*fileName=None*, *encoding='utf-8'*, *fileCollisionMethod='rename'*)

Serialize the object to the JSON format.

### Parameters

- **fileName** (*string*, or *None*) – the name of the file to create or append. Can include a relative or absolute path. If *None*, will not write to a file, but return an in-memory JSON object.
- **encoding** (*string*, optional) – The encoding to use when writing the file.
- **fileCollisionMethod** (*string*) – Collision method passed to *handleFileCollision()*. Can be either of ‘*rename*’, ‘*overwrite*’, or ‘*fail*’.

### Notes

Currently, a copy of the object is created, and the copy’s *.origin* attribute is set to an empty string before serializing because loading the created JSON file would sometimes fail otherwise.

**saveAsPickle** (*fileName*, *fileCollisionMethod='rename'*)

Saves a copy of self (with data) to a pickle file.

This can be reloaded later and further analyses carried out.

**Parameters** *fileCollisionMethod*: Collision method passed to *handleFileCollision()*

**saveAsText** (*fileName*, *delim=None*, *matrixOnly=False*, *fileCollisionMethod='rename'*, *encoding='utf-8-sig'*)

Write out text files with the data.

For MultiStairHandler this will output one file for each staircase that was run, with `_label` added to the `fileName` that you specify above (label comes from the condition dictionary you specified when you created the Handler).

#### Parameters

**fileName:** a string The name of the file, including path if needed. The extension `.tsv` will be added if not included.

**delim:** a string the delimiter to be used (e.g. `' '` for tab-delimited, `','` for csv files)

**matrixOnly:** True/False If True, prevents the output of the *extraInfo* provided at initialisation.

**fileCollisionMethod:** Collision method passed to `handleFileCollision()`

**encoding:** The encoding to use when saving a the file. Defaults to *utf-8-sig*.

**setExp** (*exp*)

Sets the ExperimentHandler that this handler is attached to

Do NOT attempt to set the experiment using:

```
trials._exp = myExperiment
```

because it needs to be performed using the *weakref* module.

## 8.4.5 QuestHandler

**class** psychopy.data.QuestHandler (*startVal*, *startValSd*, *pThreshold=0.82*, *nTrials=None*, *stopInterval=None*, *method='quantile'*, *beta=3.5*, *delta=0.01*, *gamma=0.5*, *grain=0.01*, *range=None*, *extraInfo=None*, *minVal=None*, *maxVal=None*, *staircase=None*, *originPath=None*, *name=""*, *autoLog=True*, *\*\*kwargs*)

Class that implements the Quest algorithm for quick measurement of psychophysical thresholds.

Uses Andrew Straw's [QUEST](#), which is a Python port of Denis Pelli's Matlab code.

Measures threshold using a Weibull psychometric function. Currently, it is not possible to use a different psychometric function.

Threshold 't' is measured on an abstract 'intensity' scale, which usually corresponds to log10 contrast.

The Weibull psychometric function:

$$_e = -10^{(beta * (x^2 + xThreshold))}$$

$$p2 = delta * gamma + (1 - delta) * (1 - (1 - gamma) * exp(_e))$$

**Example:**

```
# setup display/window
...
# create stimulus
stimulus = visual.RadialStim(win=win, tex='sinXsin', size=1,
                             pos=[0,0], units='deg')
...
# create staircase object
# trying to find out the point where subject's response is 50 / 50
```

(continues on next page)

(continued from previous page)

```
# if wanted to do a 2AFC then the defaults for pThreshold and gamma
# are good. As start value, we'll use 50% contrast, with SD = 20%
staircase = data.QuestHandler(0.5, 0.2,
    pThreshold=0.63, gamma=0.01,
    nTrials=20, minVal=0, maxVal=1)
...
while thisContrast in staircase:
    # setup stimulus
    stimulus.setContrast(thisContrast)
    stimulus.draw()
    win.flip()
    core.wait(0.5)
    # get response
    ...
    # inform QUEST of the response, needed to calculate next level
    staircase.addResponse(thisResp)
...
# can now access 1 of 3 suggested threshold levels
staircase.mean()
staircase.mode()
staircase.quantile(0.5) # gets the median
```

#### Typical values for pThreshold are:

- 0.82 which is equivalent to a 3 up 1 down standard staircase
- **0.63 which is equivalent to a 1 up 1 down standard staircase** (and might want gamma=0.01)

The variable(s) nTrials and/or stopSd must be specified.

*beta*, *delta*, and *gamma* are the parameters of the Weibull psychometric function.

#### Parameters

**startVal:** Prior threshold estimate or your initial guess threshold.

**startValSd:** Standard deviation of your starting guess threshold. Be generous with the sd as QUEST will have trouble finding the true threshold if it's more than one sd from your initial guess.

**pThreshold** Your threshold criterion expressed as probability of response==1. An intensity offset is introduced into the psychometric function so that the threshold (i.e., the midpoint of the table) yields pThreshold.

**nTrials: *None* or a number** The maximum number of trials to be conducted.

**stopInterval: *None* or a number** The minimum 5-95% confidence interval required in the threshold estimate before stopping. If both this and nTrials is specified, whichever happens first will determine when Quest will stop.

**method: 'quantile', 'mean', 'mode'** The method used to determine the next threshold to test. If you want to get a specific threshold level at the end of your staircasing, please use the quantile, mean, and mode methods directly.

**beta: 3.5 or a number** Controls the steepness of the psychometric function.

**delta: 0.01 or a number** The fraction of trials on which the observer presses blindly.

**gamma: 0.5 or a number** The fraction of trials that will generate response 1 when intensity=-Inf.

**grain: 0.01 or a number** The quantization of the internal table.

**range: None, or a number** The intensity difference between the largest and smallest intensity that the internal table can store. This interval will be centered on the initial guess `tGuess`. QUEST assumes that intensities outside of this range have zero prior probability (i.e., they are impossible).

**extraInfo:** A dictionary (typically) that will be stored along with collected data using `saveAsPickle()` or `saveAsText()` methods.

**minVal: None, or a number** The smallest legal value for the staircase, which can be used to prevent it reaching impossible contrast values, for instance.

**maxVal: None, or a number** The largest legal value for the staircase, which can be used to prevent it reaching impossible contrast values, for instance.

**staircase: None or StairHandler** Can supply a staircase object with intensities and results. Might be useful to give the quest algorithm more information if you have it. You can also call the `importData` function directly.

Additional keyword arguments will be ignored.

### Notes

The additional keyword arguments ***\*\*kwargs*** might for example be passed by the *MultiStairHandler*, which expects a *label* keyword for each staircase. These parameters are to be ignored by the *StairHandler*.

**`_checkFinished()`**  
checks if we are finished Updates attribute: *finished*

**`_intensity()`**  
assigns the next intensity level

**`_intensityDec()`**  
decrement the current intensity and reset counter

**`_intensityInc()`**  
increment the current intensity and reset counter

**`_terminate()`**  
Remove references to ourself in experiments and terminate the loop

**`addData(result, intensity=None)`**  
Deprecated since 1.79.00: This function name was ambiguous. Please use one of these instead:  
`.addResponse(result, intensity)` `.addOtherData('dataName', value')`

**`addOtherData(dataName, value)`**  
Add additional data to the handler, to be tracked alongside the result data but not affecting the value of the staircase

**`addResponse(result, intensity=None)`**  
Add a 1 or 0 to signify a correct / detected or incorrect / missed trial  
  
Supplying an *intensity* value here indicates that you did not use the recommended intensity in your last trial and the staircase will replace its recorded value with the one you supplied here.

**`calculateNextIntensity()`**  
based on current intensity and counter of correct responses

**`confInterval(getDifference=False)`**  
Return estimate for the 5%–95% confidence interval (CI).

### Parameters

**getDifference (bool)** If `True`, return the width of the confidence interval (95% - 5% percentiles). If `False`, return an NumPy array with estimates for the 5% and 95% boundaries.

**Returns** scalar or array of length 2.

**getExp ()**

Return the ExperimentHandler that this handler is attached to, if any. Returns `None` if not attached

**getOriginPathAndFile (originPath=None)**

Attempts to determine the path of the script that created this data file and returns both the path to that script and its contents. Useful to store the entire experiment with the data.

If `originPath` is provided (e.g. from Builder) then this is used otherwise the calling script is the `originPath` (fine from a standard python script).

**importData (intensities, results)**

import some data which wasn't previously given to the quest algorithm

**incTrials (nNewTrials)**

increase maximum number of trials Updates attribute: `nTrials`

**mean ()**

mean of Quest posterior pdf

**mode ()**

mode of Quest posterior pdf

**next ()**

Advances to next trial and returns it. Updates attributes; `thisTrial`, `thisTrialN`, `thisIndex`, `finished`, `intensities`

If the trials have ended, calling this method will raise a `StopIteration` error. This can be handled with code such as:

```
staircase = data.QuestHandler(...)
for eachTrial in staircase: # automatically stops when done
    # do stuff
```

or:

```
staircase = data.QuestHandler(...)
while True: # i.e. forever
    try:
        thisTrial = staircase.next()
    except StopIteration: # we got a StopIteration error
        break # break out of the forever loop
    # do stuff here for the trial
```

**printAsText (stimOut=None, dataOut=('all\_mean', 'all\_std', 'all\_raw'), delim='\t', matrixOnly=False)**

Exactly like `saveAsText()` except that the output goes to the screen instead of a file

**quantile (p=None)**

quantile of Quest posterior pdf

**saveAsExcel (fileName, sheetName='data', matrixOnly=False, appendFile=True, fileCollisionMethod='rename')**

Save a summary data file in Excel OpenXML format workbook (*xlsx*) for processing in most spreadsheet packages. This format is compatible with versions of Excel (2007 or greater) and with OpenOffice (>=3.0).



It has the advantage over the simpler text files (see `TrialHandler.saveAsText()`) that data can be stored in multiple named sheets within the file. So you could have a single file named after your experiment and then have one worksheet for each participant. Or you could have one file for each participant and then multiple sheets for repeated sessions etc.

The file extension `.xlsx` will be added if not given already.

The file will contain a set of values specifying the staircase level ('intensity') at each reversal, a list of reversal indices (trial numbers), the raw staircase / intensity level on *every* trial and the corresponding responses of the participant on every trial.

#### Parameters

**fileName:** **string** the name of the file to create or append. Can include relative or absolute path

**sheetName:** **string** the name of the worksheet within the file

**matrixOnly:** **True or False** If set to True then only the data itself will be output (no additional info)

**appendFile:** **True or False** If False any existing file with this name will be overwritten. If True then a new worksheet will be appended. If a worksheet already exists with that name a number will be added to make it unique.

**fileCollisionMethod:** **string** Collision method passed to `handleFileCollision()`  
This is ignored if `append` is True.

**saveAsJson** (`fileName=None, encoding='utf-8', fileCollisionMethod='rename'`)

Serialize the object to the JSON format.

#### Parameters

- **fileName** (*string, or None*) – the name of the file to create or append. Can include a relative or absolute path. If *None*, will not write to a file, but return an in-memory JSON object.
- **encoding** (*string, optional*) – The encoding to use when writing the file.
- **fileCollisionMethod** (*string*) – Collision method passed to `handleFileCollision()`. Can be either of 'rename', 'overwrite', or 'fail'.

#### Notes

Currently, a copy of the object is created, and the copy's `.origin` attribute is set to an empty string before serializing because loading the created JSON file would sometimes fail otherwise.

**saveAsPickle** (`fileName, fileCollisionMethod='rename'`)

Basically just saves a copy of self (with data) to a pickle file.

This can be reloaded if necessary and further analyses carried out.

**Parameters** `fileCollisionMethod`: Collision method passed to `handleFileCollision()`

**saveAsText** (`fileName, delim=None, matrixOnly=False, fileCollisionMethod='rename', encoding='utf-8-sig'`)

Write a text file with the data

#### Parameters

**fileName:** **a string** The name of the file, including path if needed. The extension `.tsv` will be added if not included.

**delim:** a string the delimiter to be used (e.g. ‘ ‘ for tab-delimited, ‘,’ for csv files)

**matrixOnly: True/False** If True, prevents the output of the *extraInfo* provided at initialisation.

**fileCollisionMethod:** Collision method passed to `handleFileCollision()`

**encoding:** The encoding to use when saving a the file. Defaults to *utf-8-sig*.

**sd()**  
standard deviation of Quest posterior pdf

**setExp(exp)**  
Sets the ExperimentHandler that this handler is attached to  
Do NOT attempt to set the experiment using:

```
trials._exp = myExperiment
```

because it needs to be performed using the *weakref* module.

**simulate(tActual)**  
returns a simulated user response to the next intensity level presented by Quest, need to supply the actual threshold level

### 8.4.6 FitWeibull

**class** psychopy.data.**FitWeibull**(xx, yy, *sems=1.0*, *guess=None*, *display=1*, *expectedMin=0.5*, *optimize\_kws=None*)

Fit a Weibull function (either 2AFC or YN) of the form:

```
y = chance + (1.0-chance) * (1-exp(-(xx/alpha)**(beta)))
```

and with inverse:

```
x = alpha * (-log((1.0-y)/(1-chance)))**(1.0/beta)
```

After fitting the function you can evaluate an array of x-values with `fit.eval(x)`, retrieve the inverse of the function with `fit.inverse(y)` or retrieve the parameters from `fit.params` (a list with [alpha, beta])

**\_doFit()**  
The Fit class that derives this needs to specify its `_evalFunction`

**eval(xx, params=None)**  
Evaluate xx for the current parameters of the model, or for arbitrary params if these are given.

**inverse(yy, params=None)**  
Evaluate yy for the current parameters of the model, or for arbitrary params if these are given.

### 8.4.7 FitLogistic

**class** psychopy.data.**FitLogistic**(xx, yy, *sems=1.0*, *guess=None*, *display=1*, *expectedMin=0.5*, *optimize\_kws=None*)

Fit a Logistic function (either 2AFC or YN) of the form:

```
y = chance + (1-chance) / (1+exp((PSE-xx)*JND))
```

and with inverse:

```
x = PSE - log((1-chance)/(yy-chance) - 1)/JND
```

After fitting the function you can evaluate an array of x-values with `fit.eval(x)`, retrieve the inverse of the function with `fit.inverse(y)` or retrieve the parameters from `fit.params` (a list with [PSE, JND])

**\_doFit()**

The Fit class that derives this needs to specify its `_evalFunction`

**eval**(xx, params=None)

Evaluate xx for the current parameters of the model, or for arbitrary params if these are given.

**inverse**(yy, params=None)

Evaluate yy for the current parameters of the model, or for arbitrary params if these are given.

## 8.4.8 FitNakaRushton

**class** psychopy.data.**FitNakaRushton**(xx, yy, *sems=1.0*, *guess=None*, *display=1*, *expectedMin=0.5*, *optimize\_kws=None*)

Fit a Naka-Rushton function of the form:

```
yy = rMin + (rMax-rMin) * xx**n/(xx**n+c50**n)
```

After fitting the function you can evaluate an array of x-values with `fit.eval(x)`, retrieve the inverse of the function with `fit.inverse(y)` or retrieve the parameters from `fit.params` (a list with [rMin, rMax, c50, n])

Note that this differs from most of the other functions in not using a value for the expected minimum. Rather, it fits this as one of the parameters of the model.

**\_doFit()**

The Fit class that derives this needs to specify its `_evalFunction`

**eval**(xx, params=None)

Evaluate xx for the current parameters of the model, or for arbitrary params if these are given.

**inverse**(yy, params=None)

Evaluate yy for the current parameters of the model, or for arbitrary params if these are given.

## 8.4.9 FitCumNormal

**class** psychopy.data.**FitCumNormal**(xx, yy, *sems=1.0*, *guess=None*, *display=1*, *expectedMin=0.5*, *optimize\_kws=None*)

Fit a Cumulative Normal function (aka error function or erf) of the form:

```
y = chance + (1-chance)*((special.erf((xx-xShift)/(sqrt(2)*sd))+1)*0.5)
```

and with inverse:

```
x = xShift+sqrt(2)*sd*(erfinv(((yy-chance)/(1-chance)-.5)*2))
```

After fitting the function you can evaluate an array of x-values with `fit.eval(x)`, retrieve the inverse of the function with `fit.inverse(y)` or retrieve the parameters from `fit.params` (a list with [centre, sd] for the Gaussian distribution forming the cumulative)

NB: Prior to version 1.74 the parameters had different meaning, relating to xShift and slope of the function (similar to 1/sd). Although that is more in with the parameters for the Weibull fit, for instance, it is less in

keeping with standard expectations of normal (Gaussian distributions) so in version 1.74.00 the parameters became the [centre,sd] of the normal distribution.

**`_doFit()`**

The Fit class that derives this needs to specify its `_evalFunction`

**`eval(xx, params=None)`**

Evaluate `xx` for the current parameters of the model, or for arbitrary params if these are given.

**`inverse(yy, params=None)`**

Evaluate `yy` for the current parameters of the model, or for arbitrary params if these are given.

#### 8.4.10 `importConditions()`

`psychopy.data.importConditions(fileName, returnFieldNames=False, selection="")`

Imports a list of conditions from an .xlsx, .csv, or .pkl file

The output is suitable as an input to `TrialHandler` *trialTypes* or to `MultiStairHandler` as a *conditions* list.

If *fileName* ends with:

- **.csv: import as a comma-separated-value file** (header + row x col)
- **.xlsx: import as Excel 2007 (xlsx) files.** No support for older (.xls) is planned.
- **.pkl: import from a pickle file as list of lists** (header + row x col)

The file should contain one row per type of trial needed and one column for each parameter that defines the trial type. The first row should give parameter names, which should:

- be unique
- begin with a letter (upper or lower case)
- contain no spaces or other punctuation (underscores are permitted)

*selection* is used to select a subset of condition indices to be used It can be a list/array of indices, a python *slice* object or a string to be parsed as either option. e.g.:

- "1,2,4" or [1,2,4] or (1,2,4) are the same
- "2:5" # 2, 3, 4 (doesn't include last whole value)
- "-10:2:" # tenth from last to the last in steps of 2
- slice(-10, 2, None) # the same as above
- random(5) \* 8 # five random vals 0-8

#### 8.4.11 `functionFromStaircase()`

`psychopy.data.functionFromStaircase(intensities, responses, bins=10)`

Create a psychometric function by binning data from a staircase procedure. Although the default is 10 bins Jon now always uses 'unique' bins (fewer bins looks pretty but leads to errors in slope estimation)

usage:

```
intensity, meanCorrect, n = functionFromStaircase(intensities,
                                                  responses, bins)
```

where:

**intensities** are a list (or array) of intensities to be binned

**responses** are a list of 0,1 each corresponding to the equivalent intensity value

**bins** can be an integer (giving that number of bins) or 'unique' (each bin is made from aa data for exactly one intensity value)

**intensity** a numpy array of intensity values (where each is the center of an intensity bin)

**meanCorrect** a numpy array of mean % correct in each bin

**n** a numpy array of number of responses contributing to each mean

#### 8.4.12 bootStraps ()

`psychopy.data.bootStraps (dat, n=1)`

Create a list of n bootstrapped resamples of the data

SLOW IMPLEMENTATION (Python for-loop)

**Usage:** `out = bootStraps(dat, n=1)`

**Where:**

**dat** an NxM or 1xN array (each row is a different condition, each column is a different trial)

**n** number of bootstrapped resamples to create

**out**

- `dim[0]`=conditions
- `dim[1]`=trials
- `dim[2]`=resamples

## 8.5 Encryption

Some labs may wish to better protect their data from casual inspection or accidental disclosure. This is possible within PsychoPy using a separate python package, `pyFileSec`, which grew out of PsychoPy. `pyFileSec` is distributed with the StandAlone versions of PsychoPy, or can be installed using pip or easy\_install via <https://pypi.python.org/pypi/PyFileSec/>

Some elaboration of `pyFileSec` usage and security strategy can be found here: <http://pythonhosted.org/PyFileSec>

Basic usage is illustrated in the Coder demo > misc > `encrypt_data.py`

## 8.6 psychopy.event - for keypresses and mouse clicks

**class** `psychopy.event.Mouse (visible=True, newPos=None, win=None)`

Easy way to track what your mouse is doing.

It needn't be a class, but since Joystick works better as a class this may as well be one too for consistency

Create your *visual.Window* before creating a Mouse.

**Parameters**

**visible** [**True** or **False**] makes the mouse invisible if necessary

**newPos** [**None** or [x,y]] gives the mouse a particular starting position (pygame *Window* only)

**win** [**None** or *Window*] the window to which this mouse is attached (the first found if **None** provided)

**clickReset** (*buttons*=(0, 1, 2))

Reset a 3-item list of core.Clocks use in timing button clicks.

The pyglet mouse-button-pressed handler uses their clock.getLastResetTime() when a button is pressed so the user can reset them at stimulus onset or offset to measure RT. The default is to reset all, but they can be reset individually as specified in buttons list

**getPos** ()

Returns the current position of the mouse, in the same units as the *Window* (0,0) is at centre

**getPressed** (*getTime*=False)

Returns a 3-item list indicating whether or not buttons 0,1,2 are currently pressed.

If *getTime*=True (False by default) then *getPressed* will return all buttons that have been pressed since the last call to *mouse.clickReset* as well as their time stamps:

```
buttons = mouse.getPressed()
buttons, times = mouse.getPressed(getTime=True)
```

Typically you want to call *mouse.clickReset*() at stimulus onset, then after the button is pressed in reaction to it, the total time elapsed from the last reset to click is in *mouseTimes*. This is the actual RT, regardless of when the call to *getPressed*() was made.

**getRel** ()

Returns the new position of the mouse relative to the last call to *getRel* or *getPos*, in the same units as the *Window*.

**getVisible** ()

Gets the visibility of the mouse (1 or 0)

**getWheelRel** ()

Returns the travel of the mouse scroll wheel since last call. Returns a *numpy.array*(x,y) but for most wheels y is the only value that will change (except Mac mighty mice?)

**isPressedIn** (*shape*, *buttons*=(0, 1, 2))

Returns *True* if the mouse is currently inside the shape and one of the mouse buttons is pressed. The default is that any of the 3 buttons can indicate a click; for only a left-click, specify *buttons*=[0]:

```
if mouse.isPressedIn(shape):
if mouse.isPressedIn(shape, buttons=[0]): # left-clicks only
```

Ideally, *shape* can be anything that has a *.contains()* method, like *ShapeStim* or *Polygon*. Not tested with *ImageStim*.

**mouseMoveTime** ()

**mouseMoved** (*distance*=None, *reset*=False)

Determine whether/how far the mouse has moved.

With no args returns true if mouse has moved at all since last *getPos*() call, or distance (x,y) can be set to pos or neg distances from x and y to see if moved either x or y that far from lastPos, or distance can be an int/float to test if new coordinates are more than that far in a straight line from old coords.

Retrieve time of last movement from *self.mouseClock.getTime*().

Reset can be to 'here' or to screen coords (x,y) which allows measuring distance from there to mouse when moved. If reset is (x,y) and distance is set, then *prevPos* is set to (x,y) and distance from (x,y) to here

is checked, `mouse.lastPos` is set as current (x,y) by `getPos()`, `mouse.prevPos` holds lastPos from last time `mouseMoved` was called.

**setExclusive** (*exclusivity*)

Binds the mouse to the experiment window. Only works in Pyglet.

In multi-monitor settings, or with a window that is not fullscreen, the mouse pointer can drift, and thereby PsychoPy might not get the events from that window. `setExclusive(True)` works with Pyglet to bind the mouse to the experiment window.

Note that binding the mouse pointer to a window will cause the pointer to vanish, and absolute positions will no longer be meaningful `getPos()` returns [0, 0] in this case.

**setPos** (*newPos=(0, 0)*)

Sets the current position of the mouse, in the same units as the `Window`. (0,0) is the center.

**Parameters**

**newPos** [(x,y) or [x,y]] the new position on the screen

**setVisible** (*visible*)

Sets the visibility of the mouse to 1 or 0

NB when the mouse is not visible its absolute position is held at (0, 0) to prevent it from going off the screen and getting lost! You can still use `getRel()` in that case.

**units**

The units for this mouse (will match the current units for the `Window` it lives in)

`psychopy.event.clearEvents` (*eventType=None*)

Clears all events currently in the event buffer.

Optional argument, `eventType`, specifies only certain types to be cleared.

**Parameters**

**eventType** [None, 'mouse', 'joystick', 'keyboard'] If this is not None then only events of the given type are cleared

`psychopy.event.waitKeys` (*maxWait=inf, keyList=None, modifiers=False, timeStamped=False, clearEvents=True*)

Same as `~psychopy.event.getKeys`, but halts everything (including drawing) while awaiting input from keyboard.

**Parameters**

**maxWait** [any numeric value.] Maximum number of seconds period and which keys to wait for. Default is `float('inf')` which simply waits forever.

**keyList** [None or []] Allows the user to specify a set of keys to check for. Only keypresses from this set of keys will be removed from the keyboard buffer. If the `keyList` is *None*, all keys will be checked and the key buffer will be cleared completely. NB, `pygame` doesn't return timestamps (they are always 0)

**modifiers** [False or True] If True will return a list of tuples instead of a list of keynames. Each tuple has (keyname, modifiers). The modifiers are a dict of keyboard modifier flags keyed by the modifier name (eg. 'shift', 'ctrl').

**timeStamped** [False, True, or *Clock*] If True will return a list of tuples instead of a list of keynames. Each tuple has (keyname, time). If a *core.Clock* is given then the time will be relative to the *Clock*'s last reset.

**clearEvents** [True or False] Whether to clear the keyboard event buffer (and discard preceding keypresses) before starting to monitor for new keypresses.

Returns None if times out.

`psychopy.event.getKeys` (*keyList=None, modifiers=False, timeStamped=False*)

Returns a list of keys that were pressed.

#### Parameters

**keyList** [**None** or []] Allows the user to specify a set of keys to check for. Only keypresses from this set of keys will be removed from the keyboard buffer. If the *keyList* is *None*, all keys will be checked and the key buffer will be cleared completely. NB, pygame doesn't return timestamps (they are always 0)

**modifiers** [**False** or **True**] If **True** will return a list of tuples instead of a list of keynames. Each tuple has (keyname, modifiers). The modifiers are a dict of keyboard modifier flags keyed by the modifier name (eg. 'shift', 'ctrl').

**timeStamped** [**False**, **True**, or *Clock*] If **True** will return a list of tuples instead of a list of keynames. Each tuple has (keyname, time). If a *core.Clock* is given then the time will be relative to the *Clock*'s last reset.

#### Author

- 2003 written by Jon Peirce
- 2009 *keyList* functionality added by Gary Strangman
- 2009 *timeStamped* code provided by Dave Britton
- 2016 *modifiers* code provided by 5AM Solutions

`psychopy.event.xydist` (*p1=(0.0, 0.0), p2=(0.0, 0.0)*)

Helper function returning the cartesian distance between *p1* and *p2*

## 8.7 `psychopy.filters` - helper functions for creating filters

This module has moved to *psychopy.visual.filters* but you can still (currently) import it as *psychopy.filters*

## 8.8 `psychopy.gui` - create dialogue boxes

### 8.8.1 `DlgFromDict`

```
class psychopy.gui.DlgFromDict (dictionary, title="", fixed=None, order=None, tip=None,  
                                screen=-1, sortKeys=True, copyDict=False, labels=None,  
                                show=True, **kwargs)
```

Creates a dialogue box that represents a dictionary of values. Any values changed by the user are change (in-place) by this dialogue box.

#### Parameters

- **dictionary** (*dict*) – A dictionary defining the input fields (keys) and pre-filled values (values) for the user dialog
- **title** (*str*) – The title of the dialog window
- **labels** (*dict*) – A dictionary defining labels (values) to be displayed instead of key strings (keys) defined in “dictionary”. Not all keys in “dictionary” need to be contained in labels.
- **fixed** (*list*) – A list of keys for which the values shall be displayed in non-editable fields



- **order** (*list*) – A list of keys defining the display order of keys in “dictionary”. If not all keys in “dictionary” are contained in “order”, those will appear in random order after all ordered keys.
- **tip** (*list*) – A dictionary assigning tooltips to the keys
- **screen** (*int*) – Screen number where the Dialog is displayed. If -1, the Dialog will be displayed on the primary screen.
- **sortKeys** (*bool*) – A boolean flag indicating that keys are to be sorted alphabetically.
- **copyDict** (*bool*) – If False, modify `dictionary` in-place. If True, a copy of the dictionary is created, and the altered version (after user interaction) can be retrieved from `:attr:~'psychopy.gui.DlgFromDict.dictionary'`.
- **labels** – A dictionary defining labels (dict values) to be displayed instead of key strings (dict keys) defined in “dictionary”. Not all keys in “dictionary” need to be contained in labels.
- **show** (*bool*) –  
**Whether to immediately display the dialog upon instantiation.** If False, it can be displayed at a later time by calling its `show()` method.
- **e.g.** –

**:param :::**

```
info = {'Observer':'jwp', 'GratingOri':45, 'ExpVersion': 1.1, 'Group': ['Test', 'Control']}
infoDlg = gui.DlgFromDict(dictionary=info, title='TestExperiment', fixed=['ExpVersion'])
if infoDlg.OK: print(info)
else: print('User Cancelled')
```

#### Parameters

- the code above, the contents of `info` will be updated to the values (*In*) –
- by the dialogue box. (*returned*) –
- the user cancels (rather than pressing OK), (*If*) –
- the dictionary remains unchanged. If you want to check whether (*then*) –
- user hit OK, then check whether `DlgFromDict.OK` equals (*the*) –
- or **False** (*True*) –
- GUI.py for a usage demo, including order and tip (tooltip) (*See*) –

**show()**

Display the dialog.

## 8.8.2 Dlg

```
class psychopy.gui.Dlg (title='PsychoPy Dialog', pos=None, size=None, style=None, labelButtonOK='OK', labelButtonCancel='Cancel', screen=-1)
```

A simple dialogue box. You can add text or input boxes (sequentially) and then retrieve the values.

see also the function *dlgFromDict* for an **even simpler** version

### Example

```
from psychopy import gui

myDlg = gui.Dlg(title="JWP's experiment")
myDlg.addText('Subject info')
myDlg.addField('Name:')
myDlg.addField('Age:', 21)
myDlg.addText('Experiment Info')
myDlg.addField('Grating Ori:', 45)
myDlg.addField('Group:', choices=["Test", "Control"])
ok_data = myDlg.show() # show dialog and wait for OK or Cancel
if myDlg.OK: # or if ok_data is not None
    print(ok_data)
else:
    print('user cancelled')
```

**addField** (label="", initial="", color="", choices=None, tip="", enabled=True)

Adds a (labelled) input field to the dialogue box, optional text color and tooltip.

If ‘initial’ is a bool, a checkbox will be created. If ‘choices’ is a list or tuple, a dropdown selector is created. Otherwise, a text line entry box is created.

Returns a handle to the field (but not to the label).

**addFixedField** (label="", initial="", color="", choices=None, tip="")

Adds a field to the dialog box (like addField) but the field cannot be edited. e.g. Display experiment version.

**show** ()

Presents the dialog and waits for the user to press OK or CANCEL.

If user presses OK button, function returns a list containing the updated values coming from each of the input fields created. Otherwise, None is returned.

**Returns** self.data

## 8.8.3 fileOpenDlg()

`psychopy.gui.fileOpenDlg` (tryFilePath="", tryFileName="", prompt='Select file to open', allowed=None)

A simple dialogue allowing read access to the file system.

### Parameters

**tryFilePath:** string default file path on which to open the dialog

**tryFileName:** string default file name, as suggested file

**prompt:** string (default “Select file to open”) can be set to custom prompts

**allowed:** string (available since v1.62.01) a string to specify file filters. e.g. “Text files (\*.txt) ; Image files (\*.bmp \*.gif)” See <http://pyqt.sourceforge.net/Docs/PyQt4/qfiledialog.html#getOpenFileNames> for further details

If tryFilePath or tryFileName are empty or invalid then current path and empty names are used to start search.

If user cancels, then None is returned.

### 8.8.4 fileSaveDlg()

`psychopy.gui.fileSaveDlg` (*initFilePath*="", *initFileName*="", *prompt*='Select file to save', *allowed*=None)

A simple dialogue allowing write access to the file system. (Useful in case you collect an hour of data and then try to save to a non-existent directory!!)

#### Parameters

**initFilePath:** **string** default file path on which to open the dialog

**initFileName:** **string** default file name, as suggested file

**prompt:** **string** (default "Select file to open") can be set to custom prompts

**allowed:** **string** a string to specify file filters. e.g. "Text files (\*.txt) ;; Image files (\*.bmp \*.gif)"  
See <http://pyqt.sourceforge.net/Docs/PyQt4/qfiledialog.html> #getSaveFileName for further details

If *initFilePath* or *initFileName* are empty or invalid then current path and empty names are used to start search.

If user cancels the None is returned.

## 8.9 psychopy.hardware - hardware interfaces

PsychoPy can access a wide range of external hardware. For some devices the interface has already been created in the following sub-packages of PsychoPy. For others you may need to write the code to access the serial port etc. manually.

Contents:

### 8.9.1 Cedrus (response boxes)

The pyxid package, written by Cedrus, is included in the Standalone PsychoPy distributions. See <https://github.com/cedrus-opensource/pyxid> for further info.

Example usage:

```
import pyxid

# get a list of all attached XID devices
devices = pyxid.get_xid_devices()

dev = devices[0] # get the first device to use
if dev.is_response_device():
    dev.reset_base_timer()
    dev.reset_rt_timer()

while True:
    dev.poll_for_response()
    if dev.response_queue_size() > 0:
        response = dev.get_next_response()
        # do something with the response
```

#### Useful functions

`pyxid.get_xid_device` (*device\_number*)  
returns device at a given index.

Raises ValueError if the device at the passed in index doesn't exist.

`pyxid.get_xid_devices()`

Returns a list of all Xid devices connected to your computer.

## Device classes

`class pyxid.ResponseDevice(connection, name='Unknown XID Device', keymap=None, trigger_prefix='Button')`

`clear_response_queue()`

Clears the response queue

`get_next_response()`

Pops the response at the beginning of the response queue and returns it.

This function returns a dict object with the following keys:

**pressed:** A boolean value of whether the event was a keypress or key release.

**key:** The key on the device that was pressed. This is a 0 based index.

**port:** Device port the response came from. Typically this is 0 on RB-series devices, and 2 on SV-1 voice key devices.

**time:** For the time being, this just returns 0. There is currently an issue with clock drift in the Cedrus XID devices. Once we have this issue resolved, time will report the value of the RT timer in milliseconds.

`poll_for_response()`

Polls the device for user input

If there is a keymapping for the device, the key map is applied to the key reported from the device.

If a response is waiting to be processed, the response is appended to the internal response\_queue

`response_queue_size()`

Number of responses in the response queue

`class pyxid.XidDevice(xid_connection)`

Class for interfacing with a Cedrus XID device.

At the beginning of an experiment, the developer should call:

`XidDevice.reset_base_timer()`

Whenever a stimulus is presented, the developer should call:

`XidDevice.reset_rt_timer()`

Developers Note: Currently there is a known issue of clock drift in the XID devices. Due to this, the dict returned by `XidDevice.get_next_response()` returns 0 for the reaction time value.

This issue will be resolved in a future release of this library.

`_send_command(command, expected_bytes)`

Send an XID command to the device

`init_device()`

Initializes the device with the proper keymaps and name

## 8.9.2 Cambridge Research Systems Ltd.

Cambridge Research Systems makes devices to support particularly vision research.

### For stimulus display

#### BitsPlusPlus

Control a CRS Bits# device. See typical usage in the class summary (and in the menu demos>hardware>BitsBox of PsychoPy's Coder view).

**Important:** See note on *BitsPlusPlusIdentityLUT*

### Attributes

<code>BitsPlusPlus(win[, contrast, gamma, ...])</code>	The main class to control a Bits++ box.
<code>BitsPlusPlus.mode</code>	
<code>BitsPlusPlus.setContrast(contrast[, ...])</code>	Set the contrast of the LUT for 'bits++' mode only :Parameters: contrast : float in the range 0:1 The contrast for the range being set LUTrange : float or array If a float is given then this is the fraction of the LUT to be used.
<code>BitsPlusPlus.setGamma(newGamma)</code>	Set the LUT to have the requested gamma value Currently also resets the LUT to be a linear contrast ramp spanning its full range.
<code>BitsPlusPlus.setLUT([newLUT, gammaCorrect, ...])</code>	Sets the LUT to a specific range of values in 'bits++' mode only Note that, if you leave gammaCorrect=True then any LUT values you supply will automatically be gamma corrected.

### Details

```
class psychopy.hardware.crs.bits.BitsPlusPlus (win, contrast=1.0, gamma=None,
                                             nEntries=256, mode='bits++', ramp-
                                             Type='configFile', frameRate=None)
```

The main class to control a Bits++ box. This is usually a class added within the window object and is typically accessed from there. e.g.:

```
from psychopy import visual
from psychopy.hardware import crs
win = visual.Window([800,600])
bits = crs.BitsPlusPlus(win, mode='bits++')
# use bits++ to reduce the whole screen contrast by 50%:
bits.setContrast(0.5)
```

### Parameters

**contrast** : The contrast to be applied to the LUT. See *BitsPlusPlus.setLUT()* and *BitsPlusPlus.setContrast()* for flexibility on setting just a section of the LUT to a different value

**gamma** : The value used to correct the gamma in the LUT

**nEntries** [256] [DEPRECATED feature]

**mode** ['bits++' (or 'mono++' or 'color++')] Note that, unlike the Bits#, this only affects the way the window is rendered, it does not switch the state of the Bits++ device itself (because unlike the Bits# have no way to communicate with it). The mono++ and color++ are only supported in PsychoPy 1.82.00 onwards. Even then they suffer from not having gamma correction applied on Bits++ (unlike Bits# which can apply a gamma table in the device hardware).

**rampType** ['configFile', None or an integer] if 'configFile' then we'll look for a valid config in the userPrefs folder if an integer then this will be used during win.setGamma(rampType=rampType):

frameRate : an estimate the frameRate of the monitor. If None frame rate will be calculated.

**\_Goggles()**

(private) Used to set control the goggles. Should not be needed by user if attached to a psychopy.visual.Window()

**\_ResetClock()**

(private) Used to reset Bits hardware clock. Should not be needed by user if attached to a psychopy.visual.Window() since this will automatically draw the reset code as part of the screen refresh.

**\_drawLUTtoScreen()**

(private) Used to set the LUT in 'bits++' mode. Should not be needed by user if attached to a psychopy.visual.Window() since this will automatically draw the LUT as part of the screen refresh.

**\_drawTrigtoScreen** (sendStr=None)

(private) Used to send a trigger pulse. Should not be needed by user if attached to a psychopy.visual.Window() since this will automatically draw the trigger code as part of the screen refresh.

**\_protectTrigger()**

If Goggles (or analog) outputs are used when the digital triggers are off we need to make a set of blank triggers first. But the user might have set up triggers in waiting for a later time. So this will protect them.

**\_restoreTrigger()**

Restores the triggers to previous settings

**\_setHeaders** (frameRate)

Sets up the TLock header codes and some flags that are common to operating all CRS devices

**\_setupShaders()**

creates and stores the shader programs needed for mono++ and color++ modes

**getPackets()**

Returns the number of packets available for trigger pulses.

**primeClock()**

Primes the clock to reset at the next screen flip - note only 1 clock reset signal will be issued but if the frame(s) after the reset frame is dropped the reset will be re-issued thus keeping timing good.

Resets continue to be issued on each video frame until the next win.flip so you need to have regular win.flips for this function to work properly.

**Example** bits.primeClock() drawImage while not response

```
#do some processing bits.win.flip()
```

Will get a clock reset signal ready but wont issue it until the first win.flip in the loop.

#### **reset ()**

Deprecated: This was used on the old Bits++ to power-cycle the box. It required the compiled dll, which only worked on windows and doesn't work with Bits# or Display++.

#### **resetClock ()**

Issues a clock reset code using 1 screen flip if the next frame(s) is dropped the reset will be re-issued thus keeping timing good.

Resets continue to be issued on each video frame until the next win.flip so you need to have regular win.flips for this function to work properly.

#### **Example**

```
bits.resetClock() drawImage() bits.win.flip()
```

Will issue clock resets while the image is being drawn then display the image and allow the clock to continue from the same frame.

#### **Example**

```
bits.resetClock() bits.RTBoxWait() bits.win.flip()
```

Will issue clock resets until a button is pressed.

#### **sendTrigger (triggers=0, onTime=0, duration=0, mask=65535)**

Sends a single trigger using up 1 win.flip. The trigger will be sent on the following frame.

The triggers will continue until after the next win.flip.

Actions are always 1 frame after the request.

May do odd things if Goggles and Analog are also in use.

#### **Example**

```
bits.sendTrigger(0b0000000010, 2.0, 4.0) bits.win.flip()
```

Will send a 4ms pulse on DOUT1 2ms after the start of the frame. Due to the following win.flip() the pulse should last for 1 frame only.

Triggers will continue until stopTrigger is called.

#### **setContrast (contrast, LUTrange=1.0, gammaCorrect=None)**

Set the contrast of the LUT for 'bits++' mode only :Parameters:

**contrast** [float in the range 0:1] The contrast for the range being set

**LUTrange** [float or array] If a float is given then this is the fraction of the LUT to be used. If an array of floats is given, these will specify the start / stop points as fractions of the LUT. If an array of ints (0-255) is given these determine the start stop *indices* of the LUT

#### **Examples**

**setContrast (1.0, 0.5)** will set the central 50% of the LUT so that a stimulus with contr=0.5 will actually be drawn with contrast 1.0

```
setContrast(1.0, [0.25, 0.5]) setContrast(1.0, [63, 127])
```

will set the lower-middle quarter of the LUT (which might be useful in LUT animation paradigms)

**setGamma** (*newGamma*)

Set the LUT to have the requested gamma value. Currently also resets the LUT to be a linear contrast ramp spanning its full range. May change this to read the current LUT, undo previous gamma and then apply new one?

**setLUT** (*newLUT=None, gammaCorrect=True, LUTrange=1.0*)

Sets the LUT to a specific range of values in 'bits++' mode only. Note that, if you leave *gammaCorrect=True* then any LUT values you supply will automatically be gamma corrected. The LUT will take effect on the next *Window.flip()* **Examples:**

**bitsBox.setLUT()** builds a LUT using *bitsBox.contrast* and *bitsBox.gamma*

**bitsBox.setLUT(newLUT=some256x1array)** (NB array should be float 0.0:1.0)  
Builds a luminance LUT using *newLUT* for each gun (actually array can be 256x1 or 1x256)

**bitsBox.setLUT(newLUT=some256x3array)** (NB array should be float 0.0:1.0) Allows you to use a different LUT on each gun

(NB by using *BitsBox.setContr()* and *BitsBox.setGamma()* users may not need this function)

**setTrigger** (*triggers=0, onTime=0, duration=0, mask=65535*)

Quick way to set up triggers.

Triggers is a binary word that determines which triggers will be turned on.

*onTime* specifies the start time of the trigger within the frame (in S with 100uS resolution)

*Duration* specifies how long the trigger will last. (in S with 100uS resolution).

Note that *mask* only protects the digital output lines set by other activities in the Bits. Not other triggers.

### Example

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b0111111111) bits.startTrigger()
```

Will issue a 4ms long high-going pulse, 2ms after the start of each frame on DOUT1 while protecting the value of DOUT 9.

**setTriggerList** (*triggerList=None, mask=65535*)

Sets up Trigger pulses in Bist++ using the fine grained method that can control every trigger line at 100uS intervals.

*TriggerList* should contain 1 entry for every 100uS packet (see *getPackets*) the binary word in each entry specifies which trigger line will be active during that time slot.

Note that *mask* only protects the digital output lines set by other activities in the Bits. Not other triggers.

### Example

```
packet = [0]*self._NumberPackets packet[0] = 0b0000000010 bits.setTriggerList(packet)
```

Will send a 100us pulse on DOUT1 at the start of the frame.

**Example 2:** `packet = [0]*self._NumberPackets packet[10] = 0b0000000010 packet[20] = 0b0000000001 bits.setTriggerList(packet) bits.startTrigger()`



Will send a 100us pulse on DOUT1 1000us after the start of the frame and a second 100us pulse on DOUT0 2000us after the start of the frame.

Triggers will continue until stopTrigger is called.

**startGoggles** (*left=0, right=1*)

**Starts CRS stereo goggles. Note if you are** using FE-1 goggles you should start this before connecting the goggles.

Left is the state of the left shutter on the first frame to be presented 0, False or 'closed'=closed; 1, True or 'open' = open,

right is the state of the right shutter on the first frame to be presented 0, False or

'closed'=closed; 1, True or 'open' = open

Note you can set the goggles to be both open or both closed on the same frame.

The system will always toggle the state of each lens so as to not damage FE-1 goggles.

### Example

```
bits.startGoggles(0,1) bits.win.flip() while not response
```

```
    bits.win.flip() #do some processing
```

```
bits.stopGoggles() bits.win.flip()
```

Starts toggling the goggles with the right eye open in sync with the first win.flip(0) within the loop. The open eye will alternate.

### Example

```
bits.startGoggles(1,1) bits.win.flip() while not response
```

```
    bits.win.flip() #do some processing
```

```
bits.stopGoggles() bits.win.flip()
```

Starts toggling the goggles with both eyes open in sync with the first win.flip(0) within the loop. Eyes will alternate between both open and both closed.

Note it is safe to leave the goggles toggling forever, ie to never call stopGoggles().

**startTrigger** ()

Start sending triggers on the next win flip and continue until stopped by stopTrigger Triggers start 1 frame after the frame on which the first trigger is sent.

### Example

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b0111111111) bits.startTrigger() while imageOn:
```

```
    #do some processing continue
```

```
bits.stopTrigger() bits.win.flip()
```

**stopGoggles** ()

Stop the stereo goggles from toggling

### Example

```
bits.startGoggles(0,1) bits.win.flip() while not response
```

```
    bits.win.flip() #do some processing
```

```
bits.stopGoggles() bits.win.flip()
```

Starts toggling the goggles with the right eye open in sync with the first win.flip(0) within the loop. The open eye will alternate.

Note it is safer to leave the goggles toggling forever, ie to never call stopGoggles().

### stopTrigger ()

Stop sending triggers at the next win flip

### Example

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b0111111111) bits.startTrigger() while imageOn:
```

```
    #do some processing continue
```

```
bits.stopTrigger() bits.win.flip()
```

### syncClocks (t)

Synchronise the Bits/RTBox Clock with the host clock Given by t.

## Finding the identity LUT

For the Bits++ (and related) devices to work correctly it is essential that the graphics card is not altering in any way the values being passed to the monitor (e.g. by gamma correcting). It turns out that finding the ‘identity’ LUT, where exactly the same values come out as were put in, is not trivial. The obvious LUT would have something like 0/255, 1/255, 2/255... in entry locations 0,1,2... but unfortunately most graphics cards on most operating systems are ‘broken’ in one way or another, with rounding errors and incorrect start points etc.

PsychoPy provides a few of the common variants of LUT and that can be chosen when you initialise the device using the parameter *rampType*. If no *rampType* is specified then PsychoPy will choose one for you:

```
from psychopy import visual
from psychopy.hardware import crs

win = visual.Window([1024,768], useFBO=True) #we need to be rendering to_
↳framebuffer
bits = crs.BitsPlusPlus(win, mode = 'bits++', rampType = 1)
```

The Bits# is capable of reporting back the pixels in a line and this can be used to test that a particular LUT is indeed providing identity values. If you have previously connected a *BitsSharp* device and used it with PsychoPy then a file will have been stored with a LUT that has been tested with that device. In this case set *rampType* = “*configFile*” for PsychoPy to use it if such a file is found.

## BitsSharp

Control a CRS Bits# device. See typical usage in the class summary (and in the menu demos>hardware>BitsBox of PsychoPy’s Coder view).

## Attributes

<code>BitsSharp([win, portName, mode, ...])</code>	A class to support functions of the Bits# (and most Display++ functions This device uses the CDC (serial port) connection to the Bits box.
<code>BitsSharp.mode</code>	Get/set the mode of the BitsSharp to one of – “bits++” “mono++” “color++” “status” “storage” “auto”
<code>BitsSharp.isAwake()</code>	Test whether we have an active connection on the virtual serial port
<code>BitsSharp.getInfo()</code>	Returns a python dictionary of info about the Bits Sharp box
<code>BitsSharp.checkConfig([level, demoMode, logFile])</code>	Checks whether there is a configuration for this device and whether it's correct :params: level: integer 0: do nothing 1: check that we have a config file and that the graphics card and operating system match that specified in the file.
<code>BitsSharp.gammaCorrectFile</code>	Get / set the gamma correction file to be used (as stored on the device)
<code>BitsSharp.temporalDithering</code>	Temporal dithering can be set to True or False
<code>BitsSharp.monitorEDID</code>	Get / set the EDID file for the monitor.
<code>BitsSharp.beep([freq, dur])</code>	Make a beep of a given frequency and duration
<code>BitsSharp.getVideoLine(lineN, nPixels[, ...])</code>	Return the r,g,b values for a number of pixels on a particular video line :param lineN: the line number you want to read :param nPixels: the number of pixels you want to read :param nAttempts: the first time you call this function it has to get to status mode.
<code>BitsSharp.start()</code>	[Not currently implemented] Used to begin event collection by the device.
<code>BitsSharp.stop()</code>	[Not currently implemented] Used to stop event collection by the device.

Direct communications with the serial port:

<code>BitsSharp.sendMessage(message[, autoLog])</code>	Send a command to the device (does not wait for a reply or sleep())
<code>BitsSharp.getResponse([length, timeout])</code>	Read the latest response from the serial port

Control the CLUT (Bits++ mode only):

<code>BitsSharp.setContrast(contrast[, LUTrange, ...])</code>	Set the contrast of the LUT for 'bits++' mode only :Parameters: contrast : float in the range 0:1 The contrast for the range being set LUTrange : float or array If a float is given then this is the fraction of the LUT to be used.
<code>BitsSharp.setGamma(newGamma)</code>	Set the LUT to have the requested gamma value Currently also resets the LUT to be a linear contrast ramp spanning its full range.
<code>BitsSharp.setLUT([newLUT, gammaCorrect, ...])</code>	SetLUT is only really needed for bits++ mode of bits# to set the look-up table (256 values with 14bits each).

## Details

**class** psychopy.hardware.crs.bits.**BitsSharp** (win=None, portName=None, mode="", checkConfigLevel=1, gammaCorrect='hardware', gamma=None, noComms=False)

A class to support functions of the Bits# (and most Display++ functions) This device uses the CDC (serial port) connection to the Bits box. To use it you must have followed the instructions from CRS Ltd. to get your box into the CDC communication mode. Typical usage (also see demo in Coder view demos>hardware>BitsBox):

```
from psychopy import visual
from psychopy.hardware import crs
# we need to be rendering to framebuffer
win = visual.Window([1024,768], useFBO=True)
bits = crs.BitsSharp(win, mode = 'mono++')
# You can continue using your window as normal and OpenGL shaders
# will convert the output as needed
print(bits.info)
if not bits.OK:
    print('failed to connect to Bits box')
    core.quit()
core.wait(0.1)
# now, you can change modes using
bits.mode = 'mono++' # 'color++', 'mono++', 'bits++', 'status'
```

Note that the firmware in Bits# boxes varies over time and some features of this class may not work for all firmware versions. Also Bits# boxes can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

RTBox commands that reset the key mapping have been found not to work on some firmware.

**Parameters** win : a PsychoPy *Window* object, required portName : the (virtual) serial port to which the device is

connected. If None then PsychoPy will search available serial ports and test communication (on OSX, the first match of /dev/tty.usbmodemfa\* will be used and on linux /dev/ttyS0 will be used)

mode : 'bits++', 'color++', 'mono++', 'status' checkConfigLevel : integer

Allows you to specify how much checking of the device is done to ensure a valid identity look-up table. If you specify one level and it fails then the check will be escalated to the next level (e.g. if we check level 1 and find that it fails we try to find a new LUT):

- 0 don't check at all
- 1 check that the graphics driver and OS version haven't changed since last LUT calibration
- 2 check that the current LUT calibration still provides identity (requires switch to status mode)
- 3 search for a new identity look-up table (requires switch to status mode)

gammaCorrect [string governing how gamma correction is performed]

'hardware': use the gamma correction file stored on the hardware

'FBO': gamma correct using shaders when rendering the FBO to back buffer

**'bitsMode': in bits++ mode there is a user-controlled LUT** that we can use for gamma correction

**noComms** [bool] If True then don't try to communicate with the device at all (passive mode). This can be useful if you want to debug the system without actually having a Bits# connected.

#### **RTBoxAddKeys** (*map*)

Add key mappings to an existing map. RTBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, triggers and CB6 IR input channels. The format for map is a list of tuples with each tuple containing the name of the RTBox button to be mapped and its source eg ('btn1','Din1') maps physical input Din1 to logical button btn1. RTBox has four logical buttons (btn1-4) and three auxiliary events (light, pulse and trigger) Buttons/events can be mapped to multiple physical inputs and stay mapped until reset.

Example:

```
bits.RTBoxSetKeys([('btn1', 'Din0'), ('btn2', 'Din1')])
bits.RTBoxAddKeys([('btn1', 'IRButtonA'), ('btn2', 'IRButtonB')])
```

Will link Din0 to button 1 and Din1 to button 2. Then adds IRButtonA and IRButtonB alongside the original mappings.

Now both hard wired and IR inputs will - emulating the same logical button press.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

#### **RTBoxCalibrate** ( $N=1$ )

Used to assess error between host clock and Bits# button press time stamps.

Prints each sample provided and returns the mean error.

The clock willnever be completely in sync but the aim is that there should be that the difference between them should not grow over a serie of button presses.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

#### **RTBoxClear** ()

Flushes the serial input buffer. Its good to do this before and after data collection. This just calls flush() so is a wrapper for RTBox.

#### **RTBoxDisable** ()

Disables the detection of RTBox events. This is useful to stop the Bits# from reporting key presses When you no longer need them. Nad must be done before using any other data logging methods.

It undoes any button - input mappings.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

The ability to reset keys mappings has been found not to work on some Bits# firmware.

**RTBoxEnable** (*mode=None, map=None*)

Sets up the RTBox with preset or bespoke mappings and enables event detection.

RTBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, tigers and CB6 IR input channels.

Mode is a list of strings. Preset mappings provided via mode:

CB6 for the CRS CB6 IR response box. IO for a three button box connected to Din0-2 IO6 for a six button box connected to Din0-5

If mode = None or is not set then the value of self.RTBoxMode is used.

Bespoke Mappings over write preset ones.

The format for map is a list of tuples with each tuple containing the name of the RT Box button to be mapped and its source eg ('btn1','Din0') maps physical input Din0 to logical button btn1.

Note the lowest number button event is Btn1

RTBox has four logical buttons (btn1-4) and three auxiliary events (light, pulse and trigger) Buttons/events can be mapped to multiple physical inputs and stay mapped until reset.

Mode is a list of string or list of strings that contains keywords to determine present mappings and modes for RTBox.

If mode includes 'Down' button events will be detected when pressed. If mode includes 'Up' button events will be detected when released. You can detect both types of event but note that pulse, light and trigger events don't have an 'Up' mode.

**If Trigger is included in mode the trigger** event will be mapped to the trigIn connector.

### Example

```
bits.RTBoxEnable(mode = ['Down']), map = [('btn1','Din0'), ('btn2','Din1')]
```

enable the RTBox emulation to detect Down events on buttons 1 and 2 where they are mapped to DIN0 and DIN1.

### Example

```
bits.RTBoxEnable(mode = ['Down','CB6'])
```

enable the RTBox emulation to detect Down events on the standard CB6 IR response box keys.

If no key direction has been set (mode does not contain 'Up' or 'Down') the default is 'Down'.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

The ability to reset keys mappings has been found not to work on some Bits# firmware.

**RTBoxKeysPressed** (*N=1*)

Check to see if (at least) the appropriate number of RTBox style key presses have been made.

## Example

```
bits.RTBoxKeysPressed(5)
```

will return false until 5 button presses have been recorded.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

### **RTBoxResetKeys ( )**

Resets the key mappings to no mapping. Has the effect of disabling RTBox input.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

The ability to reset keys mappings has been found not to work on some Bits# firmware.

### **RTBoxSetKeys (map)**

Set key mappings: first resets existing then adds new ones. Does not reset any event that is not in the new list. RTBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, triggers and CB6 IR input channels. The format for map is a list of tuples with each tuple containing the name of the RTBox button to be mapped and its source eg ('btn1','Din1') maps physical input Din1 to logical button btn1.

RTBox has four logical buttons (btn1-4) and three auxiliary events (light, pulse and trigger) Buttons/events can be mapped to multiple physical inputs and stay mapped until reset.

## Example

```
bits.RTBoxSetKeys([('btn1','Din0'),('light','Din9')])
```

Will link Din0 to button 1 and Din9 to the light input emulation.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

### **RTBoxWait ( )**

Waits until (at least) one of RTBox style key presses have been made Pauses program execution in mean time.

## Example

```
res = bits.RTBoxWait()
```

will suspend all other activity until 1 button press has been recorded and will then return a dict / structure containing results.

Results can be accessed as follows:

**structure** res.dir, res.button, res.time

**or dictionary** res['dir'], res['button'], res['time']

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

#### **RTBoxWaitN** (*N=1*)

Waits until (at least) the appropriate number of RTBox style key presses have been made Pauses program execution in mean time.

#### **Example**

```
res = bits.RTBoxWaitN(5)
```

will suspend all other activity until 5 button presses have been recorded and will then return a list of Dicts containing the 5 results.

Results can be accessed as follows:

**structure** `res[0].dir, res[0].button, res[0].time`

**or dictionary** `res[0]['dir'], res[0]['button'], res[0]['time']`

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

#### **\_Goggles** ()

(private) Used to set control the goggles. Should not be needed by user if attached to a `psychopy.visual.Window()`

#### **\_RTBoxDecodeResponse** (*msg, N=1*)

Helper function for decoding key presses in the RT response box format.

Not normally needed by user

#### **\_ResetClock** ()

(private) Used to reset Bits hardware clock. Should not be needed by user if attached to a `psychopy.visual.Window()` since this will automatically draw the reset code as part of the screen refresh.

#### **\_drawLUTtoScreen** ()

(private) Used to set the LUT in 'bits++' mode. Should not be needed by user if attached to a `psychopy.visual.Window()` since this will automatically draw the LUT as part of the screen refresh.

#### **\_drawTrigtoScreen** (*sendStr=None*)

(private) Used to send a trigger pulse. Should not be needed by user if attached to a `psychopy.visual.Window()` since this will automatically draw the trigger code as part of the screen refresh.

#### **\_extractStatusEvents** ()

Interprets values from status log to pullout any events.

Should not be needed by user if start/stopStatusLog or pollStatus are used

Fills statusEvents with a list of dictionary like objects with the following entries source, input, direction, time.

source = the general source of the event - e.g. DIN for Digital input, IR for IT response box

input = the individual input in the source. direction = 'up' or 'down' time = time stamp.



**Events are recorded relative to the four event flags** statusDINBase, initial values for digital ins. statusIRBase, initial values for CB6 IR box. statusTrigInBase, initial values for TrigIn. statusMode, direction(s) of events to be reported.

The data can be accessed as statusEvents[i]['time'] or statusEvents[i].time

Also set status.\_nEvents to the number of events recorded

#### **`__getStatusLog()`**

Read the log Queue

Should not be needed by user if start/stopStatusLog or pollStatus are used.

fills statusValues with a list of dictionary like objects with the following entries: sample, time, trigIn, DIN[10], DWORD, IR[6], ADC[6]

They can be accessed as statusValues[i]['sample'] or statusValues[i].sample, statusValues[i].ADC[j]

Also sets status.\_nValues to the number of values recorded.

#### **`__inWaiting()`**

Helper function to determine how many bytes are waiting on the serial port.

#### **`__protectTrigger()`**

If Goggles (or analog) outputs are used when the digital triggers are off we need to make a set of blank triggers first. But the user might have set up triggers in waiting for a later time. So this will protect them.

#### **`__restoreTrigger()`**

Restores the triggers to previous settings

#### **`__setHeaders(frameRate)`**

Sets up the TLock header codes and some flags that are common to operating all CRS devices

#### **`__setupShaders()`**

creates and stores the shader programs needed for mono++ and color++ modes

#### **`__statusBox()`**

Should not normally be called by user Called in its own thread via self.statusBoxEnable() Reads the status reports from the Bits# for default 60 seconds or until self.statusBoxDisable() is called.

Note any non status reports are found on the buffer will cause an error.

args specifies the time over which to record status events. The minimum time is 10ms, less than this results in recording stopping after about 1 status report has been read.

Puts its results into a Queue.

This function is normally run in its own thread so actions can be asynchronous.

#### **`__statusDisable()`**

Stop Bits# from recording data - and clears the buffer

Not normally needed by user

#### **`__statusEnable()`**

Sets the Bits# to continuously send back its status until stopped. You get a lot of data by leaving this going.

Not normally needed by user

#### **`__statusLog(args=60)`**

Should not normally be called by user Called in its own thread via self.startStatusLog() Reads the status reports from the Bits# for default 60 seconds or until self.stopStatusLog() is called. Ignores the last line as this is can be bogus. Note any non status reports are found on the buffer will cause an error.

args specifies the time over which to record status events. The minimum time is 10ms, less than this results in recording stopping after about 1 status report has been read.

Puts its results into a Queue.

This function is normally run in its own thread so actions can be asynchronous.

**beep** (*freq=800, dur=1*)

Make a beep of a given frequency and duration

**checkConfig** (*level=1, demoMode=False, logFile=""*)

Checks whether there is a configuration for this device and whether it's correct :params:

**level: integer** 0: do nothing 1: check that we have a config file and that the graphics

card and operating system match that specified in the file. Then assume identity LUT is correct

**2: switch the box to status mode and check that the** identity LUT is currently working

**3: force a fresh search for the identity LUT**

**clock** ()

Reads the internal clock of the Bits box via the RTBox format but note there will be a delay in reading the value back. The format for the return values is the same as for button box presses. The return value for button will be 9 and the return value for event will be time. The return value for time will be the time of the clock at the moment of the request.

### Example

```
res = bits.clock() print(res.time) print(res['time'])
```

**driverFor** = []

**flush** ()

Flushes the serial input buffer Its good to do this before and after data collection, And generally quite often.

**gammaCorrectFile**

Get / set the gamma correction file to be used (as stored on the device)

**getAllRTBoxResponses** ()

Read all of the RTBox style key presses on the input buffer. Returns a list of dict like objects with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-4 are the 'btn1-btn4' events, 5 and 6 are the 'light' and 'pulse' events, 7 is the 'trigger' event, 9 is a requested timestamp event (see Clock()).

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

'time' is the timestamp associated with the event.

Values can be read as a structure eg:

```
res = getAllRTBoxResponses()
res[0].dir, res[0].button, res[0].time
```

or dictionary:

```
res[0]['dir'], res[0]['button'], res[0]['time']
```

Note even if only 1 key press was found a list of dict / objects is returned

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

#### **getAllStatusBoxResponses()**

Read all of the statusBox style key presses on the input buffer. Returns a list of dict like objects with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-17 are the 'btn1-btn17' events.

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

'time' is the timestamp associated with the event.

Values can be read as a structure eg:

```
res= getAllStatusBoxResponses()
res[0].dir, res[0].button, res[0].time
```

or dictionary:

```
res[0]['dir'], res[0]['button'], res[0]['time']
```

Note even if only 1 key press was found a list of dict / objects is returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getAllStatusEvents()**

Returns the whole status event list

Returns a list of dictionary like objects with the following entries source, input, direction, time.

source = the general source of the event - e.g. DIN for Digital input, IR for CB6 IR response box events

input = the individual input in the source. direction = 'up' or 'down' time = time stamp.

All sources are numbered from zero. Din 0 ... 9 IR 0 ... 5 ADC 0 ... 5

mode specifies which directions of events are captured. e.g 'up' will only report up events.

The data can be accessed as value[i]['time'] or value[i].time

### **Example**

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog() res=getAllStatusEvents() print(bits.res[0].time)
```

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getAllStatusValues ()**

Returns the whole status values list.

Returns a list of dict like objects with the following entries sample, time, trigIn, DIN[10], DWORD, IR[6], ADC[6] sample is the sample ID number. time is the time stamp. trigIn is the value of the trigger input. DIN is a list of 10 digital input values. DWORD represents the digital inputs as a single decimal value. IR is a list of 10 infra-red (IR) input values. ADC is a list of 6 analog input values. These can be accessed as value[i]['sample'] or value[i].sample, values[i].ADC[j].

All sources are numbered from zero. Din 0 ... 9 IR 0 ... 5 ADC 0 ... 5

#### **Example**

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog() res=getAllStatusValues() print(bits.res[0].time)
```

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getAnalog (N=0)**

Pulls out the values of the analog inputs for the Nth status entry.

Returns a dictionary with a list of 6 floats (ADC) and a time stamp (time).

All sources are numbered from zero. ADC 0 ... 5

#### **Example**

```
bits.pollStatus() res=bits.getAnalog() print(res['ADC'])
```

will poll the status display the values of the ADC inputs in the first status entry returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getDigital (N=0)**

Pulls out the values of the digital inputs for the Nth status entry.

Returns a dictionary with a list of 10 ints that are 1 or 0 (DIN) and a time stamp (time)

All sources are numbered from zero. Din 0 ... 9

### Example

```
bits.pollStatus() res=bits.getAnalog() print(res['DIN'])
```

will poll the status display the value of the digital inputs in the first status entry returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also DBits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getDigitalWord** (*N=0*)

Pulls out the values of the digital inputs for the Nth status entry.

Returns a dictionary with a 10 bit word representing the binary values of those inputs (DWORD) and a time stamp (time).

### Example

```
bits.pollStatus() res=bits.getAnalog() print(res['DWORD'])
```

will poll the status display the value of the digital inputs as a decimal number.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getIRBox** (*N=0*)

Pulls out the values of the CB6 IR response box inputs for the Nth status entry.

Returns a dictionary with a list of 6 ints that are 1 or 0 (IRBox) and a time stamp (time).

Il sources are numbered from zero. IR 0 ... 5

### Example

```
bits.pollStatus() res=bits.getAnalog() print(res['IRBox'])
```

will poll the status display the values of the IR box buttons in the first status entry returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getInfo** ()

Returns a python dictionary of info about the Bits Sharp box

### Example

```
info=bits.getInfo print(info['ProductType'])
```

**getPackets ()**

Returns the number of packets available for trigger pulses.

**getRTBoxResponse ()**

checks for one RTBox style key presses on the input buffer then reads it. Returns a dict like object with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-4 are the 'btn1-btn4' events, 5 and 6 are the 'light' and 'pulse' events, 7 is the 'trigger' event, 9 is a requested timestamp event (see Clock()).

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

'time' is the timestamp associated with the event.

**Value can be read as a structure, eg:** res= getRTBoxResponse() res.dir, res.button, res.time

**or dictionary** res['dir'], res['button'], res['time']

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

**getRTBoxResponses (N=1)**

checks for (at least) an appropriate number of RTBox style key presses on the input buffer then reads them. Returns a list of dict like objects with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-4 are the 'btn1-btn4' events, 5 and 6 are the 'light' and 'pulse' events, 7 is the 'trigger' event, 9 is a requested timestamp event (see Clock()).

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

'time' is the timestamp associated with the event.

Values can be read as a list of structures eg:

```
res = getRTBoxResponses(3)
res[0].dir, res[0].button, res[0].time
```

or dictionaries:

```
res[0]['dir'], res[0]['button'], res[0]['time']
```

Note even if only 1 key press was requested a list of dict / objects is returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. Such variations may affect key mappings for RTBox commands.

**getResponse (length=1, timeout=0.1)**

Read the latest response from the serial port

**Params**

**length determines whether we expect:** 1: a single-line reply (use readline()) 2: a multiline reply (use readlines() which *requires* timeout) -1: may not be any EOL character; just read whatever chars are

there

#### **getStatus** ( $N=0$ )

Pulls out the Nth entry in the statusValues list.

Returns a dict like object with the following entries sample, time, trigIn, DIN[10], DWORD, IR[6], ADC[6]

sample is the sample ID number. time is the time stamp. trigIn is the value of the trigger input. DIN is a list of 10 digital input values. DWORD represents the digital inputs as a single decimal value. IR is a list of 10 infra-red (IR) input values. ADC is a list of 6 analog input values. These can be accessed as value['sample'] or value.sample, values.ADC[j].

All sources are numbered from zero. Din 0 ... 9 IR 0 ... 5 ADC 0 ... 5

#### **Example**

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog() res=getStatus(20) print(bits.res.time)
```

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getStatusBoxResponse** ()

checks for one statusBox style key presses on the input buffer then reads it. Returns a dict like object with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-17 are the 'btn1-btn17' events.

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

'time' is the timestamp associated with the event.

**Value can be read as a structure, eg:** res= getRTBoxResponse() res.dir, res.button, res.time

**or dictionary** res['dir'], res['button'], res['time']

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

#### **getStatusBoxResponses** ( $N=1$ )

checks for (at least) an appropriate number of RTBox style key presses on the input buffer then reads them. Returns a list of dict like objects with three members 'button', 'dir' and 'time'

'button' is a number from 1 to 9 to indicate the event that was detected. 1-4 are the 'btn1-btn4' events, 5 and 6 are the 'light' and 'pulse' events, 7 is the 'trigger' event, 9 is a requested timestamp event (see Clock()).

'dir' is the direction of the event eg 'up' or 'down', trigger is described as 'on' when low.

'dir' is set to 'time' if a requested timestamp event has been detected.

‘time’ is the timestamp associated with the event.

Values can be read as a list of structures eg:

```
res = getRTBoxResponses(3)
print(res[0].dir, res[0].button, res[0].time)
```

or dictionaries:

```
print(res[0]['dir'], res[0]['button'], res[0]['time'])
```

Note even if only 1 key press was requested a list of dict / objects is returned.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then ‘status’ and ‘event’ commands in this class may not work.

#### **getStatusEvent (N=0)**

pulls out the Nth event from the status event list

Returns a dictionary like object with the following entries source, input, direction, time.

source = the general source of the event - e.g. DIN for Digital input, IR for IT response box.

input = the individual input in the source. direction = ‘up’ or ‘down’ time = time stamp.

All sources are numbered from zero. Din 0 ... 9 IR 0 ... 5 ADC 0 ... 5

mode specifies which directions of events are captured, e.g ‘up’ will only report up events.

The data can be accessed as value[‘time’] or value.time

#### **Example**

bits.startStatusLog() while not event

    #do some processing continue

bits.stopStatusLog() res=getAllStatusEvents(20) print(bits.res.time)

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then ‘status’ and ‘event’ commands in this class may not work.

#### **getTrigIn (N=0)**

Pulls out the values of the trigger input for the Nth status entry.

Returns dictionary with a 0 or 1 (trigIn) and a time stamp (time)

#### **Example**

bits.pollStatus() res=bits.getAnalog() print(res[‘trigIn’])

will poll the status display the value of the trigger input.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this



class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**getVideoLine** (*lineN*, *nPixels*, *timeout=10.0*, *nAttempts=10*)

Return the r,g,b values for a number of pixels on a particular video line :param lineN: the line number you want to read :param nPixels: the number of pixels you want to read :param nAttempts: the first time you call this function it has

to get to status mode. In this case it sometimes takes a few attempts to make the call work

**Returns** an Nx3 numpy array of uint8 values

**isAwake** ()

Test whether we have an active connection on the virtual serial port

**isOpen**

**longName** = ''

**mode**

*Get/set the mode of the BitsSharp to one of – “bits++” “mono++” “color++” “status” “storage” “auto”*

**monitorEDID**

Get / set the EDID file for the monitor. The edid files will be located in the EDID subdirectory of the flash disk. The file *automatic.edid* will be the file read from the connected monitor.

**name** = b'CRS Bits#'

**pause** ()

Pause for a default period for this device

**pollStatus** (*t=0.0001*)

Reads the status reports from the Bits# for the specified usually short time period t. The script will wait for this time to lapse so not ideal for time critical applications.

If t is less than 0.01 polling will continue until at least 1 data entry has been recorded.

If you don't want to wait while this does its job use startStatusLog and stopStatusLog instead.

Fills the statusValues list with all the status values read during the time period.

Fills the statusEvents list with just those status values that are likely to be meaningful events.

the members statusValues and statusEvents will end up containing dict like objects of the following style: sample, time, trigIn, DIN[10], DWORD, IR[6], ADC[6]

They can be accessed as statusValues[i]['sample'] or stautsValues[i].sample, statusValues[x].ADC[j].

## Example

```
bits.pollStatus() print(bits.statusValues[0].IR[0])
```

will display the value of the IR InputA in the first sample recorded.

Note: Starts and stops logging for itself.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**primeClock()**

Primes the clock to reset at the next screen flip - note only 1 clock reset signal will be issued but if the frame(s) after the reset frame is dropped the reset will be re-issued thus keeping timing good.

Resets continue to be issued on each video frame until the next win.flip so you need to have regular win.flips for this function to work properly.

**Example** bits.primeClock() drawImage while not response

```
#do some processing bits.win.flip()
```

Will get a clock reset signal ready but wont issue it until the first win.flip in the loop.

**read(timeout=0.1)**

Get the current waiting characters from the serial port if there are any.

Mostly used internally but may be needed by user. Note the return message depends on what state the device is in and will need to be decoded. See the Bits# manual but also the other functions herein that do the decoding for you.

**Example**

```
message = bits.read()
```

**reset()**

Deprecated: This was used on the old Bits++ to power-cycle the box. It required the compiled dll, which only worked on windows and doesn't work with Bits# or Display++.

**resetClock()**

Issues a clock reset code using 1 screen flip if the next frame(s) is dropped the reset will be re-issued thus keeping timing good.

Resets continue to be issued on each video frame until the next win.flip so you need to have regular win.flips for this function to work properly.

**Example**

```
bits.resetClock() drawImage() bits.win.flip()
```

Will issue clock resets while the image is being drawn then display the image and allow the clock to continue from the same frame.

**Example**

```
bits.resetClock() bits.RTBoxWait() bits.win.flip()
```

Will issue clock resets until a button is pressed.

**sendAnalog(AOUT1=0, AOUT2=0)**

sends a single analog output pulse uses up 1 win flip. pulse will continue until next win flip called. Actions are always 1 frame behind the request.

May conflict with trigger and goggle settings.

### Example

```
bits.sendAnalog(4.5,-2.0) bits.win.flip()
```

**sendMessage** (*message, autoLog=True*)

Sends a command to the device (does not wait for a reply or sleep())

**sendTrigger** (*triggers=0, onTime=0, duration=0, mask=65535*)

Sends a single trigger using up 1 win.flip. The trigger will be sent on the following frame.

The triggers will continue until after the next win.flip.

Actions are always 1 frame after the request.

May do odd things if Goggles and Analog are also in use.

### Example

```
bits.sendTrigger(0b0000000010, 2.0, 4.0) bits.win.flip()
```

Will send a 4ms pulse on DOUT1 2ms after the start of the frame. Due to the following win.flip() the pulse should last for 1 frame only.

Triggers will continue until stopTrigger is called.

**setAnalog** (*AOUT1=0, AOUT2=0*)

Sets up Analog outputs in Bits# AOUT1 and AOUT2 are the two analog values required in volts. Analog commands are issued at the next win.flip() and actionsed 1 video frame later.

### Example

```
bits.set Analog(4.5,-2.2) bits.startAnalog() bits.win.flip()
```

**setContrast** (*contrast, LUTrange=1.0, gammaCorrect=None*)

Set the contrast of the LUT for 'bits++' mode only :Parameters:

**contrast** [float in the range 0:1] The contrast for the range being set

**LUTrange** [float or array] If a float is given then this is the fraction of the LUT to be used. If an array of floats is given, these will specify the start / stop points as fractions of the LUT. If an array of ints (0-255) is given these determine the start stop *indices* of the LUT

### Examples

**setContrast (1.0, 0.5)** will set the central 50% of the LUT so that a stimulus with contr=0.5 will actually be drawn with contrast 1.0

```
setContrast (1.0, [0.25, 0.5]) setContrast (1.0, [63, 127])
```

will set the lower-middle quarter of the LUT (which might be useful in LUT animation paradigms)

**setGamma** (*newGamma*)

Set the LUT to have the requested gamma value Currently also resets the LUT to be a linear contrast ramp spanning its full range. May change this to read the current LUT, undo previous gamma and then apply new one?

**setLUT** (*newLUT=None, gammaCorrect=False, LUTrange=1.0, contrast=None*)

SetLUT is only really needed for bits++ mode of bits# to set the look-up table (256 values with 14bits each). For the BitsPlusPlus device the default is to perform gamma correction here but on the BitsSharp it seems better to have the device perform that itself as the last step so gamma correction is off here by default. If no contrast has yet been set (it isn't needed for other modes) then it will be set to 1 here.

**setRTBoxMode** (*mode=['CB6', 'Down', 'Trigger']*)

Sets the RTBox mode data member - does not actually set the RTBox into this mode.

### Example

```
bits.setRTBoxMode(['CB6','Down']) # set the mode
bits.RTBoxEnable() # Enable RTBox emulation with
# the preset mode.
```

sets the RTBox mode settings for a CRS CB6 button box. and for detection of 'Down' events only.

**setStatusBoxMode** (*mode=['CB6', 'Down', 'Trigger', 'Analog']*)

Sets the statusBox mode data member - does not actually set the statusBox into this mode.

### Example

```
bits.setStatusBoxMode(['CB6','Down']) # set the mode
bits.statusBoxEnable() # Enable status Box emu-
lation with # the preset mode.
```

sets the statusBox mode settings for a CRS CB6 button box. and for detection of 'Down' events only.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**setStatusBoxThreshold** (*threshold=None*)

Sets the threshold by which analog inputs must change to trigger a button press event. If None the threshold will be set very high so that no such events are triggered.

Can be used to change the threshold for analog events without having to re enable the status box system as a whole.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**setStatusEventParams** (*DINBase=1023, IRBase=63, TrigInBase=0, ADCBase=0, threshold=9999.99, mode=['up', 'down']*)

Sets the parameters used to determine if a status value represents a reportable event.

DIN\_base = a 10 bit binary word specifying the expected starting values of the 10 digital input lines

IR\_base = a 6 bit binary word specifying the expected starting values of the 6 CB6 IR buttons

Trig\_base = the starting value of the Trigger input

mode = a list of event types to monitor can be 'up' or 'down' typically 'down' corresponds to a button press or when the input is being pulled down to zero volts.

## Example

```
bits.setStatusEventParams(DINBase=0b111111111, IRBase=0b111111, TrigInBase=0, ADCBase=0,  
threshold = 3.4, mode = ['down'])
```

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog() res=getAllStatusEvents(0) print(bits.res.time)
```

This ill start the event extraction process as if DINs and IRs are all '1', Trigger is '0' ADCs = 0 with an ADC threshold for change of 3.4 volts, and will only register 'down' events. Here we display the time stamp of the first event.

Note that the firmware in Display++ units varies over time and some features of this class may not work for all firmware versions. Also Display++ units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**setTrigger** (*triggers=0, onTime=0, duration=0, mask=65535*)

Overload for Bits# and Display++ that protects the values of any analog outputs.

Quick way to set up triggers.

Triggers is a binary word that determines which triggers will be turned on.

onTime specifies the start time of the trigger within the frame (in S with 100uS resolution)

Duration specifies how long the trigger will last. (in S with 100uS resolution).

Note that mask only protects the digital output lines set by other activities in the Bits. Not other triggers.

## Example

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b011111111) bits.startTrigger()
```

Will issue a 4ms long high-going pulse, 2ms after the start of each frame on DOUT1 while protecting the value of DOUT 9.

**setTriggerList** (*triggerList=None, mask=65535*)

Overload of Bits# and Display++ Sets up Trigger pulses via the list method while preserving the analog output settings.

Sets up Trigger pulses in Bist++ using the fine grained method that can control every trigger line at 100uS intervals.

TriggerList should contain 1 entry for every 100uS packet (see getPackets) the binary word in each entry specifies which trigger line will be active during that time slot.

Note that mask only protects the digital output lines set by other activities in the Bits. Not other triggers.

## Example

```
packet = [0]*self._NumberPackets packet[0] = 0b0000000010 bits.setTriggerList(packet)
```

Will sens a 100us pulse on DOUT1 at the start of the frame.

**Example 2:** packet = [0]\*self.\_NumberPackets packet[10] = 0b0000000010 packet[20] = 0b0000000001 bits.setTriggerList(packet) bits.startTrigger()

Will send a 100us pulse on DOUT1 1000us after the start of the frame and a second 100us pulse on DOUT0 2000us after the start of the frame.

Triggers will continue until stopTrigger is called.

**start ()**

[Not currently implemented] Used to begin event collection by the device.

Not really needed as other members now do this.

**startAnalog ()**

will start sending analog signals on the next win flip and continue until stopped.

### Example

bits.set Analog(4.5,-2.2) bits.startAnalog() bits.win.flip()

**startGoggles** (*left=0, right=1*)

**Starts CRS stereo goggles. Note if you are** using FE-1 goggles you should start this before connecting the goggles.

Left is the state of the left shutter on the first frame to be presented 0, False or 'closed'=closed; 1, True or 'open' = open,

right is the state of the right shutter on the first frame to be presented 0, False or

'closed'=closed; 1, True or 'open' = open

Note you can set the goggles to be both open or both closed on the same frame.

The system will always toggle the state of each lens so as to not damage FE-1 goggles.

### Example

bits.startGoggles(0,1) bits.win.flip() while not response

bits.win.flip() #do some processing

bits.stopGoggles() bits.win.flip()

Starts toggling the goggles with the right eye open in sync with the first win.flip(0) within the loop. The open eye will alternate.

### Example

bits.startGoggles(1,1) bits.win.flip() while not response

bits.win.flip() #do some processing

bits.stopGoggles() bits.win.flip()

Starts toggling the goggles with both eyes open in sync with the first win.flip(0) within the loop. Eyes will alternate between both open and both closed.

Note it is safe to leave the goggles toggling forever, ie to never call stopGoggles().

### **startStatusLog** (*t=60*)

Start logging data from the Bits#

Starts data logging in its own thread.

Will run for *t* seconds, default 60 or until stopStatusLog() is called.

### **Example**

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog()
```

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

### **startTrigger** ()

Start sending triggers on the next win flip and continue until stopped by stopTrigger Triggers start 1 frame after the frame on which the first trigger is sent.

### **Example**

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b0111111111) bits.startTrigger() while imageOn:
```

```
    #do some processing continue
```

```
bits.stopTrigger() bits.win.flip()
```

### **statusBoxAddKeys** (*map*)

Add key mappings to an existing map. statusBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, triggers and CB6 IR input channels. The format for map is a list of tuples with each tuple containing the name of the RTBox button to be mapped and its source eg ('btn1','Din1') maps physical input Din1 to logical button btn1. statusBox has 23 logical buttons (btn1-23). Unlike RTBox buttons/events can only be partially mapped to multiple physical inputs. That is a logical button can be mapped to more than 1 physical input but a physical input can only be mapped to 1 logical button. So, this function over write any existing mappings if the physical input is the same.

Example:

```
bits.RTBoxSetKeys([ ('btn1', 'Din0'), ('btn2', 'Din1') ])
bits.RTBoxAddKeys([ ('btn1', 'IRButtonA'), ('btn2', 'IRButtonB') ])
```

Will link Din0 to button 1 and Din1 to button 2. Then adds IRButtonA and IRButtonB alongside the original mappings.

Now both hard wired and IR inputs will emulate the same logical button press.

To match with the CRS hardware description inputs are labelled as follows.

TrigIn, Din0 ... Din9, IRButtonA ... IRButtonF, AnalogIn1 ... AnalogIn6

Logical buttons are numbered from 1 to 23.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this

class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**statusBoxDisable()**

Disables the detection of statusBox events. This is useful to stop the Bits# from reporting key presses When you no longer need them. And must be done before using any other data logging methods.

It undoes any button - input mappings

**statusBoxEnable(mode=None, map=None, threshold=None)**

Sets up the stautsBox with preset or bespoke mappings and enables event detection.

stautsBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, tigers and CB6 IR input channels.

mode is a list of strings. Preset mappings provided via mode:

CB6 for the CRS CB6 IR response box connected mapped to btn1-6 IO for a three button box connected to Din0-2 mapped to btn1-3 IO6 for a six button box connected to Din0-5 mapped to btn1-6 IO10 for a ten button box connected to Din0-9 mapped to btn1-10 Trigger maps the trigIn to btn17 Analog maps the 6 analog inputs on a Bits# to btn18-23

if CB6 and IOx are used together the Dins are mapped from btn7 onwards.

If mode = None or is not set then the value of self.statusBoxMode is used.

Bespoke Mappings over write preset ones.

The format for map is a list of tuples with each tuple containing the name of the button to be mapped and its source eg ('btn1','Din0') maps physical input Din0 to logical button btn1.

Note the lowest number button event is Btn1

statusBox has 23 logical buttons (btn1-23). Buttons/events can be mapped to multiple physical inputs and stay mapped until reset.

mode is a string or list of strings that contains keywords to determine present mappings and modes for statusBox.

If mode includes 'Down' button events will be detected when pressed. If mode includes 'Up' button events will be detected when released. You can detect both types of event noting that the event detector will look for transitions and ignore what it sees as the starting state.

To match with the CRS hardware description inputs are labelled as follows.

TrigIn, Din0 ... Din9, IRButtonA ... IRButtonF, AnalogIn1 ... AnalogIn6

Logical buttons are numbered from 1 to 23.

threshold sets the threshold by which analog inputs must change to trigger a button press event. If None the threshold will be set very high so that no such events are triggered. Analog inputs must cycle up and down by threshold to be detected as separate events. So if only 'Up' events are detected the input must go up by threshold, then come down again and then go back up to register 2 up events.

**Example**

```
bits.statusBoxEnable(mode = 'Down', map = [('btn1','Din0'), ('btn2','Din1')])
```

enable the stautsBox to detect Down events on buttons 1 and 2 where they are mapped to DIN0 and DIN1.



### Example

```
bits.statusBoxEnable(mode = ['Down','CB6'])
```

enable the status Box emulation to detect Down events on the standard CB6 IR response box keys.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**statusBoxKeysPressed** ( $N=1$ )

Check to see if (at least) the appropriate number of RTBox style key presses have been made.

### Example

```
bits.statusBoxKeysPressed(5)
```

will return false until 5 button presses have been recorded.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

**statusBoxResetKeys** ()

**statusBoxSetKeys** (*map*)

Set key mappings: first resets existing then adds new ones. Does not reset any event that is not in the new list. statusBox events can be mapped to a number of physical events on Bits# They can be mapped to digital input lines, triggers and CB6 IR input channels. The format for map is a list of tuples with each tuple containing the name of the RTBox button to be mapped and its source eg ('btn1','Din1') maps physical input Din1 to logical button btn1.

statusBox has 17 logical buttons (btn1-17) Buttons/events can be mapped to multiple physical inputs and stay mapped until reset.

### Example

```
bits.RTBoxSetKeys([('btn1','Din0'),('btn2','IRButtonA')])
```

Will link physical Din0 to logical button 1 and IRButtonA to button 2.

To match with the CRS hardware description inputs are labelled as follows.

TrigIn, Din0 ... Din9, IRButtonA ... IRButtonF, AnalogIn1 ... AnalogIn6

Logical buttons are numbered from 1 to 23.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

### **statusBoxWait()**

Waits until (at least) one of RTBox style key presses have been made Pauses program execution in mean time.

#### **Example**

```
res = bits.statusBoxWait()
```

will suspend all other activity until 1 button press has been recorded and will then return a dict / structure containing results.

Results can be accessed as follows:

**structure** res.dir, res.button, res.time

**or dictionary** res['dir'], res['button'], res['time']

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also DBits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

### **statusBoxWaitN(N=1)**

Waits until (at least) the appropriate number of RTBox style key presses have been made Pauses program execution in mean time.

#### **Example**

```
res = bits.statusBoxWaitN(5)
```

will suspend all other activity until 5 button presses have been recorded and will then return a list of Dicts containing the 5 results.

Results can be accessed as follows:

structure:

```
res[0].dir, res[0].button, res[0].time
```

or dictionary:

```
res[0]['dir'], res[0]['button'], res[0]['time']
```

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

### **stop()**

[Not currently implemented] Used to stop event collection by the device.

Not really needed as other members now do this.

### **stopAnalog()**

**will stop sending analogs signals at the next win flip.** Example:

```
bits.set Analog(4.5,-2.2) bits.startAnalog() bits.win.flip() while not response:
```

```
#do some processing. bits.win.flip()
bits.stopAnalog() bits.win.flip()
stopGoggles ()
    Stop the stereo goggles from toggling
```

### Example

```
bits.startGoggles(0,1) bits.win.flip() while not response
```

```
    bits.win.flip() #do some processing
```

```
bits.stopGoggles() bits.win.flip()
```

Starts toggling the goggles with the right eye open in sync with the first win.flip(0) within the loop. The open eye will alternate.

Note it is safer to leave the goggles toggling forever, ie to never call stopGoggles().

```
stopStatusLog ()
```

**Stop logging data from the Bits#** and extracts the raw status values and significant events and puts them in statusValues and statusEvents.

statusValues will end up containing dict like objects of the following style:

```
sample, time, trigIn, DIN[10], DWORD, IR[6], ADC[6]
```

They can be accessed as statusValues[i]['sample'] or statusValues[i].sample, statusValues[x].ADC[j].

StatusEvents will end up containing dict like objects of the following style:

```
source, input, direction, time.
```

The data can be accessed as statusEvents[i]['time'] or statusEvents[i].time

Waits for \_statusLog to finish properly so can introduce a timing delay.

### Example

```
bits.startStatusLog() while not event
```

```
    #do some processing continue
```

```
bits.stopStatusLog() print(bits.statusValues[0].time) print(bits.statusEvents[0].time)
```

Will display the time stamps of the first status value recorded and the first meaningful event.

Note that the firmware in Bits# units varies over time and some features of this class may not work for all firmware versions. Also Bits# units can be configured in various ways via their config.xml file so this class makes certain assumptions about the configuration. In particular it is assumed that all digital inputs, triggers and analog inputs are reported as part of status updates. If some of these report are disabled in your config.xml file then 'status' and 'event' commands in this class may not work.

```
stopTrigger ()
```

```
    Stop sending triggers at the next win flip.
```

## Example

```
bits.setTrigger(0b0000000010, 2.0, 4.0, 0b0111111111) bits.startTrigger() while imageOn:
    #do some processing continue
bits.stopTrigger() bits.win.flip()

syncClocks (t)
    Synchronise the Bits/RTBox Clock with the host clock Given by t.

temporalDithering
    Temporal dithering can be set to True or False

win
    The window that this box is attached to
```

## For display calibration

### ColorCAL

### Attributes

---

<code>ColorCAL([port, maxAttempts])</code>	A class to handle the CRS Ltd ColorCAL device
--	---

---

### Details

**class** psychopy.hardware.crs.colorcal.**ColorCAL** (*port=None, maxAttempts=2*)

A class to handle the CRS Ltd ColorCAL device

Open serial port connection with Colorcal II device

**Usage** cc = ColorCAL(port, maxAttempts)

**If no port is provided then the following defaults will be tried:**

- /dev/cu.usbmodem0001 (OSX)
- /dev/ttyACM0
- COM3 (windows)

**calibrateZero** ()

Perform a calibration to zero light.

For early versions of the ColorCAL this had to be called after connecting to the device. For later versions the dark calibration was performed at the factory and stored in non-volatile memory.

You can check if you need to run a calibration with:

```
ColorCAL.getNeedsCalibrateZero()
```

**driverFor** = ['colorcal']

**getCalibMatrix** ()

Get the calibration matrix from the device, needed for transforming measurements into real-world values.

This is normally retrieved during `__init__` and stored as *ColorCal.calibMatrix* so most users don't need to call this function.

#### **getInfo()**

Queries the device for information

##### **usage::**

```
(ok, serialNumber, firmwareVersion, firmwareBuild) = colorCal.getInfo()
```

*ok* will be True/False Other values will be a string or None.

#### **getLum()**

Conducts a measurement and returns the measured luminance

---

**Note:** The luminance is always also stored as `.lastLum`

---

#### **getNeedsCalibrateZero()**

Check whether the device needs a dark calibration

In initial versions of CRS ColorCAL mkII the device stored its zero calibration in volatile memory and needed to be calibrated in darkness each time you connected it to the USB

This function will check whether your device requires that (based on firmware build number and whether you've already done it since python connected to the device).

**Returns** True or False

**longName** = 'CRS ColorCAL'

#### **measure()**

Conduct a measurement and return the X,Y,Z values

Usage:

```
ok, X, Y, Z = colorCal.measure()
```

**Where:** *ok* is True/False X, Y, Z are the CIE coordinates (Y is luminance in  $\text{cd/m}^2$ )

Following a call to `measure`, the values `ColorCAL.lastLum` will also be populated with, for compatibility with other devices used by PsychoPy (notably the PR650/PR655)

#### **readline (size=None, eol='\n\r')**

This should be used in place of the standard `serial.Serial.readline()` because that doesn't allow us to set the `eol` character

#### **sendMessage (message, timeout=0.1)**

Send a command to the photometer and wait an allotted timeout for a response.

### 8.9.3 egi (pynetstation)

Interface to [EGI Netstation](#)

This is currently a simple import of [pynetstation](#) which is now simply called [egi](#) on pypi.

[egi](#) is included in Standalone distributions of PsychoPy but you can install it with:

```
pip install egi
```

For examples on usage see the *example\_simple* and *example\_multi* files on the [egi github repository](#)

For an example see the demos menu of the PsychoPy Coder For further documentation see the [pynetstation website](#)

## 8.9.4 Launch an fMRI experiment: Test or Scan

Idea: Run or debug an experiment script using exactly the same code, i.e., for both testing and online data acquisition. To debug timing, you can emulate sync pulses and user responses. Limitations: pyglet only; keyboard events only.

**class** psychopy.hardware.emulator.**ResponseEmulator** (*simResponses=None*)

Class to allow simulation of a user's keyboard responses during a scan.

Given a list of response tuples (time, key), the thread will simulate a user pressing a key at a specific time (relative to the start of the run).

Author: Jeremy Gray; Idea: Mike MacAskill

**\_delete** ()

Remove current thread from the dict of currently running threads.

**\_set\_tstate\_lock** ()

Set a lock object which will be released by the interpreter when the underlying thread state (see `pystate.h`) gets deleted.

**daemon**

A boolean value indicating whether this thread is a daemon thread.

This must be set before `start()` is called, otherwise `RuntimeError` is raised. Its initial value is inherited from the creating thread; the main thread is not a daemon thread and therefore all threads created in the main thread default to `daemon = False`.

The entire Python program exits when no alive non-daemon threads are left.

**ident**

Thread identifier of this thread or `None` if it has not been started.

This is a nonzero integer. See the `thread.get_ident()` function. Thread identifiers may be recycled when a thread exits and another thread is created. The identifier is available even after the thread has exited.

**isAlive** ()

Return whether the thread is alive.

This method returns `True` just before the `run()` method starts until just after the `run()` method terminates. The module function `enumerate()` returns a list of all alive threads.

**is\_alive** ()

Return whether the thread is alive.

This method returns `True` just before the `run()` method starts until just after the `run()` method terminates. The module function `enumerate()` returns a list of all alive threads.

**join** (*timeout=None*)

Wait until the thread terminates.

This blocks the calling thread until the thread whose `join()` method is called terminates – either normally or through an unhandled exception or until the optional timeout occurs.

When the timeout argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof). As `join()` always returns `None`, you must call `isAlive()` after `join()` to decide whether a timeout happened – if the thread is still alive, the `join()` call timed out.

When the timeout argument is not present or `None`, the operation will block until the thread terminates.

A thread can be join()ed many times.

join() raises a RuntimeError if an attempt is made to join the current thread as that would cause a deadlock. It is also an error to join() a thread before it has been started and attempts to do so raises the same exception.

**name**

A string used for identification purposes only.

It has no semantics. Multiple threads may be given the same name. The initial name is set by the constructor.

**run()**

Method representing the thread's activity.

You may override this method in a subclass. The standard run() method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the args and kwargs arguments, respectively.

**start()**

Start the thread's activity.

It must be called at most once per thread object. It arranges for the object's run() method to be invoked in a separate thread of control.

This method will raise a RuntimeError if called more than once on the same thread object.

```
class psychopy.hardware.emulator.SyncGenerator (TR=1.0,    TA=1.0,    volumes=10,
                                              sync='5',    skip=0,    sound=False,
                                              **kwargs)
```

Class for a character-emitting metronome thread (emulate MR sync pulse).

Aim: Allow testing of temporal robustness of fMRI scripts by emulating a hardware sync pulse. Adds an arbitrary 'sync' character to the key buffer, with sub-millisecond precision (less precise if CPU is maxed). Recommend: TR=1.000 or higher and less than 100% CPU. Shorter TR -> higher CPU load.

**Parameters**

- **TR** – seconds between volume acquisitions
- **TA** – seconds to acquire one volume
- **volumes** – number of 3D volumes to obtain in a given scanning run
- **sync** – character used as flag for sync timing, default='5'
- **skip** – how many frames to silently omit initially during T1 stabilization, no sync pulse. Not needed to test script timing, but will give more accurate feel to start of run. aka “disc-dacqs”.
- **sound** – simulate scanner noise

**\_delete()**

Remove current thread from the dict of currently running threads.

**\_set\_tstate\_lock()**

Set a lock object which will be released by the interpreter when the underlying thread state (see pystate.h) gets deleted.

**daemon**

A boolean value indicating whether this thread is a daemon thread.

This must be set before start() is called, otherwise RuntimeError is raised. Its initial value is inherited from the creating thread; the main thread is not a daemon thread and therefore all threads created in the main thread default to daemon = False.

The entire Python program exits when no alive non-daemon threads are left.

**ident**

Thread identifier of this thread or None if it has not been started.

This is a nonzero integer. See the `thread.get_ident()` function. Thread identifiers may be recycled when a thread exits and another thread is created. The identifier is available even after the thread has exited.

**isAlive()**

Return whether the thread is alive.

This method returns True just before the `run()` method starts until just after the `run()` method terminates. The module function `enumerate()` returns a list of all alive threads.

**is\_alive()**

Return whether the thread is alive.

This method returns True just before the `run()` method starts until just after the `run()` method terminates. The module function `enumerate()` returns a list of all alive threads.

**join(timeout=None)**

Wait until the thread terminates.

This blocks the calling thread until the thread whose `join()` method is called terminates – either normally or through an unhandled exception or until the optional timeout occurs.

When the timeout argument is present and not None, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof). As `join()` always returns None, you must call `isAlive()` after `join()` to decide whether a timeout happened – if the thread is still alive, the `join()` call timed out.

When the timeout argument is not present or None, the operation will block until the thread terminates.

A thread can be `join()`ed many times.

`join()` raises a `RuntimeError` if an attempt is made to join the current thread as that would cause a deadlock. It is also an error to `join()` a thread before it has been started and attempts to do so raises the same exception.

**name**

A string used for identification purposes only.

It has no semantics. Multiple threads may be given the same name. The initial name is set by the constructor.

**run()**

Method representing the thread's activity.

You may override this method in a subclass. The standard `run()` method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the `args` and `kwargs` arguments, respectively.

**start()**

Start the thread's activity.

It must be called at most once per thread object. It arranges for the object's `run()` method to be invoked in a separate thread of control.

This method will raise a `RuntimeError` if called more than once on the same thread object.

```
psychopy.hardware.emulator.launchScan(win, settings, globalClock=None, simRe-
sponses=None, mode=None, esc_key='escape',
instr='select Scan or Test, press enter',
wait_msg='waiting for scanner..', wait_timeout=300,
log=True)
```



Accepts up to four fMRI scan parameters (TR, volumes, sync-key, skip), and launches an experiment in one of two modes: Scan, or Test.

**Usage** See Coder Demo -> experiment control -> fMRI\_launchScan.py.

In brief: 1) from psychopy.hardware.emulator import launchScan; 2) Define your args; and 3) add 'vol = launchScan(args)' at the top of your experiment script.

launchScan() waits for the first sync pulse and then returns, allowing your experiment script to proceed. The key feature is that, in test mode, it first starts an autonomous thread that emulates sync pulses (i.e., emulated by your CPU rather than generated by an MRI machine). The thread places a character in the key buffer, exactly like a keyboard event does. launchScan will wait for the first such sync pulse (i.e., character in the key buffer). launchScan returns the number of sync pulses detected so far (i.e., 1), so that a script can account for them explicitly.

If a globalClock is given (highly recommended), it is reset to 0.0 when the first sync pulse is detected. If a mode was not specified when calling launchScan, the operator is prompted to select Scan or Test.

If **scan mode** is selected, the script will wait until the first scan pulse is detected. Typically this would be coming from the scanner, but note that it could also be a person manually pressing that key.

If **test mode** is selected, launchScan() starts a separate thread to emit sync pulses / key presses. Note that this thread is effectively nothing more than a key-pressing metronome, emitting a key at the start of every TR, doing so with high temporal precision.

If your MR hardware interface does not deliver a key character as a sync flag, you can still use launchScan() to test script timing. You have to code your experiment to trigger on either a sync character (to test timing) or your usual sync flag (for actual scanning).

**Parameters** win: a *Window* object (required)

**settings** [a dict containing up to 5 parameters] (2 required: TR, volumes)

**TR** : seconds per whole-brain volume (minimum value = 0.1s)

**volumes** : number of whole-brain (3D) volumes to obtain in a given scanning run.

**sync** : (optional) key for sync timing, default = '5'.

**skip** : (optional) how many volumes to silently omit initially (during T1 stabilization, no sync pulse). default = 0.

**sound** : (optional) whether to play a sound when simulating scanner sync pulses

**globalClock** : optional but highly recommended *Clock* to be used during the scan; if one is given, it is reset to 0.000 when the first sync pulse is received.

**simResponses** : optional list of tuples [(time, key), (time, key), ...]. time values are seconds after the first scan pulse is received.

**esc\_key** : key to be used for user-interrupt during launch. default = 'escape'

**mode** : if mode is 'Test' or 'Scan', launchScan() will start in that mode.

**instr** : instructions to be displayed to the scan operator during mode selection.

**wait\_msg** : message to be displayed to the subject while waiting for the scan to start (i.e., after operator indicates start but before the first scan pulse is received).

**wait\_timeout** : time in seconds that launchScan will wait before assuming something went wrong and exiting. Defaults to 300sec (5 min). Raises a RuntimeError if no sync pulse is received in the allowable time.

**class** psychopy.hardware.emulator.**ResponseEmulator** (simResponses=None)

Class to allow simulation of a user's keyboard responses during a scan.

Given a list of response tuples (time, key), the thread will simulate a user pressing a key at a specific time (relative to the start of the run).

Author: Jeremy Gray; Idea: Mike MacAskill

**run()**

Method representing the thread's activity.

You may override this method in a subclass. The standard run() method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the args and kwargs arguments, respectively.

```
class psychopy.hardware.emulator.SyncGenerator (TR=1.0,    TA=1.0,    volumes=10,
                                              sync='5',    skip=0,    sound=False,
                                              **kwargs)
```

Class for a character-emitting metronome thread (emulate MR sync pulse).

Aim: Allow testing of temporal robustness of fMRI scripts by emulating a hardware sync pulse. Adds an arbitrary 'sync' character to the key buffer, with sub-millisecond precision (less precise if CPU is maxed). Recommend: TR=1.000 or higher and less than 100% CPU. Shorter TR -> higher CPU load.

#### Parameters

- **TR** – seconds between volume acquisitions
- **TA** – seconds to acquire one volume
- **volumes** – number of 3D volumes to obtain in a given scanning run
- **sync** – character used as flag for sync timing, default='5'
- **skip** – how many frames to silently omit initially during T1 stabilization, no sync pulse. Not needed to test script timing, but will give more accurate feel to start of run. aka “disc-dacqs”.
- **sound** – simulate scanner noise

**run()**

Method representing the thread's activity.

You may override this method in a subclass. The standard run() method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the args and kwargs arguments, respectively.

### 8.9.5 fORP response box

fORP fibre optic (MR-compatible) response devices by CurrentDesigns: <http://www.curdes.com/> This class is only useful when the fORP is connected via the serial port.

If you're connecting via USB, just treat it like a standard keyboard. E.g., use a Keyboard component, and typically listen for Allowed keys '1', '2', '3', '4', '5'. Or use `event.getKeys()`.

```
class psychopy.hardware.forp.ButtonBox (serialPort=1, baudrate=19200)
    Serial line interface to the fORP MRI response box.
```

To use this object class, select the box use setting `serialPort`, and connect the serial line. To emulate key presses with a serial connection, use `getEvents(asKeys=True)` (e.g., to be able to use a RatingScale object during scanning). Alternatively connect the USB cable and use fORP to emulate a keyboard.

fORP sends characters at 800Hz, so you should check the buffer frequently. Also note that the trigger event numpyl the fORP is typically extremely short (occurs for a single 800Hz epoch).

#### Parameters

**serialPort** : should be a number (where 1=COM1, ...)

**baud** : the communication rate (baud), eg, 57600

**classmethod** `_decodePress` (*pressCode*)

Returns a list of buttons and whether they're pressed, given a character code.

**pressCode** : A number with a bit set for every button currently pressed. Will be between 0 and 31.

**\_generateEvents** (*pressCode*)

For a given button press, returns a list buttons that went from unpressed to pressed. Also flags any unpressed buttons as unpressed.

**pressCode** : a number with a bit set for every button currently pressed.

**clearBuffer** ()

Empty the input buffer of all characters

**clearStatus** ()

Resets the pressed statuses, so `getEvents` will return pressed buttons, even if they were already pressed in the last call.

**getEvents** (*returnRaw=False, asKeys=False, allowRepeats=False*)

Returns a list of unique events (one event per button pressed) and also stores a copy of the full list of events since last `getEvents()` (stored as `ForpBox.rawEvts`)

**returnRaw** : return (not just store) the full event list

**asKeys** : If True, will also emulate pyglet keyboard events, so that button 1 will register as a keyboard event with value "1", and as such will be detectable using `event.getKeys()`

**allowRepeats** : If True, this will return pressed buttons even if they were held down between calls to `getEvents()`. If the fORP is on the "Eprime" setting, you will get a stream of button presses while a button is held down. On the "Bitwise" setting, you will get a set of all currently pressed buttons every time a button is pressed or released. This option might be useful if you think your participant may be holding the button down before you start checking for presses.

**getUniqueEvents** (*fullEvts=False*)

Returns a Python set of the unique (unordered) events of either a list given or the current `rawEvts` buffer

## 8.9.6 iolab

This provides a basic `ButtonBox` class, and imports the `ioLab` python library.

**class** `psychopy.hardware.iolab.ButtonBox`

PsychoPy's interface to `ioLabs.USBBox`. Voice key completely untested.

Original author: Jonathan Roberts PsychoPy rewrite: Jeremy Gray, 2013

Class to detect and report `ioLab` button box.

The `ioLabs` library needs to be installed. It is included in the *Standalone* distributions of PsychoPy as of version 1.62.01. Otherwise try "pip install ioLabs"

Usage:

```
from psychopy.hardware import iolab
bbox = iolab.ButtonBox()
```

For examples see the demos menu of the PsychoPy Coder or go to the URL above.

All times are reported in units of seconds.

**\_getTime** (*log=False*)

Return the time on the bbox internal clock, relative to last reset.

Status: `rtcget()` not working

*log=True* will log the bbox time and elapsed CPU (python) time.

**clearEvents** ()

Discard all button / voice key events.

**getBaseTime** ()

Return the time since init (using the CPU clock, not ioLab bbox).

Aim is to provide a similar API as for a Cedrus box. Could let both clocks run for a long time to assess relative drift.

**getEnabled** ()

Return a list of the buttons that are currently enabled.

**getEvents** (*downOnly=True*)

Detect and return a list of all events (likely just one); no block.

Use *downOnly=False* to include button-release events.

**resetClock** (*log=True*)

Reset the clock on the bbox internal clock, e.g., at the start of a trial.

~1ms for me; logging is much faster than the reset

**setEnabled** (*buttonList=(0, 1, 2, 3, 4, 5, 6, 7)*, *voice=False*)

Set a filter to suppress events from non-enabled buttons.

The ioLabs bbox filters buttons in hardware; here we just tell it what we want: `None` - disable all buttons an integer (0..7) - enable a single button a list of integers (0..7) - enable all buttons in the list

Set *voice=True* to enable the voiceKey - gets reported as button 64

**setLights** (*lightList=(0, 1, 2, 3, 4, 5, 6, 7)*)

Turn on the specified LEDs (`None`, 0..7, list of 0..7)

**standby** ()

Disable all buttons and lights.

**waitEvents** (*downOnly=True*, *timeout=0*, *escape='escape'*, *wait=0.002*)

Wait for and return the first button press event.

Always calls `clearEvents()` first (like PsychoPy keyboard `waitKeys`).

Use *downOnly=False* to include button-release events.

*escape* is a list/tuple of keyboard events that, if pressed, will interrupt the bbox wait; `waitKeys` will return `None` in that case.

*timeout* is the max time to wait in seconds before returning `None`. *timeout* of 0 means no time-out (= default).

## 8.9.7 joystick (pyglet and pygame)

AT THE MOMENT JOYSTICK DOES NOT APPEAR TO WORK UNDER PYGLET. We need someone motivated and capable to go and get this right (problem is with event polling under pyglet)

Control joysticks and gamepads from within PsychoPy.

You do need a window (and you need to be flipping it) for the joystick to be updated.

### Known issues:

- currently under pygame the joystick axes initialise to a value of zero and stay like this until the first time that axis moves
- currently pygame (1.9.1) spits out lots of debug messages about the joystick and these can't be turned off :-/

### Typical usage:

```
from psychopy.hardware import joystick
from psychopy import visual

joystick.backend='pyglet' # must match the Window
win = visual.Window([400,400], winType='pyglet')

nJoys = joystick.getNumJoysticks() # to check if we have any
id = 0
joy = joystick.Joystick(id) # id must be <= nJoys - 1

nAxes = joy.getNumAxes() # for interest
while True: # while presenting stimuli
    joy.getX()
    # ...
    win.flip() # flipping implicitly updates the joystick info
```

**class** psychopy.hardware.joystick.XboxController(*id*, \**args*, \*\**kwargs*)

Joystick template class for the Xbox 360 controller.

### Usage:

xbctrl = XboxController(0) # joystick ID y\_btn\_state = xbctrl.y # get the state of the 'Y' button

**\_clip\_range**(*val*)

Clip the range of a value between -1.0 and +1.0. Needed for joystick axes.

**Parameters** *val* –

**Returns**

**get\_a**()

Get the 'A' button state.

**Returns** bool, True if pressed down

**get\_b**()

Get the 'B' button state.

**Returns** bool, True if pressed down

**get\_back**()

Get 'back' button state (button to the right of the left joystick).

**Returns** bool, True if pressed down

**get\_hat\_axis**()

Get the states of the hat (sometimes called the 'directional pad'). The hat can only indicate direction but not displacement.

This function reports hat values in the same way as a joystick so it may be used interchangeably with existing analog joystick code.

Returns a tuple (X,Y) indicating which direction the hat is pressed between -1.0 and +1.0. Positive values indicate presses in the right or up direction.

**Returns** tuple, zero centered X, Y values.

**get\_left\_shoulder()**

Get left 'shoulder' trigger state.

**Returns** bool, True if pressed down

**get\_left\_thumbstick()**

Get the state of the left joystick button; activated by pressing down on the stick.

**Returns** bool, True if pressed down

**get\_left\_thumbstick\_axis()**

Get the axis displacement values of the left thumbstick.

Returns a tuple (X,Y) indicating thumbstick displacement between -1.0 and +1.0. Positive values indicate the stick is displaced right or up.

**Returns** tuple, zero centered X, Y values.

**get\_named\_buttons(button\_names)**

Get the states of multiple buttons using names. A list of button states is returned for each string in list 'names'.

**Parameters** **button\_names** – tuple or list of button names

**Returns**

**get\_right\_shoulder()**

Get right 'shoulder' trigger state.

**Returns** bool, True if pressed down

**get\_right\_thumbstick()**

Get the state of the right joystick button; activated by pressing down on the stick.

**Returns** bool, True if pressed down

**get\_right\_thumbstick\_axis()**

Get the axis displacement values of the right thumbstick.

Returns a tuple (X,Y) indicating thumbstick displacement between -1.0 and +1.0. Positive values indicate the stick is displaced right or up.

**Returns** tuple, zero centered X, Y values.

**get\_start()**

Get 'start' button state (button to the left of the 'X' button).

**Returns** bool, True if pressed down

**get\_trigger\_axis()**

Get the axis displacement values of both index triggers.

Returns a tuple (L,R) indicating index trigger displacement between -1.0 and +1.0. Values increase from -1.0 to 1.0 the further a trigger is pushed.

**Returns** tuple, zero centered L, R values.

**get\_x()**

Get the 'X' button state.

**Returns** bool, True if pressed down

**get\_y()**

Get the 'Y' button state.

**Returns** bool, True if pressed down

`psychopy.hardware.joystick.getNumJoysticks()`  
Return a count of the number of joysticks available.

**class** `psychopy.hardware.joystick.Joystick(id)`  
An object to control a multi-axis joystick or gamepad.

**Known issues** Currently under pygame backends the axis values initialise to zero rather than reading the current true value. This gets fixed on the first change to each axis.

**getAllAxes()**  
Get a list of all current axis values.

**getAllButtons()**  
Get the state of all buttons as a list.

**getAllHats()**  
Get the current values of all available hats as a list of tuples.  
Each value is a tuple (x, y) where x and y can be -1, 0, +1

**getAxis(axisId)**  
Get the value of an axis by an integer id.  
(from 0 to number of axes - 1)

**getButton(buttonId)**  
Get the state of a given button.  
buttonId should be a value from 0 to the number of buttons-1

**getHat(hatId=0)**  
Get the position of a particular hat.  
The position returned is an (x, y) tuple where x and y can be -1, 0 or +1

**getName()**  
Return the manufacturer-defined name describing the device.

**getNumAxes()**  
Return the number of joystick axes found.

**getNumButtons()**  
Return the number of digital buttons on the device.

**getNumHats()**  
Get the number of hats on this joystick.  
The GLFW backend makes no distinction between hats and buttons. Calling 'getNumHats()' will return 0.

**getX()**  
Return the X axis value (equivalent to `joystick.getAxis(0)`).

**getY()**  
Return the Y axis value (equivalent to `joystick.getAxis(1)`).

**getZ()**  
Return the Z axis value (equivalent to `joystick.getAxis(2)`).

## 8.9.8 labjacks (USB I/O devices)

PsychoPy provides an interface to the labjack U3 class with a couple of minor additions.

This is accessible by:

```
from psychopy.hardware.labjacks import U3
```

Except for the additional *setdata* function the U3 class operates exactly as that in the U3 library that labjack provides, documented here:

<http://labjack.com/support/labjackpython>

---

**Note:** To use labjack devices you do need also to install the driver software described on the page above

---

**class** psychopy.hardware.labjacks.U3 (*debug=False, autoOpen=True, \*\*kargs*)

Name: U3.\_\_init\_\_(debug = False, autoOpen = True, **\*\*openArgs**)

**Args:** **debug**, enables debug output autoOpen, if true, the class will try to open a U3 using openArgs **\*\*openArgs**, the arguments to pass to the open call. See U3.open()

**Desc:** Instantiates a new U3 object. If autoOpen == True, then it will also open a U3.

Examples: Simplest: >>> import u3 >>> d = u3.U3()

For debug output: >>> import u3 >>> d = u3.U3(debug = True)

To open a U3 with Local ID = 2: >>> import u3 >>> d = u3.U3(localId = 2)

**setData** (*byte, endian='big', address=6701*)

Write 1 byte of data to the U3 port

### Parameters

- **byte** (-) – the value to write (must be an integer 0:255)
- **endian** (-) – ['big' or 'small'] ignored from 1.84 onwards; automatic?
- **address** (-) – the memory address to send the byte to - 6700 = FIO - 6701 (default) = EIO (the DB15 connector) - 6702 = CIO

## 8.9.9 Minolta

Minolta light-measuring devices See <http://www.konicaminolta.com/instruments>

**class** psychopy.hardware.minolta.LS100 (*port, maxAttempts=1*)

A class to define a Minolta LS100 (or LS110?) photometer

You need to connect a LS100 to the serial (RS232) port and **when you turn it on press the F key** on the device. This will put it into the correct mode to communicate with the serial port.

usage:

```
from psychopy.hardware import minolta
phot = minolta.LS100(port)
if phot.OK: # then we successfully made a connection
    print(phot.getLum())
```



**Parameters** port: string

the serial port that should be checked

**maxAttempts: int** If the device doesn't respond first time how many attempts should be made? If you're certain that this is the correct port and the device is on and correctly configured then this could be set high. If not then set this low.

**Troubleshooting** Various messages are printed to the log regarding the function of this device, but to see them you need to set the printing of the log to the correct level:

```
from psychopy import logging
logging.console.setLevel(logging.ERROR) # error messages only
logging.console.setLevel(logging.INFO) # more info
logging.console.setLevel(logging.DEBUG) # log all communications
```

If you're using a keyspan adapter (at least on macOS) be aware that it needs a driver installed. Otherwise no ports will be found.

Error messages:

**ERROR: Couldn't connect to Minolta LS100/110 on \_\_\_\_:** This likely means that the device is not connected to that port (although the port has been found and opened). Check that the device has the / in the bottom right of the display; if not turn off and on again holding the *F* key.

**ERROR: No reply from LS100:** The port was found, the connection was made and an initial command worked, but then the device stopped communicating. If the first measurement taken with the device after connecting does not yield a reasonable intensity the device can sulk (not a technical term!). The “[” on the display will disappear and you can no longer communicate with the device. Turn it off and on again (with *F* depressed) and use a reasonably bright screen for your first measurement. Subsequent measurements can be dark (or we really would be in trouble!!).

**checkOK** (*msg*)

Check that the message from the photometer is OK. If there's an error show it (printed).

Then return True (OK) or False.

**clearMemory** ()

Clear the memory of the device from previous measurements

**getLum** ()

Makes a measurement and returns the luminance value

**measure** ()

Measure the current luminance and set .lastLum to this value

**sendMessage** (*message, timeout=5.0*)

Send a command to the photometer and wait an allotted timeout for a response.

**setMaxAttempts** (*maxAttempts*)

Changes the number of attempts to send a message and read the output. Typically this should be low initially, if you aren't sure that the device is setup correctly but then, after the first successful reading, set it higher.

**setMode** (*mode='04'*)

Set the mode for measurements. Returns True (success) or False

'04' means absolute measurements. '08' = peak '09' = cont

See user manual for other modes

## 8.9.10 PhotoResearch

Supported devices:

- *PR650*
- *PR655/PR670*

PhotoResearch spectrophotometers See <http://www.photoresearch.com/>

---

**class** psychopy.hardware.pr.PR650 (*port, verbose=None*)

An interface to the PR650 via the serial port.

(Added in version 1.63.02)

example usage:

```
from psychopy.hardware.pr import PR650
myPR650 = PR650(port)
myPR650.getLum() # make a measurement
nm, power = myPR650.getLastSpectrum() # get a power spectrum for the
last measurement
```

NB *psychopy.hardware.findPhotometer()* will locate and return any supported device for you so you can also do:

```
from psychopy import hardware
phot = hardware.findPhotometer()
print(phot.getLum())
```

**Troubleshooting** Various messages are printed to the log regarding the function of this device, but to see them you need to set the printing of the log to the correct level:

```
from psychopy import logging
logging.console.setLevel(logging.ERROR) # error messages only
logging.console.setLevel(logging.INFO) # will give more info
logging.console.setLevel(logging.DEBUG) # log all communications
```

If you're using a keyspan adapter (at least on macOS) be aware that it needs a driver installed. Otherwise no ports will be found.

Also note that the attempt to connect to the PR650 must occur within the first few seconds after turning it on.

**getLastLum()**

This retrieves the luminance (in  $\text{cd/m}^2$ ) from the last call to *.measure()*

**getLastSpectrum(parse=True)**

This retrieves the spectrum from the last call to *.measure()*

If *parse=True* (default): The format is a num array with 100 rows [nm, power]

otherwise: The output will be the raw string from the PR650 and should then be passed to *.parseSpectrumOutput()*. It's more efficient to parse R,G,B strings at once than each individually.

**getLum()**

Makes a measurement and returns the luminance value

**getSpectrum(*parse=True*)**

Makes a measurement and returns the current power spectrum

**If *parse=True* (default):** The format is a num array with 100 rows [nm, power]

**If *parse=False* (default):** The output will be the raw string from the PR650 and should then be passed to `.parseSpectrumOutput()`. It's slightly more efficient to parse R,G,B strings at once than each individually.

**measure(*timeOut=30.0*)**

Make a measurement with the device. For a PR650 the device is instructed to make a measurement and then subsequent commands are issued to retrieve info about that measurement.

**parseSpectrumOutput(*rawStr*)**

Parses the strings from the PR650 as received after sending the command 'd5'. The input argument "rawStr" can be the output from a single phosphor spectrum measurement or a list of 3 such measurements [rawR, rawG, rawB].

**sendMessage(*message, timeout=0.5, DEBUG=False*)**

Send a command to the photometer and wait an allotted timeout for a response (Timeout should be long for low light measurements)

**class psychopy.hardware.pr.PR655(*port*)**

An interface to the PR655/PR670 via the serial port.

example usage:

```
from psychopy.hardware.pr import PR655
myPR655 = PR655(port)
myPR655.getLum() # make a measurement
nm, power = myPR655.getLastSpectrum() # get a power spectrum for the
last measurement
```

NB `psychopy.hardware.findPhotometer()` will locate and return any supported device for you so you can also do:

```
from psychopy import hardware
phot = hardware.findPhotometer()
print(phot.getLum())
```

**Troubleshooting** If the device isn't responding try turning it off and turning it on again, and/or disconnecting/reconnecting the USB cable. It may be that the port has become controlled by some other program.

**endRemoteMode()**

Puts the colorimeter back into normal mode

**getDeviceSN()**

Return the device serial number

**getDeviceType()**

Return the device type (e.g. 'PR-655' or 'PR-670')

**getLastColorTemp()**

Fetches (from the device) the color temperature (K) of the last measurement

**Returns** list: status, units, exponent, correlated color temp (Kelvins), CIE 1960 deviation

See also `measure()` automatically populates `pr655.lastColorTemp` with the color temp in Kelvins

**getLastSpectrum** (*parse=True*)

This retrieves the spectrum from the last call to `measure()`

If *parse=True* (default):

The format is a num array with 100 rows [nm, power]

otherwise:

The output will be the raw string from the PR650 and should then be passed to `parseSpectrumOutput()`. It's more efficient to parse R,G,B strings at once than each individually.

**getLastTristim** ()

Fetches (from the device) the last CIE 1931 Tristimulus values

**Returns** list: status, units, Tristimulus Values

See also `measure()` automatically populates `pr655.lastTristim` with just the tristimulus coordinates

**getLastUV** ()

Fetches (from the device) the last CIE 1976 u,v coords

**Returns** list: status, units, Photometric brightness, u, v

See also `measure()` automatically populates `pr655.lastUV` with [u,v]

**getLastXY** ()

Fetches (from the device) the last CIE 1931 x,y coords

**Returns** list: status, units, Photometric brightness, x,y

See also `measure()` automatically populates `pr655.lastXY` with [x,y]

**measure** (*timeOut=30.0*)

Make a measurement with the device.

This automatically populates:

- `.lastLum`
- `.lastSpectrum`
- `.lastCIExy`
- `.lastCIEuv`

**parseSpectrumOutput** (*rawStr*)

Parses the strings from the PR650 as received after sending the command 'D5'. The input argument "rawStr" can be the output from a single phosphor spectrum measurement or a list of 3 such measurements [rawR, rawG, rawB].

**sendMessage** (*message, timeout=0.5, DEBUG=False*)

Send a command to the photometer and wait an allotted timeout for a response (Timeout should be long for low light measurements)

**startRemoteMode** ()

Sets the Colorimeter into remote mode

### 8.9.11 pylink (SR research)

For now the SR Research pylink module is packaged with the Standalone flavours of PsychoPy and can be imported with:

```
import pylink
```

You do need to install the Display Software (which they also call EyeLink Developers Kit) for your particular platform. This can be found by following the threads from:

<https://www.sr-support.com/forums/forumdisplay.php?f=17>

for pylink documentation see:

<https://www.sr-support.com/forums/showthread.php?t=14>

Performing research with eye-tracking equipment typically requires a long-term investment in software tools to collect, process, and analyze data. Much of this involves real-time data collection, saccadic analysis, calibration routines, and so on. The EyeLink® eye-tracking system is designed to implement most of the required software base for data collection and conversion. It is most powerful when used with the Ethernet link interface, which allows remote control of data collection and real-time data transfer. The PyLink toolkit includes Pylink module, which implements all core EyeLink functions and classes for EyeLink connection and the eyelink graphics, such as the display of camera image, calibration, validation, and drift correct. The EyeLink graphics is currently implemented using Simple Direct Media Layer (SDL: [www.libsdl.org](http://www.libsdl.org)).

The Pylink library contains a set of classes and functions, which are used to program experiments on many different platforms, such as MS-DOS, Windows, Linux, and the Macintosh. Some programming standards, such as placement of messages in the EDF file by your experiment, and the use of special data types, have been implemented to allow portability of the development kit across platforms. The standard messages allow general analysis tools such as EDF2ASC converter or EyeLink Data Viewer to process your EDF files.

**pylink.alert** (*message*)

This method is used to give a notification to the user when an error occurs. Parameters <message>: Text message to be displayed. Return Value: None Remarks: This function does not allow printf formatting as in c. However you can do a formatted string argument in python. This is equivalent to the C API void alert\_printf(char \*fmt, ...);

**pylink.beginRealTimeMode** (*delay*)

Sets the application priority and cleans up pending Windows activity to place the application in realtime mode. This could take up to 100 milliseconds, depending on the operation system, to set the application priority. Parameters <delay> an integer, used to set the minimum time this function takes, so that this function can act as a useful delay. Return Value None This function is equivalent to the C API void begin\_realtime\_mode(UINT32 delay);

**pylink.bitmapSave** (*iwidth, iheight, pixels, xs, ys, width, height, fname, path, sv\_options*) *iwidth* - original image width *iheight* - original image height *pixels* - Pixels of the image in one of two possible formats: *pixel*=[line1, line2, ... linen] *line*=[pix1, pix2, ..., pixn], *pix*=(r,g,b). *pixel*=[line1, line2, ... linen] *line*=[pix1, pix2, ..., pixn], *pix*=0xAARRGGBB. *xs* - crop x position *ys* - crop y position *width* - crop width *height* - crop height *fname* - file name to save *path* - path to save *sv\_options* - save options (SV\_NOREPLACE, SV\_MAKEPATH)

**pylink.closeGraphics** ()

Notifies the eyelink\_core\_graphics to close or release the graphics. Parameters None Return Value None This is equivalent to the C API void close\_expt\_graphics(void); This function should not be used with custom graphics

**pylink.closeMessageFile** ()

DOC UNDONE

**pylink.currentTime** ()

Returns the current millisecond time since the initialization of the EyeLink library. Parameters None. Return

Value Long integer for the current millisecond time since the initialization of the EyeLink library This function is equivalent to the C API `UINT32 current_time(void)`;

`pylink.currentUsec()`

Returns the current microsecond time since the initialization of the EyeLink library. Parameters None. Return Value Long integer for the current microsecond time since the initialization of the EyeLink library This is equivalent to the C API `UINT32 current_usec(void)`;

`pylink.enableExtendedRealtime()`

DOC UNDONE

`pylink.enablePCRSample()`

If enabled, the raw data can be obtained

`pylink.endRealTimeMode()`

Returns the application to a priority slightly above normal, to end realtime mode. This function should execute rapidly, but there is the possibility that Windows will allow other tasks to run after this call, causing delays of 1-20 milliseconds. Parameters None Return Value None This function is equivalent to the C API `void end_realtime_mode(void)`;

`pylink.flushGetkeyQueue()`

Initializes the key queue used by `getkey()`. It may be called at any time to get rid any of old keys from the queue. Parameters None Return Value None This is equivalent to the C API `void flush_getkey_queue(void)`;

`pylink.getDisplayInformation()`

Returns the display configuration. Parameters None Return Value Instance of `DisplayInfo` class. The width, height, bits, and refresh rate of the display can be accessed from the returned value. For example. `display = getDisplayInformation() print display.width, display.height, display.bits, display.refresh`

`pylink.getLastError()`

get error number returned by last call to corresponding C-API function

`pylink.inRealTimeMode()`

DOC UNDONE

`pylink.msecDelay(delay)`

Does a unblocked delay using `currentTime()`. Parameters `<delay>`: an integer for number of milliseconds to delay. Return Value None This is equivalent to the C API `void msec_delay(UINT32 n)`;

`pylink.openCustomGraphicsInternal()`

DOC UNDONE

`pylink.openGraphics()`

`openGraphics(dimension, bits)`; Opens the graphics if the display mode is not set. If the display mode is already set, uses the existing display mode. Parameters `<dimension>`: two-item tuple of display containing width and height information. `<bits>`: color bits. Return Value None or run-time error. This is equivalent to the SDL version C API `INT16 init_expt_graphics(SDL_Surface * s, DISPLAYINFO *info)`.

`pylink.openMessageFile()`

DOC UNDONE

`pylink.pumpDelay(delay)`

During calls to `msecDelay()`, Windows is not able to handle messages. One result of this is that windows may not appear. This is the preferred delay function when accurate timing is not needed. It calls `pumpMessages()` until the last 20 milliseconds of the delay, allowing Windows to function properly. In rare cases, the delay may be longer than expected. It does not process modeless dialog box messages. Parameters `<delay>`: an integer, which sets number of milliseconds to delay. Return Value None Use the This is equivalent to the C API `void pump_delay(UINT32 delay)`;

`pylink.resetBackground()`

DOC UNDONE

`pylink.sendMessageToFile()`  
DOC UNDONE

`pylink.setCalibrationColors` (*foreground\_color, background\_color*)

Passes the colors of the display background and fixation target to the `eyelink_core_graphics` library. During calibration, camera image display, and drift correction, the display background should match the brightness of the experimental stimuli as closely as possible, in order to maximize tracking accuracy. This function passes the colors of the display background and fixation target to the `eyelink_core_graphics` library. This also prevents flickering of the display at the beginning and end of drift correction. Parameters `<foreground_color>`: color for foreground calibration target. `<background_color>`: color for foreground calibration background. Both colors must be a threeinteger (from 0 to 255) tuple encoding the red, blue, and green color component. Return Value None This is equivalent to the C API void `set_calibration_colors(SDL_Color *fg, SDL_Color *bg)`; Example: `setCalibrationColors((0, 0, 0), (255, 255, 255))` This sets the calibration target in black and calibration background in white.

`pylink.setCalibrationSounds` (*target, good, error*)

Selects the sounds to be played during `do_tracker_setup()`, including calibration, validation and drift correction. These events are the display or movement of the target, successful conclusion of calibration or good validation, and failure or interruption of calibration or validation. Note: If no sound card is installed, the sounds are produced as beeps from the PC speaker. Otherwise, sounds can be selected by passing a string. If the string is (empty), the default sounds are played. If the string is off, no sound will be played for that event. Otherwise, the string should be the name of a .WAV file to play. Parameters `<target>`: Sets sound to play when target moves; `<good>`: Sets sound to play on successful operation; `<error>`: Sets sound to play on failure or interruption. Return Value None This function is equivalent to the C API void `set_cal_sounds(char *target, char *good, char *error)`;

`pylink.setCameraPosition` (*left, top, right, bottom*)

Sets the camera position on the display computer. Moves the top left hand corner of the camera position to new location. Parameters `<left>`: x-coord of upper-left corner of the camera image window; `<top>`: y-coord of upper-left corner of the camera image window; `<right>`: x-coord of lower-right corner of the camera image window; `<bottom>`: y-coord of lower-right corner of the camera image window. Return Value None

`pylink.setDriftCorrectSounds` (*target, good, setup*)

Selects the sounds to be played during `doDriftCorrect()`. These events are the display or movement of the target, successful conclusion of drift correction, and pressing the ESC key to start the Setup menu. Note: If no sound card is installed, the sounds are produced as beeps from the PC speaker. Otherwise, sounds can be selected by passing a string. If the string is (empty), the default sounds are played. If the string is off, no sound will be played for that event. Otherwise, the string should be the name of a .WAV file to play. Parameters `<target>`: Sets sound to play when target moves; `<good>`: Sets sound to play on successful operation; `<setup>`: Sets sound to play on ESC key pressed. Return Value None This function is equivalent to the C API void `set_dcorr_sounds(char *target, char *good, char *setup)`;

`pylink.setTargetSize` (*diameter, holesize*)

The standard calibration and drift correction target is a disk (for peripheral delectability) with a central hole target (for accurate fixation). The sizes of these features may be set with this function. Parameters `<diameter>`: Size of outer disk, in pixels. `<holesize>`: Size of central feature, in pixels. If `holesize` is 0, no central feature will be drawn. The disk is drawn in the calibration foreground color, and the hole is drawn in the calibration background color. Return Value None This function is equivalent to the C API void `set_target_size(UINT16 diameter, UINT16 holesize)`;

### 8.9.12 `psychopy.hardware.pump` - A simple interface to the Cetoni neMESYS syringe pump system

Please specify the name of the pump configuration to use in the PsychoPy preferences under Hardware / Qmix pump configuration. See the [readme file](#) of the `pyqmix` project for details on how to set up your computer and



create the configuration file.

`psychopy.hardware.findPhotometer` (*ports=None, device=None*)

Try to find a connected photometer/photospectrometer!

PsychoPy will sweep a series of serial ports trying to open them. If a port successfully opens then it will try to issue a command to the device. If it responds with one of the expected values then it is assumed to be the appropriate device.

#### Parameters

**ports** [a list of ports to search] Each port can be a string (e.g. 'COM1', '/dev/tty.Keyspan1.1') or a number (for win32 comports only). If none are provided then PsychoPy will sweep COM0-10 on win32 and search known likely port names on macOS and Linux.

**device** [string giving expected device (e.g. 'PR650', 'PR655', 'LS100', 'LS110'). If this is not given then an attempt will be made to find a device of any type, but this often fails]

#### Returns

- An object representing the first photometer found
- None if the ports didn't yield a valid response
- None if there were not even any valid ports (suggesting a driver not being installed)

e.g.:

```
# sweeps ports 0 to 10 searching for a PR655
photom = findPhotometer(device='PR655')
print(photom.getLum())
if hasattr(photom, 'getSpectrum'):
    # can retrieve spectrum (e.g. a PR650)
    print(photom.getSpectrum())
```

## 8.10 psychopy.info - functions for getting information about the system

This module has tools for fetching data about the system or the current Python process. Such info can be useful for understanding the context in which an experiment was run.

**class** `psychopy.info.RuntimeInfo` (*author=None, version=None, win=None, refreshTest='grating', userProcsDetailed=False, verbose=False*)

Returns a snapshot of your configuration at run-time, for immediate or archival use.

Returns a dict-like object with info about PsychoPy, your experiment script, the system & OS, your window and monitor settings (if any), python & packages, and openGL.

If you want to skip testing the refresh rate, use 'refreshTest=None'

Example usage: see runtimeInfo.py in coder demos.

#### Author

- 2010 written by Jeremy Gray, input from Jon Peirce and Alex Holcombe

#### Parameters

**win** [*None*, *False*, *Window* instance] what window to use for refresh rate testing (if any) and settings. *None* -> temporary window using defaults; *False* -> no window created, used, nor profiled; a *Window()* instance you have already created



**author** [*None*, string] *None* = try to autodetect first `__author__` in `sys.argv[0]`; string = user-supplied author info (of an experiment)

**version** [*None*, string] *None* = try to autodetect first `__version__` in `sys.argv[0]`; string = user-supplied version info (of an experiment)

**verbose** : *False*, *True*; how much detail to assess

**refreshTest** [*None*, *False*, *True*, 'grating'] *True* or 'grating' = assess refresh average, median, and SD of 60 `win.flip()`s, using `visual.getMsPerFrame()` 'grating' = show a visual during the assessment; *True* = assess without a visual

**userProcsDetailed**: *False*, *True* get details about concurrent user's processes (command, process-ID)

**Returns** a flat dict (but with several groups based on key names):

**psychopy** [version, rush() availability] `psychopyVersion`, `psychopyHaveExtRush`, git branch and current commit hash if available

**experiment** [author, version, directory, name, current time-stamp,] SHA1 digest, VCS info (if any, svn or hg only), `experimentAuthor`, `experimentVersion`, ...

**system** [hostname, platform, user login, count of users,] user process info (count, cmd + pid), flagged processes `systemHostname`, `systemPlatform`, ...

**window** [(see output; many details about the refresh rate, window,] and monitor; units are noted) `windowWinType`, `windowWaitBlanking`, ... `windowRefreshTimeSD_ms`, ... `windowMonitor.<details>`, ...

**python** [version of python, versions of key packages] (wx, numpy, scipy, matplotlib, pyglet, pygame) `pythonVersion`, `pythonScipyVersion`, ...

**openGL** [version, vendor, rendering engine, plus info on whether] several extensions are present `openGLVersion`, ..., `openGLextGL_EXT_framebuffer_object`, ...

**\_\_setCurrentProcessInfo** (*verbose=False*, *userProcsDetailed=False*)

What other processes are currently active for this user?

**\_\_setExperimentInfo** (*author*, *version*, *verbose*)

Auto-detect `__author__` and `__version__` in `sys.argv[0]` (= the # users's script)

**\_\_setPythonInfo** ()

External python packages, python details

**\_\_setSystemInfo** ()

System info

**\_\_setWindowInfo** (*win*, *verbose=False*, *refreshTest='grating'*, *usingTempWin=True*)

Find and store info about the window: refresh rate, configuration info.

`psychopy.info.__getHgVersion` (*filename*)

Tries to discover the mercurial (hg) parent and id of a file.

Not thoroughly tested; untested on Windows Vista, Win 7, FreeBSD

#### Author

- 2010 written by Jeremy Gray

`psychopy.info.__getShalhexDigest` (*thing*, *isfile=False*)

Returns base64 / hex encoded sha1 digest of `str(thing)`, or of a file contents. Return *None* if a file is requested but no such file exists

#### Author

- 2010 Jeremy Gray; updated 2011 to be more explicit,
- 2012 to remove sha.new()

```
>>> _getSha1hexdigest('1')
'356a192b7913b04c54574d18c28d46e6395428ab'
>>> _getSha1hexdigest(1)
'356a192b7913b04c54574d18c28d46e6395428ab'
```

`psychopy.info._getSvnVersion(filename)`

Tries to discover the svn version (revision #) for a file.

Not thoroughly tested; untested on Windows Vista, Win 7, FreeBSD

### Author

- 2010 written by Jeremy Gray

`psychopy.info._getUserNameUID()`

Return user name, UID.

UID values can be used to infer admin-level: -1=undefined, 0=full admin/root, >499=assume non-admin/root (>999 on debian-based)

### Author

- 2010 written by Jeremy Gray

`psychopy.info.getMemoryUsage()`

Get the memory (RAM) currently used by this Python process, in M.

`psychopy.info.getRAM()`

Return system's physical RAM & available RAM, in M.

## 8.11 psychopy.iohub - ioHub event monitoring framework

ioHub monitors for device events in parallel with the PsychoPy experiment execution by running in a separate process than the main PsychoPy script. This means, for instance, that keyboard and mouse event timing is not quantized by the rate at which the `window.flip()` method is called.

ioHub reports device events to the PsychoPy experiment runtime as they occur. Optionally, events can be saved to a [HDF5](#) file.

All iohub events are timestamped using the PsychoPy global time base (`psychopy.core.getTime()`). Events can be accessed as a device independent event stream, or from a specific device of interest.

A comprehensive set of examples that each use at least one of the iohub devices is available in the `psychopy/demos/coder/iohub` folder.

---

**Note:** This documentation is in very early stages of being written. Comments and contributions are welcome.

---

### 8.11.1 Starting the psychopy.iohub Process

To use ioHub within your PsychoPy Coder experiment script, ioHub needs to be started at the start of the experiment script. The easiest way to do this is by calling the `launchHubServer` function.

## launchHubServer function

`psychopy.iohub.client.launchHubServer(**kwargs)`

Starts the ioHub Server subprocess, and return a `psychopy.iohub.client.ioHubConnection` object that is used to access enabled iohub device's events, get events, and control the ioHub process during the experiment.

By default (no kwargs specified), the ioHub server does not create an ioHub HDF5 file, events are available to the experiment program at runtime. The following Devices are enabled by default:

- Keyboard: named 'keyboard', with runtime event reporting enabled.
- Mouse: named 'mouse', with runtime event reporting enabled.
- Monitor: named 'monitor'.
- Experiment: named 'experiment'.

To customize how the ioHub Server is initialized when started, use one or more of the following keyword arguments when calling the function:

kwarg Name	Value Type	Description
experiment_code	str, <= 24 char	If experiment_code is provided, an ioHub HDF5 file will be created for the session.
session_code	str, <= 24 char	When specified, used as the name of the ioHub HDF5 file created for the session.
experiment_info	dict	Can be used to save the following experiment meta-data fields:
		<ul style="list-style-type: none"> <li>• code: str, &lt;= 24 char</li> <li>• title: str, &lt;= 48 char</li> <li>• description: str, &lt; 256 char</li> <li>• version: str, &lt;= 6 char</li> </ul>
session_info	dict	Can be used to save the following session metadata fields:
		<ul style="list-style-type: none"> <li>• code: str, &lt;= 24 char</li> <li>• name: str, &lt;= 48 char</li> <li>• comments: str, &lt; 256 char</li> <li>• user_variables: dict</li> </ul>
datastore_name	str	Used to provide an ioHub HDF5 file name different than the session_code.
psychopy_monitor_name	str	Provides the path of a PsychoPy Monitor Center config file. Information like display size is read and used to update the ioHub Display Device config.
iohub_config_name	str	Specifies the name of the iohub_config.yaml file that contains the ioHub Device list to be used by the ioHub Server. i.e. the 'device_list' section of the yaml file.
iohub.device.path Multiple Device's can be specified using separate kwarg entries.	dict	Add an ioHub Device by using the device class path as the key, and the device's configuration in a dict value.

## Examples

1. Wait for the 'q' key to be pressed:

```
from psychopy.iohub.client import launchHubServer

# Start the ioHub process. 'io' can now be used during the
# experiment to access iohub devices and read iohub device events.
io=launchHubServer()

print "Press any Key to Exit Example....."

# Wait until a keyboard event occurs
keys = io.devices.keyboard.waitForKeys(['q',])

print("Key press detected: {}".format(keys))
print("Exiting experiment....")

# Stop the ioHub Server
io.quit()
```

Please see the `psychopy/demos/coder/iohub/launchHub.py` demo for examples of different ways to use the `launchHubServer` function.

## ioHubConnection Class

The `psychopy.iohub.ioHubConnection` object returned from the `launchHubServer` function provides methods for controlling the iohub process and accessing iohub devices and events.

**class** `psychopy.iohub.client.ioHubConnection` (*object*)

`ioHubConnection` is responsible for creating, sending requests to, and reading replies from the ioHub Process. This class is also used to shut down and disconnect the ioHub Server process.

The `ioHubConnection` class is also used as the interface to any ioHub Device instances that have been created so that events from the device can be monitored. These device objects can be accessed via the `ioHubConnection` `.devices` attribute, providing 'dot name' access to enabled devices. Alternatively, the `.getDevice(name)` method can be used and will return `None` if the device name specified does not exist.

Using the `.devices` attribute is handy if you know the name of the device to be accessed and you are sure it is actually enabled on the ioHub Process.

An example of accessing a device using the `.devices` attribute:

```
# get the Mouse device, named mouse
mouse=hub.devices.mouse
mouse_position = mouse.getPosition()

print 'mouse position: ', mouse_position

# Returns something like:
# >> mouse position:  [-211.0, 371.0]
```

**getDevice** (*deviceName*)

Returns the `ioHubDeviceView` that has a matching name (based on the `device : name` property specified in the `ioHub_config.yaml` for the experiment). If no device with the given name is found, `None` is returned. Example, accessing a Keyboard device that was named 'kb'

```
keyboard = self.getDevice('kb')
kb_events= keyboard.getEvent()
```

This is the same as using the ‘natural naming’ approach supported by the .devices attribute, i.e:

```
keyboard = self.devices.kb
kb_events= keyboard.getEvent()
```

However the advantage of using `getDevice(device_name)` is that an exception is not created if you provide an invalid device name, or if the device is not enabled on the ioHub server; None is returned instead.

**Parameters** `deviceName` (*str*) – Name given to the ioHub Device to be returned

**Returns** The `ioHubDeviceView` instance for `deviceName`.

**getEvents** (*device\_label=None, as\_type='namedtuple'*)

Retrieve any events that have been collected by the ioHub Process from monitored devices since the last call to `getEvents()` or `clearEvents()`.

By default all events for all monitored devices are returned, with each event being represented as a named-tuple of all event attributes.

When events are retrieved from an event buffer, they are removed from that buffer as well.

If events are only needed from one device instead of all devices, providing a valid device name as the `device_label` argument will result in only events from that device being returned.

Events can be received in one of several object types by providing the optional `as_type` property to the method. Valid values for `as_type` are the following str values:

- ‘list’: Each event is a list of ordered attributes.
- ‘namedtuple’: Each event is converted to a namedtuple object.
- ‘dict’: Each event converted to a dict object.
- ‘object’: Each event is converted to a `DeviceEvent` subclass based on the event’s type.

**Parameters**

- **device\_label** (*str*) – Name of device to retrieve events for. If None ( the default ) returns device events from all devices.
- **as\_type** (*str*) – Returned event object type. Default: ‘namedtuple’.

**Returns** List of event objects; object type controlled by ‘as\_type’.

**Return type** `tuple`

**clearEvents** (*device\_label='all'*)

Clears unread events from the ioHub Server’s Event Buffer(s) so that unneeded events are not discarded.

If `device_label` is ‘all’, ( the default ), then events from both the ioHub *Global Event Buffer* and all *Device Event Buffer*’s are cleared.

If `device_label` is None then all events in the ioHub *Global Event Buffer* are cleared, but the *Device Event Buffers* are unaffected.

If `device_label` is a str giving a valid device name, then that *Device Event Buffer* is cleared, but the *Global Event Buffer* is not affected.

**Parameters** **device\_label** (*str*) – device name, ‘all’, or None

**Returns** None

**sendMessageEvent** (*text*, *category*=", *offset*=0.0, *sec\_time*=None)

Create and send an Experiment MessageEvent to the ioHub Server for storage in the ioDataStore hdf5 file.

---

**Note:** MessageEvents can be thought of as DeviceEvents from the virtual PsychoPy Process "Device".

---

#### Parameters

- **text** (*str*) – The text message for the message event. 128 char max.
- **category** (*str*) – A str grouping code for the message. Optional. 32 char max.
- **offset** (*float*) – Optional sec.msec offset applied to the message event time stamp. Default 0.
- **sec\_time** (*float*) – Absolute sec.msec time stamp for the message in. If not provided, or None, then the MessageEvent is time stamped when this method is called using the global timer (core.getTime()).

**Returns** True

**Return type** bool

**createTrialHandlerRecordTable** (*trials*, *cv\_order*=None)

Create a condition variable table in the ioHub data file based on the a psychopy TrialHandler. By doing so, the iohub data file can contain the DV and IV values used for each trial of an experiment session, along with all the iohub device events recorded by iohub during the session.

Example psychopy code usage:

```
# Load a trial handler and
# create an associated table in the iohub data file
#
from psychopy.data import TrialHandler, importConditions

exp_conditions=importConditions('trial_conditions.xlsx')
trials = TrialHandler(exp_conditions, 1)

# Inform the ioHub server about the TrialHandler
#
io.createTrialHandlerRecordTable(trials)

# Read a row of the trial handler for
# each trial of your experiment
#
for trial in trials:
    # do whatever...

# During the trial, trial variable values can be updated
#
trial['TRIAL_START']=flip_time

# At the end of each trial, before getting
# the next trial handler row, send the trial
# variable states to iohub so they can be stored for future
# reference.
#
io.addTrialHandlerRecord(trial)
```

**addTrialHandlerRecord** (*cv\_row*)

Adds the values from a TrialHandler row / record to the iohub data file for future data analysis use.

**Parameters** *cv\_row* –

**Returns** None

**getTime** ()

**Deprecated Method:** Use Computer.getTime instead. Remains here for testing time bases between processes only.

**setPriority** (*level='normal', disable\_gc=False*)

See Computer.setPriority documentation, where current process will be the iohub process.

**getPriority** ()

See Computer.getPriority documentation, where current process will be the iohub process.

**getProcessAffinity** ()

Returns the current **ioHub Process** affinity setting, as a list of ‘processor’ id’s (from 0 to `getSystemProcessorCount()-1`). A Process’s Affinity determines which CPU’s or CPU cores a process can run on. By default the ioHub Process can run on any CPU or CPU core.

This method is not supported on OS X at this time.

**Parameters** None –

**Returns**

A list of integer values between 0 and `Computer.getSystemProcessorCount()-1`, where values in the list indicate processing unit indexes that the ioHub process is able to run on.

**Return type** list

**setProcessAffinity** (*processor\_list*)

Sets the **ioHub Process** Affinity based on the value of *processor\_list*.

A Process’s Affinity determines which CPU’s or CPU cores a process can run on. By default the ioHub Process can run on any CPU or CPU core.

The *processor\_list* argument must be a list of ‘processor’ id’s; integers in the range of 0 to `Computer.processing_unit_count-1`, representing the processing unit indexes that the ioHub Server should be allowed to run on.

If *processor\_list* is given as an empty list, the ioHub Process will be able to run on any processing unit on the computer.

This method is not supported on OS X at this time.

**Parameters** *processor\_list* (*list*) – A list of integer values between 0 and `Computer.processing_unit_count-1`, where values in the list indicate processing unit indexes that the ioHub process is able to run on.

**Returns** None

**flushDataStoreFile** ()

Manually tell the ioDataStore to flush any events it has buffered in memory to disk.”.

**Parameters** None –

**Returns** None

**startCustomTasklet** (*task\_name, task\_class\_path, \*\*class\_kwargs*)

Instruct the iohub server to start running a custom tasklet given by *task\_class\_path*. It is important that the custom task does not block for any significant amount of time, or the processing of events by the iohub server will be negatively effected.

See the customtask.py demo for an example of how to make a long running task not block the rest of the iohub server.

**stopCustomTasklet** (*task\_name*)

Instruct the iohub server to stop the custom task that was previously started by calling `self.startCustomTasklet(...)`. *task\_name* identifies which custom task should be stopped and must match the *task\_name* of a previously started custom task.

**shutdown** ()

Tells the ioHub Server to close all ioHub Devices, the ioDataStore, and the connection monitor between the PsychoPy and ioHub Processes. Then end the server process itself.

**Parameters** None –

**Returns** None

**quit** ()

Same as the shutdown() method, but has same name as PsychoPy core.quit() so maybe easier to remember.

## 8.11.2 Supported Devices

psychopy.iohub supports several different types of devices, including Keyboards, Mice, and Eye Trackers.

Details for each device can be found in the following sections.

### Keyboard Device

The iohub Keyboard device provides methods to:

- Check for any new keyboard events that have occurred since the last time keyboard events were checked or cleared.
- Wait until a keyboard event occurs.
- Clear the device of any unread events.
- Get a list of all currently pressed keys.

**class** psychopy.iohub.client.keyboard.**Keyboard** (*ioclient, dev\_cls\_name, dev\_config*)

The Keyboard device provides access to KeyboardPress and KeyboardRelease events as well as the current keyboard state.

### Examples

1. Print all keyboard events received for 5 seconds:

```
from psychopy.iohub import launchHubServer
from psychopy.core import getTime

# Start the ioHub process. 'io' can now be used during the
# experiment to access iohub devices and read iohub device events.
io = launchHubServer()

keyboard = io.devices.keyboard

# Check for and print any Keyboard events received for 5 seconds.
stime = getTime()
```

(continues on next page)



(continued from previous page)

```
while getTime()-stime < 5.0:
    for e in keyboard.getEvents():
        print(e)

# Stop the ioHub Server
io.quit()
```

2. Wait for a keyboard press event (max of 5 seconds):

```
from psychopy.iohub import launchHubServer
from psychopy.core import getTime

# Start the ioHub process. 'io' can now be used during the
# experiment to access iohub devices and read iohub device events.
io = launchHubServer()

keyboard = io.devices.keyboard

# Wait for a key keypress event ( max wait of 5 seconds )
presses = keyboard.waitForPresses(maxWait=5.0)

print(presses)

# Stop the ioHub Server
io.quit()
```

**getKey** (*keys=None, chars=None, mods=None, duration=None, etype=None, clear=True*)

Return a list of any KeyboardPress or KeyboardRelease events that have occurred since the last time either:

- this method was called with the kwarg `clear=True` (default)
- the `keyboard.clear()` method was called.

Other than the ‘clear’ kwarg, any kwargs that are not None or an empty list are used to filter the possible events that can be returned. If multiple filter criteria are provided, only events that match **all** specified criteria are returned.

If no KeyboardEvent’s are found that match the filtering criteria, an empty tuple is returned.

Returned events are sorted by time.

#### Parameters

- **keys** – Include events where `.key` in `keys`.
- **chars** – Include events where `.char` in `chars`.
- **mods** – Include events where `.modifiers` include  $\geq 1$  `mods` element.
- **duration** – Include KeyboardRelease events where `.duration > duration` or `.duration < -(duration)`.
- **etype** – Include events that match `etype` of `Keyboard.KEY_PRESS` or `Keyboard.KEY_RELEASE`.
- **clear** – True (default) = clear returned events from event buffer, False = leave the keyboard event buffer unchanged.

**Returns** tuple of KeyboardEvent instances, or ()

**getPresses** (*keys=None, chars=None, mods=None, clear=True*)

See the `getKeys()` method documentation.

This method is identical, but only returns `KeyboardPress` events.

**getReleases** (*keys=None, chars=None, mods=None, duration=None, clear=True*)

See the `getKeys()` method documentation.

This method is identical, but only returns `KeyboardRelease` events.

### reporting

Specifies if the the keyboard device is reporting / recording events.

- **True**: keyboard events are being reported.
- **False**: keyboard events are not being reported.

By default, the `Keyboard` starts reporting events automatically when the `ioHub` process is started and continues to do so until the process is stopped.

This property can be used to read or set the device reporting state:

```
# Read the reporting state of the keyboard.
is_reporting_keyboard_event = keyboard.reporting

# Stop the keyboard from reporting any new events.
keyboard.reporting = False
```

### state

Returns all currently pressed keys as a dictionary of key – time values. The key is taken from the originating press event `.key` field. The time value is time of the key press event.

Note that any pressed, or active, modifier keys are included in the return value.

**Returns** dict

**waitForKey** (*maxWait=None, keys=None, chars=None, mods=None, duration=None, etype=None, clear=True, checkInterval=0.002*)

Blocks experiment execution until at least one matching `KeyboardEvent` occurs, or until `maxWait` seconds has passed since the method was called.

Keyboard events are filtered the same way as in the `getKeys()` method.

As soon as at least one matching `KeyboardEvent` occurs prior to `maxWait`, the matching events are returned as a tuple.

Returned events are sorted by time.

### Parameters

- **maxWait** – Maximum seconds method waits for  $\geq 1$  matching event. If  $\leq 0.0$ , method functions the same as `getKeys()`. If `None`, the methods blocks indefinitely.
- **keys** – Include events where `.key` in `keys`.
- **chars** – Include events where `.char` in `chars`.
- **mods** – Include events where `.modifiers` include  $\geq 1$  `mods` element.
- **duration** – Include `KeyboardRelease` events where `.duration > duration` or `.duration < -(duration)`.
- **etype** – Include events that match `etype` of `Keyboard.KEY_PRESS` or `Keyboard.KEY_RELEASE`.

- **clear** – True (default) = clear returned events from event buffer, False = leave the keyboard event buffer unchanged.
- **checkInterval** – The time between `getKeyEvents()` calls while waiting. The method sleeps between `getKeyEvents()` calls, up until `checkInterval*2.0` sec prior to the `maxWait`. After that time, keyboard events are constantly checked until the method times out.

**Returns** tuple of `KeyboardEvent` instances, or ()

**waitForPresses** (*maxWait=None, keys=None, chars=None, mods=None, duration=None, clear=True, checkInterval=0.002*)

See the `waitForKeys()` method documentation.

This method is identical, but only returns `KeyPress` events.

**waitForReleases** (*maxWait=None, keys=None, chars=None, mods=None, duration=None, clear=True, checkInterval=0.002*)

See the `waitForKeys()` method documentation.

This method is identical, but only returns `KeyboardRelease` events.

## Keyboard Events

The Keyboard device can return two types of events, which represent key press and key release actions on the keyboard.

### KeyPress Event

**class** `psychopy.iohub.client.keyboard.KeyboardPress` (*ioe\_array*)

An iohub Keyboard device key press event.

**char**

The unicode value of the keyboard event, if available. This field is only populated when the keyboard event results in a character that could be printable.

**Returns** unicode, “” if no char value is available for the event.

**device**

The `ioHubDeviceView` that is associated with the event, i.e. the iohub device view for the device that generated the event.

**Returns** `ioHubDeviceView`

**modifiers**

A list of any modifier keys that were pressed when this keyboard event occurred. Each element of the list contains a keyboard modifier string constant. Possible values are:

- ‘lctrl’, ‘rctrl’
- ‘lshift’, ‘rshift’
- ‘alt’, ‘ralt’ (labelled as ‘option’ keys on Apple Keyboards)
- ‘lcmd’, ‘rcmd’ (map to the ‘windows’ key(s) on Windows keyboards)
- ‘menu’
- ‘capslock’
- ‘numlock’
- ‘function’ (OS X only)

- ‘modhelp’ (OS X only)

If no modifiers were active when the event occurred, an empty list is returned.

**Returns** tuple

**time**

The time stamp of the event. Uses the same time base that is used by `psychopy.core.getTime()`

**Returns** float

**type**

The event type string constant.

**Returns** str

## KeyboardRelease Event

**class** `psychopy.iohub.client.keyboard.KeyboardRelease` (*ioe\_array*)

An iohub Keyboard device key release event.

**duration**

The duration (in seconds) of the key press. This is calculated by subtracting the current event.time from the associated keypress.time.

If no matching keypress event was reported prior to this event, then 0.0 is returned. This can happen, for example, when the key was pressed prior to psychopy starting to monitor the device. This condition can also happen when `keyboard.reset()` method is called between the press and release event times.

**Returns** float

**pressEventID**

The event.id of the associated press event.

The key press id is 0 if no associated KeyboardPress event was found. See the duration property documentation for details on when this can occur.

**Returns** unsigned int

**char**

The unicode value of the keyboard event, if available. This field is only populated when the keyboard event results in a character that could be printable.

**Returns** unicode, ‘’ if no char value is available for the event.

**device**

The `ioHubDeviceView` that is associated with the event, i.e. the iohub device view for the device that generated the event.

**Returns** `ioHubDeviceView`

**modifiers**

A list of any modifier keys that were pressed when this keyboard event occurred. Each element of the list contains a keyboard modifier string constant. Possible values are:

- ‘lctrl’, ‘rctrl’
- ‘lshift’, ‘rshift’
- ‘alt’, ‘ralt’ (labelled as ‘option’ keys on Apple Keyboards)
- ‘lcmd’, ‘rcmd’ (map to the ‘windows’ key(s) on Windows keyboards)
- ‘menu’

- 'capslock'
- 'numlock'
- 'function' (OS X only)
- 'modhelp' (OS X only)

If no modifiers were active when the event occurred, an empty list is returned.

**Returns** tuple

**time**

The time stamp of the event. Uses the same time base that is used by `psychopy.core.getTime()`

**Returns** float

**type**

The event type string constant.

**Returns** str

## The ioHub Mouse Device

**Platforms:** Windows, macOS, Linux

### Mouse Event Types

The Mouse device supports the following event types. Device events returned by `getEvents()` are automatically converted to either `namedtuple` or dictionary objects with the same attributes / keys as the associated event class attributes.

## ioHub Common Eye Tracker Interface

The iohub common eye tracker interface provides a consistent way to configure and collected data from several different eye tracker manufacturers, including GazePoint, SR Research, and Tobii.

### Supported Eye Trackers

The following eye trackers are currently supported by iohub.

#### Gazepoint

**Platforms:**

- Windows 7 / 10 only

**Required Python Version:**

- Python 3.6 +

**Supported Models:**

- Gazepoint GP3

## Additional Software Requirements

To use your Gazepoint GP3 during an experiment you must first start the Gazepoint Control software on the computer running PsychoPy.

## EyeTracker Class

**class** psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.**EyeTracker**

To start iohub with a Gazepoint GP3 eye tracker device, add a GP3 device to the device dictionary passed to launchHubServer or the experiment's iohub\_config.yaml:

```
eyetracker.hw.gazepoint.gp3.EyeTracker
```

---

**Note:** The Gazepoint control application **must** be running while using this interface.

---

## Examples

1. Start ioHub with Gazepoint GP3 device and run tracker calibration:

```
from psychopy.iohub import launchHubServer
from psychopy.core import getTime, wait

iohub_config = {'eyetracker.hw.gazepoint.gp3.EyeTracker':
    {'name': 'tracker', 'device_timer': {'interval': 0.005}}}

io = launchHubServer(**iohub_config)

# Get the eye tracker device.
tracker = io.devices.tracker

# run eyetracker calibration
r = tracker.runSetupProcedure()
```

2. Print all eye tracker events received for 2 seconds:

```
# Check for and print any eye tracker events received...
tracker.setRecordingState(True)

stime = getTime()
while getTime()-stime < 2.0:
    for e in tracker.getEvents():
        print(e)
```

3. Print current eye position for 5 seconds:

```
# Check for and print current eye position every 100 msec.
stime = getTime()
while getTime()-stime < 5.0:
    print(tracker.getPosition())
    wait(0.1)

tracker.setRecordingState(False)
```

(continues on next page)

(continued from previous page)

```
# Stop the ioHub Server
io.quit()
```

**clearEvents** (*event\_type=None, filter\_id=None, call\_proc\_events=True*)

Clears any DeviceEvents that have occurred since the last call to the device's `getEvents()`, or `clearEvents()` methods.

Note that calling `clearEvents()` at the device level only clears the given device's event buffer. The ioHub Process's Global Event Buffer is unchanged.

**Parameters** **None** –

**Returns** **None**

**enableEventReporting** (*enabled=True*)

`enableEventReporting` is functionally identical to the eye tracker device specific `setRecordingState` method.

**getConfiguration** ()

Retrieve the configuration settings information used to create the device instance. This will be the default settings for the device, found in `iohub.devices.<device_name>.default_<device_name>.yaml`, updated with any device settings provided via `launchHubServer(...)`.

Changing any values in the returned dictionary has no effect on the device state.

**Parameters** **None** –

**Returns** The dictionary of the device configuration settings used to create the device.

**Return type** (**dict**)

**getEvents** (*\*args, \*\*kwargs*)

Retrieve any DeviceEvents that have occurred since the last call to the device's `getEvents()` or `clearEvents()` methods.

Note that calling `getEvents()` at a device level does not change the Global Event Buffer's contents.

**Parameters**

- **event\_type\_id** (*int*) – If specified, provides the ioHub DeviceEvent ID for which events should be returned for. Events that have occurred but do not match the event ID specified are ignored. Event type ID's can be accessed via the `EventConstants` class; all available event types are class attributes of `EventConstants`.
- **clearEvents** (*int*) – Can be used to indicate if the events being returned should also be removed from the device event buffer. `True` (the default) indicates to remove events being returned. `False` results in events being left in the device event buffer.
- **asType** (*str*) – Optional kwarg giving the object type to return events as. Valid values are 'namedtuple' (the default), 'dict', 'list', or 'object'.

**Returns** New events that the ioHub has received since the last `getEvents()` or `clearEvents()` call to the device. Events are ordered by the ioHub time of each event, older event at index 0. The event object type is determined by the `asType` parameter passed to the method. By default a namedtuple object is returned for each event.

**Return type** (**list**)

**getLastGazePosition** ()

The `getLastGazePosition` method returns the most recent eye gaze position received from the Eye Tracker.

This is the position on the calibrated 2D surface that the eye tracker is reporting as the current eye position. The units are in the units in use by the ioHub Display device.

If binocular recording is being performed, the average position of both eyes is returned.

If no samples have been received from the eye tracker, or the eye tracker is not currently recording data, None is returned.

**Parameters** None –

**Returns**

If this method is not supported by the eye tracker interface, EyeTrackerConstants.EYETRACKER\_INTERFACE\_METHOD\_NOT\_SUPPORTED is returned.

None: If the eye tracker is not currently recording data or no eye samples have been received.

tuple: Latest (gaze\_x,gaze\_y) position of the eye(s)

**Return type** `int`

**getLastSample()**

The getLastSample method returns the most recent eye sample received from the Eye Tracker. The Eye Tracker must be in a recording state for a sample event to be returned, otherwise None is returned.

**Parameters** None –

**Returns**

If this method is not supported by the eye tracker interface, EyeTrackerConstants.FUNCTIONALITY\_NOT\_SUPPORTED is returned.

None: If the eye tracker is not currently recording data.

EyeSample: If the eye tracker is recording in a monocular tracking mode, the latest sample event of this event type is returned.

BinocularEyeSample: If the eye tracker is recording in a binocular tracking mode, the latest sample event of this event type is returned.

**Return type** `int`

**getPosition()**

The getPosition method is the same as the getLastGazePosition method, provided as a consistent cross device method to access the current screen position reported by a device.

See getLastGazePosition for further details.

**isRecordingEnabled()**

isRecordingEnabled returns the recording state from the eye tracking device.

**Parameters** None –

**Returns** True == the device is recording data; False == Recording is not occurring

**Return type** `bool`

**runSetupProcedure()**

runSetupProcedure opens the GP3 Calibration window.

**setRecordingState(recording)**

setRecordingState is used to start or stop the recording of data from the eye tracking device.

**Parameters** **recording** (`bool`) – if True, the eye tracker will start recording available eye data and sending it to the experiment program if data streaming was enabled for the device.



If recording == False, then the eye tracker stops recording eye data and streaming it to the experiment.

If the eye tracker is already recording, and setRecordingState(True) is called, the eye tracker will simply continue recording and the method call is a no-op. Likewise if the system has already stopped recording and setRecordingState(False) is called again.

**Parameters** **recording** (*bool*) – if True, the eye tracker will start recording data.; false = stop recording data.

**Return:****trackerTime** bool: the current recording state of the eye tracking device

**trackerSec** ()

Same as the GP3 implementation of trackerTime().

**trackerTime** ()

Current eye tracker time in the eye tracker's native time base. The GP3 system uses a sec.usec timebase based on the Windows QPC.

**Parameters** **None** –

**Returns** current native eye tracker time in sec.msec format.

**Return type** *float*

## Supported Event Types

The Gazepoint GP3 provides real-time access to binocular sample data. iohub creates a BinocularEyeSampleEvent for each sample received from the GP3.

The following fields of the BinocularEyeSample event are supported:

**class** psychopy.iohub.devices.eyetracker.**BinocularEyeSampleEvent** (*object*)

The BinocularEyeSampleEvent event represents the eye position and eye attribute data collected from one frame or reading of an eye tracker device that is recording both eyes of a participant.

Event Type ID: EventConstants.BINOCULAR\_EYE\_SAMPLE

Event Type String: 'BINOCULAR\_EYE\_SAMPLE'

**time**

time of event, in sec.msec format, using psychopy timebase.

**left\_gaze\_x**

The horizontal position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint LPOGX field.

**left\_gaze\_y**

The vertical position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint LPOGY field.

**left\_raw\_x**

The uncalibrated x position of the left eye in a device specific coordinate space. Uses Gazepoint LPCX field.

**left\_raw\_y**

The uncalibrated y position of the left eye in a device specific coordinate space. Uses Gazepoint LPCY field.

**left\_pupil\_measure\_1**

Left eye pupil diameter. (in camera pixels??). Uses Gazepoint LPD field.

**right\_gaze\_x**

The horizontal position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint RPOGX field.

**right\_gaze\_y**

The vertical position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint RPOGY field.

**right\_raw\_x**

The uncalibrated x position of the right eye in a device specific coordinate space. Uses Gazepoint RPCX field.

**right\_raw\_y**

The uncalibrated y position of the right eye in a device specific coordinate space. Uses Gazepoint RPCY field.

**right\_pupil\_measure\_1**

Right eye pupil diameter. (in camera pixels??). Uses Gazepoint RPD field.

**status**

Indicates if eye sample contains 'valid' data for left and right eyes. 0 = Eye sample is OK. 2 = Right eye data is likely invalid. 20 = Left eye data is likely invalid. 22 = Eye sample is likely invalid.

iohub also creates basic start and end fixation events by using Gazepoint FPOG\* fields. Identical / duplicate fixation events are created for the left and right eye.

**class** psychopy.iohub.devices.eyetracker.**FixationStartEvent** (*object*)

A FixationStartEvent is generated when the beginning of an eye fixation ( in very general terms, a period of relatively stable eye position ) is detected by the eye trackers sample parsing algorithms.

Event Type ID: EventConstants.FIXATION\_START

Event Type String: 'FIXATION\_START'

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**gaze\_x**

The calibrated horizontal eye position on the computer screen at the start of the fixation. Units are same as Display. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint FPOGX field.

**gaze\_y**

The calibrated horizontal eye position on the computer screen at the start of the fixation. Units are same as Display. Calibration must be done prior to reading (meaningful) gaze data. Uses Gazepoint FPOGY field.

**class** psychopy.iohub.devices.eyetracker.**FixationEndEvent** (*object*)

A FixationEndEvent is generated when the end of an eye fixation ( in very general terms, a period of relatively stable eye position ) is detected by the eye trackers sample parsing algorithms.

Event Type ID: EventConstants.FIXATION\_END

Event Type String: 'FIXATION\_END'

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

### average\_gaze\_x

Average calibrated horizontal eye position during the fixation, specified in Display Units. Uses Gazepoint FPOGX field.

### average\_gaze\_y

Average calibrated vertical eye position during the fixation, specified in Display Units. Uses Gazepoint FPOGY field.

### duration

Duration of the fixation in sec.msec format. Uses Gazepoint FPOGD field.

## Default Device Settings

```
eyetracker.hw.gazepoint.gp3.EyeTracker:
    # Indicates if the device should actually be loaded at experiment runtime.
    enable: True

    # The variable name of the device that will be used to access the ioHub Device_
    ↪class
    # during experiment run-time, via the devices.[name] attribute of the ioHub
    # connection or experiment runtime class.
    name: tracker

    # Should eye tracker events be saved to the ioHub DataStore file when the device
    # is recording data ?
    save_events: True

    # Should eye tracker events be sent to the Experiment process when the device
    # is recording data ?
    stream_events: True

    # How many eye events (including samples) should be saved in the ioHub event_
    ↪buffer before
    # old eye events start being replaced by new events. When the event buffer reaches
    # the maximum event length of the buffer defined here, older events will start to_
    ↪be dropped.
    event_buffer_length: 1024

    # The GP3 implementation of the common eye tracker interface supports the
    # BinocularEyeSampleEvent event type.
    monitor_event_types: [ BinocularEyeSampleEvent, FixationStartEvent,
    ↪FixationEndEvent]

    device_timer:
        interval: 0.005

    calibration:
        # target_duration is the number of sec.msec that a calibration point should
        # be displayed before moving onto the next point.
        # (Sets the GP3 CALIBRATE_TIMEOUT)
        target_duration: 1.25
        # target_delay specifies the target animation duration in sec.msec.
        # (Sets the GP3 CALIBRATE_DELAY)
        target_delay: 0.5

    # The model name of the device.
    model_name: GP3
```

(continues on next page)

(continued from previous page)

```
# The serial number of the GP3 device.
serial_number:

# manufacturer_name is used to store the name of the maker of the eye tracking
# device. This is for informational purposes only.
manufacturer_name: GazePoint
```

**Last Updated:** April, 2019

### SR Research

#### Platforms:

- Windows 7 / 10
- Linux (not tested)
- macOS (not tested)

#### Required Python Version:

- Python 3.6 +

#### Supported Models:

- EyeLink 1000
- EyeLink 1000 Remote (not tested)
- EyeLink 1000 Plus (not tested)

### Additional Software Requirements

The SR Research EyeLink implementation of the ioHub common eye tracker interface uses the pylink package written by SR Research. If using a PsychoPy3 standalone installation, this package should already be included.

If you are manually installing PsychoPy3, please install the appropriate version of pylink. Downloads are available to SR Research customers from their support website.

### EyeTracker Class

**class** psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.**EyeTracker**

The SR Research EyeLink implementation of the Common Eye Tracker Interface can be used by providing the following EyeTracker path as the device class in the iohub\_config.yaml device settings file:

```
eyetracker.hw.sr_research.eyelink
```

### Examples

1. Start ioHub with SR Research EyeLink 1000 and run tracker calibration:

```

from psychopy.iohub import launchHubServer
from psychopy.core import getTime, wait

iohub_config = {'eyetracker.hw.sr_research.eyelink.EyeTracker':
                {'name': 'tracker',
                 'model_name': 'EYELINK 1000 DESKTOP',
                 'runtime_settings': {'sampling_rate': 500,
                                     'track_eyes': 'RIGHT'}}
                }
io = launchHubServer(**iohub_config)

# Get the eye tracker device.
tracker = io.devices.tracker

# run eyetracker calibration
r = tracker.runSetupProcedure()
    
```

2. Print all eye tracker events received for 2 seconds:

```

# Check for and print any eye tracker events received...
tracker.setRecordingState(True)

stime = getTime()
while getTime()-stime < 2.0:
    for e in tracker.getEvents():
        print(e)
    
```

3. Print current eye position for 5 seconds:

```

# Check for and print current eye position every 100 msec.
stime = getTime()
while getTime()-stime < 5.0:
    print(tracker.getPosition())
    wait(0.1)

tracker.setRecordingState(False)

# Stop the ioHub Server
io.quit()
    
```

**clearEvents** (*event\_type=None, filter\_id=None, call\_proc\_events=True*)

Clears any DeviceEvents that have occurred since the last call to the device's `getEvents()`, or `clearEvents()` methods.

Note that calling `clearEvents()` at the device level only clears the given device's event buffer. The ioHub Process's Global Event Buffer is unchanged.

**Parameters** None –

**Returns** None

**enableEventReporting** (*enabled=True*)

`enableEventReporting` is the device type independent method that is equivalent to the EyeTracker specific `setRecordingState` method.

**getConfiguration** ()

Retrieve the configuration settings information used to create the device instance. This will the default set-

tings for the device, found in `iohub.devices.<device_name>.default_<device_name>.yaml`, updated with any device settings provided via `launchHubServer(...)`.

Changing any values in the returned dictionary has no effect on the device state.

**Parameters** `None` –

**Returns** The dictionary of the device configuration settings used to create the device.

**Return type** (`dict`)

**getEvents** (*\*args*, *\*\*kwargs*)

Retrieve any DeviceEvents that have occurred since the last call to the device's `getEvents()` or `clearEvents()` methods.

Note that calling `getEvents()` at a device level does not change the Global Event Buffer's contents.

**Parameters**

- **event\_type\_id** (*int*) – If specified, provides the ioHub DeviceEvent ID for which events should be returned for. Events that have occurred but do not match the event ID specified are ignored. Event type ID's can be accessed via the EventConstants class; all available event types are class attributes of EventConstants.
- **clearEvents** (*int*) – Can be used to indicate if the events being returned should also be removed from the device event buffer. True (the default) indicates to remove events being returned. False results in events being left in the device event buffer.
- **asType** (*str*) – Optional kwarg giving the object type to return events as. Valid values are 'namedtuple' (the default), 'dict', 'list', or 'object'.

**Returns** New events that the ioHub has received since the last `getEvents()` or `clearEvents()` call to the device. Events are ordered by the ioHub time of each event, older event at index 0. The event object type is determined by the `asType` parameter passed to the method. By default a namedtuple object is returned for each event.

**Return type** (`list`)

**getLastGazePosition** ()

`getLastGazePosition` returns the most recent x,y eye position, in Display device coordinate space, received by the ioHub server from the EyeLink device. In the case of binocular recording, and if both eyes are successfully being tracked, then the average of the two eye positions is returned. If the eye tracker is not recording or is not connected, then `None` is returned. The `getLastGazePosition` method returns the most recent eye gaze position retrieved from the eye tracker device. This is the position on the calibrated 2D surface that the eye tracker is reporting as the current eye position. The units are in the units in use by the Display device.

If binocular recording is being performed, the average position of both eyes is returned.

If no samples have been received from the eye tracker, or the eye tracker is not currently recording data, `None` is returned.

**Parameters** `None` –

**Returns**

If the eye tracker is not currently recording data or no eye samples have been received.

tuple: Latest (`gaze_x`, `gaze_y`) position of the eye(s)

**Return type** `None`

**getLastSample** ()

`getLastSample` returns the most recent EyeSampleEvent received from the EyeLink system. Any position

fields are in Display device coordinate space. If the eye tracker is not recording or is not connected, then None is returned.

**Parameters** None –

**Returns**

If the eye tracker is not currently recording data.

EyeSample: If the eye tracker is recording in a monocular tracking mode, the latest sample event of this event type is returned.

BinocularEyeSample: If the eye tracker is recording in a binocular tracking mode, the latest sample event of this event type is returned.

**Return type** None

**getPosition()**

The getPosition method is the same as the getLastGazePosition method, provided as a consistent cross device method to access the current screen position reported by a device.

See getLastGazePosition for further details.

**isRecordingEnabled()**

isRecordingEnabled returns True if the eye tracking device is currently connected and sending eye event data to the ioHub server. If the eye tracker is not recording, or is not connected to the ioHub server, False will be returned.

**Parameters** None –

**Returns** True == the device is recording data; False == Recording is not occurring

**Return type** bool

**runSetupProcedure()**

Start the EyeLink Camera Setup and Calibration procedure.

During the system setup, the following keys can be used on either the Host PC or Experiment PC to control the state of the setup procedure:

- C = Start Calibration
- V = Start Validation
- ENTER should be pressed at the end of a calibration or validation to accept the calibration, or in the case of validation, use the option drift correction that can be performed as part of the validation process in the EyeLink system.
- ESC can be pressed at any time to exit the current state of the setup procedure and return to the initial blank screen state.
- O = Exit the runSetupProcedure method and continue with the experiment.

**sendCommand(key, value=None)**

The sendCommand method sends an EyeLink command key and value to the EyeLink device. Any valid EyeLink command can be sent using this method. However, not that doing so is a device dependent operation, and will have no effect on other implementations of the Common EyeTracker Interface, unless the other eye tracking device happens to support the same command, value format.

If both key and value are provided, internally they are combined into a string of the form:

“key = value”

and this is sent to the EyeLink device. If only key is provided, it is assumed to include both the command name and any value or arguments required by the EyeLink all in the one argument, which is sent to the EyeLink device untouched.

**sendMessage** (*message\_contents*, *time\_offset=None*)

The sendMessage method sends a string (max length 128 characters) to the EyeLink device.

The message will be time stamped and inserted into the native EDF file, if one is being recorded. If no native EyeLink data file is being recorded, this method is a no-op.

**setRecordingState** (*recording*)

setRecordingState enables (recording=True) or disables (recording=False) the recording of eye data by the eye tracker and the sending of any eye data to the ioHub Server. The eye tracker must be connected to the ioHub Server by using the setConnectionState(True) method for recording to be possible.

**Parameters** **recording** (*bool*) – if True, the eye tracker will start recording data.; false = stop recording data.

**Returns** the current recording state of the eye tracking device

**Return type** *bool*

**trackerSec** ()

trackerSec returns the current EyeLink Host Application time in sec.msec format.

**trackerTime** ()

trackerTime returns the current EyeLink Host Application time in msec format as a long integer.

## Supported Event Types

The EyeLink implementation of the ioHub eye tracker interface supports monocular or binocular eye samples as well as fixation, saccade, and blink events.

## Eye Samples

**class** psychopy.iohub.devices.eyetracker.**MonocularEyeSampleEvent** (*object*)

A MonocularEyeSampleEvent represents the eye position and eye attribute data collected from one frame or reading of an eye tracker device that is recording from only one eye, or is recording from both eyes and averaging the binocular data.

Event Type ID: EventConstants.MONOCULAR\_EYE\_SAMPLE

Event Type String: 'MONOCULAR\_EYE\_SAMPLE'

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the sample. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**gaze\_x**

The horizontal position of the eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.

**gaze\_y**

The vertical position of the eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.



**angle\_x**

Horizontal eye angle.

**angle\_y**

Vertical eye angle.

**raw\_x**

The uncalibrated x position of the eye in a device specific coordinate space.

**raw\_y**

The uncalibrated y position of the eye in a device specific coordinate space.

**pupil\_measure\_1**

Pupil size. Use pupil\_measure1\_type to determine what type of pupil size data was being saved by the tracker.

**pupil\_measure1\_type**

Coordinate space type being used for left\_pupil\_measure\_1.

**ppd\_x**

Horizontal pixels per visual degree for this eye position as reported by the eye tracker.

**ppd\_y**

Vertical pixels per visual degree for this eye position as reported by the eye tracker.

**velocity\_x**

Horizontal velocity of the eye at the time of the sample; as reported by the eye tracker.

**velocity\_y**

Vertical velocity of the eye at the time of the sample; as reported by the eye tracker.

**velocity\_xy**

2D Velocity of the eye at the time of the sample; as reported by the eye tracker.

**status**

Indicates if eye sample contains 'valid' data. 0 = Eye sample is OK. 2 = Eye sample is invalid.

**class** psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent (*object*)

The BinocularEyeSampleEvent event represents the eye position and eye attribute data collected from one frame or reading of an eye tracker device that is recording both eyes of a participant.

Event Type ID: EventConstants.BINOCULAR\_EYE\_SAMPLE

Event Type String: 'BINOCULAR\_EYE\_SAMPLE'

**time**

time of event, in sec.msec format, using psychopy timebase.

**left\_gaze\_x**

The horizontal position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.

**left\_gaze\_y**

The vertical position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.

**left\_angle\_x**

The horizontal angle of left eye the relative to the head.

**left\_angle\_y**

The vertical angle of left eye the relative to the head.

**left\_raw\_x**

The uncalibrated x position of the left eye in a device specific coordinate space.

**left\_raw\_y**

The uncalibrated y position of the left eye in a device specific coordinate space.

**left\_pupil\_measure\_1**

Left eye pupil diameter.

**left\_pupil\_measure1\_type**

Coordinate space type being used for left\_pupil\_measure\_1.

**left\_ppd\_x**

Pixels per degree for left eye horizontal position as reported by the eye tracker. Display distance must be correctly set for this to be accurate at all.

**left\_ppd\_y**

Pixels per degree for left eye vertical position as reported by the eye tracker. Display distance must be correctly set for this to be accurate at all.

**left\_velocity\_x**

Horizontal velocity of the left eye at the time of the sample; as reported by the eye tracker.

**left\_velocity\_y**

Vertical velocity of the left eye at the time of the sample; as reported by the eye tracker.

**left\_velocity\_xy**

2D Velocity of the left eye at the time of the sample; as reported by the eye tracker.

**right\_gaze\_x**

The horizontal position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.

**right\_gaze\_y**

The vertical position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data.

**right\_angle\_x**

The horizontal angle of right eye the relative to the head.

**right\_angle\_y**

The vertical angle of right eye the relative to the head.

**right\_raw\_x**

The uncalibrated x position of the right eye in a device specific coordinate space.

**right\_raw\_y**

The uncalibrated y position of the right eye in a device specific coordinate space.

**right\_pupil\_measure\_1**

Right eye pupil diameter.

**right\_pupil\_measure1\_type**

Coordinate space type being used for right\_pupil\_measure1\_type.

**right\_ppd\_x**

Pixels per degree for right eye horizontal position as reported by the eye tracker. Display distance must be correctly set for this to be accurate at all.

**right\_ppd\_y**

Pixels per degree for right eye vertical position as reported by the eye tracker. Display distance must be correctly set for this to be accurate at all.

**right\_velocity\_x**

Horizontal velocity of the right eye at the time of the sample; as reported by the eye tracker.

**right\_velocity\_y**

Vertical velocity of the right eye at the time of the sample; as reported by the eye tracker.

**right\_velocity\_xy**

2D Velocity of the right eye at the time of the sample; as reported by the eye tracker.

**status**

Indicates if eye sample contains 'valid' data for left and right eyes. 0 = Eye sample is OK. 2 = Right eye data is likely invalid. 20 = Left eye data is likely invalid. 22 = Eye sample is likely invalid.

## Fixation Events

Successful eye tracker calibration must be performed prior to reading (meaningful) fixation event data.

**class** psychopy.iohub.devices.eyetracker.FixationStartEvent (*object*)

A FixationStartEvent is generated when the beginning of an eye fixation ( in very general terms, a period of relatively stable eye position ) is detected by the eye trackers sample parsing algorithms.

Event Type ID: EventConstants.FIXATION\_START

Event Type String: 'FIXATION\_START'

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**gaze\_x**

Horizontal gaze position at the start of the event, in Display Coordinate Type Units.

**gaze\_y**

Vertical gaze position at the start of the event, in Display Coordinate Type Units.

**angle\_x**

Horizontal eye angle at the start of the event.

**angle\_y**

Vertical eye angle at the start of the event.

**pupil\_measure\_1**

Pupil size. Use pupil\_measure1\_type to determine what type of pupil size data was being saved by the tracker.

**pupil\_measure1\_type**

EyeTrackerConstants.PUPIL\_AREA

**ppd\_x**

Horizontal pixels per degree at start of event.

**ppd\_y**

Vertical pixels per degree at start of event.

**velocity\_xy**

2D eye velocity at the start of the event.

**status**

Event status as reported by the eye tracker.

**class** psychopy.iohub.devices.eyetracker.**FixationEndEvent** (*object*)

A FixationEndEvent is generated when the end of an eye fixation ( in very general terms, a period of relatively stable eye position ) is detected by the eye trackers sample parsing algorithms.

Event Type ID: EventConstants.FIXATION\_END

Event Type String: 'FIXATION\_END'

**time**  
time of event, in sec.msec format, using psychopy timebase.

**eye**  
Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**duration**  
Duration of the event in sec.msec format.

**start\_gaze\_x**  
Horizontal gaze position at the start of the event, in Display Coordinate Type Units.

**start\_gaze\_y**  
Vertical gaze position at the start of the event, in Display Coordinate Type Units.

**start\_angle\_x**  
Horizontal eye angle at the start of the event.

**start\_angle\_y**  
Vertical eye angle at the start of the event.

**start\_pupil\_measure\_1**  
Pupil size at the start of the event.

**start\_pupil\_measure1\_type**  
EyeTrackerConstants.PUPIL\_AREA

**start\_ppd\_x**  
Horizontal pixels per degree at start of event.

**start\_ppd\_y**  
Vertical pixels per degree at start of event.

**start\_velocity\_xy**  
2D eye velocity at the start of the event.

**end\_gaze\_x**  
Horizontal gaze position at the end of the event, in Display Coordinate Type Units.

**end\_gaze\_y**  
Vertical gaze position at the end of the event, in Display Coordinate Type Units.

**end\_angle\_x**  
Horizontal eye angle at the end of the event.

**end\_angle\_y**  
Vertical eye angle at the end of the event.

**end\_pupil\_measure\_1**  
Pupil size at the end of the event.

**end\_pupil\_measure1\_type**  
EyeTrackerConstants.PUPIL\_AREA

**end\_ppd\_x**  
Horizontal pixels per degree at end of event.

**end\_ppd\_y**  
Vertical pixels per degree at end of event.

**end\_velocity\_xy**  
2D eye velocity at the end of the event.

**average\_gaze\_x**  
Average horizontal gaze position during the event, in Display Coordinate Type Units.

**average\_gaze\_y**  
Average vertical gaze position during the event, in Display Coordinate Type Units.

**average\_angle\_x**  
Average horizontal eye angle during the event,

**average\_angle\_y**  
Average vertical eye angle during the event,

**average\_pupil\_measure\_1**  
Average pupil size during the event.

**average\_pupil\_measure1\_type**  
EyeTrackerConstants.PUPIL\_AREA

**average\_velocity\_xy**  
Average 2D velocity of the eye during the event.

**peak\_velocity\_xy**  
Peak 2D velocity of the eye during the event.

**status**  
Event status as reported by the eye tracker.

## Saccade Events

Successful eye tracker calibration must be performed prior to reading (meaningful) saccade event data.

**class** psychopy.iohub.devices.eyetracker.**SaccadeStartEvent** (*object*)

**time**  
time of event, in sec.msec format, using psychopy timebase.

**eye**  
Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**gaze\_x**  
Horizontal gaze position at the start of the event, in Display Coordinate Type Units.

**gaze\_y**  
Vertical gaze position at the start of the event, in Display Coordinate Type Units.

**angle\_x**  
Horizontal eye angle at the start of the event.

**angle\_y**  
Vertical eye angle at the start of the event.

**pupil\_measure\_1**

Pupil size. Use pupil\_measure1\_type to determine what type of pupil size data was being saved by the tracker.

**pupil\_measure1\_type**

EyeTrackerConstants.PUPIL\_AREA

**ppd\_x**

Horizontal pixels per degree at start of event.

**ppd\_y**

Vertical pixels per degree at start of event.

**velocity\_xy**

2D eye velocity at the start of the event.

**status**

Event status as reported by the eye tracker.

**class** psychopy.iohub.devices.eyetracker.**SaccadeEndEvent** (*object*)

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**duration**

Duration of the event in sec.msec format.

**start\_gaze\_x**

Horizontal gaze position at the start of the event, in Display Coordinate Type Units.

**start\_gaze\_y**

Vertical gaze position at the start of the event, in Display Coordinate Type Units.

**start\_angle\_x**

Horizontal eye angle at the start of the event.

**start\_angle\_y**

Vertical eye angle at the start of the event.

**start\_pupil\_measure\_1**

Pupil size at the start of the event.

**start\_pupil\_measure1\_type**

EyeTrackerConstants.PUPIL\_AREA

**start\_ppd\_x**

Horizontal pixels per degree at start of event.

**start\_ppd\_y**

Vertical pixels per degree at start of event.

**start\_velocity\_xy**

2D eye velocity at the start of the event.

**end\_gaze\_x**

Horizontal gaze position at the end of the event, in Display Coordinate Type Units.

**end\_gaze\_y**  
Vertical gaze position at the end of the event, in Display Coordinate Type Units.

**end\_angle\_x**  
Horizontal eye angle at the end of the event.

**end\_angle\_y**  
Vertical eye angle at the end of the event.

**end\_pupil\_measure\_1**  
Pupil size at the end of the event.

**end\_pupil\_measure1\_type**  
EyeTrackerConstants.PUPIL\_AREA

**end\_ppd\_x**  
Horizontal pixels per degree at end of event.

**end\_ppd\_y**  
Vertical pixels per degree at end of event.

**end\_velocity\_xy**  
2D eye velocity at the end of the event.

**average\_gaze\_x**  
Average horizontal gaze position during the event, in Display Coordinate Type Units.

**average\_gaze\_y**  
Average vertical gaze position during the event, in Display Coordinate Type Units.

**average\_angle\_x**  
Average horizontal eye angle during the event,

**average\_angle\_y**  
Average vertical eye angle during the event,

**average\_pupil\_measure\_1**  
Average pupil size during the event.

**average\_pupil\_measure1\_type**  
EyeTrackerConstants.PUPIL\_AREA

**average\_velocity\_xy**  
Average 2D velocity of the eye during the event.

**peak\_velocity\_xy**  
Peak 2D velocity of the eye during the event.

**status**  
Event status as reported by the eye tracker.

## Blink Events

**class** psychopy.iohub.devices.eyetracker.**BlinkStartEvent** (*object*)

**time**  
time of event, in sec.msec format, using psychopy timebase.

**eye**  
Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**status**

Event status as reported by the eye tracker.

**class** psychopy.iohub.devices.eyetracker.**BlinkEndEvent** (*object*)

**time**

time of event, in sec.msec format, using psychopy timebase.

**eye**

Eye that generated the event. Either EyeTrackerConstants.LEFT\_EYE or EyeTrackerConstants.RIGHT\_EYE.

**duration**

Blink duration, in sec.msec format.

**status**

Event status as reported by the eye tracker.

## Default Device Settings

```
# This section includes all valid sr_research.eyelink.EyeTracker Device
# settings that can be specified in an iohub_config.yaml
# or in a Python dictionary form and passed to the launchHubServer
# method. Any device parameters not specified when the device class is
# created by the ioHub Process will be assigned the default value
# indicated here.
#
eyetracker.hw.sr_research.eyelink.EyeTracker:
    # name: The unique name to assign to the device instance created.
    #   The device is accessed from within the PsychoPy script
    #   using the name's value; therefore it must be a valid Python
    #   variable name as well.
    #
    name: tracker

    # enable: Specifies if the device should be enabled by ioHub and monitored
    #   for events.
    #   True = Enable the device on the ioHub Server Process
    #   False = Disable the device on the ioHub Server Process. No events for
    #   this device will be reported by the ioHub Server.
    #
    enable: True

    # saveEvents: *If* the ioHubDataStore is enabled for the experiment, then
    #   indicate if events for this device should be saved to the
    #   data_collection/keyboard event group in the hdf5 event file.
    #   True = Save events for this device to the ioDataStore.
    #   False = Do not save events for this device in the ioDataStore.
    #
    saveEvents: True

    # streamEvents: Indicate if events from this device should be made available
    #   during experiment runtime to the PsychoPy Process.
    #   True = Send events for this device to the PsychoPy Process in real-time.
    #   False = Do *not* send events for this device to the PsychoPy Process in real-
    ↪time.
```

(continues on next page)



(continued from previous page)

```

#
streamEvents: True

# auto_report_events: Indicate if events from this device should start being
# processed by the ioHub as soon as the device is loaded at the start of an
↪experiment,
# or if events should only start to be monitored on the device when a call to
↪the
# device's enableEventReporting method is made with a parameter value of True.
# True = Automatically start reporting events for this device when the
↪experiment starts.
# False = Do not start reporting events for this device until
↪enableEventReporting(True)
# is set for the device during experiment runtime.
#
auto_report_events: False

# event_buffer_length: Specify the maximum number of events (for each
# event type the device produces) that can be stored by the ioHub Server
# before each new event results in the oldest event of the same type being
# discarded from the ioHub device event buffer.
#
event_buffer_length: 1024

# device_timer: The EyeGaze EyeTracker class uses the polling method to
# check for new events received from the EyeTracker device. device_timer.
↪interval
# specifies the sec.msec time between device polls. 0.004 = 4 msec, so the
↪device will
# be polled at a maximum rate of 250 Hz. This polling rate is a 'target' value,
# and may not always be achieved depending on your computer specifications and
↪the
# number and type of other devices being used. This can be checked by reviewing
↪the
# confidence_interval column of any of the eye event tables saved to the
↪DataStore
#
device_timer:
    interval: 0.001

# monitor_event_types: The eyelink implementation of the common eye tracker
# interface supports the following event types. If you would like to
# exclude certain events from being saved or streamed during runtime,
# remove them from the list below.
#
monitor_event_types: [ MonocularEyeSampleEvent, BinocularEyeSampleEvent,
↪FixationStartEvent, FixationEndEvent, SaccadeStartEvent, SaccadeEndEvent,
↪BlinkStartEvent, BlinkEndEvent]

calibration:
    # IMPORTANT: Note that while the gaze position data provided by ioHub
    # will be in the Display's coordinate system, the EyeLink internally
    # always uses a 0,0 pixel_width, pixel_height coordinate system
    # since internally calibration point positions are given as integers,
    # so if the actual display coordinate system was passed to EyeLink,
    # coordinate types like deg and norm would become very coarse in
    # possible target locations during calibration.
    
```

(continues on next page)

(continued from previous page)

```

# type: sr_research.eyelink.EyeTracker supports the following
#   calibration types:
#   THREE_POINTS, FIVE_POINTS, NINE_POINTS, THIRTEEN_POINTS
type: NINE_POINTS

# auto_pace: If True, the eye tracker will automatically progress from
# one calibration point to the next. If False, a manual key or button press
# is needed to progress to the next point.
#
auto_pace: True

# pacing_speed: The number of sec.msec that a calibration point should
# be displayed before moving onto the next point when auto_pace is set to_
→true.
# If auto_pace is False, pacing_speed is ignored.
#
pacing_speed: 1.5

# screen_background_color: Specifies the r,g,b,a background color to
# set the calibration, validation, etc, screens to. Each element of the_
→color
# should be a value between 0 and 255. 0 == black, 255 == white. In general
# the last value of the color list (alpha) can be left at 255, indicating
# the color not mixed with the background color at all.
screen_background_color: [128,128,128,255]

# target_type: Defines what form of calibration graphic should be used
# during calibration, validation, etc. modes. sr_research.eyelink.EyeTracker
# supports the CIRCLE_TARGET type.
#
target_type: CIRCLE_TARGET

# target_attributes: The asociated target attributes must be supplied
# for the given target_type. If target type attribute sections are provided
# for target types other than the entry associated with the specified
# target_type value they will simple be ignored.
#
target_attributes:
    # outer_diameter and inner_diameter are specified in pixels
    outer_diameter: 33
    inner_diameter: 6
    outer_color: [255,255,255,255]
    inner_color: [0,0,0,255]

# network_settings: Specify the Host computer IP address. Normally
# leaving it set to the default value is fine.
#
network_settings: 100.1.1.1

# default_native_data_file_name: The sr_research.eyelink.EyeTracker supports
# saving a native eye tracker edf data file, the
# default_native_data_file_name value is used to set the default name for
# the file that will be saved, not including the .edf file type extension.
#
default_native_data_file_name: et_data

```

(continues on next page)

(continued from previous page)

```
# simulation_mode: Indicate if the eye tracker should provide mouse simulated
# eye data instead of sending eye data based on a participants actual
# eye movements.
#
simulation_mode: False

# enable_interface_without_connection: Specifying if the ioHub Device
# should be enabled without truly connecting to the underlying eye tracking
# hardware. If True, ioHub EyeTracker methods can be called but will
# provide no-op results and no eye data will be received by the ioHub Server.
# This mode can be useful for working on aspects of an eye tracking experiment.
↳when the
# actual eye tracking device is not available, for example stimulus presentation
# or other non eye tracker dependent experiment functionality.
#
enable_interface_without_connection: False

runtime_settings:
# sampling_rate: Specify the desired sampling rate to use. Actual
# sample rates depend on the model being used.
# Overall, possible rates are 250, 500, 1000, and 2000 Hz.
#
sampling_rate: 250

# track_eyes: Which eye(s) should be tracked?
# Supported Values: LEFT_EYE, RIGHT_EYE, BINOCULAR
#
track_eyes: RIGHT_EYE

# sample_filtering: Defines the native eye tracker filtering level to be
# applied to the sample event data before it is sent to the specified data.
↳stream.
# The sample filter section can contain multiple key : value entries if
# the tracker implementation supports it, where each key is a sample stream.
↳type,
# and each value is the associated filter level for that sample data stream.
# sr_research.eyelink.EyeTracker supported stream types are:
# FILTER_ALL, FILTER_FILE, FILTER_ONLINE
# Supported sr_research.eyelink.EyeTracker filter levels are:
# FILTER_LEVEL_OFF, FILTER_LEVEL_1, FILTER_LEVEL_2
# Note that if FILTER_ALL is specified, then other sample data stream.
↳values are
# ignored. If FILTER_ALL is not provided, ensure to specify the setting
# for both FILTER_FILE and FILTER_ONLINE as in this case if either is not.
↳provided then
# the missing filter type will have filter level set to FILTER_OFF.
#
sample_filtering:
    FILTER_ALL: FILTER_LEVEL_OFF

vog_settings:
# pupil_measure_types: sr_research.eyelink.EyeTracker supports one
# pupil_measure_type parameter that is used for all eyes being tracked.
# Valid options are:
# PUPIL_AREA, PUPIL_DIAMETER,
#
pupil_measure_types: PUPIL_AREA
```

(continues on next page)

(continued from previous page)

```

# tracking_mode: Define whether the eye tracker should run in a pupil only
# mode or run in a pupil-cr mode. Valid options are:
#     PUPIL_CR_TRACKING, PUPIL_ONLY_TRACKING
# Depending on other settings on the eyelink Host and the model and mode_
↳ of
# eye tracker being used, this parameter may not be able to set the
# specified tracking mode. Check the mode listed on the camera setup
# screen of the Host PC after the experiment has started to confirm if
# the requested tracking mode was enabled. IMPORTANT: only use
# PUPIL_ONLY_TRACKING mode if using an EyeLink II system, or using
# the EyeLink 1000 is a head **fixed** setup. Any head movement
# when using PUPIL_ONLY_TRACKING will result in eye position signal_
↳ drift.
#
tracking_mode: PUPIL_CR_TRACKING

# pupil_center_algorithm: The pupil_center_algorithm defines what
# type of image processing approach should
# be used to determine the pupil center during image processing.
# Valid possible values are for eyetracker.hw.sr_research.eyelink.
↳ EyeTracker are:
#     ELLIPSE_FIT, or CENTROID_FIT
#
pupil_center_algorithm: ELLIPSE_FIT

# model_name: The model_name setting allows the definition of the eye tracker_
↳ model being used.
# For the eyelink implementation, valid values are:
#     'EYELINK 1000 DESKTOP', 'EYELINK 1000 TOWER', 'EYELINK 1000 REMOTE',
#     'EYELINK 1000 LONG RANGE', 'EYELINK 2'
model_name: EYELINK 1000 DESKTOP

# manufacturer_name: manufacturer_name is used to store the name of the
# maker of the eye tracking device. This is for informational purposes only.
#
manufacturer_name: SR Research Ltd.

# model_name: The below parameters are not used by the EyeGaze eye tracker
# implementation, so they can be left as is, or filled out for FYI only.
#
model_name: N/A

# serial_number: The serial number for the specific instance of device used
# can be specified here. It is not used by the ioHub, so is FYI only.
#
serial_number: N/A

# manufacture_date: The date of manufacturer of the device
# can be specified here. It is not used by the ioHub,
# so is FYI only.
#
manufacture_date: DD-MM-YYYY

# hardware_version: The device's hardware version can be specified here.
# It is not used by the ioHub, so is FYI only.
#

```

(continues on next page)

(continued from previous page)

```
hardware_version: N/A

# firmware_version: If the device has firmware, its revision number
#   can be indicated here. It is not used by the ioHub, so is FYI only.
#
firmware_version: N/A

# model_number: The device model number can be specified here.
#   It is not used by the ioHub, so is FYI only.
#
model_number: N/A

# software_version: The device driver and / or SDK software version number.
#   This field is not used by ioHub, so is FYI only.
software_version: N/A

# device_number: The device number to assign to the Analog Input device.
#   device_number is not used by this device type.
#
device_number: 0
```

**Last Updated:** April, 2019

## Tobii

### Platforms:

- Windows 7 / 10
- Linux (not tested)
- macOS (not tested)

### Required Python Version:

- Python 3.6

### Supported Models:

Any Tobii model that supports screen based calibration and can use the tobii\_research API. Tested using a Tobii T120.

## Additional Software Requirements

To use the ioHub interface for Tobii, the Tobii Pro SDK must be installed in your Python environment. If a recent standalone installation of PsychoPy3, this package should already be included.

To install tobii\_research type:

```
pip install tobii_research
```

## EyeTracker Class

**class** psychopy.iohub.devices.eyetracker.hw.tobii.**EyeTracker**

To start ioHub with a Tobii eye tracker device, add the Tobii device to the dictionary passed to launchHubServer

or the experiment's `iohub_config.yaml`:

```
eyetracker.hw.tobii.EyeTracker
```

## Examples

1. Start ioHub with a Tobii device and run tracker calibration:

```
from psychopy.iohub import launchHubServer
from psychopy.core import getTime, wait

iohub_config = {'eyetracker.hw.tobii.EyeTracker':
    {'name': 'tracker', 'runtime_settings': {'sampling_rate': 120}}}

io = launchHubServer(**iohub_config)

# Get the eye tracker device.
tracker = io.devices.tracker

# run eyetracker calibration
r = tracker.runSetupProcedure()
```

2. Print all eye tracker events received for 2 seconds:

```
# Check for and print any eye tracker events received...
tracker.setRecordingState(True)

stime = getTime()
while getTime()-stime < 2.0:
    for e in tracker.getEvents():
        print(e)
```

3. Print current eye position for 5 seconds:

```
# Check for and print current eye position every 100 msec.
stime = getTime()
while getTime()-stime < 5.0:
    print(tracker.getPosition())
    wait(0.1)

tracker.setRecordingState(False)

# Stop the ioHub Server
io.quit()
```

**clearEvents** (*event\_type=None, filter\_id=None, call\_proc\_events=True*)

Clears any DeviceEvents that have occurred since the last call to the device's `getEvents()`, or `clearEvents()` methods.

Note that calling `clearEvents()` at the device level only clears the given device's event buffer. The ioHub Process's Global Event Buffer is unchanged.

**Parameters** None –

**Returns** None

**enableEventReporting** (*enabled=True*)

enableEventReporting is functionally identical to the eye tracker device specific enableEventReporting method.

**getConfiguration** ()

Retrieve the configuration settings information used to create the device instance. This will be the default settings for the device, found in `iohub.devices.<device_name>.default_<device_name>.yaml`, updated with any device settings provided via `launchHubServer(...)`.

Changing any values in the returned dictionary has no effect on the device state.

**Parameters** None –

**Returns** The dictionary of the device configuration settings used to create the device.

**Return type** (dict)

**getEvents** (\*args, \*\*kwargs)

Retrieve any DeviceEvents that have occurred since the last call to the device's getEvents() or clearEvents() methods.

Note that calling getEvents() at a device level does not change the Global Event Buffer's contents.

**Parameters**

- **event\_type\_id** (*int*) – If specified, provides the ioHub DeviceEvent ID for which events should be returned for. Events that have occurred but do not match the event ID specified are ignored. Event type ID's can be accessed via the EventConstants class; all available event types are class attributes of EventConstants.
- **clearEvents** (*int*) – Can be used to indicate if the events being returned should also be removed from the device event buffer. True (the default) indicates to remove events being returned. False results in events being left in the device event buffer.
- **asType** (*str*) – Optional kwarg giving the object type to return events as. Valid values are 'namedtuple' (the default), 'dict', 'list', or 'object'.

**Returns** New events that the ioHub has received since the last getEvents() or clearEvents() call to the device. Events are ordered by the ioHub time of each event, older event at index 0. The event object type is determined by the asType parameter passed to the method. By default a namedtuple object is returned for each event.

**Return type** (list)

**getLastGazePosition** ()

Returns the latest 2D eye gaze position retrieved from the Tobii device. This represents where the eye tracker is reporting each eye gaze vector is intersecting the calibrated surface.

In general, the y or vertical component of each eyes gaze position should be the same value, since in typical user populations the two eyes are yoked vertically when they move. Therefore any difference between the two eyes in the y dimension is likely due to eye tracker error.

Differences between the x, or horizontal component of the gaze position, indicate that the participant is being reported as looking behind or in front of the calibrated plane. When a user is looking at the calibration surface, the x component of the two eyes gaze position should be the same. Differences between the x value for each eye either indicates that the user is not focussing at the calibrated depth, or that there is error in the eye data.

The above remarks are true for any eye tracker in general.

The getLastGazePosition method returns the most recent eye gaze position retrieved from the eye tracker device. This is the position on the calibrated 2D surface that the eye tracker is reporting as the current eye position. The units are in the units in use by the Display device.

If binocular recording is being performed, the average position of both eyes is returned.

If no samples have been received from the eye tracker, or the eye tracker is not currently recording data, None is returned.

**Parameters** None –

**Returns**

If the eye tracker is not currently recording data or no eye samples have been received.

tuple: Latest (gaze\_x,gaze\_y) position of the eye(s)

**Return type** None

**getLastSample()**

Returns the latest sample retrieved from the Tobii device. The Tobii system always using the BinocularSample Event type.

**Parameters** None –

**Returns**

If the eye tracker is not currently recording data.

EyeSample: If the eye tracker is recording in a monocular tracking mode, the latest sample event of this event type is returned.

BinocularEyeSample: If the eye tracker is recording in a binocular tracking mode, the latest sample event of this event type is returned.

**Return type** None

**getPosition()**

The getPosition method is the same as the getLastGazePosition method, provided as a consistent cross device method to access the current screen position reported by a device.

See getLastGazePosition for further details.

**isRecordingEnabled()**

isRecordingEnabled returns the recording state from the eye tracking device.

**Parameters** None –

**Returns** True == the device is recording data; False == Recording is not occurring

**Return type** bool

**runSetupProcedure()**

runSetupProcedure performs a calibration routine for the Tobii eye tracking system.

**setRecordingState(recording)**

setRecordingState is used to start or stop the recording of data from the eye tracking device.

**Parameters** **recording** (bool) – if True, the eye tracker will start recording available eye data and sending it to the experiment program if data streaming was enabled for the device.

If recording == False, then the eye tracker stops recording eye data and streaming it to the experiment.

If the eye tracker is already recording, and setRecordingState(True) is called, the eye tracker will simply continue recording and the method call is a no-op. Likewise if the system has already stopped recording and setRecordingState(False) is called again.

**Parameters** **recording** (bool) – if True, the eye tracker will start recording data.; false = stop recording data.



**Returns** the current recording state of the eye tracking device

**Return type** `bool`

## Supported Event Types

tobii\_research provides real-time access to binocular sample data.

The following fields of the ioHub BinocularEyeSample event are supported:

**class** `psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent` (*object*)

The BinocularEyeSample event represents the eye position and eye attribute data collected from one frame or reading of an eye tracker device that is recording both eyes of a participant.

Event Type ID: `EventConstants.BINOCULAR_EYE_SAMPLE`

Event Type String: `'BINOCULAR_EYE_SAMPLE'`

**time**

time of event, in sec.msec format, using psychopy timebase.

**left\_gaze\_x**

The horizontal position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses tobii\_research gaze data `'left_gaze_point_on_display_area'[0]` field.

**left\_gaze\_y**

The vertical position of the left eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses tobii\_research gaze data `'left_gaze_point_on_display_area'[1]` field.

**left\_eye\_cam\_x**

The left x eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data `'left_gaze_origin_in_trackbox_coordinate_system'[0]` field.

**left\_eye\_cam\_y**

The left y eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data `'left_gaze_origin_in_trackbox_coordinate_system'[1]` field.

**left\_eye\_cam\_z**

The left z eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data `'left_gaze_origin_in_trackbox_coordinate_system'[2]` field.

**left\_pupil\_measure\_1**

Left eye pupil diameter in mm. Uses tobii\_research gaze data `'left_pupil_diameter'` field.

**right\_gaze\_x**

The horizontal position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses tobii\_research gaze data `'right_gaze_point_on_display_area'[0]` field.

**right\_gaze\_y**

The vertical position of the right eye on the computer screen, in Display Coordinate Type Units. Calibration must be done prior to reading (meaningful) gaze data. Uses tobii\_research gaze data `'right_gaze_point_on_display_area'[1]` field.

**right\_eye\_cam\_x**

The right x eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data `'right_gaze_origin_in_trackbox_coordinate_system'[0]` field.

#### **right\_eye\_cam\_y**

The right y eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data 'right\_gaze\_origin\_in\_trackbox\_coordinate\_system'[1] field.

#### **right\_eye\_cam\_z**

The right z eye position in the eye trackers 3D coordinate space. Uses tobii\_research gaze data 'right\_gaze\_origin\_in\_trackbox\_coordinate\_system'[2] field.

#### **right\_pupil\_measure\_1**

Right eye pupil diameter in mm. Uses tobii\_research gaze data 'right\_pupil\_diameter' field.

#### **status**

Indicates if eye sample contains 'valid' data for left and right eyes. 0 = Eye sample is OK. 2 = Right eye data is likely invalid. 20 = Left eye data is likely invalid. 22 = Eye sample is likely invalid.

### Default Device Settings

```
eyetracker.hw.tobii.EyeTracker:
    # Indicates if the device should actually be loaded at experiment runtime.
    enable: True

    # The variable name of the device that will be used to access the ioHub Device_
    ↪class
    # during experiment run-time, via the devices.[name] attribute of the ioHub
    # connection or experiment runtime class.
    name: tracker

    # Should eye tracker events be saved to the ioHub DataStore file when the device
    # is recording data ?
    save_events: True

    # Should eye tracker events be sent to the Experiment process when the device
    # is recording data ?
    stream_events: True

    # How many eye events (including samples) should be saved in the ioHub event_
    ↪buffer before
    # old eye events start being replaced by new events. When the event buffer reaches
    # the maximum event length of the buffer defined here, older events will start to_
    ↪be dropped.
    event_buffer_length: 1024

    # The Tobii implementation of the common eye tracker interface supports the
    # BinocularEyeSampleEvent event type.
    monitor_event_types: [ BinocularEyeSampleEvent, ]

    # The model name of the Tobii device that you wish to connect to can be specified_
    ↪here,
    # and only Tobii systems matching that model name will be considered as possible_
    ↪candidates for connection.
    # If you only have one Tobii system connected to the computer, this field can_
    ↪just be left empty.
    model_name:

    # The serial number of the Tobii device that you wish to connect to can be_
    ↪specified here,
    # and only the Tobii system matching that serial number will be connected to, if_
    ↪found.
```

(continues on next page)

(continued from previous page)

```
# If you only have one Tobii system connected to the computer, this field can_
→ just be left empty,
# in which case the first Tobii device found will be connected to.
serial_number:

calibration:
    # Should the PsychoPy Window created by the PsychoPy Process be minimized
    # before displaying the Calibration Window created by the ioHub Process.
    #
    minimize_psychopy_win: False

    # The Tobii ioHub Common Eye Tracker Interface currently support
    # a 3, 5 and 9 point calibration mode.
    # THREE_POINTS, FIVE_POINTS, NINE_POINTS
    #
    type: NINE_POINTS

    # Should the target positions be randomized?
    #
    randomize: True

    # auto_pace can be True or False. If True, the eye tracker will
    # automatically progress from one calibration point to the next.
    # If False, a manual key or button press is needed to progress to
    # the next point.
    #
    auto_pace: True

    # pacing_speed is the number of sec.msec that a calibration point should
    # be displayed before moving onto the next point when auto_pace is set to_
→ true.
    # If auto_pace is False, pacing_speed is ignored.
    #
    pacing_speed: 1.5

    # screen_background_color specifies the r,g,b background color to
    # set the calibration, validation, etc, screens to. Each element of the color
    # should be a value between 0 and 255. 0 == black, 255 == white.
    #
    screen_background_color: [128, 128, 128]

    # Target type defines what form of calibration graphic should be used
    # during calibration, validation, etc. modes.
    # Currently the Tobii implementation supports the following
    # target type: CIRCLE_TARGET.
    # To do: Add support for other types, etc.
    #
    target_type: CIRCLE_TARGET

    # The associated target attribute properties can be supplied
    # for the given target_type.
    target_attributes:
        # CIRCLE_TARGET is drawn using two PsychoPy
        # Circle Stim. The _outer_ circle is drawn first, and should be
        # be larger than the _inner_ circle, which is drawn on top of the
        # outer circle. The target_attributes starting with 'outer_' define
        # how the outer circle of the calibration targets should be drawn.
```

(continues on next page)

(continued from previous page)

```

# The target_attributes starting with 'inner_' define
# how the inner circle of the calibration targets should be drawn.
#
# outer_diameter: The size of the outer circle of the calibration target
#
outer_diameter: 35
# outer_stroke_width: The thickness of the outer circle edge.
#
outer_stroke_width: 2
# outer_fill_color: RGB255 color to use to fill the outer circle.
#
outer_fill_color: [128,128,128]
# outer_line_color: RGB255 color to used for the outer circle edge.
#
outer_line_color: [255,255,255]
# inner_diameter: The size of the inner circle calibration target
#
inner_diameter: 7
# inner_stroke_width: The thickness of the inner circle edge.
#
inner_stroke_width: 1
# inner_fill_color: RGB255 color to use to fill the inner circle.
#
inner_fill_color: [0,0,0]
# inner_line_color: RGB255 color to used for the inner circle edge.
#
inner_line_color: [0,0,0]
# The Tobii Calibration routine supports using moving target graphics.
# The following parameters control target movement (if any).
#
animate:
    # enable: True if the calibration target should be animated.
    # False specifies that the calibration targets could just jump
    # from one calibration position to another.
    #
    enable: True
    # movement_velocity: The velocity that a calibration target
    # graphic should use when gliding from one calibration
    # point to another. Always in pixels / second.
    #
    movement_velocity: 600.0
    # expansion_ratio: The outer circle of the calibration target
    # can expand (and contract) when displayed at each position.
    # expansion_ratio gives the largest size of the outer circle
    # as a ratio of the outer_diameter length. For example,
    # if outer_diameter = 30, and expansion_ratio = 2.0, then
    # the outer circle of each calibration point will expand out
    # to 60 pixels. Set expansion_ratio to 1.0 for no expansion.
    #
    expansion_ratio: 3.0
    # expansion_speed: The rate at which the outer circle
    # graphic should expand. Always in pixels / second.
    #
    expansion_speed: 30.0
    # contract_only: If the calibration target should expand from
    # the outer circle initial diameter to the larger diameter
    # and then contract back to the original diameter, set

```

(continues on next page)

(continued from previous page)

```
        # contract_only to False. To only have the outer circle target
        # go from an expanded state to the smaller size, set this to True.
        #
        contract_only: True

runtime_settings:
    # The supported sampling rates for Tobii are model dependent.
    # Using a default of 60 Hz, with the assumption it is the most common.
    sampling_rate: 60

    # Tobii implementation supports BINOCULAR tracking mode only.
    track_eyes: BINOCULAR

    # manufacturer_name is used to store the name of the maker of the eye tracking
    # device. This is for informational purposes only.
    manufacturer_name: Tobii Technology
```

**Last Updated:** April 2019

### 8.11.3 psychopy.iohub Specific Requirements

#### Computer Specifications

The design / requirements of your experiment itself can obviously influence what the minimum computer specification should be to provide good timing / performance.

The dual process design when running using psychopy.iohub also influences the minimum suggested specifications as follows:

- Intel i5 or i7 CPU. A minimum of **two** CPU cores is needed.
- 8 GB of RAM
- Windows 7 +, OS X 10.7.5 +, or Linux Kernel 2.6 +

Please see the [Recommended hardware](#) section for further information that applies to PsychoPy in general.

#### Usage Considerations

When using psychopy.iohub, the following constraints should be noted:

1. The pygame graphics backend must be used; pygame is not supported.
2. ioHub devices that report position data use the unit type defined by the PsychoPy Window. However, position data is reported using the full screen area and size the window was created in. Therefore, for accurate window position reporting, the PsychoPy window must be made full screen.
3. On macOS, Assistive Device support must be enabled when using psychopy.iohub.
  - For OS X 10.7 - 10.8.5, instructions can be found [here](#).
  - For OS X 10.9 +, the program being used to start your experiment script must be specifically authorized. Example instructions on authorizing an OS X 10.9 + app can be viewed [here](#).

### Software Requirements

When running PsychoPy using the macOS or Windows standalone distribution, all the necessary python package dependencies have already been installed, so the rest of this section can be skipped.

---

**Note:** Hardware specific software may need to be installed depending on the device being used. See the documentation page for the specific device hardware in question for further details.

---

If psychopy.iohub is being manually installed, first ensure the python packages listed in the dependencies section of the manual are installed.

psychopy.iohub requires the following extra dependencies to be installed:

1. `psutil` (version 1.2 +) A cross-platform process and system utilities module for Python.
2. `msgpack` It's like JSON. but fast and small.
3. `greenlet` The greenlet package is a spin-off of Stackless, a version of CPython that supports micro-threads called "tasklets".
4. `gevent` (version 1.0 or greater)\*\* A coroutine-based Python networking library.
5. `numexpr` Fast numerical array expression evaluator for Python and NumPy.
6. `pytables` PyTables is a package for managing hierarchical datasets.
7. `pyYAML` PyYAML is a YAML parser and emitter for Python.

#### Windows installations only

1. `pyHook` Python wrapper for global input hooks in Windows.

#### Linux installations only

1. `python-xlib` The Python X11R6 client-side implementation.

#### OSX installations only

1. `pyobjc` : A Python ObjectiveC binding.

## 8.12 `psychopy.logging` - control what gets logged

Provides functions for logging error and other messages to one or more files and/or the console, using python's own logging module. Some warning messages and error messages are generated by PsychoPy itself. The user can generate more using the functions in this module.

There are various levels for logged messages with the following order of importance: ERROR, WARNING, DATA, EXP, INFO and DEBUG.

When setting the level for a particular log target (e.g. LogFile) the user can set the minimum level that is required for messages to enter the log. For example, setting a level of INFO will result in INFO, EXP, DATA, WARNING and ERROR messages to be recorded but not DEBUG messages.

By default, PsychoPy will record messages of WARNING level and above to the console. The user can silence that by setting it to receive only CRITICAL messages, (which PsychoPy doesn't use) using the commands:

```
from psychopy import logging
logging.console.setLevel(logging.CRITICAL)
```

**class** psychopy.logging.LogFile (*f=None, level=30, filemode='a', logger=None, encoding='utf8'*)

A text stream to receive inputs from the logging system

Create a log file as a target for logged entries of a given level

#### Parameters

- **f**: this could be a string to a path, that will be created if it doesn't exist. Alternatively this could be a file object, sys.stdout or any object that supports .write() and .flush() methods
- **level**: The minimum level of importance that a message must have to be logged by this target.
- **filemode**: 'a', 'w' Append or overwrite existing log file

**setLevel** (*level*)

Set a new minimal level for the log file/stream

**write** (*txt*)

Write directly to the log file (without using logging functions). Useful to send messages that only this file receives

**class** psychopy.logging.\_Logger (*format='%%(t).4f t%(levelname)s t%(message)s'*)

Maintains a set of log targets (text streams such as files or stdout)

self.targets is a list of dicts { 'stream':stream, 'level':level }

The string-formatted elements %(xxxx)f can be used, where each xxxx is an attribute of the LogEntry. e.g. t, t\_ms, level, levelname, message

**addTarget** (*target*)

Add a target, typically a LogFile to the logger

**flush** ()

Process all current messages to each target

**log** (*message, level, t=None, obj=None*)

Add the *message* to the log stack at the appropriate *level*

If no relevant targets (files or console) exist then the message is simply discarded.

**removeTarget** (*target*)

Remove a target, typically a LogFile from the logger

psychopy.logging.addLevel (*level, levelName*)

Associate 'levelName' with 'level'.

This is used when converting levels to text during message formatting.

psychopy.logging.critical (*message*)

Send the message to any receiver of logging info (e.g. a LogFile) of level *log.CRITICAL* or higher

psychopy.logging.data (*msg, t=None, obj=None*)

Log a message about data collection (e.g. a key press)

**usage::** log.data(message)

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.DATA* or higher

psychopy.logging.debug (*msg, t=None, obj=None*)

Log a debugging message (not likely to be wanted once experiment is finalised)

**usage::** log.debug(message)

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.DEBUG* or higher

`psychoPy.logging.error` (*message*)

Send the message to any receiver of logging info (e.g. a LogFile) of level *log.ERROR* or higher

`psychoPy.logging.exp` (*msg, t=None, obj=None*)

Log a message about the experiment (e.g. a new trial, or end of a stimulus)

**usage::** `log.exp(message)`

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.EXP* or higher

`psychoPy.logging.fatal` (*msg, t=None, obj=None*)

`log.critical(message)` Send the message to any receiver of logging info (e.g. a LogFile) of level *log.CRITICAL* or higher

`psychoPy.logging.flush` (*logger=<psychoPy.logging.\_Logger object>*)

Send current messages in the log to all targets

`psychoPy.logging.getLevel` (*level*)

Return the textual representation of logging level 'level'.

If the level is one of the predefined levels (CRITICAL, ERROR, WARNING, INFO, DEBUG) then you get the corresponding string. If you have associated levels with names using `addLevelName` then the name you have associated with 'level' is returned.

If a numeric value corresponding to one of the defined levels is passed in, the corresponding string representation is returned.

Otherwise, the string "Level %s" % level is returned.

`psychoPy.logging.info` (*msg, t=None, obj=None*)

Log some information - maybe useful, maybe not

**usage::** `log.info(message)`

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.INFO* or higher

`psychoPy.logging.log` (*msg, level, t=None, obj=None*)

Log a message

**usage::** `log(level, msg, t=t, obj=obj)`

Log the msg, at a given level on the root logger

`psychoPy.logging.setDefaultClock` (*clock*)

Set the default clock to be used to reference all logging times. Must be a `psychoPy.core.Clock` object. Beware that if you reset the clock during the experiment then the resets will be reflected here. That might be useful if you want your logs to be reset on each trial, but probably not.

`psychoPy.logging.warn` (*msg, t=None, obj=None*)

`log.warning(message)`

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.WARNING* or higher

`psychoPy.logging.warning` (*message*)

Sends the message to any receiver of logging info (e.g. a LogFile) of level *log.WARNING* or higher

### 8.12.1 `flush()`

`psychoPy.logging.flush` (*logger=<psychoPy.logging.\_Logger object>*)

Send current messages in the log to all targets



## 8.12.2 setDefaultClock()

`psychopy.logging.setDefaultClock(clock)`

Set the default clock to be used to reference all logging times. Must be a `psychopy.core.Clock` object. Beware that if you reset the clock during the experiment then the resets will be reflected here. That might be useful if you want your logs to be reset on each trial, but probably not.

## 8.13 psychopy.microphone - Capture and analyze sound

(Available as of version 1.74.00; Advanced features available as of 1.77.00)

### 8.13.1 Overview

**AudioCapture()** allows easy audio recording and saving of arbitrary sounds to a file (wav format). AudioCapture will likely be replaced entirely by AdvAudioCapture in the near future.

**AdvAudioCapture()** can do everything AudioCapture does, and also allows onset-marker sound insertion and detection, loudness computation (RMS audio “power”), and lossless file compression (flac). The Builder microphone component now uses AdvAudioCapture by default.

### 8.13.2 Audio Capture

`psychopy.microphone.switchOn(sampleRate=48000, outputDevice=None, bufferSize=None)`

You need to switch on the microphone before use, which can take several seconds. The only time you can specify the sample rate (in Hz) is during switchOn().

Considerations on the default sample rate 48kHz:

```
DVD or video = 48,000
CD-quality   = 44,100 / 24 bit
human hearing: ~15,000 (adult); children & young adult higher
human speech: 100-8,000 (useful for telephone: 100-3,300)
Google speech API: 16,000 or 8,000 only
Nyquist frequency: twice the highest rate, good to oversample a bit
```

pyo’s `downsamp()` function can reduce 48,000 to 16,000 in about 0.02s (uses integer steps sizes). So recording at 48kHz will generate high-quality archival data, and permit easy downsampling.

**outputDevice, bufferSize:** set these parameters on the `pyoSndServer` before booting; None means use pyo’s default values

**class** `psychopy.microphone.AdvAudioCapture` (*name='advMic', filename='', saveDir='', sampletype=0, buffering=16, chnl=0, stereo=True, autoLog=True*)

Class extends AudioCapture, plays marker sound as a “start” indicator.

Has method for retrieving the marker onset time from the file, to allow calculation of vocal RT (or other sound-based RT).

See Coder demo > input > latencyFromTone.py

**compress** (*keep=False*)

Compress using FLAC (lossless compression).

**getLoudness** ( )

Return the RMS loudness of the saved recording.

**getMarkerInfo** ( )

Returns (hz, duration, volume) of the marker sound. Custom markers always return 0 hz (regardless of the sound).

**getMarkerOnset** (*chunk=128, secs=0.5, filename=""*)

Return (onset, offset) time of the first marker within the first *secs* of the saved recording.

Has approx ~1.33ms resolution at 48000Hz, *chunk=64*. Larger chunks can speed up processing times, at a sacrifice of some resolution, e.g., to pre-process long recordings with multiple markers.

If given a filename, it will first set that file as the one to work with, and then try to detect the onset marker.

**playMarker** ( )

Plays the current marker sound. This is automatically called at the start of recording, but can be called anytime to insert a marker.

**playback** (*block=True, loops=0, stop=False, log=True*)

Plays the saved .wav file, as just recorded or resampled. Execution blocks by default, but can return immediately with *block=False*.

*loops* : number of extra repetitions; 0 = play once

*stop* : True = immediately stop ongoing playback (if there is one), and return

**record** (*sec, filename="", block=False*)

Starts recording and plays an onset marker tone just prior to returning. The idea is that the start of the tone in the recording indicates when this method returned, to enable you to sync a known recording onset with other events.

**resample** (*newRate=16000, keep=True, log=True*)

Re-sample the saved file to a new rate, return the full path.

Can take several visual frames to resample a 2s recording.

The default values for `resample()` are for Google-speech, keeping the original (presumably recorded at 48kHz) to archive. A warning is generated if the new rate not an integer factor / multiple of the old rate.

To control anti-aliasing, use `pyo.downsamp()` or `upsamp()` directly.

**reset** (*log=True*)

Restores to fresh state, ready to record again

**setFile** (*filename*)

Sets the name of the file to work with.

**setMarker** (*tone=19000, secs=0.015, volume=0.03, log=True*)

Sets the onset marker, where *tone* is either in hz or a custom sound.

The default tone (19000 Hz) is recommended for auto-detection, as being easier to isolate from speech sounds (and so reliable to detect). The default duration and volume are appropriate for a quiet setting such as a lab testing room. A louder volume, longer duration, or both may give better results when recording loud sounds or in noisy environments, and will be auto-detected just fine (even more easily). If the hardware microphone in use is not physically near the speaker hardware, a louder volume is likely to be required.

Custom sounds cannot be auto-detected, but are supported anyway for presentation purposes. E.g., a recording of someone saying “go” or “stop” could be passed as the onset marker.

**stop** (*log=True*)

Interrupt a recording that is in progress; close & keep the file.

Ends the recording before the duration that was initially specified. The same file name is retained, with the same onset time but a shorter duration.

The same recording cannot be resumed after a stop (it is not a pause), but you can start a new one.

**uncompress** (*keep=False*)

Uncompress from FLAC to .wav format.

### 8.13.3 Speech recognition

Google's speech to text API is no longer available. AT&T, IBM, and wit.ai have a similar (paid) service.

### 8.13.4 Misc

Functions for file-oriented Discrete Fourier Transform and RMS computation are also provided.

`psychopy.microphone.wav2flac` (*path, keep=True, level=5*)

Lossless compression: convert .wav file (on disk) to .flac format.

If *path* is a directory name, convert all .wav files in the directory.

*keep* to retain the original .wav file(s), default *True*.

**level is compression level: 0 is fastest but larger, 8 is slightly smaller but much slower.**

`psychopy.microphone.flac2wav` (*path, keep=True*)

Uncompress: convert .flac file (on disk) to .wav format (new file).

If *path* is a directory name, convert all .flac files in the directory.

*keep* to retain the original .flac file(s), default *True*.

`psychopy.microphone.getDft` (*data, sampleRate=None, wantPhase=False*)

Compute and return magnitudes of `numpy.fft.fft()` of the data.

If given a sample rate (samples/sec), will return (magn, freq). If *wantPhase* is *True*, phase in radians is also returned (magn, freq, phase). *data* should have power-of-2 samples, or will be truncated.

`psychopy.microphone.getRMS` (*data*)

Compute and return the audio power ("loudness").

Uses `numpy.std()` as RMS. `std()` is same as RMS if the mean is 0, and .wav data should have a mean of 0. Returns an array if given stereo data (RMS computed within-channel).

*data* can be an array (1D, 2D) or filename; .wav format only. data from .wav files will be normalized to -1..+1 before RMS is computed.

## 8.14 psychopy.misc - miscellaneous routines for converting units etc

Wrapper for all miscellaneous functions and classes from `psychopy.tools`

`psychopy.misc` has gradually grown very large and the underlying code for its functions are distributed in multiple files. You can still (at least for now) import the functions here using `from psychopy import misc` but you can also import them from the *tools* sub-modules.

### 8.14.1 From `psychopy.tools.filetools`

<code>toFile(filename, data)</code>	Save data (of any sort) as a pickle file.
<code>fromFile(filename[, encoding])</code>	Load data from a pickle or JSON file.
<code>mergeFolder(src, dst[, pattern])</code>	Merge a folder into another.

### 8.14.2 From `psychopy.tools.colourspacetools`

<code>dkl2rgb(dkl[, conversionMatrix])</code>	Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.
<code>dklCart2rgb(LUM, LM, S[, conversionMatrix])</code>	Like <code>dkl2rgb</code> except that it uses cartesian coords (LM,S,LUM) rather than spherical coords for DKL (elev, azim, contr).
<code>rgb2dklCart(picture[, conversionMatrix])</code>	Convert an RGB image into Cartesian DKL space.
<code>hsv2rgb(hsv_Nx3)</code>	Convert from HSV color space to RGB gun values.
<code>lms2rgb(lms_Nx3[, conversionMatrix])</code>	Convert from cone space (Long, Medium, Short) to RGB.
<code>rgb2lms(rgb_Nx3[, conversionMatrix])</code>	Convert from RGB to cone space (LMS).
<code>dkl2rgb(dkl[, conversionMatrix])</code>	Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.

### 8.14.3 From `psychopy.tools.coordinatetools`

<code>cart2pol(x, y[, units])</code>	Convert from cartesian to polar coordinates.
<code>cart2sph(z, y, x)</code>	Convert from cartesian coordinates (x,y,z) to spherical (elevation, azimuth, radius).
<code>pol2cart(theta, radius[, units])</code>	Convert from polar to cartesian coordinates.
<code>sph2cart(*args)</code>	Convert from spherical coordinates (elevation, azimuth, radius) to cartesian (x,y,z).

### 8.14.4 From `psychopy.tools.monitorunittools`

<code>convertToPix(vertices, pos, units, win)</code>	Takes vertices and position, combines and converts to pixels from any unit
<code>cm2pix(cm, monitor)</code>	Convert size in cm to size in pixels for a given Monitor object.
<code>cm2deg(cm, monitor[, correctFlat])</code>	Convert size in cm to size in degrees for a given Monitor object
<code>deg2cm(degrees, monitor[, correctFlat])</code>	Convert size in degrees to size in pixels for a given Monitor object.
<code>deg2pix(degrees, monitor[, correctFlat])</code>	Convert size in degrees to size in pixels for a given Monitor object
<code>pix2cm(pixels, monitor)</code>	Convert size in pixels to size in cm for a given Monitor object
<code>pix2deg(pixels, monitor[, correctFlat])</code>	Convert size in pixels to size in degrees for a given Monitor object

### 8.14.5 From `psychopy.tools.imagetools`

<code>array2image(a)</code>	Takes an array and returns an image object (PIL)
<code>image2array(im)</code>	Takes an image object (PIL) and returns a numpy array
<code>makeImageAuto(inarray)</code>	Combines float_uint8 and image2array operations ie.

### 8.14.6 From `psychopy.tools.plottools`

<code>plotFrameIntervals(intervals)</code>	Plot a histogram of the frame intervals.
--	--

### 8.14.7 From `psychopy.tools.typetools`

<code>float_uint8(inarray)</code>	Converts arrays, lists, tuples and floats ranging -1:1 into an array of Uint8s ranging 0:255
<code>uint8_float(inarray)</code>	Converts arrays, lists, tuples and UINTs ranging 0:255 into an array of floats ranging -1:1
<code>float_uint16(inarray)</code>	Converts arrays, lists, tuples and floats ranging -1:1 into an array of Uint16s ranging 0:2^16

### 8.14.8 From `psychopy.tools.unittools`

<code>radians</code>	<code>radians(x, /, out=None, *, where=True, casting='same_kind', order='K', dtype=None, subok=True[, signature, extobj])</code>
<code>degrees</code>	<code>degrees(x, /, out=None, *, where=True, casting='same_kind', order='K', dtype=None, subok=True[, signature, extobj])</code>

## 8.15 `psychopy.monitors` - for those that don't like Monitor Center

Most users won't need to use the code here. In general the Monitor Centre interface is sufficient and monitors setup that way can be passed as strings to `Window` s. If there is some aspect of the normal calibration that you wish to override. eg:

```
from psychopy import visual, monitors
mon = monitors.Monitor('SonyG55') #fetch the most recent calib for this monitor
mon.setDistance(114) #further away than normal?
win = visual.Window(size=[1024,768], monitor=mon)
```

You might also want to fetch the `Photometer` class for conducting your own calibrations

### 8.15.1 `Monitor`

```
class psychopy.monitors.Monitor(name, width=None, distance=None, gamma=None,
                                notes=None, useBits=None, verbose=True, current-
                                Calib=None, autoLog=True)
```

Creates a monitor object for storing calibration details. This will be loaded automatically from disk if the monitor name is already defined (see methods).

Many settings from the stored monitor can easily be overridden either by adding them as arguments during the initial call.

**arguments:**

- `width`, `distance`, `gamma` are details about the calibration
- `notes` is a text field to store any useful info
- `useBits` True, False, None
- `verbose` True, False, None
- **`currentCalib` is a dictionary object containing various** fields for a calibration. Use with caution since the dictionary may not contain all the necessary fields that a monitor object expects to find.

**eg:**

`myMon = Monitor('sony500', distance=114)` Fetches the info on the sony500 and overrides its usual distance to be 114cm for this experiment.

These can be saved to the monitor file using `save()` or not (in which case the changes will be lost)

**`_loadAll()`**

Fetches the calibrations for this monitor from disk, storing them as `self.calibs`

**`copyCalib(calibName=None)`**

Stores the settings for the current calibration settings as new monitor.

**`delCalib(calibName)`**

Remove a specific calibration from the current monitor. Won't be finalised unless monitor is saved

**`gammaIsDefault()`**

Determine whether we're using the default gamma values

**`getCalibDate()`**

As a python date object (convert to string using `calibTools.strFromDate`)

**`getDKL_RGB(RECOMPUTE=False)`**

Returns the DKL->RGB conversion matrix. If one has been saved this will be returned. Otherwise, if power spectra are available for the monitor a matrix will be calculated.

**`getDistance()`**

Returns distance from viewer to the screen in cm, or None if not known

**`getGamma()`**

Returns just the gamma value (not the whole grid)

**`getGammaGrid()`**

Gets the min,max,gamma values for the each gun

**`getLMS_RGB(recompute=False)`**

Returns the LMS->RGB conversion matrix. If one has been saved this will be returned. Otherwise (if power spectra are available for the monitor) a matrix will be calculated.

**`getLevelsPost()`**

Gets the measured luminance values from last calibration TEST

**`getLevelsPre()`**

Gets the measured luminance values from last calibration

**`getLinearizeMethod()`**

Gets the method that this monitor is using to linearize the guns

**getLumsPost ()**  
Gets the measured luminance values from last calibration TEST

**getLumsPre ()**  
Gets the measured luminance values from last calibration

**getMeanLum ()**  
Returns the mean luminance of the screen if explicitly stored

**getNotes ()**  
Notes about the calibration

**getPsychopyVersion ()**  
Returns the version of PsychoPy that was used to create this calibration

**getSizePix ()**  
Returns the size of the current calibration in pixels, or None if not defined

**getSpectra ()**  
Gets the wavelength values from the last spectrometer measurement (if available)

**usage:**

- nm, power = monitor.getSpectra()

**getUseBits ()**  
Was this calibration carried out with a bits++ box

**getWidth ()**  
Of the viewable screen in cm, or None if not known

**lineariseLums (desiredLums, newInterpolators=False, overrideGamma=None)**  
Equivalent of `linearizeLums ()`.

**linearizeLums (desiredLums, newInterpolators=False, overrideGamma=None)**  
lums should be uncalibrated luminance values (e.g. a linear ramp) ranging 0:1

**newCalib (calibName=None, width=None, distance=None, gamma=None, notes=None, useBits=False, verbose=True)**  
create a new (empty) calibration for this monitor and makes this the current calibration

**save ()**  
Save the current calibrations to disk.

This will write a *json* file to the *monitors* subfolder of your PsychoPy configuration folder (typically *~/psychopy3/monitors* on Linux and macOS, and *%APPDATA%\psychopy3monitors* on Windows).

Additionally saves a pickle (*.calib*) file if you are running Python 2.7.

**saveMon ()**  
Equivalent of `save ()`.

**setCalibDate (date=None)**  
Sets the current calibration to have a date/time or to the current date/time if none given. (Also returns the date as set)

**setCurrent (calibration=-1)**  
Sets the current calibration for this monitor. Note that a single file can hold multiple calibrations each stored under a different key (the date it was taken)

The argument is either a string (naming the calib) or an integer eg:

```
myMon.setCurrent('mainCalib')
```

fetches the calibration named mainCalib. You can name calibrations what you want but PsychoPy will give them names of date/time by default. In Monitor Center you can ‘copy...’ a calibration and give it a new name to keep a second version.

`calibName = myMon.setCurrent(0)` fetches the first calibration (alphabetically) for this monitor

`calibName = myMon.setCurrent(-1)` fetches the last **alphabetical** calibration for this monitor (this is default). If default names are used for calibrations (ie date/time stamp) then this will import the most recent.

**setDKL\_RGB** (*dkl\_rgb*)

Sets the DKL->RGB conversion matrix for a chromatically calibrated monitor (matrix is a 3x3 num array).

**setDistance** (*distance*)

To the screen (cm)

**setGamma** (*gamma*)

Sets the gamma value(s) for the monitor. This only uses a single gamma value for the three guns, which is fairly approximate. Better to use `setGammaGrid` (which uses one gamma value for each gun)

**setGammaGrid** (*gammaGrid*)

Sets the min,max,gamma values for the each gun

**setLMS\_RGB** (*lms\_rgb*)

Sets the LMS->RGB conversion matrix for a chromatically calibrated monitor (matrix is a 3x3 num array).

**setLevelsPost** (*levels*)

Sets the last set of luminance values measured AFTER calibration

**setLevelsPre** (*levels*)

Sets the last set of luminance values measured during calibration

**setLineariseMethod** (*method*)

Sets the method for linearising 0 uses  $y=a+(bx)^{\text{gamma}}$  1 uses  $y=(a+bx)^{\text{gamma}}$  2 uses linear interpolation over the curve

**setLumsPost** (*lums*)

Sets the last set of luminance values measured AFTER calibration

**setLumsPre** (*lums*)

Sets the last set of luminance values measured during calibration

**setMeanLum** (*meanLum*)

Records the mean luminance (for reference only)

**setNotes** (*notes*)

For you to store notes about the calibration

**setPsychopyVersion** (*version*)

To store the version of PsychoPy that this calibration used

**setSizePix** (*pixels*)

Set the size of the screen in pixels x,y

**setSpectra** (*nm, rgb*)

Sets the phosphor spectra measured by the spectrometer

**setUseBits** (*usebits*)

DEPRECATED: Use the new hardware classes to control these devices

**setWidth** (*width*)

Of the viewable screen (cm)



### 8.15.2 GammaCalculator

**class** psychopy.monitors.**GammaCalculator** (*inputs=()*, *lums=()*, *gamma=None*, *bitsIN=8*, *bitsOUT=8*, *eq=1*)

Class for managing gamma tables

**Parameters:**

- **inputs (required)**= values at which you measured screen luminance either in range 0.0:1.0, or range 0:255. Should include the min and max of the monitor

Then give EITHER “lums” or “gamma”:

- **lums** = measured luminance at given input levels
- **gamma** = your own gamma value (single float)
- **bitsIN** = number of values in your lookup table
- **bitsOUT** = number of bits in the DACs

`myTable.gammaModel myTable.gamma`

**fitGammaErrFun** (*params, x, y, minLum, maxLum*)  
Provides an error function for fitting gamma function  
(used by `fitGammaFun`)

**fitGammaFun** (*x, y*)  
Fits a gamma function to the monitor calibration data.

**Parameters:** -xVals are the monitor look-up-table vals, either 0-255 or 0.0-1.0 -yVals are the measured luminances from a photometer/spectrometer

---

### 8.15.3 getAllMonitors ()

`psychopy.monitors.getAllMonitors ()`  
Find the names of all monitors for which calibration files exist

### 8.15.4 findPR650 ()

### 8.15.5 getLumSeriesPR650 ()

`psychopy.monitors.getLumSeriesPR650` (*lumLevels=8*, *winSize=(800, 600)*, *monitor=None*, *gamma=1.0*, *allGuns=True*, *useBits=False*, *autoMode='auto'*, *stimSize=0.3*, *photometer='COM1'*)  
DEPRECATED (since v1.60.01): Use `psychopy.monitors.getLumSeries ()` instead

### 8.15.6 getRGBspectra ()

`psychopy.monitors.getRGBspectra` (*stimSize=0.3*, *winSize=(800, 600)*, *photometer='COM1'*)  
**usage:** `getRGBspectra(stimSize=0.3, winSize=(800,600), photometer='COM1')`

**Params**

- ‘photometer’ could be a photometer object or a serial port

name on which a photometer might be found (not recommended)

### 8.15.7 `gammaFun()`

`psychoPy.monitors.gammaFun(xx, minLum, maxLum, gamma, eq=1, a=None, b=None, k=None)`

Returns gamma-transformed luminance values.  $y = \text{gammaFun}(x, \text{minLum}, \text{maxLum}, \text{gamma})$

$a$  and  $b$  are calculated directly from  $\text{minLum}$ ,  $\text{maxLum}$ ,  $\text{gamma}$

**Parameters:**

- **xx** are the input values (range 0-255 or 0.0-1.0)
- **minLum** = the minimum luminance of your monitor
- **maxLum** = the maximum luminance of your monitor (for this gun)
- **gamma** = the value of gamma (for this gun)

### 8.15.8 `gammaInvFun()`

`psychoPy.monitors.gammaInvFun(yy, minLum, maxLum, gamma, b=None, eq=1)`

Returns inverse gamma function for desired luminance values.  $x = \text{gammaInvFun}(y, \text{minLum}, \text{maxLum}, \text{gamma})$

$a$  and  $b$  are calculated directly from  $\text{minLum}$ ,  $\text{maxLum}$ ,  $\text{gamma}$  **Parameters:**

- **xx** are the input values (range 0-255 or 0.0-1.0)
- **minLum** = the minimum luminance of your monitor
- **maxLum** = the maximum luminance of your monitor (for this gun)
- **gamma** = the value of gamma (for this gun)
- **eq determines the gamma equation used;**  $\text{eq}=1$ [default]:  $yy = a + (b * xx)^{\text{gamma}}$   $\text{eq}=2$ :  $yy = (a + b * xx)^{\text{gamma}}$

### 8.15.9 `makeDKL2RGB()`

`psychoPy.monitors.makeDKL2RGB(nm, powerRGB)`

Creates a 3x3 DKL->RGB conversion matrix from the spectral input powers

### 8.15.10 `makeLMS2RGB()`

`psychoPy.monitors.makeLMS2RGB(nm, powerRGB)`

Creates a 3x3 LMS->RGB conversion matrix from the spectral input powers

## 8.16 `psychoPy.parallel` - functions for interacting with the parallel port

This module provides read / write access to the parallel port for Linux or Windows.

The `Parallel` class described below will attempt to load whichever parallel port driver is first found on your system and should suffice in most instances. If you need to use a specific driver then, instead of using `ParallelPort` shown below you can use one of the following as drop-in replacements, forcing the use of a specific driver:

- `psychopy.parallel.PParallelInpOut`
- `psychopy.parallel.PParallelDLPortIO`
- `psychopy.parallel.PParallelLinux`

Either way, each instance of the class can provide access to a different parallel port.

There is also a legacy API which consists of the routines which are directly in this module. That API assumes you only ever want to use a single parallel port at once.

**class** `psychopy.parallel.ParallelPort` (*address*)  
 Class for read/write access to the parallel port on Windows & Linux

Usage:

```
from psychopy import parallel
port = parallel.ParallelPort(address=0x0378)

port.setData(4)
port.readPin(2)
port.setPin(2, 1)
```

This is just a dummy constructor to avoid errors when the parallel port cannot be initiated

**readData** ()  
 Return the value currently set on the data pins (2-9)

**readPin** (*pinNumber*)  
 Determine whether a desired (input) pin is high(1) or low(0).  
 Pins 2-13 and 15 are currently read here

**setData** (*data*)  
 Set the data to be presented on the parallel port (one ubyte). Alternatively you can set the value of each pin (data pins are pins 2-9 inclusive) using `setPin()`

Examples:

```
from psychopy import parallel
port = parallel.ParallelPort(address=0x0378)

port.setData(0) # sets all pins low
port.setData(255) # sets all pins high
port.setData(2) # sets just pin 3 high (pin2 = bit0)
port.setData(3) # sets just pins 2 and 3 high
```

You can also convert base 2 to int easily in python:

```
port.setData( int("00000011", 2) ) # pins 2 and 3 high
port.setData( int("00000101", 2) ) # pins 2 and 4 high
```

## 8.16.1 Legacy functions

We would strongly recommend you use the class above instead: these are provided for backwards compatibility only.

`parallel.setPortAddress()`

Set the memory address or device node for your parallel port of your parallel port, to be used in subsequent commands

Common port addresses:

```
LPT1 = 0x0378 or 0x03BC
LPT2 = 0x0278 or 0x0378
LPT3 = 0x0278
```

**or for Linux::** /dev/parport0

This routine will attempt to find a usable driver depending on your platform

`parallel.setData()`

Set the data to be presented on the parallel port (one ubyte). Alternatively you can set the value of each pin (data pins are pins 2-9 inclusive) using `setPin()`

Examples:

```
parallel.setData(0) # sets all pins low
parallel.setData(255) # sets all pins high
parallel.setData(2) # sets just pin 3 high (remember that pin2=bit0)
parallel.setData(3) # sets just pins 2 and 3 high
```

You can also convert base 2 to int v easily in python:

```
parallel.setData(int("00000011", 2)) # pins 2 and 3 high
parallel.setData(int("00000101", 2)) # pins 2 and 4 high
```

`parallel.setPin(state)`

Set a desired pin to be high (1) or low (0).

Only pins 2-9 (incl) are normally used for data output:

```
parallel.setPin(3, 1) # sets pin 3 high
parallel.setPin(3, 0) # sets pin 3 low
```

`parallel.readPin()`

Determine whether a desired (input) pin is high(1) or low(0).

Pins 2-13 and 15 are currently read here

## 8.17 psychopy.preferences - getting and setting preferences

You can set preferences on a per-experiment basis. For example, if you would like to use a specific *audio library*, but don't want to touch your user settings in general, you can import preferences and set the option *audioLib* accordingly:

```
from psychopy import prefs
prefs.general['audioLib'] = ['pyo']
from psychopy import sound
```

**!!IMPORTANT!!** You must import the sound module **AFTER** setting the preferences. To check that you are getting what you want (don't do this in your actual experiment):

```
print sound.Sound
```

The output should be `<class 'psychopy.sound.SoundPyo'>` for pyo, or `<class 'psychopy.sound.SoundPygame'>` for pygame.

You can find the names of the preferences sections and their different options [here](#).

### 8.17.1 Preferences

Class for loading / saving prefs

**class** psychopy.preferences.Preferences

Users can alter preferences from the dialog box in the application, by editing their user preferences file (which is what the dialog box does) or, within a script, preferences can be controlled like this:

```
import psychopy
psychopy.prefs.hardware['audioLib'] = ['pyo', 'pygame']
print(prefs)
# prints the location of the user prefs file and all the current vals
```

Use the instance of *prefs*, as above, rather than the *Preferences* class directly if you want to affect the script that's running.

**loadAll()**

Load the user prefs and the application data

**loadUserPrefs()**

load user prefs, if any; don't save to a file because doing so will break `easy_install`. Saving to files within the psychopy/ is fine, eg for key-bindings, but outside it (where user prefs will live) is not allowed by `easy_install` (security risk)

**resetPrefs()**

removes userPrefs.cfg, does not touch appData.cfg

**restoreBadPrefs(cfg, result)**

result = result of validate

**saveAppData()**

Save the various setting to the appropriate files (or discard, in some cases)

**saveUserPrefs()**

Validate and save the various setting to the appropriate files (or discard, in some cases)

**validate()**

Validate (user) preferences and reset invalid settings to defaults

## 8.18 psychopy.serial - functions for interacting with the serial port

PsychoPy is compatible with Chris Liechti's `pyserial` package. You can use it like this:

```
import serial
ser = serial.Serial(0, 19200, timeout=1) # open first serial port
#ser = serial.Serial('/dev/ttyS1', 19200, timeout=1) # or something like this for Mac/
# Linux machines
ser.write('someCommand')
line = ser.readline() # read a '\n' terminated line
ser.close()
```

Ports are fully configurable with all the options you would expect of RS232 communications. See <http://pyserial.sourceforge.net> for further details and documentation.

pyserial is packaged in the Standalone (Windows and Mac distributions), for manual installations you should install this yourself.

## 8.19 psychopy.sound - play various forms of sound

### 8.19.1 Sound

PsychoPy currently supports a choice of three sound libraries: pyo, sounddevice or pygame. Select which will be used via the *audioLib* preference. *sound.Sound()* will then refer to one of *SoundDevice*, *SoundPyo* or *SoundPygame*. This can be set on a per-experiment basis by importing preferences, and *setting the audioLib option* to use.

- The *pygame* backend is the oldest and should always work without errors, but has the least good performance. Use it if latencies for your audio don't matter.
- The *pyo* library is, in theory, the highest performer, but in practice it has often had issues (at least on macOS) with crashes and freezing of experiments, or causing them not to finish properly. If those issues aren't affecting your studies then this could be the one for you.
- The *sounddevice* library looks like the way of the future. The performance appears to be good (although this might be less so in cases where you have complex rendering being done as well because it operates from the same computer core as the main experiment code). It's newer than *pyo* and so more prone to bugs and we haven't yet added microphone support to record your participants.

Sounds are actually generated by a variety of classes, depending on which “backend” you use (like *pyo* or *sounddevice*) and these different backends can have slightly different attributes, as below.

The user should typically do:

```
from psychopy.sound import Sound
```

but the class that gets imported will then be an alias of one of the following.

### 8.19.2 SoundDevice backend

```
class psychopy.sound.backend_sounddevice.SoundDeviceSound (value='C', secs=0.5,
                                                             octave=4, stereo=-1,
                                                             volume=1.0, loops=0,
                                                             sampleRate=None,
                                                             blockSize=128,
                                                             preBuffer=-1, ham-
                                                             ming=True, start-
                                                             Time=0, stopTime=-
                                                             1, name="", au-
                                                             toLog=True)
```

Play a variety of sounds using the new SoundDevice library

#### Parameters

- **value** – note name (“C”, “Bf”), filename or frequency (Hz)
- **secs** – duration (for synthesised tones)
- **octave** – which octave to use for note names (4 is middle)
- **stereo** – -1 (auto), True or False to force sounds to stereo or mono

- **volume** – float 0-1
- **loops** – number of loops to play (-1=forever, 0=single repeat)
- **sampleRate** – sample rate (for synthesized tones)
- **blockSize** – the size of the buffer on the sound card (small for low latency, large for stability)
- **preBuffer** – integer to control streaming/buffering - -1 means store all - 0 (no buffer) means stream from disk - potentially we could buffer a few secs(!?)
- **hamming** – boolean (default True) to indicate if the sound should be apodized (i.e., the onset and offset smoothly ramped up from down to zero). The function apodize uses a Hanning window, but arguments named 'hamming' are preserved so that existing code is not broken by the change from Hamming to Hanning internally. Not applied to sounds from files.
- **startTime** – for sound files this controls the start of snippet
- **stopTime** – for sound files this controls the end of snippet
- **name** – string for logging purposes
- **autoLog** – whether to automatically log every change

**\_EOS** (*reset=True*)

Function called on End Of Stream

**\_channelCheck** (*array*)

Checks whether stream has fewer channels than data. If True, ValueError

**pause** ()

Stop the sound but play will continue from here if needed

**play** (*loops=None*)

Start the sound playing

**setSound** (*value, secs=0.5, octave=4, hamming=None, log=True*)

Set the sound to be played.

Often this is not needed by the user - it is called implicitly during initialisation.

### Parameters

**value: can be a number, string or an array:**

- If it's a number between 37 and 32767 then a tone will be generated at that frequency in Hz.
- It could be a string for a note ('A', 'Bb', 'B', 'C', 'C#', ...). Then you may want to specify which octave.
- Or a string could represent a filename in the current location, or mediaLocation, or a full path combo
- Or by giving an Nx2 numpy array of floats (-1:1) you can specify the sound yourself as a waveform

**secs: duration (only relevant if the value is a note name or a frequency value)**

**octave: is only relevant if the value is a note name.** Middle octave of a piano is 4. Most computers won't output sounds in the bottom octave (1) and the top octave (8) is generally painful

**stop** (*reset=True*)

Stop the sound and return to beginning

**stream**

Read-only property returns the the stream on which the sound will be played

### 8.19.3 Pyo backend

```
class psychopy.sound.backend_pyo.SoundPyo(value='C', secs=0.5, octave=4, stereo=True,  
volume=1.0, loops=0, sampleRate=44100,  
bits=16, hamming=True, start=0, stop=-1,  
name="", autoLog=True)
```

Create a sound object, from one of MANY ways.

**value: can be a number, string or an array:**

- If it's a number between 37 and 32767 then a tone will be generated at that frequency in Hz.
- It could be a string for a note ('A', 'Bf', 'B', 'C', 'Csh', ...). Then you may want to specify which octave as well
- Or a string could represent a filename in the current location, or mediaLocation, or a full path combo
- Or by giving an Nx2 numpy array of floats (-1:1) you can specify the sound yourself as a waveform

By default, a Hanning window (5ms duration) will be applied to a generated tone, so that onset and offset are smoother (to avoid clicking). To disable the Hanning window, set *hamming=False*.

**secs:** Duration of a tone. Not used for sounds from a file.

**start** [float] Where to start playing a sound file; default = 0s (start of the file).

**stop** [float] Where to stop playing a sound file; default = end of file.

**octave: is only relevant if the value is a note name.** Middle octave of a piano is 4. Most computers won't output sounds in the bottom octave (1) and the top octave (8) is generally painful

**stereo: True (= default, two channels left and right), False (one channel)**

**volume: loudness to play the sound, from 0.0 (silent) to 1.0 (max).** Adjustments are not possible during playback, only before.

**loops** [int] How many times to repeat the sound after it plays once. If *loops == -1*, the sound will repeat indefinitely until stopped.

**sampleRate (= 44100): if the psychopy.sound.init() function has been** called or if another sound has already been created then this argument will be ignored and the previous setting will be used

**bits:** has no effect for the pyo backend

**hamming: boolean (default True) to indicate if the sound should** be apodized (i.e., the onset and offset smoothly ramped up from down to zero). The function apodize uses a Hanning window, but arguments named 'hamming' are preserved so that existing code is not broken by the change from Hamming to Hanning internally. Not applied to sounds from files.

**play** (*loops=None, autoStop=True, log=True*)

Starts playing the sound on an available channel.

**loops** [int] (same as above)

For playing a sound file, you cannot specify the start and stop times when playing the sound, only when creating the sound initially.



Playing a sound runs in a separate thread i.e. your code won't wait for the sound to finish before continuing. To pause while playing, you need to use a `psychopy.core.wait(mySound.getDuration())`. If you call `play()` while something is already playing the sounds will be played over each other.

**stop** (*log=True*)  
Stops the sound immediately

## 8.19.4 pygame backend

**class** `psychopy.sound.backend_pygame.SoundPygame` (*value='C', secs=0.5, octave=4, sampleRate=44100, bits=16, name="", autoLog=True, loops=0, stereo=True*)

Create a sound object, from one of many ways.

### Parameters

**value:** can be a number, string or an array:

- If it's a number between 37 and 32767 then a tone will be generated at that frequency in Hz.
- It could be a string for a note ('A', 'Bf', 'B', 'C', 'Csh', ...). Then you may want to specify which octave as well
- Or a string could represent a filename in the current location, or mediaLocation, or a full path combo
- Or by giving an Nx2 numpy array of floats (-1:1) you can specify the sound yourself as a waveform

**secs:** duration (only relevant if the value is a note name or a frequency value)

**octave:** is only relevant if the value is a note name. Middle octave of a piano is 4. Most computers won't output sounds in the bottom octave (1) and the top octave (8) is generally painful

**sampleRate(=44100):** If a sound has already been created or if the

**bits(=16):** Pygame uses the same bit depth for all sounds once initialised

**fadeOut** (*mSecs*)

fades out the sound (when playing) over mSecs. Don't know why you would do this in psychophysics but it's easy and fun to include as a possibility :)

**getDuration** ()

Get's the duration of the current sound in secs

**getVolume** ()

Returns the current volume of the sound (0.0:1.0)

**play** (*fromStart=True, log=True, loops=None*)

Starts playing the sound on an available channel.

### Parameters

**fromStart** [bool] Not yet implemented.

**log** [bool] Whether or not to log the playback event.

**loops** [int] How many times to repeat the sound after it plays once. If *loops* == -1, the sound will repeat indefinitely until stopped.

**Notes** If no sound channels are available, it will not play and return None. This runs off a separate thread i.e. your code won't wait for the sound to finish before continuing. You need to use a `psychopy.core.wait()` command if you want things to pause. If you call `play()` while something is already playing the sounds will be played over each other.

**setVolume** (*newVol*, *log=True*)  
Sets the current volume of the sound (0.0:1.0)

**stop** (*log=True*)  
Stops the sound immediately

## 8.20 psychopy.tools - miscellaneous tools

Container for all miscellaneous functions and classes

### 8.20.1 psychopy.tools.colorspectools

Functions and classes related to color space conversion.

<code>dkl2rgb(dkl[, conversionMatrix])</code>	Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.
<code>dklCart2rgb(LUM, LM, S[, conversionMatrix])</code>	Like <code>dkl2rgb</code> except that it uses cartesian coords (LM,S,LUM) rather than spherical coords for DKL (elev, azim, contr).
<code>rgb2dklCart(picture[, conversionMatrix])</code>	Convert an RGB image into Cartesian DKL space.
<code>hsv2rgb(hsv_Nx3)</code>	Convert from HSV color space to RGB gun values.
<code>lms2rgb(lms_Nx3[, conversionMatrix])</code>	Convert from cone space (Long, Medium, Short) to RGB.
<code>rgb2lms(rgb_Nx3[, conversionMatrix])</code>	Convert from RGB to cone space (LMS).
<code>dkl2rgb(dkl[, conversionMatrix])</code>	Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.
<code>cielab2rgb(lab[, whiteXYZ, ...])</code>	Transform CIE L*a*b* (1976) color space coordinates to RGB tristimulus values.
<code>cielch2rgb(lch[, whiteXYZ, ...])</code>	Transform CIE L*C*h* coordinates to RGB tristimulus values.
<code>srgbTF(rgb[, reverse])</code>	Apply sRGB transfer function (or gamma) to linear RGB values.
<code>rec709TF(rgb, **kwargs)</code>	Apply the Rec.

#### Function details

`psychopy.tools.colorspectools.dkl2rgb` (*dkl*, *conversionMatrix=None*)

Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.

Requires a conversion matrix, which will be generated from generic Sony Trinitron phosphors if not supplied (note that this will not be an accurate representation of the color space unless you supply a conversion matrix).

usage:

```
rgb(Nx3) = dkl2rgb(dkl_Nx3(e1,az,radius), conversionMatrix)
rgb(NxNx3) = dkl2rgb(dkl_NxNx3(e1,az,radius), conversionMatrix)
```

`psychopy.tools.colorspacetools.dk1Cart2rgb` (*LUM, LM, S, conversionMatrix=None*)

Like `dkl2rgb` except that it uses cartesian coords (LM,S,LUM) rather than spherical coords for DKL (elev, azim, contr).

NB: this may return `rgb` values  $>1$  or  $<-1$

`psychopy.tools.colorspacetools.rgb2dk1Cart` (*picture, conversionMatrix=None*)

Convert an RGB image into Cartesian DKL space.

`psychopy.tools.colorspacetools.hsv2rgb` (*hsv\_Nx3*)

Convert from HSV color space to RGB gun values.

usage:

```
rgb_Nx3 = hsv2rgb(hsv_Nx3)
```

Note that in some uses of HSV space the Hue component is given in radians or cycles (range 0:1]). In this version H is given in degrees (0:360).

Also note that the RGB output ranges -1:1, in keeping with other PsychoPy functions.

`psychopy.tools.colorspacetools.lms2rgb` (*lms\_Nx3, conversionMatrix=None*)

Convert from cone space (Long, Medium, Short) to RGB.

Requires a conversion matrix, which will be generated from generic Sony Trinitron phosphors if not supplied (note that you will not get an accurate representation of the color space unless you supply a conversion matrix)

usage:

```
rgb_Nx3 = lms2rgb(dkl_Nx3(el,az,radius), conversionMatrix)
```

`psychopy.tools.colorspacetools.rgb2lms` (*rgb\_Nx3, conversionMatrix=None*)

Convert from RGB to cone space (LMS).

Requires a conversion matrix, which will be generated from generic Sony Trinitron phosphors if not supplied (note that you will not get an accurate representation of the color space unless you supply a conversion matrix)

usage:

```
lms_Nx3 = rgb2lms(rgb_Nx3(el,az,radius), conversionMatrix)
```

`psychopy.tools.colorspacetools.dk12rgb` (*dkl, conversionMatrix=None*)

Convert from DKL color space (Derrington, Krauskopf & Lennie) to RGB.

Requires a conversion matrix, which will be generated from generic Sony Trinitron phosphors if not supplied (note that this will not be an accurate representation of the color space unless you supply a conversion matrix).

usage:

```
rgb(Nx3) = dk12rgb(dkl_Nx3(el,az,radius), conversionMatrix)
rgb(NxNx3) = dk12rgb(dkl_NxNx3(el,az,radius), conversionMatrix)
```

`psychopy.tools.colorspacetools.cielab2rgb` (*lab, whiteXYZ=None, conversionMatrix=None, transferFunc=None, clip=False, \*\*kwargs*)

Transform CIE  $L^*a^*b^*$  (1976) color space coordinates to RGB tristimulus values.

CIE  $L^*a^*b^*$  are first transformed into CIE XYZ (1931) color space, then the RGB conversion is applied. By default, the sRGB conversion matrix is used with a reference D65 white point. You may specify your own RGB conversion matrix and white point (in CIE XYZ) appropriate for your display.

### Parameters

- **lab** (*tuple, list or ndarray*) – 1-, 2-, 3-D vector of CIE L\*a\*b\* coordinates to convert. The last dimension should be length-3 in all cases specifying a single coordinate.
- **whiteXYZ** (*tuple, list or ndarray*) – 1-D vector coordinate of the white point in CIE-XYZ color space. Must be the same white point needed by the conversion matrix. The default white point is D65 if None is specified, defined as X, Y, Z = 0.9505, 1.0000, 1.0890.
- **conversionMatrix** (*tuple, list or ndarray*) – 3x3 conversion matrix to transform CIE-XYZ to RGB values. The default matrix is sRGB with a D65 white point if None is specified. Note that values must be gamma corrected to appear correctly according to the sRGB standard.
- **transferFunc** (*pyfunc or None*) – Signature of the transfer function to use. If None, values are kept as linear RGB (it's assumed your display is gamma corrected via the hardware CLUT). The TF must be appropriate for the conversion matrix supplied (default is sRGB). Additional arguments to 'transferFunc' can be passed by specifying them as key-word arguments. Gamma functions that come with PsychoPy are 'srgbTF' and 'rec709TF', see their docs for more information.
- **clip** (*bool*) – Make all output values representable by the display. However, colors outside of the display's gamut may not be valid!

**Returns** Array of RGB tristimulus values.

**Return type** ndarray

## Example

Converting a CIE L\*a\*b\* color to linear RGB:

```
import psychopy.tools.colorspacetools as cst
cielabColor = (53.0, -20.0, 0.0) # greenish color (L*, a*, b*)
rgbColor = cst.cielab2rgb(cielabColor)
```

Using a transfer function to convert to sRGB:

```
rgbColor = cst.cielab2rgb(cielabColor, transferFunc=cst.srgbTF)
```

psychopy.tools.colorspacetools.**cielch2rgb** (*lch, whiteXYZ=None, conversionMatrix=None, transferFunc=None, clip=False, \*\*kwargs*)

Transform CIE L\*C\*h\* coordinates to RGB tristimulus values.

## Parameters

- **lch** (*tuple, list or ndarray*) – 1-, 2-, 3-D vector of CIE L\*C\*h\* coordinates to convert. The last dimension should be length-3 in all cases specifying a single coordinate. The hue angle \*h is expected in degrees.
- **whiteXYZ** (*tuple, list or ndarray*) – 1-D vector coordinate of the white point in CIE-XYZ color space. Must be the same white point needed by the conversion matrix. The default white point is D65 if None is specified, defined as X, Y, Z = 0.9505, 1.0000, 1.0890
- **conversionMatrix** (*tuple, list or ndarray*) – 3x3 conversion matrix to transform CIE-XYZ to RGB values. The default matrix is sRGB with a D65 white point if None is specified. Note that values must be gamma corrected to appear correctly according to the sRGB standard.

- **transferFunc** (*pyfunc or None*) – Signature of the transfer function to use. If None, values are kept as linear RGB (it's assumed your display is gamma corrected via the hardware CLUT). The TF must be appropriate for the conversion matrix supplied. Additional arguments to 'transferFunc' can be passed by specifying them as keyword arguments. Gamma functions that come with PsychoPy are 'srgbTF' and 'rec709TF', see their docs for more information.
- **clip** (*boolean*) – Make all output values representable by the display. However, colors outside of the display's gamut may not be valid!

**Returns** array of RGB tristimulus values

**Return type** ndarray

`psychoPy.tools.colorspacertools.srgbTF(rgb, reverse=False, **kwargs)`

Apply sRGB transfer function (or gamma) to linear RGB values.

Input values must have been transformed using a conversion matrix derived from sRGB primaries relative to D65.

**Parameters**

- **rgb** (*tuple, list or ndarray of floats*) – Nx3 or NxNx3 array of linear RGB values, last dim must be size == 3 specifying RGB values.
- **reverse** (*boolean*) – If True, the reverse transfer function will convert sRGB -> linear RGB.

**Returns** Array of transformed colors with same shape as input.

**Return type** ndarray

`psychoPy.tools.colorspacertools.rec709TF(rgb, **kwargs)`

Apply the Rec. 709 transfer function (or gamma) to linear RGB values.

This transfer function is defined in the ITU-R BT.709 (2015) recommendation document (<http://www.itu.int/rec/R-REC-BT.709-6-201506-1/en>) and is commonly used with HDTV televisions.

**Parameters** **rgb** (*tuple, list or ndarray of floats*) – Nx3 or NxNx3 array of linear RGB values, last dim must be size == 3 specifying RGB values.

**Returns** Array of transformed colors with same shape as input.

**Return type** ndarray

## 8.20.2 psychoPy.tools.coordinatetools

Functions and classes related to coordinate system conversion

<code>cart2pol(x, y[, units])</code>	Convert from cartesian to polar coordinates.
<code>cart2sph(z, y, x)</code>	Convert from cartesian coordinates (x,y,z) to spherical (elevation, azimuth, radius).
<code>pol2cart(theta, radius[, units])</code>	Convert from polar to cartesian coordinates.
<code>sph2cart(*args)</code>	Convert from spherical coordinates (elevation, azimuth, radius) to cartesian (x,y,z).

## Function details

`psychoPy.tools.coordinatetools.cart2pol(x, y, units='deg')`

Convert from cartesian to polar coordinates.

**Usage** `theta, radius = cart2pol(x, y, units='deg')`

`units` refers to the units (rad or deg) for `theta` that should be returned

`psychoPy.tools.coordinatetools.cart2sph(z, y, x)`

Convert from cartesian coordinates (x,y,z) to spherical (elevation, azimuth, radius). Output is in degrees.

**usage:** `array3xN[el,az,rad] = cart2sph(array3xN[x,y,z])` OR `elevation, azimuth, radius = cart2sph(x,y,z)`

If working in DKL space, `z` = Luminance, `y` = S and `x` = LM

`psychoPy.tools.coordinatetools.pol2cart(theta, radius, units='deg')`

Convert from polar to cartesian coordinates.

**usage:**

`x, y = pol2cart(theta, radius, units='deg')`

`psychoPy.tools.coordinatetools.sph2cart(*args)`

Convert from spherical coordinates (elevation, azimuth, radius) to cartesian (x,y,z).

**usage:** `array3xN[x,y,z] = sph2cart(array3xN[el,az,rad])` OR `x,y,z = sph2cart(elev, azim, radius)`

## 8.20.3 psychoPy.tools.filetools

Functions and classes related to file and directory handling

`psychoPy.tools.filetools.toFile(filename, data)`

Save data (of any sort) as a pickle file.

simple wrapper of the cPickle module in core python

`psychoPy.tools.filetools.fromFile(filename, encoding='utf-8')`

Load data from a pickle or JSON file.

**Parameters** `encoding` (*str*) – The encoding to use when reading a JSON file. This parameter will be ignored for any other file type.

`psychoPy.tools.filetools.mergeFolder(src, dst, pattern=None)`

Merge a folder into another.

Existing files in `dst` folder with the same name will be overwritten. Non-existent files/folders will be created.

`psychoPy.tools.filetools.openOutputFile(fileName=None, append=False, fileCollisionMethod='rename', encoding='utf-8-sig')`

Open an output file (or standard output) for writing.

### Parameters

**fileName** [None, 'stdout', or str] The desired output file name. If *None* or *stdout*, return *sys.stdout*. Any other string will be considered a filename.

**append** [bool, optional] If *True*, append data to an existing file; otherwise, overwrite it with new data. Defaults to *True*, i.e. appending.

**fileCollisionMethod** [string, optional] How to handle filename collisions. Valid values are 'rename', 'overwrite', and 'fail'. This parameter is ignored if `append` is set to *True*. Defaults to *rename*.

**encoding** [string, optional] The encoding to use when writing the file. This parameter will be ignored if *append* is *False* and *fileName* ends with *.psydat* or *.npy* (i.e. if a binary file is to be written). Defaults to 'utf-8'.

#### Returns

**f** [file] A writable file handle.

`psychopy.tools.filetools.genDelimiter(fileName)`

Return a delimiter based on a filename.

#### Parameters

**fileName** [string] The output file name.

#### Returns

**delim** [string] A delimiter picked based on the supplied filename. This will be `,` if the filename extension is `.csv`, and a tabulator character otherwise.

## 8.20.4 psychopy.tools.gltools

OpenGL related helper functions.

<code>createFBO([attachments])</code>	Create a Framebuffer Object.
<code>attach(attachPoint, imageBuffer)</code>	Attach an image to a specified attachment point on the presently bound FBO.
<code>isComplete()</code>	Check if the currently bound framebuffer is complete.
<code>deleteFBO(fbo)</code>	Delete a framebuffer.
<code>blitFBO(srcRect[, dstRect, filter])</code>	Copy a block of pixels between framebuffers via blitting.
<code>useFBO(fbo)</code>	Context manager for Framebuffer Object bindings.
<code>createRenderbuffer(width, height[, ...])</code>	Create a new Renderbuffer Object with a specified internal format.
<code>deleteRenderbuffer(renderBuffer)</code>	Free the resources associated with a renderbuffer.
<code>createTexImage2D(width, height[, target, ...])</code>	Create a 2D texture in video memory.
<code>createTexImage2DMultisample(width, height[, ...])</code>	Create a 2D multisampled texture.
<code>deleteTexture(texture)</code>	Free the resources associated with a texture.
<code>createVBO(data[, size, dtype, target])</code>	Create a single-storage array buffer, often referred to as Vertex Buffer Object (VBO).
<code>createVAO(vertexBuffers[, indexBuffer])</code>	Create a Vertex Array Object (VAO) with specified Vertex Buffer Objects.
<code>drawVAO(vao[, mode, flush])</code>	Draw a vertex array using <code>glDrawArrays</code> .
<code>deleteVBO(vbo)</code>	Delete a Vertex Buffer Object (VBO).
<code>deleteVAO(vao)</code>	Delete a Vertex Array Object (VAO).
<code>createMaterial([params, textures, face])</code>	Create a new material.
<code>useMaterial(material[, useTextures])</code>	Use a material for proceeding vertex draws.
<code>createLight([params])</code>	Create a point light source.
<code>useLights(lights[, setupOnly])</code>	Use specified lights in successive rendering operations.
<code>setAmbientLight(color)</code>	Set the global ambient lighting for the scene when lighting is enabled.
<code>loadObjFile(objFile)</code>	Load a Wavefront OBJ file (*.obj).

Continued on next page

Table 27 – continued from previous page

<code>loadMtlFile(mtlFilePath[, texParameters])</code>	Load a material library (*.mtl).
<code>getIntegerv(parName)</code>	Get a single integer parameter value, return it as a Python integer.
<code>getFloatv(parName)</code>	Get a single float parameter value, return it as a Python float.
<code>getString(parName)</code>	Get a single string parameter value, return it as a Python UTF-8 string.
<code>getOpenGLInfo()</code>	Get general information about the OpenGL implementation on this machine.

## Function details

`psychopy.tools.gltools.createFBO(attachments=())`

Create a Framebuffer Object.

**Parameters** `attachments` (list or tuple of tuple) – Optional attachments to initialize the Framebuffer with. Attachments are specified as a list of tuples. Each tuple must contain an attachment point (e.g. `GL_COLOR_ATTACHMENT0`, `GL_DEPTH_ATTACHMENT`, etc.) and a buffer descriptor type (Renderbuffer or `TexImage2D`). If using a combined depth/stencil format such as `GL_DEPTH24_STENCIL8`, `GL_DEPTH_ATTACHMENT` and `GL_STENCIL_ATTACHMENT` must be passed the same buffer. Alternatively, one can use `GL_DEPTH_STENCIL_ATTACHMENT` instead. If using multisample buffers, all attachment images must use the same number of samples!. As an example, one may specify attachments as `'attachments=(( GL.GL_COLOR_ATTACHMENT0, frameTexture), (GL.GL_DEPTH_STENCIL_ATTACHMENT, depthRenderBuffer))'`.

**Returns** Framebuffer descriptor.

**Return type** `Framebuffer`

## Notes

- All buffers must have the same number of samples.
- The 'userData' field of the returned descriptor is a dictionary that can be used to store arbitrary data associated with the FBO.
- Framebuffers need a single attachment to be complete.

## Examples

```
# empty framebuffer with no attachments fbo = createFBO() # invalid until attachments are added
# create a render target with multiple color texture attachments colorTex = createTexImage2D(1024,1024) #
empty texture depthRb = createRenderbuffer(800,600,internalFormat=GL.GL_DEPTH24_STENCIL8)

# attach images GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, fbo.id) at-
tach(GL.GL_COLOR_ATTACHMENT0, colorTex) attach(GL.GL_DEPTH_ATTACHMENT, depthRb) at-
tach(GL.GL_STENCIL_ATTACHMENT, depthRb) # or attach(GL.GL_DEPTH_STENCIL_ATTACHMENT,
depthRb) GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, 0)

# above is the same as with useFBO(fbo):
```



```

attach(GL.GL_COLOR_ATTACHMENT0, colorTex) attach(GL.GL_DEPTH_ATTACHMENT,
depthRb) attach(GL.GL_STENCIL_ATTACHMENT, depthRb)

# examples of userData some custom function might access fbo.userData['flags'] = ['left_eye',
'clear_before_use']

# depth only texture (for shadow mapping?) depthTex = createTexImage2D(800, 600,
    internalFormat=GL.GL_DEPTH_COMPONENT24, pixelFormat=GL.GL_DEPTH_COMPONENT)

fbo = createFBO([(GL.GL_DEPTH_ATTACHMENT, depthTex)]) # is valid

# discard FBO descriptor, just give me the ID framebuffer = createFBO().id
psychopy.tools.gltools.attach (attachPoint, imageBuffer)
    Attach an image to a specified attachment point on the presently bound FBO.

:param attachPoint int: Attachment point for 'imageBuffer' (e.g. GL.GL_COLOR_ATTACHMENT0).
:param imageBuffer: Framebuffer-attachable buffer descriptor. :type imageBuffer: TexImage2D or
Renderbuffer

```

#### Returns

**Return type** `None`

### Examples

```

# with descriptors colorTex and depthRb GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, fbo) at-
tach(GL.GL_COLOR_ATTACHMENT0, colorTex) attach(GL.GL_DEPTH_STENCIL_ATTACHMENT,
depthRb) GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, lastBoundFbo)

# same as above, but using a context manager with useFBO(fbo):

attach(GL.GL_COLOR_ATTACHMENT0, colorTex) attach(GL.GL_DEPTH_STENCIL_ATTACHMENT,
depthRb)

psychopy.tools.gltools.isComplete ()
    Check if the currently bound framebuffer is complete.

Returns

Return type obj:'bool'

psychopy.tools.gltools.deleteFBO (fbo)
    Delete a framebuffer.

Returns

Return type obj:'None'

psychopy.tools.gltools.blitFBO (srcRect, dstRect=None, filter=9729)
    Copy a block of pixels between framebuffers via blitting. Read and draw framebuffers must be bound prior to
    calling this function. Beware, the scissor box and viewport are changed when this is called to dstRect.

```

#### Parameters

- **srcRect** (*list* of *int*) – List specifying the top-left and bottom-right coordinates of the region to copy from (<X0>, <Y0>, <X1>, <Y1>).
- **dstRect** (*list* of *int* or *None*) – List specifying the top-left and bottom-right coordinates of the region to copy to (<X0>, <Y0>, <X1>, <Y1>). If *None*, srcRect is used for dstRect.

- **filter** (*int*) – Interpolation method to use if the image is stretched, default is GL\_LINEAR, but can also be GL\_NEAREST.

**Returns**

**Return type** *None*

### Examples

```
# bind framebuffer to read pixels from GL.glBindFramebuffer(GL.GL_READ_FRAMEBUFFER, srcFbo)
# bind framebuffer to draw pixels to GL.glBindFramebuffer(GL.GL_DRAW_FRAMEBUFFER, dstFbo)
gltools.blitFBO((0,0,800,600), (0,0,800,600))
# unbind both read and draw buffers GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, 0)
psychopy.tools.gltools.useFBO (fbo)
Context manager for Framebuffer Object bindings. This function yields the framebuffer name as an integer.
:param fbo int or Framebuffer: OpenGL Framebuffer Object name/ID or descriptor.
```

**Yields** *int* – OpenGL name of the framebuffer bound in the context.

**Returns**

**Return type** *None*

### Examples

```
# FBO bound somewhere deep in our code GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, someOtherFBO)
...
# create a new FBO, but we have no idea what the currently bound FBO is fbo = createFBO()
# use a context to bind attachments with bindFBO(fbo):
attach(GL.GL_COLOR_ATTACHMENT0, colorTex) attach(GL.GL_DEPTH_ATTACHMENT,
depthRb) attach(GL.GL_STENCIL_ATTACHMENT, depthRb) isComplete = gltools.isComplete()
# someOtherFBO is still bound!
psychopy.tools.gltools.createRenderbuffer (width, height, internalFormat=32856, sam-
ples=1)
```

Create a new Renderbuffer Object with a specified internal format. A multisample storage buffer is created if samples > 1.

Renderbuffers contain image data and are optimized for use as render targets. See [https://www.khronos.org/opengl/wiki/Renderbuffer\\_Object](https://www.khronos.org/opengl/wiki/Renderbuffer_Object) for more information.

#### Parameters

- **width** (*int*) – Buffer width in pixels.
- **height** (*int*) – Buffer height in pixels.
- **internalFormat** (*int*) – Format for renderbuffer data (e.g. GL\_RGBA8, GL\_DEPTH24\_STENCIL8).
- **samples** (*int*) – Number of samples for multi-sampling, should be >1 and power-of-two. Work with one sample, but will raise a warning.

**Returns** A descriptor of the created renderbuffer.

**Return type** `Renderbuffer`

## Notes

The 'userData' field of the returned descriptor is a dictionary that can be used to store arbitrary data associated with the buffer.

`psychopy.tools.gltools.deleteRenderbuffer(renderBuffer)`

Free the resources associated with a renderbuffer. This invalidates the renderbuffer's ID.

## Returns

**Return type** `obj:None`

`psychopy.tools.gltools.createTexImage2D(width, height, target=3553, level=0, internalFormat=32856, pixelFormat=6408, dataType=5126, data=None, unpackAlignment=4, texParameters=())`

Create a 2D texture in video memory. This can only create a single 2D texture with targets `GL_TEXTURE_2D` or `GL_TEXTURE_RECTANGLE`.

## Parameters

- **width** (`int`) – Texture width in pixels.
- **height** (`int`) – Texture height in pixels.
- **target** (`int`) – The target texture should only be either `GL_TEXTURE_2D` or `GL_TEXTURE_RECTANGLE`.
- **level** (`int`) – LOD number of the texture, should be 0 if `GL_TEXTURE_RECTANGLE` is the target.
- **internalFormat** (`int`) – Internal format for texture data (e.g. `GL_RGBA8`, `GL_R11F_G11F_B10F`).
- **pixelFormat** (`int`) – Pixel data format (e.g. `GL_RGBA`, `GL_DEPTH_STENCIL`).
- **dataType** (`int`) – Data type for pixel data (e.g. `GL_FLOAT`, `GL_UNSIGNED_BYTE`).
- **data** (`ctypes` or `None`) – Ctypes pointer to image data. If `None` is specified, the texture will be created but pixel data will be uninitialized.
- **unpackAlignment** (`int`) – Alignment requirements of each row in memory. Default is 4.
- **texParameters** (`list of tuple of int`) – Optional texture parameters specified as a list of tuples. These values are passed to 'glTexParameter'. Each tuple must contain a parameter name and value. For example, `texParameters=[(GL.GL_TEXTURE_MIN_FILTER, GL.GL_LINEAR), (GL.GL_TEXTURE_MAG_FILTER, GL.GL_LINEAR)]`

**Returns** A `TexImage2D` descriptor.

**Return type** `TexImage2D`

## Notes

The 'userData' field of the returned descriptor is a dictionary that can be used to store arbitrary data associated with the texture.

Previous textures are unbound after calling ‘createTexImage2D’.

## Examples

```
import pyglet.gl as GL # using Pyglet for now

# empty texture textureDesc = createTexImage2D(1024, 1024, internalFormat=GL.GL_RGBA8)

# load texture data from an image file using Pillow and NumPy from PIL
import Image
import numpy as np
im = Image.open(imageFile) # 8bpp!
im = im.transpose(Image.FLIP_TOP_BOTTOM) # OpenGL origin is at bottom
im = im.convert("RGBA")
pixelData = np.array(im).ctypes # convert to ctypes!

width = pixelData.shape[1]
height = pixelData.shape[0]
textureDesc = gltools.createTexImage2D(
    width, height, internalFormat=GL.GL_RGBA, pixelFormat=GL.GL_RGBA,
    dataType=GL.GL_UNSIGNED_BYTE, data=texture_array.ctypes, unpackAlignment=1, tex-
    Parameters=[(GL.GL_TEXTURE_MAG_FILTER, GL.GL_LINEAR),
                (GL.GL_TEXTURE_MIN_FILTER, GL.GL_LINEAR)])

GL.glBindTexture(GL.GL_TEXTURE_2D, textureDesc.id)

psychopy.tools.gltools.createTexImage2DMultisample(width, height, target=37120, sam-
                                                    ples=1, internalFormat=32856,
                                                    texParameters=())
```

Create a 2D multisampled texture.

### Parameters

- **width** (*int*) – Texture width in pixels.
- **height** (*int*) – Texture height in pixels.
- **target** (*int*) – The target texture (e.g. GL\_TEXTURE\_2D\_MULTISAMPLE).
- **samples** (*int*) – Number of samples for multi-sampling, should be >1 and power-of-two. Work with one sample, but will raise a warning.
- **internalFormat** (*int*) – Internal format for texture data (e.g. GL\_RGBA8, GL\_R11F\_G11F\_B10F).
- **texParameters** (*list of tuple of int*) – Optional texture parameters specified as a list of tuples. These values are passed to ‘glTexParameter’. Each tuple must contain a parameter name and value. For example, texParameters=[(GL.GL\_TEXTURE\_MIN\_FILTER, GL.GL\_LINEAR), (GL.GL\_TEXTURE\_MAG\_FILTER, GL.GL\_LINEAR)]

**Returns** A TexImage2DMultisample descriptor.

**Return type** TexImage2DMultisample

```
psychopy.tools.gltools.deleteTexture(texture)
```

Free the resources associated with a texture. This invalidates the texture’s ID.

### Returns

**Return type** obj:‘None’

```
psychopy.tools.gltools.createVBO(data, size=3, dtype=5126, target=34962)
```

Create a single-storage array buffer, often referred to as Vertex Buffer Object (VBO).

### Parameters

- **data** (*list* or *tuple* of *float* or *int*) – Coordinates as a 1D array of floats (e.g. [X0, Y0, Z0, X1, Y1, Z1, ...])
- **size** (*int*) – Number of coordinates per-vertex, default is 3.
- **dtype** (*int*) – Data type OpenGL will interpret that data as, should be compatible with the type of 'data'.
- **target** (*int*) – Target used when binding the buffer (e.g. GL\_VERTEX\_ARRAY)

**Returns** A descriptor with vertex buffer information.

**Return type** VertexBufferObject

## Notes

Creating vertex buffers is a computationally expensive operation. Be sure to load all resources before entering your experiment's main loop.

## Examples

```
# vertices of a triangle verts = [ 1.0, 1.0, 0.0, # v0
                                0.0, -1.0, 0.0, # v1
                                -1.0, 1.0, 0.0] # v2
```

```
# load vertices to graphics device, return a descriptor vboDesc = createVBO(verts, 3)
```

```
# draw GL.glBindBuffer(GL.GL_ARRAY_BUFFER, vboDesc.id) GL.glVertexPointer(vboDesc.vertexSize,
vboDesc.dtype, 0, None) GL.glEnableClientState(vboDesc.bufferType) GL.glDrawArrays(GL.GL_TRIANGLES,
0, vboDesc.indices) GL.glFlush()
```

```
psychopy.tools.gltools.createVAO(vertexBuffers, indexBuffer=None)
```

Create a Vertex Array Object (VAO) with specified Vertex Buffer Objects. VAOs store buffer binding states, reducing CPU overhead when drawing objects with vertex data stored in VBOs.

### Parameters

- **vertexBuffers** (*list* of *tuple*) – Specify vertex attributes VBO descriptors apply to.
- **indexBuffer** (*list* of *int*, optional) – Index array of elements. If provided, an element array is created from the array. The returned descriptor will have `isIndexed=True`. This requires the VAO be drawn with `glDrawElements` instead of `glDrawArrays`.

**Returns** A descriptor with vertex array information.

**Return type** VertexArrayObject

## Examples

```
# create a VAO vaoDesc = createVAO(vboVerts, vboTexCoords, vboNormals)
```

```
# draw the VAO, renders the mesh drawVAO(vaoDesc, GL.GL_TRIANGLES)
```

```
psychopy.tools.gltools.drawVAO(vao, mode=4, flush=False)
```

Draw a vertex array using `glDrawArrays`. This method does not require shaders.

### Parameters

- **vao** (VertexArrayObject) – Vertex Array Object (VAO) to draw.
- **mode** (`int`, optional) – Drawing mode to use (e.g. `GL_TRIANGLES`, `GL_QUADS`, `GL_POINTS`, etc.)
- **flush** (`bool`, optional) – Flush queued drawing commands before returning.

**Returns**

**Return type** `None`

### Examples

```
# create a VAO vaoDesc = createVAO(vboVerts, vboTexCoords, vboNormals)
# draw the VAO, renders the mesh drawVAO(vaoDesc, GL.GL_TRIANGLES)
```

```
psychopy.tools.gltools.deleteVBO(vbo)
Delete a Vertex Buffer Object (VBO).
```

**Returns**

**Return type** `obj:None`

```
psychopy.tools.gltools.deleteVAO(vao)
Delete a Vertex Array Object (VAO). This does not delete array buffers bound to the VAO.
```

**Returns**

**Return type** `obj:None`

```
psychopy.tools.gltools.createMaterial(params=(), textures=(), face=1032)
Create a new material.
```

**Parameters** **params** (`list` of `tuple`, optional) – List of material modes and values. Each mode is assigned a value as (mode, color). Modes can be `GL_AMBIENT`, `GL_DIFFUSE`, `GL_SPECULAR`, `GL_EMISSION`, `GL_SHININESS` or `GL_AMBIENT_AND_DIFFUSE`. Colors must be a tuple of 4 floats which specify reflectance values for each RGBA component. The value of `GL_SHININESS` should be a single float. If no values are specified, an empty material will be created.

**:param textures** `list` of `tuple`, optional: List of texture units and `TexImage2D` descriptors. These will be written to the 'textures' field of the returned descriptor. For example, `[(GL.GL_TEXTURE0, texDesc0), (GL.GL_TEXTURE1, texDesc1)]`. The number of texture units per-material is `GL_MAX_COMBINED_TEXTURE_IMAGE_UNITS`.

**Parameters** **face** (`int`, optional) – Faces to apply material to. Values can be `GL_FRONT_AND_BACK`, `GL_FRONT` and `GL_BACK`. The default is `GL_FRONT_AND_BACK`.

**Returns** A descriptor with material properties.

**Return type** `Material`

### Examples

```
# The values for the material below can be found at # http://devernay.free.fr/cours/opengl/materials.html
# create a gold material gold = createMaterial([
```

```
(GL.GL_AMBIENT, (0.24725, 0.19950, 0.07450, 1.0)), (GL.GL_DIFFUSE, (0.75164, 0.60648,
0.22648, 1.0)), (GL.GL_SPECULAR, (0.628281, 0.555802, 0.366065, 1.0)), (GL.GL_SHININESS,
0.4 * 128.0))]
```

```
# use the material when drawing useMaterial(gold) drawVAO( ... ) # all meshes will be gold useMaterial(None)
# turn off material when done
```

```
# create a red plastic material, but define reflectance and shine later red_plastic = createMaterial()
```

```
# you need to convert values to ctypes! red_plastic.values[GL_AMBIENT] = (GLfloat * 4)(0.0, 0.0, 0.0, 1.0)
red_plastic.values[GL_DIFFUSE] = (GLfloat * 4)(0.5, 0.0, 0.0, 1.0) red_plastic.values[GL_SPECULAR] =
(GLfloat * 4)(0.7, 0.6, 0.6, 1.0) red_plastic.values[GL_SHININESS] = 0.25 * 128.0
```

```
# set and draw useMaterial(red_plastic) drawVertexbuffers( ... ) # all meshes will be red plastic useMaterial(None)
```

`psychopy.tools.gltools.useMaterial(material, useTextures=True)`

Use a material for proceeding vertex draws.

#### Parameters

- **material** (`Material` or `None`) – Material descriptor to use. Default material properties are set if `None` is specified. This is equivalent to disabling materials.
- **useTextures** (`bool`) – Enable textures. Textures specified in a material descriptor’s ‘texture’ attribute will be bound and their respective texture units will be enabled. Note, when disabling materials, the value of `useTextures` must match the previous call. If there are no textures attached to the material, `useTexture` will be silently ignored.

#### Returns

**Return type** `None`

#### Notes

1. If a material mode has a value of `None`, a color with all components 0.0 will be assigned.
2. Material colors and shininess values are accessible from shader programs after calling ‘useMaterial’. Values can be accessed via built-in ‘gl\_FrontMaterial’ and ‘gl\_BackMaterial’ structures (e.g. `gl_FrontMaterial.diffuse`).

#### Examples

```
# use the material when drawing useMaterial(metalMaterials.gold) drawVAO( ... ) # all meshes drawn will be
gold useMaterial(None) # turn off material when done
```

`psychopy.tools.gltools.createLight(params=())`

Create a point light source.

`psychopy.tools.gltools.useLights(lights, setupOnly=False)`

Use specified lights in successive rendering operations. All lights will be transformed using the present modelview matrix.

#### Parameters

- **lights** (`List of Light` or `None`) – Descriptor of a light source. If `None`, lighting is disabled.
- **setupOnly** (`bool`, optional) – Do not enable lighting or lights. Specify `True` if lighting is being computed via fragment shaders.

## Returns

**Return type** `None`

`psychopy.tools.gltools.setAmbientLight` (*color*)

Set the global ambient lighting for the scene when lighting is enabled. This is equivalent to `GL.glLightModelfv(GL.GL_LIGHT_MODEL_AMBIENT, color)` and does not contribute to the `GL_MAX_LIGHTS` limit.

**Parameters** `color` (`tuple`) – Ambient lighting RGBA intensity for the whole scene.

## Returns

**Return type** `None`

## Notes

If unset, the default value is (0.2, 0.2, 0.2, 1.0) when `GL_LIGHTING` is enabled.

`psychopy.tools.gltools.loadObjFile` (*objFile*)

Load a Wavefront OBJ file (\*.obj).

**Parameters** `objFile` (`str`) – Path to the \*.OBJ file to load.

## Returns

**Return type** `WavefrontObjModel`

## Notes

1. This importer should work fine for most sanely generated files. Export your model with Blender for best results, even if you used some other package to create it.
2. The model must be triangulated, quad faces are not supported.

## Examples

```
# load a model from file objModel = loadObjFile('/path/to/file.obj')
# load the material (*.mtl) file, textures are also loaded materials = loadMtl('/path/to/' + objModel.mtlFile)
# apply settings GL.glEnable(GL.GL_CULL_FACE) GL.glEnable(GL.GL_DEPTH_TEST)
GL.glDepthFunc(GL.GL_LEQUAL) GL.glDepthMask(GL.GL_TRUE) GL.glShadeModel(GL.GL_SMOOTH)
GL.glCullFace(GL.GL_BACK) GL.glDisable(GL.GL_BLEND)
# lights useLights(light0)
# draw the model for group, vao in obj.drawGroups.items():
    useMaterial(materials[group]) drawVAO(vao)
# disable materials and lights useMaterial(None) useLights(None)
```

`psychopy.tools.gltools.loadMtlFile` (*mtlFilePath*, *texParameters=None*)

Load a material library (\*.mtl).

`psychopy.tools.gltools.getIntegerv` (*parName*)

Get a single integer parameter value, return it as a Python integer.

**Parameters** `pName` (`:obj:'int'`) – OpenGL property enum to query (e.g. `GL_MAJOR_VERSION`).



### Returns

**Return type** `int`

`psychopy.tools.gltools.getFloat(parName)`

Get a single float parameter value, return it as a Python float.

**Parameters** `pName (:obj:'float')` – OpenGL property enum to query.

### Returns

**Return type** `int`

`psychopy.tools.gltools.getString(parName)`

Get a single string parameter value, return it as a Python UTF-8 string.

**Parameters** `pName (:obj:'int')` – OpenGL property enum to query (e.g. `GL_VENDOR`).

### Returns

**Return type** `str`

`psychopy.tools.gltools.getOpenGLInfo()`

Get general information about the OpenGL implementation on this machine. This should provide a consistent means of doing so regardless of the OpenGL interface we are using.

Returns are dictionary with the following fields:

vendor, renderer, version, majorVersion, minorVersion, doubleBuffer, maxTextureSize, stereo, maxSamples, extensions

Supported extensions are returned as a list in the 'extensions' field. You can check if a platform supports an extension by checking the membership of the extension name in that list.

### Returns

**Return type** `OpenGLInfo`

## Examples

### Working with Framebuffer Objects (FBOs):

Creating an empty framebuffer with no attachments:

```
fbo = createFBO() # invalid until attachments are added
```

Create a render target with multiple color texture attachments:

```
colorTex = createTexImage2D(1024,1024) # empty texture
depthRb = createRenderbuffer(800,600,internalFormat=GL.GL_DEPTH24_STENCIL8)

GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, fbo.id)
attach(GL.GL_COLOR_ATTACHMENT0, colorTex)
attach(GL.GL_DEPTH_ATTACHMENT, depthRb)
attach(GL.GL_STENCIL_ATTACHMENT, depthRb)
# or attach(GL.GL_DEPTH_STENCIL_ATTACHMENT, depthRb)
GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, 0)
```

Attach FBO images using a context. This automatically returns to the previous FBO binding state when complete. This is useful if you don't know the current binding state:

```
with useFBO(fbo):
    attach(GL.GL_COLOR_ATTACHMENT0, colorTex)
    attach(GL.GL_DEPTH_ATTACHMENT, depthRb)
    attach(GL.GL_STENCIL_ATTACHMENT, depthRb)
```

How to set userData some custom function might access:

```
fbo.userData['flags'] = ['left_eye', 'clear_before_use']
```

Binding an FBO for drawing/reading:

```
GL.glBindFramebuffer(GL.GL_FRAMEBUFFER, fb.id)
```

Depth-only framebuffers are valid, sometimes need for generating shadows:

```
depthTex = createTexImage2D(800, 600,
                            internalFormat=GL.GL_DEPTH_COMPONENT24,
                            pixelFormat=GL.GL_DEPTH_COMPONENT)
fbo = createFBO([(GL.GL_DEPTH_ATTACHMENT, depthTex)])
```

Deleting a framebuffer when done with it. This invalidates the framebuffer's ID and makes it available for use:

```
deleteFBO(fbo)
```

## 8.20.5 psychopy.tools.imagetools

Functions and classes related to image handling

<i>array2image(a)</i>	Takes an array and returns an image object (PIL)
<i>image2array(im)</i>	Takes an image object (PIL) and returns a numpy array
<i>makeImageAuto(inarray)</i>	Combines float_uint8 and image2array operations ie.

### Function details

`psychopy.tools.imagetools.array2image(a)`

Takes an array and returns an image object (PIL)

`psychopy.tools.imagetools.image2array(im)`

Takes an image object (PIL) and returns a numpy array

`psychopy.tools.imagetools.makeImageAuto(inarray)`

Combines float\_uint8 and image2array operations ie. scales a numeric array from -1:1 to 0:255 and converts to PIL image format

## 8.20.6 psychopy.tools.mathtools

Assorted math functions for working with vectors, matrices, and quaternions. These functions are intended to provide basic support for common mathematical operations associated with displaying stimuli (e.g. animation, posing, rendering, etc.)

## Warning

Sub-routines used by functions here will perform arithmetic using the highest floating-point precision of the provided input arguments. Vectors provided as Python lists and tuples will be coerced into 64-bit floating-point arrays.

Various math functions for working with vectors, matrices, and quaternions.

<code>normalize(v)</code>	Normalize a vector or quaternion.
<code>lerp(v0, v1, t[, out])</code>	Linear interpolation (LERP) between two vectors/coordinates.
<code>slerp(q0, q1, t)</code>	Spherical linear interpolation (SLERP) between two quaternions.
<code>multQuat(q0, q1[, out])</code>	Multiply quaternion <i>q0</i> and <i>q1</i> .
<code>invertQuat(q)</code>	Get the multiplicative inverse of a quaternion.
<code>quatToAxisAngle(q[, degrees])</code>	Convert a quaternion to <i>axis</i> and <i>angle</i> representation.
<code>quatFromAxisAngle(axis, angle[, degrees])</code>	Create a quaternion to represent a rotation about <i>axis</i> vector by <i>angle</i> .
<code>matrixFromQuat(q[, out])</code>	Create a rotation matrix from a quaternion.
<code>scaleMatrix(s)</code>	Create a scaling matrix.
<code>rotationMatrix(angle, axis)</code>	Create a rotation matrix.
<code>translationMatrix(t)</code>	Create a translation matrix.
<code>concatenate(*args, **kwargs)</code>	Concatenate matrix transformations.
<code>applyMatrix(m, points[, out])</code>	Apply a transformation matrix over a 2D array of points.
<code>poseToMatrix(pos, ori[, out])</code>	Convert a pose to a 4x4 transformation matrix.

## Function details

`psychoPy.tools.mathtools.normalize(v)`

Normalize a vector or quaternion.

**v** [tuple, list or ndarray of float] Vector to normalize.

**Returns** Normalized vector *v*.

**Return type** ndarray

## Notes

- If the vector is degenerate (length is zero), a vector of all zeros is returned.

`psychoPy.tools.mathtools.lerp(v0, v1, t, out=None)`

Linear interpolation (LERP) between two vectors/coordinates.

### Parameters

- **v0** (tuple, list or ndarray of float) – Initial vector. Can be 2D where each row is a point.
- **v1** (tuple, list or ndarray of float) – Final vector. Must be the same shape as *v0*.
- **t** (float) – Interpolation weight factor [0, 1].
- **out** (ndarray, optional) – Optional output array. Must have the same *shape* and *dtype* as *v0*.

**Returns** Vector at  $t$  with same shape as  $v0$  and  $v1$ .

**Return type** ndarray

## Examples

Find the coordinate of the midpoint between two vectors:

```
u = [0., 0., 0.]
v = [0., 0., 1.]
midpoint = lerp(u, v, 0.5) # 0.5 to interpolate half-way between points
```

`psychoPy.tools.mathtools.slerp(q0, q1, t)`

Spherical linear interpolation (SLERP) between two quaternions.

Interpolation occurs along the shortest arc between the initial and final quaternion.

### Parameters

- **q0** (*tuple, list or ndarray of float*) – Initial quaternion in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- **q1** (*tuple, list or ndarray of float*) – Final quaternion in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- **t** (*float*) – Interpolation weight factor [0, 1].

**Returns** Quaternion [x, y, z, w] at  $t$ .

**Return type** ndarray

## Notes

- If the dot product between quaternions is  $>0.9995$ , linear interpolation is used instead of SLERP.

`psychoPy.tools.mathtools.multQuat(q0, q1, out=None)`

Multiply quaternion  $q0$  and  $q1$ .

The orientation of the returned quaternion is the combination of the input quaternions.

### Parameters

- **q1** ( $q0,$ ) – Quaternions to multiply in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- **out** (*ndarray or None*) – Alternative array to write values. Must be *shape* == (4,) and same *dtype* as the *dtype* argument.

**Returns** Combined orientation of  $q0$  and  $q1$ . Returns *None* if *out* is specified.

**Return type** ndarray

## Notes

- Quaternions are normalized prior to multiplication.

`psychopy.tools.mathtools.invertQuat(q)`

Get the multiplicative inverse of a quaternion.

This gives a quaternion which rotates in the opposite direction with equal magnitude. Multiplying a quaternion by its inverse returns an identity quaternion as both orientations cancel out.

**Parameters** `q` (*ndarray, list, or tuple of float*) – Quaternion to invert in form [x, y, z, w] where w is real and x, y, z are imaginary components.

**Returns** Inverse of quaternion `q`.

**Return type** ndarray

## Examples

Show that multiplying a quaternion by its inverse returns an identity quaternion where [x=0, y=0, z=0, w=1]:

```
angle = 90.0
axis = [0., 0., -1.]
q = quatFromAxisAngle(axis, angle, degrees=True)
qinv = invertQuat(q)
qr = multQuat(q, qinv)
qi = np.array([0., 0., 0., 1.]) # identity quaternion
print(np.allclose(qi, qr)) # True
```

## Notes

- Quaternions are normalized prior to inverting.

`psychopy.tools.mathtools.quatToAxisAngle(q, degrees=False)`

Convert a quaternion to *axis* and *angle* representation.

This allows you to use quaternions to set the orientation of stimuli that have an *ori* property.

### Parameters

- `q` (*tuple, list or ndarray of float*) – Quaternion in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- `degrees` (*bool*) – Indicate *angle* is to be returned in degrees, otherwise *angle* will be returned in radians.

**Returns** Axis and angle of quaternion in form ([ax, ay, az], angle). If *degrees* is *True*, the angle returned is in degrees, radians if *False*.

**Return type** tuple

## Examples

Using a quaternion to rotate a stimulus each frame:

```
# initial orientation, axis rotates in the Z direction
qr = quatFromAxisAngle(0.0, [0., 0., -1.], degrees=True)
# rotation per-frame, here it's 0.1 degrees per frame
qf = quatFromAxisAngle(0.1, [0., 0., -1.], degrees=True)
```

(continues on next page)

(continued from previous page)

```
# ---- within main experiment loop ----
# myStim is a GratingStim or anything with an 'ori' argument which
# accepts angle in degrees
qr = multQuat(qr, qf) # cumulative rotation
_, angle = quatToAxisAngle(qr) # discard axis, only need angle
myStim.ori = angle
myStim.draw()
```

`psychopy.tools.mathtools.quatFromAxisAngle` (*axis*, *angle*, *degrees=False*)

Create a quaternion to represent a rotation about *axis* vector by *angle*.

#### Parameters

- **axis** (*tuple*, *list* or *ndarray* of *float*) – Axis of rotation [x, y, z].
- **angle** (*float*) – Rotation angle in radians (or degrees if *degrees* is *True*. Rotations are right-handed about the specified *axis*.
- **degrees** (*bool*) – Indicate *angle* is in degrees, otherwise *angle* will be treated as radians.

**Returns** Quaternion [x, y, z, w].

**Return type** *ndarray*

### Examples

Create a quaternion from specified *axis* and *angle*:

```
axis = [0., 0., -1.] # rotate about -Z axis
angle = 90.0 # angle in degrees
ori = quatFromAxisAngle(axis, angle, degrees=True) # using degrees!
```

`psychopy.tools.mathtools.matrixFromQuat` (*q*, *out=None*)

Create a rotation matrix from a quaternion.

#### Parameters

- **q** (*tuple*, *list* or *ndarray* of *float*) – Quaternion to convert in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- **out** (*ndarray* or *None*) – Alternative array to write values. Must be *shape* == (4,4,) and same *dtype* as the *dtype* argument.

**Returns** 4x4 rotation matrix in row-major order. Returns *None* if *out* is specified.

**Return type** *ndarray* or *None*

### Examples

Convert a quaternion to a rotation matrix:

```
point = [0., 1., 0., 1.] # 4-vector form [x, y, z, 1.0]
ori = [0., 0., 0., 1.]
rotMat = matrixFromQuat(ori)
# rotate 'point' using matrix multiplication
newPoint = np.matmul(rotMat.T, point) # returns [-1., 0., 0., 1.]
```

Rotate all points in an array (each row is a coordinate):

```
points = np.asarray([[0., 0., 0., 1.],
                    [0., 1., 0., 1.],
                    [1., 1., 0., 1.]])
newPoints = points.dot(rotMat)
```

## Notes

- Quaternions are normalized prior to conversion.

`psychopy.tools.mathtools.scaleMatrix(s)`

Create a scaling matrix.

The resulting matrix is the same as a generated by a *glScale* call.

**Parameters** *s* (*ndarray*, *tuple*, or *list of float*) – Scaling factors [sx, sy, sz].

**Returns** 4x4 scaling matrix in row-major order.

**Return type** *ndarray*

`psychopy.tools.mathtools.rotationMatrix(angle, axis)`

Create a rotation matrix.

The resulting matrix will rotate points about *axis* by *angle*. The resulting matrix is similar to that produced by a *glRotate* call.

**Parameters**

- **angle** (*float*) – Rotation angle in degrees.
- **axis** (*ndarray*, *list*, or *tuple of float*) – Axis vector components.

**Returns** 4x4 scaling matrix in row-major order.

**Return type** *ndarray*

## Notes

- Vector *axis* is normalized before creating the matrix.

`psychopy.tools.mathtools.translationMatrix(t)`

Create a translation matrix.

The resulting matrix is the same as generated by a *glTranslate* call.

**Parameters** *t* (*ndarray*, *tuple*, or *list of float*) – Translation vector [tx, ty, tz].

**Returns** 4x4 translation matrix in row-major order.

**Return type** *ndarray*

`psychopy.tools.mathtools.concatenate(*args, **kwargs)`

Concatenate matrix transformations.

Combine transformation matrices into a single matrix. This is similar to what occurs when building a matrix stack in OpenGL using *glRotate*, *glTranslate*, and *glScale* calls. Matrices are multiplied together from right-to-left, or the last argument to first. Note that changing the order of the input matrices changes the final result.

**Parameters**

- **\*args** – 4x4 matrices to combine of type *ndarray*. Matrices are multiplied from right-to-left.
- **out** (*ndarray*) – Optional 4x4 output array. All computations will use the data type of this array.

**Returns** Concatenation of input matrices as a 4x4 matrix in row-major order. *None* is returned if *out* was specified.

**Return type** *ndarray*

## Examples

Create an SRT (scale, rotate, and translate) matrix to convert model-space coordinates to world-space:

```
S = scaleMatrix([2.0, 2.0, 2.0]) # scale model 2x
R = rotationMatrix(-90., [0., 0., -1]) # rotate -90 about -Z axis
T = translationMatrix([0., 0., -5.]) # translate point 5 units away
SRT = concatenate(S, R, T)

# transform a point in model-space coordinates to world-space
pointModel = np.array([0., 1., 0., 1.])
pointWorld = np.matmul(SRT, pointModel.T) # point in WCS
```

Create a model-view matrix from a world-space pose represented by an orientation (quaternion) and position (vector). The resulting matrix will transform model-space coordinates to eye-space:

```
# stimulus pose as quaternion and vector
stimOri = quatFromAxisAngle([0., 0., -1.], -45.0)
stimPos = [0., 1.5, -5.]

# create model matrix
R = matrixFromQuat(stimOri)
T = translationMatrix(stimPos)
M = concatenate(R, T) # model matrix

# create a view matrix, can also be represented as 'pos' and 'ori'
eyePos = [0., 1.5, 0.]
eyeFwd = [0., 0., -1.]
eyeUp = [0., 1., 0.]
V = lookAt(eyePos, eyeFwd, eyeUp) # from viewtools

# modelview matrix
MV = concatenate(M, V)
```

You can put the created matrix in the OpenGL matrix stack as shown below. Note that the matrix must have a 32-bit floating-point data type and needs to be loaded transposed.:

```
GL.glMatrixMode(GL.GL_MODELVIEW)
MV = np.asarray(MV, dtype='float32') # must be 32-bit float!
ptrMV = MV.ctypes.data_as(ctypes.POINTER(ctypes.c_float))
GL.glLoadTransposeMatrixf(ptrMV)
```

Furthermore, you can go from model-space to homogeneous clip-space by concatenating the projection, view, and model matrices:



```
# compute projection matrix, functions here are from 'viewtools'
screenWidth = 0.52
screenAspect = w / h
scrDistance = 0.55
frustum = computeFrustum(screenWidth, screenAspect, scrDistance)
P = perspectiveProjectionMatrix(*frustum)

# multiply model-space points by MVP to convert them to clip-space
MVP = concatenate(M, V, P)
pointModel = np.array([0., 1., 0., 1.])
pointClipSpace = np.matmul(MVP, pointModel.T)
```

`psychopy.tools.mathtools.applyMatrix` (*m*, *points*, *out=None*)

Apply a transformation matrix over a 2D array of points.

#### Parameters

- **m** (*ndarray*) – Transformation matrix.
- **points** (*ndarray*) – 2D array of points/coordinates to transform, where each row is a single point and the number of columns should match the dimensions of the matrix.
- **out** (*ndarray*, *optional*) – Optional output array to write values. Must be same *shape* and *dtype* as *points*.

**Returns** Transformed points. If *None* if *out* was specified.

**Return type** `ndarray` or `None`

#### Examples

Transform an array of points by some transformation matrix:

```
S = scaleMatrix([5.0, 5.0, 5.0]) # scale 2x
R = rotationMatrix(180., [0., 0., -1]) # rotate 180 degrees
T = translationMatrix([0., 1.5, -3.]) # translate point up and away
M = concatenate(S, R, T) # create transform matrix

# points to transform, must be 2D!
points = np.array([[0., 1., 0., 1.], [-1., 0., 0., 1.]]) # [x, y, z, w]
newPoints = applyMatrix(M, points) # apply the transformation
```

Extract the 3x3 rotation sub-matrix from a 4x4 matrix and apply it to points. Here the result is written to an already allocated array:

```
points = np.array([[0., 1., 0.], [-1., 0., 0.]]) # [x, y, z]
outPoints = np.zeros(points.shape)
M = rotationMatrix(90., [1., 0., 0.])
M3x3 = M[:3, :3] # extract rotation groups from the 4x4 matrix
# apply transformations, write to result to existing array
applyMatrix(M3x3, points, out=outPoints)
```

`psychopy.tools.mathtools.poseToMatrix` (*pos*, *ori*, *out=None*)

Convert a pose to a 4x4 transformation matrix.

A pose is represented by a position coordinate *pos* and orientation quaternion *ori*.

#### Parameters

- **pos** (*ndarray, tuple, or list of float*) – Position vector [x, y, z].
- **ori** (*tuple, list or ndarray of float*) – Orientation quaternion in form [x, y, z, w] where w is real and x, y, z are imaginary components.
- **out** (*ndarray, optional*) – Optional output array for 4x4 matrix. All computations will use the data type of this array.

**Returns** 4x4 transformation matrix. Returns *None* if *out* is specified.

**Return type** ndarray

## 8.20.7 psychopy.tools.monitorunittools

Functions and classes related to unit conversion respective to a particular monitor

<code>convertToPix(vertices, pos, units, win)</code>	Takes vertices and position, combines and converts to pixels from any unit
<code>cm2deg(cm, monitor[, correctFlat])</code>	Convert size in cm to size in degrees for a given Monitor object
<code>cm2pix(cm, monitor)</code>	Convert size in cm to size in pixels for a given Monitor object.
<code>deg2cm(degrees, monitor[, correctFlat])</code>	Convert size in degrees to size in pixels for a given Monitor object.
<code>deg2pix(degrees, monitor[, correctFlat])</code>	Convert size in degrees to size in pixels for a given Monitor object
<code>pix2cm(pixels, monitor)</code>	Convert size in pixels to size in cm for a given Monitor object
<code>pix2deg(pixels, monitor[, correctFlat])</code>	Convert size in pixels to size in degrees for a given Monitor object

### Function details

`psychopy.tools.monitorunittools.convertToPix(vertices, pos, units, win)`

Takes vertices and position, combines and converts to pixels from any unit

The reason that *pos* and *vertices* are provided separately is that it allows the conversion from deg to apply flat-screen correction to each separately.

The reason that these use function args rather than relying on *self.pos* is that some stimuli use other terms (e.g. *ElementArrayStim* uses *fieldPos*).

`psychopy.tools.monitorunittools.cm2deg(cm, monitor, correctFlat=False)`

Convert size in cm to size in degrees for a given Monitor object

`psychopy.tools.monitorunittools.cm2pix(cm, monitor)`

Convert size in cm to size in pixels for a given Monitor object.

`psychopy.tools.monitorunittools.deg2cm(degrees, monitor, correctFlat=False)`

Convert size in degrees to size in pixels for a given Monitor object.

If *correctFlat == False* then the screen will be treated as if all points are equal distance from the eye. This means that each “degree” will be the same size irrespective of its position.

If *correctFlat == True* then the *degrees* argument must be an Nx2 matrix for X and Y values (the two cannot be calculated separately in this case).

With `correctFlat == True` the positions may look strange because more eccentric vertices will be spaced further apart.

`psychoPy.tools.monitorunittools.deg2pix` (*degrees, monitor, correctFlat=False*)

Convert size in degrees to size in pixels for a given Monitor object

`psychoPy.tools.monitorunittools.pix2cm` (*pixels, monitor*)

Convert size in pixels to size in cm for a given Monitor object

`psychoPy.tools.monitorunittools.pix2deg` (*pixels, monitor, correctFlat=False*)

Convert size in pixels to size in degrees for a given Monitor object

## 8.20.8 `psychoPy.tools.plottools`

Functions and classes related to plotting

`psychoPy.tools.plottools.plotFrameIntervals` (*intervals*)

Plot a histogram of the frame intervals.

Where *intervals* is either a filename to a file, saved by `Window.saveFrameIntervals`, or simply a list (or array) of frame intervals

## 8.20.9 `psychoPy.tools.rifttools`

## 8.20.10 `psychoPy.tools.typetools`

Functions and classes related to variable type conversion

`psychoPy.tools.typetools.float_uint8` (*inarray*)

Converts arrays, lists, tuples and floats ranging -1:1 into an array of Uint8s ranging 0:255

```
>>> float_uint8(-1)
0
>>> float_uint8(0)
128
```

`psychoPy.tools.typetools.uint8_float` (*inarray*)

Converts arrays, lists, tuples and UINTs ranging 0:255 into an array of floats ranging -1:1

```
>>> uint8_float(0)
-1.0
>>> uint8_float(128)
0.0
```

`psychoPy.tools.typetools.float_uint16` (*inarray*)

Converts arrays, lists, tuples and floats ranging -1:1 into an array of Uint16s ranging 0:2<sup>16</sup>

```
>>> float_uint16(-1)
0
>>> float_uint16(0)
32768
```

## 8.20.11 `psychoPy.tools.unittools`

Functions and classes related to unit conversion

`psychoPy.tools.unittools.radians` (*x*, /, *out=None*, \*, *where=True*, *casting='same\_kind'*, *order='K'*, *dtype=None*, *subok=True* [, *signature*, *extobj* ])

Convert angles from degrees to radians.

#### Parameters

- **x** (*array\_like*) – Input array in degrees.
- **out** (*ndarray, None, or tuple of ndarray and None, optional*) – A location into which the result is stored. If provided, it must have a shape that the inputs broadcast to. If not provided or *None*, a freshly-allocated array is returned. A tuple (possible only as a keyword argument) must have length equal to the number of outputs.
- **where** (*array\_like, optional*) – Values of True indicate to calculate the ufunc at that position, values of False indicate to leave the value in the output alone.
- **\*\*kwargs** – For other keyword-only arguments, see the ufunc docs.

**Returns** *y* – The corresponding radian values. This is a scalar if *x* is a scalar.

**Return type** ndarray

See also:

`deg2rad()` equivalent function

#### Examples

Convert a degree array to radians

```
>>> deg = np.arange(12.) * 30.
>>> np.radians(deg)
array([ 0.          ,  0.52359878,  1.04719755,  1.57079633,  2.0943951 ,
        2.61799388,  3.14159265,  3.66519143,  4.1887902 ,  4.71238898,
        5.23598776,  5.75958653])
```

```
>>> out = np.zeros((deg.shape))
>>> ret = np.radians(deg, out)
>>> ret is out
True
```

`psychoPy.tools.unittools.degrees` (*x*, /, *out=None*, \*, *where=True*, *casting='same\_kind'*, *order='K'*, *dtype=None*, *subok=True* [, *signature*, *extobj* ])

Convert angles from radians to degrees.

#### Parameters

- **x** (*array\_like*) – Input array in radians.
- **out** (*ndarray, None, or tuple of ndarray and None, optional*) – A location into which the result is stored. If provided, it must have a shape that the inputs broadcast to. If not provided or *None*, a freshly-allocated array is returned. A tuple (possible only as a keyword argument) must have length equal to the number of outputs.
- **where** (*array\_like, optional*) – Values of True indicate to calculate the ufunc at that position, values of False indicate to leave the value in the output alone.
- **\*\*kwargs** – For other keyword-only arguments, see the ufunc docs.

**Returns** *y* – The corresponding degree values; if *out* was supplied this is a reference to it. This is a scalar if *x* is a scalar.

**Return type** ndarray of floats

**See also:**

**rad2deg()** equivalent function

## Examples

Convert a radian array to degrees

```
>>> rad = np.arange(12.)*np.pi/6
>>> np.degrees(rad)
array([  0.,  30.,  60.,  90., 120., 150., 180., 210., 240.,
        270., 300., 330.] )
```

```
>>> out = np.zeros((rad.shape))
>>> r = degrees(rad, out)
>>> np.all(r == out)
True
```

## 8.20.12 psychopy.tools.viewtools

Tools for working with view projections for 2- and 3-D rendering.

<i>computeFrustum</i> (scrWidth, scrAspect, scrDist)	Calculate frustum parameters.
<i>generalizedPerspectiveProjection</i> (...[, ...])	Generalized derivation of projection and view matrices based on the physical configuration of the display system.
<i>orthoProjectionMatrix</i> (left, right, bottom, ...)	Compute an orthographic projection matrix with provided frustum parameters.
<i>perspectiveProjectionMatrix</i> (left, right, ...)	Compute an perspective projection matrix with provided frustum parameters.
<i>lookAt</i> (eyePos, centerPos[, upVec])	Create a transformation matrix to orient a view towards some point.
<i>pointToNdc</i> (wcsPos, viewMatrix, projectionMatrix)	Map the position of a point in world space to normalized device coordinates/space.

## Function details

`psychopy.tools.viewtools.computeFrustum` (*scrWidth*, *scrAspect*, *scrDist*, *convergeOffset*=0.0, *eyeOffset*=0.0, *nearClip*=0.01, *farClip*=100.0)

Calculate frustum parameters. If an eye offset is provided, an asymmetric frustum is returned which can be used for stereoscopic rendering.

### Parameters

- **scrWidth** (*float*) – The display’s width in meters.
- **scrAspect** (*float*) – Aspect ratio of the display (width / height).
- **scrDist** (*float*) – Distance to the screen from the view in meters. Measured from the center of their eyes.

- **convergeOffset** (*float*) – Offset of the convergence plane from the screen. Objects falling on this plane will have zero disparity. For best results, the convergence plane should be set to the same distance as the screen (0.0 by default).
- **eyeOffset** (*float*) – Half the inter-ocular separation (i.e. the horizontal distance between the nose and center of the pupil) in meters. If eyeOffset is 0.0, a symmetric frustum is returned.
- **nearClip** (*float*) – Distance to the near clipping plane in meters from the viewer. Should be at least less than scrDist.
- **farClip** (*float*) – Distance to the far clipping plane from the viewer in meters. Must be >nearClip.

**Returns** Namedtuple with frustum parameters. Can be directly passed to glFrustum (e.g. glFrustum(\*f)).

**Return type** Frustum

## Notes

- The view point must be transformed for objects to appear correctly. Offsets in the X-direction must be applied +/- eyeOffset to account for inter-ocular separation. A transformation in the Z-direction must be applied to account for screen distance. These offsets **MUST** be applied to the GL\_MODELVIEW matrix, not the GL\_PROJECTION matrix! Doing so may break lighting calculations.

## Examples

Creating a frustum and setting a window's projection matrix:

```
scrWidth = 0.5 # screen width in meters
scrAspect = win.size[0] / win.size[1]
scrDist = win.scrDistCM * 100.0 # monitor setting, can be anything
frustum = viewtools.computeFrustum(scrWidth, scrAspect, scrDist)
```

Accessing frustum parameters:

```
left, right, bottom, top, nearVal, farVal = frustum
# ... or ...
left = frustum.left
```

Off-axis frustums for stereo rendering:

```
# compute view matrix for each eye, these value usually don't change
eyeOffset = (-0.035, 0.035) # +/- IOD / 2.0
scrDist = 0.50 # 50cm
scrWidth = 0.53 # 53cm
scrAspect = 1.778
leftFrustum = viewtools.computeFrustum(scrWidth, scrAspect, scrDist, eyeOffset[0])
rightFrustum = viewtools.computeFrustum(scrWidth, scrAspect, scrDist,
    ↪eyeOffset[1])
# make sure your view matrix accounts for the screen distance and eye offsets!
```

Using computed view frustums with a window:

```
win.projectionMatrix = viewtools.perspectiveProjectionMatrix(*frustum)
# generate a view matrix looking ahead with correct viewing distance,
# origin is at the center of the screen. Assumes eye is centered with
# the screen.
eyePos = [0.0, 0.0, scrDist]
screenPos = [0.0, 0.0, 0.0] # look at screen center
eyeUp = [0.0, 1.0, 0.0]
win.viewMatrix = viewtools.lookAt(eyePos, screenPos, eyeUp)
win.applyViewTransform() # call before drawing
```

`psychopy.tools.viewtools.generalizedPerspectiveProjection` (*posBottomLeft*, *posBottomRight*, *posTopLeft*, *eyePos*, *nearClip*=0.01, *farClip*=100.0)

Generalized derivation of projection and view matrices based on the physical configuration of the display system.

This implementation is based on Robert Kooima's 'Generalized Perspective Projection' method<sup>1</sup>.

#### Parameters

- **posBottomLeft** (*list of float or ndarray*) – Bottom-left 3D coordinate of the screen in meters.
- **posBottomRight** (*list of float or ndarray*) – Bottom-right 3D coordinate of the screen in meters.
- **posTopLeft** (*list of float or ndarray*) – Top-left 3D coordinate of the screen in meters.
- **eyePos** (*list of float or ndarray*) – Coordinate of the eye in meters.
- **nearClip** (*float*) – Near clipping plane distance from viewer in meters.
- **farClip** (*float*) – Far clipping plane distance from viewer in meters.

**Returns** The 4x4 projection and view matrix.

**Return type** `tuple`

See also:

`computeFrustum()` Compute frustum parameters.

#### Notes

- The resulting projection frustums are off-axis relative to the center of the display.
- The returned matrices are row-major. Values are floats with 32-bits of precision stored as a contiguous (C-order) array.

#### References

Electron. Eng. Comput. Sci.

<sup>1</sup> Kooima, R. (2009). Generalized perspective projection. J. Sch.

## Examples

Computing a projection and view matrices for a window:

```
projMatrix, viewMatrix = viewtools.generalizedPerspectiveProjection(
    posBottomLeft, posBottomRight, posTopLeft, eyePos)
# set the window matrices
win.projectionMatrix = projMatrix
win.viewMatrix = viewMatrix
# before rendering
win.applyEyeTransform()
```

Stereo-pair rendering example from Kooima (2009):

```
# configuration of screen and eyes
posBottomLeft = [-1.5, -0.75, -18.0]
posBottomRight = [1.5, -0.75, -18.0]
posTopLeft = [-1.5, 0.75, -18.0]
posLeftEye = [-1.25, 0.0, 0.0]
posRightEye = [1.25, 0.0, 0.0]
# create projection and view matrices
leftProjMatrix, leftViewMatrix = generalizedPerspectiveProjection(
    posBottomLeft, posBottomRight, posTopLeft, posLeftEye)
rightProjMatrix, rightViewMatrix = generalizedPerspectiveProjection(
    posBottomLeft, posBottomRight, posTopLeft, posRightEye)
```

`psychopy.tools.viewtools.orthoProjectionMatrix`(*left, right, bottom, top, nearClip, farClip*)

Compute an orthographic projection matrix with provided frustum parameters.

### Parameters

- **left** (*float*) – Left clipping plane coordinate.
- **right** (*float*) – Right clipping plane coordinate.
- **bottom** (*float*) – Bottom clipping plane coordinate.
- **top** (*float*) – Top clipping plane coordinate.
- **nearClip** (*float*) – Near clipping plane distance from viewer.
- **farClip** (*float*) – Far clipping plane distance from viewer.

**Returns** 4x4 projection matrix

**Return type** ndarray

See also:

[`perspectiveProjectionMatrix\(\)`](#) Compute a perspective projection matrix.

## Notes

- The returned matrix is row-major. Values are floats with 32-bits of precision stored as a contiguous (C-order) array.

`psychopy.tools.viewtools.perspectiveProjectionMatrix`(*left, right, bottom, top, nearClip, farClip*)

Compute an perspective projection matrix with provided frustum parameters. The frustum can be asymmetric.



### Parameters

- **left** (*float*) – Left clipping plane coordinate.
- **right** (*float*) – Right clipping plane coordinate.
- **bottom** (*float*) – Bottom clipping plane coordinate.
- **top** (*float*) – Top clipping plane coordinate.
- **nearClip** (*float*) – Near clipping plane distance from viewer.
- **farClip** (*float*) – Far clipping plane distance from viewer.

**Returns** 4x4 projection matrix

**Return type** ndarray

See also:

***orthoProjectionMatrix()*** Compute a orthographic projection matrix.

### Notes

- The returned matrix is row-major. Values are floats with 32-bits of precision stored as a contiguous (C-order) array.

`psychopy.tools.viewtools.lookAt(eyePos, centerPos, upVec=(0.0, 1.0, 0.0))`

Create a transformation matrix to orient a view towards some point. Based on the same algorithm as ‘gluLookAt’. This does not generate a projection matrix, but rather the matrix to transform the observer’s view in the scene.

For more information see: <https://www.khronos.org/registry/OpenGL-Refpages/gl2.1/xhtml/gluLookAt.xml>

### Parameters

- **eyePos** (*list of float or ndarray*) – Eye position in the scene.
- **centerPos** (*list of float or ndarray*) – Position of the object center in the scene.
- **upVec** (*list of float or ndarray, optional*) – Vector defining the up vector. Default is +Y is up.

**Returns** 4x4 view matrix

**Return type** ndarray

### Notes

- The returned matrix is row-major. Values are floats with 32-bits of precision stored as a contiguous (C-order) array.

`psychopy.tools.viewtools.pointToNdc(wcsPos, viewMatrix, projectionMatrix)`

Map the position of a point in world space to normalized device coordinates/space.

### Parameters

- **wcsPos** (*tuple, list or ndarray*) – 3x1 position vector(s) (xyz) in world space coordinates

- **viewMatrix** (*ndarray*) – 4x4 view matrix
- **projectionMatrix** (*ndarray*) – 4x4 projection matrix

**Returns** 3x1 vector of normalized device coordinates with type 'float32'

**Return type** ndarray

### Notes

- The point is not visible, falling outside of the viewing frustum, if the returned coordinates fall outside of -1 and 1 along any dimension.
- In the rare instance the point falls directly on the eye in world space where the frustum converges to a point (singularity), the divisor will be zero during perspective division. To avoid this, the divisor is 'bumped' to 1e-5.
- This function assumes the display area is rectilinear. Any distortion or warping applied in normalized device or viewport space is not considered.

### Examples

Determine if a point is visible:

```
point = (0.0, 0.0, 10.0) # behind the observer
ndc = pointToNdc(point, win.viewMatrix, win.projectionMatrix)
isVisible = not np.any((ndc > 1.0) | (ndc < -1.0))
```

Convert NDC to viewport (or pixel) coordinates:

```
scrRes = (1920, 1200)
point = (0.0, 0.0, -5.0) # forward -5.0 from eye
x, y, z = pointToNdc(point, win.viewMatrix, win.projectionMatrix)
pixelX = ((x + 1.0) / 2.0) * scrRes[0]
pixelY = ((y + 1.0) / 2.0) * scrRes[1]
# object at point will appear at (pixelX, pixelY)
```

## 8.21 psychopy.voicekey - Real-time sound processing

(Available as of version 1.83.00)

### 8.21.1 Overview

Hardware voice-keys are used to detect and signal acoustic properties in real time, e.g., the onset of a spoken word in word-naming studies. PsychoPy provides two virtual voice-keys, one for detecting vocal onsets and one for vocal offsets.

All PsychoPy voice-keys can take their input from a file or from a microphone. Event detection is typically quite similar in both cases.

The base class is very general, and is best thought of as providing a toolkit for developing a wide range of custom voice-keys. It would be possible to develop a set of voice-keys, each optimized for detecting different initial phonemes. Band-pass filtered data and zero-crossing counts are computed in real-time every 2ms.

## 8.21.2 Voice-Keys

**class** psychopy.voicekey.OnsetVoiceKey (*sec=0, file\_out="", file\_in="", \*\*config*)

Class for speech onset detection.

Uses bandpass-filtered signal (100-3000Hz). When the voice key trips, the best voice-onset RT estimate is saved as *self.event\_onset*, in sec.

### Parameters

**sec:** duration to record in seconds

**file\_out:** name for output filename (for microphone input)

**file\_in:** name of input file for sound source (not microphone)

config: kwargs dict of parameters for configuration. defaults are:

‘msPerChunk’: 2; duration of each real-time analysis chunk, in ms

‘signaler’: default None

‘autosave’: **True; False means manual saving to a file is still possible** (by calling *.save()* but not called automatically upon stopping

‘chnl\_in’ [microphone channel;] see *psychopy.sound.backend.get\_input\_devices()*

‘chnl\_out’: not implemented; output device to use

‘start’: 0, select section from a file based on (start, stop) time

‘stop’: -1, end of file (default)

‘vol’: 0.99, volume 0..1

‘low’: 100, Hz, low end of bandpass; can vary for M/F speakers

‘high’: 3000, Hz, high end of bandpass

‘threshold’: 10

‘baseline’: 0; 0 = auto-detect; give a non-zero value to use that

‘more\_processing’: **True; compute more stats per chunk including** bandpass; try False if 32-bit python can’t keep up

‘zero\_crossings’: True

### **\_do\_chunk** ()

Core function to handle a chunk (= a few ms) of input.

There can be small temporal gaps between or within chunks, i.e., *slippage*. Adjust several parameters until this is small: *msPerChunk*, and what processing is done within *.process()*.

A trigger (*\_chunktrig*) signals that *\_chunktable* has been filled and has set *\_do\_chunk* as the function to call upon triggering. *.play()* the trigger again to start recording the next chunk.

### **\_process** (*chunk*)

Calculate and store basic stats about the current chunk.

This gets called every chunk – keep it efficient, esp 32-bit python

### **\_set\_baseline** ()

Set *self.baseline* = rms(silent period) using *\_baselinetable* data.

Called automatically (via *pyo* trigger) when the baseline table is full. This is better than using chunks (which have gaps between them) or the whole table (which can be very large = slow to work with).

**\_set\_defaults()**

Set remaining defaults, initialize lists to hold summary stats

**\_set\_signaler()**

Set the signaler to be called by trip()

**\_set\_source()**

Data source: file\_in, array, or microphone

**\_set\_tables()**

Set up the pyo tables (allocate memory, etc).

One source -> three pyo tables: chunk=short, whole=all, baseline. triggers fill tables from self.\_source; make triggers in .start()

**detect()**

Trip if recent audio power is greater than the baseline.

**join(sec=None)**

Sleep for sec or until end-of-input, and then call stop().

**save(ftype="", dtype='int16')**

Save new data to file, return the size of the saved file (or None).

The file format is inferred from the filename extension, e.g., *flac*. This will be overridden by the *ftype* if one is provided; defaults to *wav* if nothing else seems reasonable. The optional *dtype* (e.g., *int16*) can be any of the sample types supported by *pyo*.

**slippage**

*Diagnostic* – Ratio of the actual (elapsed) time to the ideal time.

Ideal ratio = 1 = sample-perfect acquisition of msPerChunk, without any gaps between or within chunks.  
1. / slippage is the proportion of samples contributing to chunk stats.

**start(silent=False)**

Start reading and processing audio data from a file or microphone.

**started**

Boolean property, whether .start() has been called.

**stop()**

Stop a voice-key in progress.

Ends and saves the recording if using microphone input.

**wait\_for\_event(plus=0)**

Start, join, and wait until the voice-key trips, or it times out.

Optionally wait for some extra time, *plus*, before calling stop().

**class psychopy.voicekey.OffsetVoiceKey(sec=10, file\_out="", file\_in="", delay=0.3, \*\*kwargs)**

Class to detect the offset of a single-word utterance.

Record and ends the recording after speech offset. When the voice key trips, the best voice-offset RT estimate is saved as *self.event\_offset*, in seconds.

**Parameters**

**sec:** duration of recording in the absence of speech or other sounds.

**delay:** extra time to record after speech offset, default 0.3s.

The same methods are available as for class OnsetVoiceKey.

### 8.21.3 Signal-processing functions

Several utility functions are available for real-time sound analysis.

`psychoPy.voicekey.smooth` (*data*, *win*=16, *tile*=True)

Running smoothed average, via convolution over *win* window-size.

*tile* with the mean at start and end by default; otherwise replace with 0.

`psychoPy.voicekey.bandpass` (*data*, *low*=80, *high*=1200, *rate*=44100, *order*=6)

Return bandpass filtered *data*.

`psychoPy.voicekey.rms` (*data*)

Basic audio-power measure: root-mean-square of data.

Identical to *std* when the mean is zero; faster to compute just rms.

`psychoPy.voicekey.std` (*data*)

Like rms, but also subtracts the mean (= slower).

`psychoPy.voicekey.zero_crossings` (*data*)

Return a vector of length n-1 of zero-crossings within vector *data*.

1 if the adjacent values switched sign, or 0 if they stayed the same sign.

`psychoPy.voicekey.tone` (*freq*=440, *sec*=2, *rate*=44100, *vol*=0.99)

Return a np.array suitable for use as a tone (pure sine wave).

`psychoPy.voicekey.apodize` (*data*, *ms*=5, *rate*=44100)

Apply a Hanning window (5ms) to reduce a sound's 'click' onset / offset.

### 8.21.4 Sound file I/O

Several helper functions are available for converting and saving sound data from several data formats (numpy arrays, pyo tables) and file formats. All file formats that *pyo* supports are available, including *wav*, *flac* for lossless compression. *mp3* format is not supported (but you can convert to .wav using another utility).

`psychoPy.voicekey.samples_from_table` (*table*, *start*=0, *stop*=-1, *rate*=44100)

Return samples as a np.array read from a pyo table.

A (start, stop) selection in seconds may require a non-default rate.

`psychoPy.voicekey.table_from_samples` (*samples*, *start*=0, *stop*=-1, *rate*=44100)

Return a pyo DataTable constructed from samples.

A (start, stop) selection in seconds may require a non-default rate.

`psychoPy.voicekey.table_from_file` (*file\_in*, *start*=0, *stop*=-1)

Read data from files, any pyo format, returns (rate, pyo SndTable)

`psychoPy.voicekey.samples_from_file` (*file\_in*, *start*=0, *stop*=-1)

Read data from files, returns tuple (rate, np.array(.float64))

`psychoPy.voicekey.samples_to_file` (*samples*, *rate*, *file\_out*, *fmt*="", *dtype*='int16')

Write data to file, using requested format or infer from file .ext.

Only integer *rate* values are supported.

See <http://ajaxsoundstudio.com/pyodoc/api/functions/sndfile.html>

`psychoPy.voicekey.table_to_file` (*table*, *file\_out*, *fmt*="", *dtype*='int16')

Write data to file, using requested format or infer from file .ext.

## 8.22 psychopy.web - Web methods

### 8.22.1 Test for access

`psychopy.web.haveInternetAccess` (*forceCheck=False*)

Detect active internet connection or fail quickly.

If *forceCheck* is *False*, will rely on a cached value if possible.

`psychopy.web.requireInternetAccess` (*forceCheck=False*)

Checks for access to the internet, raise error if no access.

### 8.22.2 Proxy set-up and testing

`psychopy.web.setupProxy` (*log=True*)

Set up the urllib proxy if possible.

The function will use the following methods in order to try and determine proxies:

1. standard `urllib.request.urlopen` (which will use any statically-defined http-proxy settings)
2. previous stored proxy address (in prefs)
3. proxy.pac files if these have been added to system settings
4. auto-detect proxy settings (WPAD technology)

**Returns** True (success) or False (failure)

Further information:

## TROUBLESHOOTING

Regrettably, PsychoPy is not bug-free. Running on all possible hardware and all platforms is a big ask. That said, a huge number of bugs have been resolved by the fact that there are literally 1000s of people using the software that have *contributed either bug reports and/or fixes*.

Below are some of the more common problems and their workarounds, as well as advice on how to get further help.

### 9.1 The application doesn't start

You may find that you try to launch the PsychoPy application, the splash screen appears and then goes away and nothing more happens. What this means is that an error has occurred during startup itself.

Commonly, the problem is that a preferences file is somehow corrupt. To fix that see [Cleaning preferences and app data](#), below.

If resetting the preferences files doesn't help then we need to get to an error message in order to work out why the application isn't starting. The way to get that message depends on the platform (see below).

*Windows users* (starting from the Command Prompt):

1. Did you get an error message that “This application failed to start because the application configuration is incorrect. Reinstalling the application may fix the problem”? If so that indicates you need to [update your .NET installation to SP1](#).
2. **open a Command Prompt (terminal):**
  - (a) go to the Windows Start menu
  - (b) select Run... and type in cmd <Return>
3. paste the following into that window (Ctrl-V doesn't work in Cmd.exe but you can right-click and select Paste):

`"C:\Program Files\PsychoPy2\python.exe" -m psychopy.app.psychopyApp`
4. when you hit <return> you will hopefully get a moderately useful error message that you can *Contribute to the Forum* (mailing list)

*Mac users:*

1. open the Console app (open spotlight and type console)
2. if there are a huge number of messages there you might find it easiest to clear them (the brush icon) and then start PsychoPy again to generate a new set of messages

## 9.2 I run a Builder experiment and nothing happens

An error message may have appeared in a dialog box that is hidden (look to see if you have other open windows somewhere).

**An error message may have been generated that was sent to output of the Coder view:**

1. go to the Coder view (from the Builder>View menu if not visible)
2. if there is no Output panel at the bottom of the window, go to the View menu and select Output
3. try running your experiment again and see if an error message appears in this Output view

If you still don't get an error message but the application still doesn't start then manually turn off the viewing of the Output (as below) and try the above again.

## 9.3 Manually turn off the viewing of output

Very occasionally an error will occur that crashes the application *after* the application has opened the Coder Output window. In this case the error message is still not sent to the console or command prompt.

To turn off the Output view so that error messages are sent to the command prompt/terminal on startup, open your appData.cfg file (see [Cleaning preferences and app data](#)), find the entry:

```
[coder]
showOutput = True
```

and set it to `showOutput = False` (note the capital 'F').

## 9.4 Use the source (Luke?)

PsychoPy comes with all the source code included. You may not think you're much of a programmer, but have a go at reading the code. You might find you understand more of it than you think!

**To have a look at the source code do one of the following:**

- when you get an error message in the [Coder](#) click on the hyperlinked error lines to see the relevant code
- **on Windows**
  - go to *<location of PsychoPy app>\Lib\site-packages\psychopy*
  - have a look at some of the files there
- **on Mac**
  - right click the PsychoPy app and select *Show Package Contents*
  - navigate to *Contents/Resources/lib/pythonX.X/psychopy*

## 9.5 Cleaning preferences and app data

Every time you shut down PsychoPy (by normal means) your current preferences and the state of the application (the location and state of the windows) are saved to disk. If PsychoPy is crashing during startup you may need to edit those files or delete them completely.



The exact location of those files varies by machine but on windows it will be something like `%APPDATA%\psychopy3` and on Linux/MacOS it will be something like `~/psychopy3`. You can find it running this in the commandline (if you have multiple Python installations then make sure you change *python* to the appropriate one for PsychoPy:

```
python -c "from psychopy import prefs; print(prefs.paths['userPrefsDir'])"
```

Within that folder you will find *userPrefs.cfg* and *appData.cfg*. The files are simple text, which you should be able to edit in any text editor.

If the problem is that you have a corrupt experiment file or script that is trying and failing to load on startup, you could simply delete the *appData.cfg* file. Please *also Contribute to the Forum (mailing list)* a copy of the file that isn't working so that the underlying cause of the problem can be investigated (google first to see if it's a known issue).



## RECIPES (“HOW-TO”S)

Below are various tips/tricks/recipes/how-tos for PsychoPy. They involve something that is a little more involved than you would find in FAQs, but too specific for the manual as such (should they be there?).

### 10.1 Adding external modules to Standalone PsychoPy

You might find that you want to add some additional Python module/package to your Standalone version of PsychoPy. To do this you need to:

- download a copy of the package (make sure it’s for Python 2.7 on your particular platform)
- unzip/open it into a folder
- add that folder to the path of PsychoPy by one of the methods below

Avoid adding the entire path (e.g. the site-packages folder) of separate installation of Python, because that may contain conflicting copies of modules that PsychoPy is also providing.

#### 10.1.1 Using preferences

As of version 1.70.00 you can do this using the PsychoPy preferences/general. There you will find a preference for *paths* which can be set to a list of strings e.g. `['/Users/jwp/code', '~/code/thirdParty']`

These only get added to the Python path when you import psychopy (or one of the psychopy packages) in your script.

#### 10.1.2 Adding a .pth file

An alternative is to add a file into the site-packages folder of your application. This file should be pure text and have the extension .pth to indicate to Python that it adds to the path.

On win32 the site-packages folder will be something like:

`C:/Program Files/PsychoPy2/lib/site-packages`

On macOS you need to right-click the application icon, select ‘Show Package Contents’ and then navigate down to Contents/Resources/lib/python2.6. Put your .pth file here, next to the various libraries.

The advantage of this method is that you don’t need to do the import psychopy step. The downside is that when you update PsychoPy to a new major release you’ll need to repeat this step (patch updates won’t affect it though).

## 10.2 Animation

General question: How can I animate something?

Conceptually, animation just means that you vary some aspect of the stimulus over time. So the key idea is to draw something slightly different on each frame. This is how movies work, and the same principle can be used to create scrolling text, or fade-in / fade-out effects, and the like.

(copied & pasted from the email list; see the list for people's names and a working script.)

## 10.3 Scrolling text

Key idea: Vary the **position** of the stimulus across frames.

Question: How can I produce scrolling text (like html's <marquee behavior = "scroll" > directive)?

Answer: PsychoPy has animation capabilities built-in (it can even produce and export movies itself (e.g. if you want to show your stimuli in presentations)). But here you just want to animate stimuli directly.

e.g. create a text stimulus. In the 'pos' (position) field, type:

```
[frameN, 0]
```

and select "set every frame" in the popup button next to that field.

Push the Run button and your text will move from left to right, at one pixel per screen refresh, but stay at a fixed y-coordinate. In essence, you can enter an arbitrary formula in the position field and the stimulus will be-redrawn at a new position on each frame. frameN here refers to the number of frames shown so far, and you can extend the formula to produce what you need.

You might find performance issues (jittering motion) if you try to render a lot of text in one go, in which case you may have to switch to using images of text.

I wanted my text to scroll from right to left. So if you keep your eyes in the middle of the screen the next word to read would come from the right (as if you were actually reading text). The original formula posted above scrolls the other way. So, you have to put a negative sign in front of the formula for it to scroll the other way. You have to change the units to pixel. Also, you have to make sure you have an end time set, otherwise it just flickers. I also set my letter height to 100 pixels. The other problem I had was that I wanted the text to start blank and scroll into the screen. So, I wrote

```
[2000-frameN, 0]
```

and this worked really well.

## 10.4 Fade-in / fade-out effects

Key idea: vary the **opacity** of the stimulus over frames.

Question: I'd like to present an image with the image appearing progressively and disappearing progressively too. How to do that?

Answer: The Patch stimulus has an opacity field. Set the button next to it to be "set every frame" so that its value can be changed progressively, and enter an equation in the box that does what you want.

e.g. if your screen refresh rate is 60 Hz, then entering:

```
frameN/120
```

would cycle the opacity linearly from 0 to 1.0 over 2s (it will then continue incrementing but it doesn't seem to matter if the value exceeds 1.0).

Using a code component might allow you to do more sophisticated things (e.g. fade in for a while, hold it, then fade out). Or more simply, you just create multiple successive Patch stimulus components, each with a different equation or value in the opacity field depending on their place in the timeline.

## 10.5 Building an application from your script

A lot of people ask how they can build a standalone application from their Python script. Usually this is because they have a collaborator and want to just send them the experiment.

In general this is not advisable - the resulting bundle of files (single file on macOS) will be on the order of 100Mb and will not provide the end user with any of the options that they might need to control the task (for example, Monitor Center won't be provided so they can't to calibrate their monitor). A better approach in general is to get your collaborator to install the Standalone PsychoPy on their own machine, open your script and press run. (You don't send a copy of Microsoft Word when you send someone a document - you expect the reader to install it themselves and open the document).

Nonetheless, it is technically possible to create exe files on Windows, and Ricky Savjani (savjani at bcm.edu) has kindly provided the following instructions for how to do it. A similar process might be possible on macOS using py2app - if you've done that then feel free to contribute the necessary script or instructions.

### 10.5.1 Using py2exe to build an executable

Instructions:

1. Download and install py2exe (<http://www.py2exe.org/>)
2. Develop your PsychoPy script as normal
3. Copy this setup.py file into the same directory as your script
4. Change the Name of progName variable in this file to the Name of your desired executable program name
5. Use cmd (or bash, terminal, etc.) and run the following in the directory of your the two files: python setup.py py2exe
6. Open the 'dist' directory and run your executable

A example setup.py script:

```
# Created 8-09-2011
# Ricky Savjani
# (savjani at bcm.edu)

#import necessary packages
from distutils.core import setup
import os, matplotlib
import py2exe

#the name of your .exe file
progName = 'MultipleSchizophrenia.py'

#Initialize Holder Files
preference_files = []
app_files = []
```

(continues on next page)

(continued from previous page)

```
my_data_files=matplotlib.get_py2exe_datafiles()

#define which files you want to copy for data_files
for files in os.listdir('C:\\Program Files\\PsychoPy2\\Lib\\site-packages\\PsychoPy-1.
↳65.00-py2.6.egg\\psychopy\\preferences\\'):
    f1 = 'C:\\Program Files\\PsychoPy2\\Lib\\site-packages\\PsychoPy-1.65.00-py2.6.
↳egg\\psychopy\\preferences\\' + files
    preference_files.append(f1)

#if you might need to import the app files
#for files in os.listdir('C:\\Program Files\\PsychoPy2\\Lib\\site-packages\\PsychoPy-
↳1.65.00-py2.6.egg\\psychopy\\app\\'):
#    f1 = 'C:\\Program Files\\PsychoPy2\\Lib\\site-packages\\PsychoPy-1.65.00-py2.6.
↳egg\\psychopy\\app\\' + files
#    app_files.append(f1)

#all_files = [("psychopy\\preferences", preference_files), ("psychopy\\app", app_
↳files), my_data_files[0]]

#combine the files
all_files = [("psychopy\\preferences", preference_files), my_data_files[0]]

#define the setup
setup(
    console=[progName],
    data_files = all_files,
    options = {
        "py2exe":{
            "skip_archive": True,
            "optimize": 2
        }
    }
)
```

## 10.6 Builder - providing feedback

If you're using the Builder then the way to provide feedback is with a *Code Component* to generate an appropriate message (and then a text to present that message). PsychoPy will be keeping track of various aspects of the stimuli and responses for you throughout the experiment and the key is knowing where to find those.

The following examples assume you have a *Loop* called *trials*, containing a *Routine* with a *Keyboard Component* called *key\_resp*. Obviously these need to be adapted in the code below to fit your experiment.

---

**Note:** The following generate strings use python 'formatted strings'. These are very powerful and flexible but a little strange when you aren't used to them (they contain odd characters like `%2f`). See *Generating formatted strings* for more info.

---

### 10.6.1 Feedback after a trial

This is actually demonstrated in the demo, *ExtendedStroop* (in the Builder>demos menu, unpack the demos and then look in the menu again. tada!)

If you have a Keyboard Component called *key\_resp* then, after every trial you will have the following variables:

```
key_resp.keys #a python list of keys pressed
key_resp.rt #the time to the first key press
key_resp.corr #None, 0 or 1, if you are using 'store correct'
```

To create your *msg*, insert the following into the ‘start experiment’ section of the *Code Component*:

```
msg='doh!'#if this comes up we forgot to update the msg!
```

and then insert the following into the *Begin Routine* section (this will get run every repeat of the routine):

```
if not key_resp.keys :
    msg="Failed to respond"
elif resp.corr:#stored on last run routine
    msg="Correct! RT=%.3f" %(resp.rt)
else:
    msg="Oops! That was wrong"
```

## 10.6.2 Feedback after a block

In this case the feedback routine would need to come after the loop (the block of trials) and the message needs to use the stored data from the loop rather than the *key\_resp* directly. Accessing the data from a loop is not well documented but totally possible.

In this case, to get all the keys pressed in a *numpy* array:

```
trials.data['key_resp.keys'] #numpy array with size=[ntrials,ntypes]
```

If you used the ‘Store Correct’ feature of the Keyboard Component (and told psychopy what the correct answer was) you will also have a variable:

```
#numpy array storing whether each response was correct (1) or not (0)
trials.data['resp.corr']
```

So, to create your *msg*, insert the following into the ‘start experiment’ section of the *Code Component*:

```
msg='doh!'#if this comes up we forgot to update the msg!
```

and then insert the following into the *Begin Routine* section (this will get run every repeat of the routine):

```
nCorr = trials.data['key_resp.corr'].sum() #.std(), .mean() also available
meanRt = trials.data['key_resp.rt'].mean()
msg = "You got %i trials correct (rt=%.2f)" %(nCorr,meanRt)
```

## 10.6.3 Draw your message to the screen

Using one of the above methods to generate your *msg* in a *Code Component*, you then need to present it to the participant by adding a text to your *feedback* Routine and setting its text to *\$msg*.

**Warning:** The Text Component needs to be below the Code Component in the Routine (because it needs to be updated after the code has been run) and it needs to *set every repeat*.

## 10.7 Builder - terminating a loop

People often want to terminate their *Loops* before they reach the designated number of trials based on subjects' responses. For example, you might want to use a Loop to repeat a sequence of images that you want to continue until a key is pressed, or use it to continue a training period, until a criterion performance is reached.

To do this you need a *Code Component* inserted into your *routine*. All loops have an attribute called *finished* which is set to *True* or *False* (in Python these are really just other names for *1* and *0*). This *finished* property gets checked on each pass through the loop. So the key piece of code to end a loop called *trials* is simply:

```
trials.finished=True #or trials.finished=1 if you prefer
```

Of course you need to check the condition for that with some form of *if* statement.

**Example 1:** You have a change-blindness study in which a pair of images flashes on and off, with intervening blanks, in a loop called *presentationLoop*. You record the key press of the subject with a *Keyboard Component* called *resp1*. Using the 'ForceEndTrial' parameter of *resp1* you can end the current cycle of the loop but to end the loop itself you would need a *Code Component*. Insert the following two lines in the *End Routine* parameter for the Code Component, which will test whether more than zero keys have been pressed:

```
if resp1.keys is not None and len(resp1.keys)>0 :
    trials.finished=1
```

or:

```
if resp1.keys :
    presentationLoop.finished=1
```

**Example 2:** Sometimes you may have more possible trials than you can actually display. By default, a loop will present all possible trials (*nReps* \* *length-of-list*). If you only want to present the first 10 of all possible trials, you can use a code component to count how many have been shown, and then finish the loop after doing 10.

This example assumes that your loop is named 'trials'. You need to add two things, the first to initialize the count, and the second to update and check it.

*Begin Experiment:*

```
myCount = 0
```

*Begin Routine:*

```
myCount = myCount + 1
if myCount > 10:
    trials.finished = True
```

---

**Note:** In Python there is no *end* to finish an *if* statement. The content of the *if* or of a for-loop is determined by the indentation of the lines. In the above example only one line was indented so that one line will be executed if the statement evaluates to *True*.

---

## 10.8 Installing PsychoPy in a classroom (administrators)

For running PsychoPy in a classroom environment it is probably preferable to have a 'partial' network installation. The PsychoPy library features frequent new releases, including bug fixes and you want to be able to update machines



with these new releases. But PsychoPy depends on many other python libraries (over 200Mb in total) that tend not to change so rapidly, or at least not in ways critical to the running of experiments. If you install the whole PsychoPy application on the network then all of this data has to pass backwards and forwards, and starting the app will take even longer than normal.

The basic aim of this document is to get to a state whereby;

- Python and the major dependencies of PsychoPy are installed on the local machine (probably a disk image to be copied across your lab computers)
- PsychoPy itself (only ~2Mb) is installed in a network location where it can be updated easily by the administrator
- a file is created in the installation that provides the path to the network drive location
- Start-Menu shortcuts need to be set to point to the local Python but the remote PsychoPy application launcher

Once this is done, the vast majority of updates can be performed simply by replacing the PsychoPy library on the network drive.

### 10.8.1 1. Install dependencies locally

Download the latest version of the Standalone PsychoPy distribution, and run as administrator. This will install a copy of Python and many dependencies to a default location of

*C:\Program Files\PsychoPy2\*

### 10.8.2 2. Move the PsychoPy to the network

You need a network location that is going to be available, with read-only access, to all users on your machines. You will find all the contents of PsychoPy itself at something like this (version dependent obviously):

*C:\Program Files\PsychoPy2\Lib\site-packages\PsychoPy-1.70.00-py2.6.egg*

Move that entire folder to your network location and call it psychopyLib (or similar, getting rid of the version-specific part of the name). Now the following should be a valid path:

*<NETWORK\_LOC>\psychopyLib\psychopy*

### 10.8.3 3. Update the Python path

The Python installation (in C:\Program Files\PsychoPy2) needs to know about the network location. If Python finds a text file with extension *.pth* anywhere on its existing path then it will add to the path any valid paths it finds in the file. So create a text file that has one line in it:

*<NETWORK\_LOC>\psychopyLib*

You can test if this has worked. Go to *C:\Program Files\PsychoPy2* and double-click on python.exe. You should get a Python terminal window come up. Now try:

```
>>> import psychopy
```

If psychopy is not found on the path then there will be an import error. Try adjusting the *.pth* file, restarting python.exe and importing again.

## 10.8.4 4. Update the Start Menu

The shortcut in the Windows Start Menu will still be pointing to the local (now non-existent) PsychoPy library. Right-click it to change properties and set the shortcut to point to something like:

```
"C:\Program Files\PsychoPy2\pythonw.exe" "<NETWORK_LOC>
↪\psychopyLib\psychopy\app\psychopyApp.py"
```

You probably spotted from this that the PsychoPy app is simply a Python script. You may want to update the file associations too, so that *.psyexp* and *.py* are opened with:

```
"C:\Program Files\PsychoPy2\pythonw.exe" "<NETWORK_LOC>
↪\psychopyLib\psychopy\app\psychopyApp.py" "%1"
```

Lastly, to make the shortcut look pretty, you might want to update the icon too. Set the icon's location to:

```
"<NETWORK_LOC>\psychopyLib\psychopy\app\Resources\psychopy.ico"
```

## 10.8.5 5. Updating to a new version

Fetch the latest .zip release. Unpack it and replace the contents of *<NETWORK\_LOC>\psychopyLib\* with the contents of the zip file.

## 10.9 Generating formatted strings

A formatted string is a variable which has been converted into a string (text). In python the specifics of how this is done is determined by what kind of variable you want to print.

Example 1: You have an experiment which generates a string variable called *text*. You want to insert this variable into a string so you can print it. This would be achieved with the following code:

```
message = 'The result is %s' %(text)
```

This will produce a variable *message* which if used in a text object would print the phrase 'The result is' followed by the variable *text*. In this instance *%s* is used as the variable being entered is a string. This is a marker which tells the script where the variable should be entered. *%text* tells the script which variable should be entered there.

Multiple formatted strings (of potentially different types) can be entered into one string object:

```
longMessage = 'Well done %s that took %0.3f seconds' %(info['name'], time)
```

Some of the handy formatted string types:

```
>>> x=5
>>> x1=5124
>>> z='someText'
>>> 'show %s' %(z)
'show someText'
>>> '%0.1f' %(x)    #will show as a float to one decimal place
'5.0'
>>> '%3i' %(x)      #an integer, at least 3 chars wide, padded with spaces
'  5'
>>> '%03i' %(x)     #as above but pad with zeros (good for participant numbers)
'005'
```

See the [python documentation](#) for a more complete list.

## 10.10 Coder - interleave staircases

Often psychophysicists using staircase procedures want to interleave multiple staircases, either with different start points, or for different conditions.

There is now a class, `psychopy.data.MultiStairHandler` to allow simple access to interleaved staircases of either basic or QUEST types. That can also be used from the *Loops* in the *Builder*. The following method allows the same to be created in your own code, for greater options.

The method works by nesting a pair of loops, one to loop through the number of trials and another to loop across the staircases. The staircases can be shuffled between trials, so that they do not simply alternate.

**Note:** Note the need to create a *copy* of the info. If you simply do `thisInfo=info` then all your staircases will end up pointing to the same object, and when you change the info in the final one, you will be changing it for all.

```
from __future__ import print_function
from builtins import next
from builtins import range
from psychopy import visual, core, data, event
from numpy.random import shuffle
import copy, time #from the std python libs

#create some info to store with the data
info={}
info['startPoints']=[1.5,3,6]
info['nTrials']=10
info['observer']='jwp'

win=visual.Window([400,400])
#-----
#create the stimuli
#-----

#create staircases
stairs=[]
for thisStart in info['startPoints']:
    #we need a COPY of the info for each staircase
    #(or the changes here will be made to all the other staircases)
    thisInfo = copy.copy(info)
    #now add any specific info for this staircase
    thisInfo['thisStart']=thisStart #we might want to keep track of this
    thisStair = data.StairHandler(startVal=thisStart,
        extraInfo=thisInfo,
        nTrials=50, nUp=1, nDown=3,
        minVal = 0.5, maxVal=8,
        stepSizes=[4,4,2,2,1,1])
    stairs.append(thisStair)

for trialN in range(info['nTrials']):
    shuffle(stairs) #this shuffles 'in place' (ie stairs itself is changed, nothing_
    ↪returned)
    #then loop through our randomised order of staircases for this repeat
```

(continues on next page)

(continued from previous page)

```

for thisStair in stairs:
    thisIntensity = next(thisStair)
    print('start=%.2f, current=%.4f' % (thisStair.extraInfo['thisStart'],
↪thisIntensity))

    #-----
    #run your trial and get an input
    #-----
    keys = event.waitKeys() #(we can simulate by pushing left for 'correct')
    if 'left' in keys: wasCorrect=True
    else: wasCorrect = False

    thisStair.addData(wasCorrect) #so that the staircase adjusts itself

    #this trial (of all staircases) has finished
#all trials finished

#save data (separate pickle and txt files for each staircase)
dateStr = time.strftime("%b_%d_%H%M", time.localtime())#add the current time
for thisStair in stairs:
    #create a filename based on the subject and start value
    filename = "%s start%.2f %s" % (thisStair.extraInfo['observer'], thisStair.
↪extraInfo['thisStart'], dateStr)
    thisStair.saveAsPickle(filename)
    thisStair.saveAsText(filename)

```

## 10.11 Making isoluminant stimuli

From the mailing list (see there for names, etc):

### Q1: How can I create colours (RGB) that are isoluminant?

A1: The easiest way to create isoluminant stimuli (or control the luminance content) is to create the stimuli in DKL space and then convert them into RGB space for presentation on the monitor.

More details on DKL space can be found in the section about [Color spaces](#) and conversions between DKL and RGB can be found in the API reference for [psychopy.misc](#)

### Q2: There's a difference in luminance between my stimuli. How could I correct for that?

I'm running an experiment where I manipulate color chromatic saturation, keeping luminance constant. I've coded the colors (red and blue) in rgb255 for 6 saturation values (10%, 20%, 30%, 40%, 50%, 60%, 90%) using a conversion from HSL to RGB color space.

Note that we don't possess spectrophotometers such as PR650 in our lab to calibrate each color gun. I've calibrated the gamma of my monitor psychophysically. Gamma was set to 1.7 (threshold) for gamm(lum), gamma(R), gamma(G), gamma(B). Then I've measured the luminance of each stimuli with a Brontes colorimeter. But there's a difference in luminance between my stimuli. How could I correct for that?

A2: Without a spectroradiometer you won't be able to use the color spaces like DKL which are designed to help this sort of thing.

If you don't care about using a specific colour space though you should be able to deduce a series of isoluminant colors manually, because the luminance outputs from each gun should sum linearly. e.g. on my monitor:

```
maxR=46cd/m2
maxG=114
maxB=15
```

(note that green is nearly always brightest)

So I could make a 15cd/m2 stimulus using various appropriate fractions of those max values (requires that the screen is genuinely gamma-corrected):

```
R=0, G=0, B=255
R=255*15/46, G=0, B=0
R=255*7.5/46, G=255*15/114, B=0
```

Note that, if you want a pure fully-saturated blue, then you're limited by the monitor to how bright you can make your stimulus. If you want brighter colours your blue will need to include some of the other guns (similarly for green if you want to go above the max luminance for that gun).

A2.1. You should also consider that even if you set appropriate RGB values to display your pairs of chromatic stimuli at the same luminance that they might still appear different, particularly between observers (and even if your light measurement device says the luminance is the same, and regardless of the colour space you want to work in). To make the pairs perceptually isoluminant, each observer should really determine their own isoluminant point. You can do this with the minimum motion technique or with heterochromatic flicker photometry.

## 10.12 Adding a web-cam

From the mailing list (see there for names, etc):

"I spent some time today trying to get a webcam feed into my psychopy proj, inside my visual.window. The solution involved using the opencv module, capturing the image, converting that to PIL, and then feeding the PIL into a SimpleImageStim and looping and win.flipping. Also, to avoid looking like an Avatar in my case, you will have to change the default decoder used in PIL fromstring to utilize BGR instead of RGB in the decoding. I thought I would save some time for people in the future who might be interested in using a webcam feed for their psychopy project. All you need to do is import the opencv module into psychopy (importing modules was well documented by psychopy online) and integrate something like this into your psychopy script."

```
from __future__ import print_function

from psychopy import visual, event, core
import Image, time, pylab, cv, numpy

mywin = visual.Window(allowGUI=False, monitor='testMonitor', units='norm', colorSpace=
    ↳ 'rgb', color=[-1,-1,-1], fullscr=True)
mywin.setMouseVisible(False)

capture = cv.CaptureFromCAM(0)
img = cv.QueryFrame(capture)
pi = Image.fromstring("RGB", cv.GetSize(img), img.tostring(), "raw", "BGR", 0, 1)
print(pi.size)
myStim = visual.GratingStim(win=mywin, tex=pi, pos=[0,0.5], size = [0.6,0.6], opacity=
    ↳ 1.0, units = 'norm')
myStim.setAutoDraw(True)

while True:
    img = cv.QueryFrame(capture)
    pi = Image.fromstring("RGB", cv.GetSize(img), img.tostring(), "raw", "BGR", 0, 1)
```

(continues on next page)

(continued from previous page)

```
myStim.setTex(pi)
mywin.flip()
theKey = event.getKeys()
if len(theKey) != 0:
    break
```

## FREQUENTLY ASKED QUESTIONS (FAQS)

### 11.1 Why is the bits++ demo not working?

So far PsychoPy supports bits++ only in the bits++ mode (rather than mono++ or color++). In this mode, a code (the T-lock code) is written to the lookup table on the bits++ device by drawing a line at the top of the window. The most likely reason that the demo isn't working for you is that this line is not being detected by the device, and so the lookup table is not being modified. Most of these problems are actually nothing to do with PsychoPy /per se/, but to do with your graphics card and the CRS bits++ box itself.

There are a number of reasons why the T-lock code is not being recognised:

- the bits++ device is in the wrong mode. Open the utility that CRS supply and make sure you're in the right mode. Try resetting the bits++ (turn it off and on).
- the T-lock code is not fully on the screen. If you create a window that's too big for the screen or badly positioned then the code will be broken/not visible to the device.
- the T-lock code is on an 'odd' pixel.
- the graphics card is doing some additional filtering (win32). Make sure you turn off any filtering in the advanced display properties for your graphics card
- the gamma table of the graphics card is not set to be linear (but this should normally be handled by PsychoPy, so don't worry so much about it).
- you've got a Mac that's performing temporal dithering (new Macs, around 2009). Apple have come up with a new, very annoying idea, where they continuously vary the pixel values coming out of the graphics card every frame to create additional intermediate colours. This will break the T-lock code on 1/2-2/3rds of frames.

### 11.2 Can PsychoPy run my experiment with sub-millisecond timing?

This question is common enough and complex enough to have a section of the manual all of its own. See [\*Timing Issues and synchronisation\*](#)





## RESOURCES (E.G. FOR TEACHING)

There are a number of further resources to help learn/teach about PsychoPy.

If you also have PsychoPy materials/course then please let us know so that we can link to them from here too!

### 12.1 Workshops

At Nottingham we run an annual workshop on Python/PsychoPy (ie. programming, not Builder). Please see the page on officialWorkshops for further details.

### 12.2 Youtube tutorials

- [Youtube PsychoPy tutorial](#) showing how to build a basic experiment in the *Builder* interface. That's a great way to get started; build your own complete experiment in 15 minutes flat!
- There's also a [subtitled version of the stroop video tutorial](#) (Thanks Kevin Cole for doing that!)
- Jason Ozubko has added a series of great [PsychoPy Builder video tutorials](#) too
- Damien Mannion added a similarly great series of [PsychoPy programming videos on YouTube](#)

### 12.3 Materials for Builder

- The **most comprehensive guide** is the book [Building Experiments in PsychoPy](#) by Peirce and MacAskill. The book is suitable for a wide range of needs and skill sets, with 3 sections for:
  - The Beginner (suitable for undergraduate teaching)
  - The Professional (more detail for creating more precise studies)
  - The Specialist (with info about specialist needs such as studies in fMRI, EEG, ...)
- At [School of Psychology, University of Nottingham](#), PsychoPy is now used for all first year practical class teaching. The classes that comprise that first year course are provided below. They were created partially with funding from the former [Higher Education Academy Psychology Network](#). Note that the materials here will be updated frequently as they are further developed (e.g. to update screenshots etc) so make sure you have the latest version of them!

[PsychoPy\\_pracs\\_2011v2.zip](#) (21MB) (last updated: 15 Dec 2011)

- The [GestaltReVision group \(University of Leuven\) wiki](#) covering PsychoPy (some Builder info and great tutorials for Python/PsychoPy coding of experiments).

- There's a set of tools for [teaching psychophysics using PsychoPy](#) and a [PsychoPysics poster from VSS](#). Thanks James Ferwerda

## 12.4 Materials for Coder

- Please see the [page on official Workshops](#) for further details on coming to an intensive residential Python workshop in Nottingham.
  - Marco Bertamini's book, [Programming Illusions for Everyone](#) is a fun way to learn about stimulus rendering in PsychoPy by learning how to create visual illusions
  - [Gary Lupyan](#) runs a class on programming experiments using Python/PsychoPy and makes his lecture materials available [on this wiki](#)
  - The [GestaltReVision group](#) (University of Leuven) offers a [three-day crash course to Python and PsychoPy on a IPython Notebook](#), and has lots of great information taking you from basic programming to advanced techniques.
  - Radboud University, Nijmegen also has a [PsychoPy programming course](#)
  - [Programming for Psychology in Python - Vision Science](#) has lessons and screencasts on PsychoPy (by Damien Mannion, UNSW Australia).
- 

## 12.5 Previous events

- ECEM, August 2013 : Python for eye-tracking workshop with (Sol Simpson, Michael MacAskill and Jon Peirce). [Download Python-for-eye-tracking materials](#)
- VSS
- [Yale, 21-23 July](#) : The first ever dedicated PsychoPy workshop/conference was at Yale, 21-23 July 2011. Thanks Jeremy for organising!
- EPS Satellite workshop, 8 July 2011
- [BPS Maths Stats and Computing Section](#) workshop (Dec 2010):

For developers:

## FOR DEVELOPERS

There is a separate mailing list to discuss development ideas and issues.

For developers the best way to use PsychoPy is to install a version to your own copy of python (preferably 3.6 but we try to support a reasonable range). Make sure you have all the dependencies, including the extra suggestedPackages for developers.

Don't *install* PsychoPy. Instead fetch a copy of the git repository and add this to the python path using a .pth file. Other users of the computer might have their own standalone versions installed without your repository version touching them.

### 13.1 Using the repository

---

**Note:** Much of the following is explained with more detail in the [nitime documentation](#), and then in further detail in numerous online tutorials.

---

#### 13.1.1 Workflow

The use of git and the following workflow allows people to contribute changes that can easily be incorporated back into the project, while (hopefully) maintaining order and consistency in the code. All changes should be tracked and reversible.

- Create a fork of the central psychopy/psychopy repository
- Create a local clone of that fork
- **For small changes**
  - make the changes directly in the master branch
  - push back to your fork
  - submit a pull request to the central repository
- **For substantial changes (new features)**
  - create a branch
  - when finished run unit tests
  - when the unit tests pass merge changes back into the *master* branch
  - submit a pull request to the central repository

### 13.1.2 Create your own fork of the central repository

Go to [github](#), create an account and make a fork of the [psychopy repository](#). You can change your fork in any way you choose without it affecting the central project. You can also share your fork with others, including the central project.

### 13.1.3 Fetch a local copy

[Install git on your computer](#). Create and upload an ssh key to your github account - this is necessary for you to push changes back to your fork of the project at github.

Then, in a folder of your choosing fetch your fork:

```
$ git clone git@github.com:USER/psychopy.git
$ cd psychopy
$ git remote add upstream git://github.com/psychopy/psychopy.git
```

The last line connects your copy (with read access) to the central server so you can easily fetch any updates to the central repository.

### 13.1.4 Fetching the latest version

Periodically it's worth fetching any changes to the central psychopy repository (into your *master* branch, more on that below):

```
$ git checkout master
$ git pull upstream master # here 'master' is the desired branch of psychopy to fetch
```

### 13.1.5 Run PsychoPy using your local copy

Now that you've fetched the latest version of psychopy using git, you should run this version in order to try out yours/others latest improvements. See [this guide](#) on how to permanently run your git version of psychopy instead of the version you previously installed.

*Run git version for just one session (Linux and Mac only):* If you want to switch between the latest-and-greatest development version from git and the stable version installed on your system, you can choose to only temporarily run the git version. Open a terminal and set a temporary python path to your psychopy git folder:

```
$ export PYTHONPATH=/path/to/local/git/folder/
```

To check that worked you should open python in the terminal and try to import psychopy:

```
$ python
Python 2.7.6 (default, Mar 22 2014, 22:59:56)
[GCC 4.8.2] on linux2
Type "help", "copyright", "credits" or "license" for more information.
>>> import psychopy
```

PsychoPy depends on a lot of other packages and you may get a variety of failures to import them until you have them all installed in your custom environment!

### 13.1.6 Fixing bugs and making minor improvements

You can make minor changes directly in the *master* branch of your fork. After making a change you need to *commit* a set of changes to your files with a message. This enables you to group together changes and you will subsequently be able to go back to any previous *commit*, so your changes are reversible.

I (Jon) usually do this by opening the graphical user interface that comes with git:

```
$ git gui
```

From the GUI you can select (or *stage* in git terminology) the files that you want to include in this particular *commit* and give it a message. Give a clear summary of the changes for the first line. You can add more details about the changes on lower lines if needed.

If you have internet access then you could also push your changes back up to your fork (which is called your *origin* by default), either by pressing the *push* button in the GUI or by closing that and typing:

```
$ git push
```

### 13.1.7 Commit messages

Informative commit messages are really useful when we have to go back through the repository finding the time that a particular change to the code occurred. Precede your message with one or more of the following to help us spot easily if this is a bug fix (which might need pulling into other development branches) or new feature (which we might want to avoid pulling in if it might disrupt existing code).

- *BF* : bug fix
- *FF* : ‘feature’ fix. This is for fixes to code that hasn’t been released
- *RF* : refactoring
- *NF* : new feature
- *ENH* : enhancement (improvement to existing code)
- *DOC*: for all kinds of documentation related commits
- *TEST*: for adding or changing tests

When making commits that fall into several commit categories (e.g., BF and TEST), **please make separate commits for each category** and **avoid concatenating commit message prefixes**. E.g., please do not use *BF/TEST*, because this will affect how commit messages are sorted when we pull in fixes for each release.

NB: The difference between BF and FF is that BF indicates a fix that is appropriate for back-porting to earlier versions, whereas FF indicates a fix to code that has not been released, and so cannot be back-ported.

### 13.1.8 Share your improvement with others

Only a couple of people have direct write-access to the psychopy repository, but you can get your changes included in *upstream* by pushing your changes back to your github fork and then [submitting a pull request](#). Communication is good, and hopefully you have already been in touch (via the user or dev lists) about your changes.

When adding an improvement or new feature, consider how it might impact others. Is it likely to be generally useful, or is it something that only you or your lab would need? (It’s fun to contribute, but consider: does it actually need to be part of PsychoPy?) Including more features has a downside in terms of complexity and bloat, so try to be sure that there is a “business case” for including it. If there is, try at all times to be backwards compatible, e.g., by adding

a new keyword argument to a method or function (not always possible). If it's not possible, it's crucial to get wider input about the possible impacts. Flag situations that would break existing user scripts in your commit messages.

Part of sharing your code means making things sensible to others, which includes good coding style and writing some documentation. You are the expert on your feature, and so are in the best position to elaborate nuances or gotchas. Use meaningful variable names, and include comments in the code to explain non-trivial things, especially the intention behind specific choices. Include or edit the appropriate doc-string, because these are automatically turned into API documentation (via sphinx). Include doc-tests if that would be meaningful. The existing code base has a comment / code ratio of about 28%, which earns it high marks.

For larger changes and especially new features, you might need to create some usage examples, such as a new Coder demo, or even a Builder demo. These can be invaluable for being a starting point from which people can adapt things to the needs of their own situation. This is a good place to elaborate usage-related gotchas.

In terms of style, try to make your code blend in with and look like the existing code (e.g., using about the same level of comments, use camelCase for var names, despite the conflict with the usual PEP – we'll eventually move to the underscore style, but for now keep everything consistent within the code base). In your own code, write however you like of course. This is just about when contributing to the project.

### 13.1.9 Add a new feature branch

For more substantial work, you should create a new branch in your repository. Often while working on a new feature other aspects of the code will get broken and the *master* branch should always be in a working state. To create a new branch:

```
$ git branch feature-somethingNew
```

You can now switch to your new feature branch with:

```
$ git checkout feature-somethingNew
```

And get back to your *master* branch with:

```
$ git checkout master
```

You can push your new branch back to your fork (*origin*) with:

```
$ git push origin feature-somethingNew
```

### 13.1.10 Completing work on a feature

When you're done run the unit tests for your feature branch. Set the *debug* preference setting (in the app section) to True, and restart psychopy. This will enable access to the test-suite. In debug mode, from the Coder (not Builder) you can now do Ctrl-T / Cmd-T (see Tools menu, Unit Testing) to bring up the unit test window. You can select a subset of tests to run, or run them all.

It's also possible to run just selected tests, such as doctests within a single file. From a terminal window:

```
cd psychopy/tests/ #eg /Users/jgray/code/psychopy/psychopy/tests
./run.py path/to/file_with_doctests.py
```

If the tests pass you hopefully haven't damaged other parts of PsychoPy (!?). If possible add a unit test for your new feature too, so that if other people make changes they don't break your work!

You can merge your changes back into your master branch with:

```
$ git checkout master
$ git merge feature-somethingNew
```

Merge conflicts happen, and need to be resolved. If you configure your git preferences (`~/.gitconfig`) to include:

```
[merge]
    summary = true
    log = true
    tool = opendiff
```

then you'll be able to use a handy GUI interface (opendiff) for reviewing differences and conflicts, just by typing:

```
git mergetool
```

from the command line after hitting a merge conflict (such as during a *git pull upstream master*).

Once you've folded your new code back into your master and pushed it back to your github fork then it's time to *Share your improvement with others*.

## 13.2 Adding documentation

There are several ways to add documentation, all of them useful: doc strings, comments in the code, and demos to show an example of actual usage. To further explain something to end-users, you can create or edit a `.rst` file that will automatically become formatted for the web, and eventually appear on [www.psychopy.org](http://www.psychopy.org).

You make a new file under `psychopy/docs/source/`, either as a new file or folder or within an existing one.

To test that your doc source code (`.rst` file) does what you expect in terms of formatting for display on the web, you can simply do something like (this is my actual path, unlikely to be yours):

```
$ cd /Users/jgray/code/psychopy/docs/
$ make html
```

Do this within your docs directory (requires sphinx to be installed, try "easy\_install sphinx" if it's not working). That will add a `build/html` sub-directory.

Then you can view your new doc in a browser, e.g., for me:

<file:///Users/jgray/code/psychopy/docs/build/html/>

Push your changes to your github repository (using a "DOC:" commit message) and let Jon know, e.g. with a pull request.

## 13.3 Adding a new Builder Component

Builder Components are auto-detected and displayed to the experimenter as icons (in the right-most panel of the Builder interface panel). This makes it straightforward to add new ones.

All you need to do is create a list of parameters that the Component needs to know about (that will automatically appear in the Component's dialog) and a few pieces of code specifying what code should be called at different points in the script (e.g. beginning of the Routine, every frame, end of the study etc...). Many of these will come simply from subclassing the `_base` or `_visual` Components.

To get started, *Add a new feature branch* for the development of this component. (If this doesn't mean anything to you then see *Using the repository* )

You'll mainly be working in the directory `.../psychopy/experiment/components/`. Take a look at several existing Components (such as `image.py`), and key files including `_base.py` and `_visual.py`.

There are three main steps, the first being by far the most involved.

### 13.3.1 1. Create the file defining the component: `newcomp.py`

It's most straightforward to model a new Component on one of the existing ones. Be prepared to specify what your Component needs to do at several different points in time: the first trial, every frame, at the end of each routine, and at the end of the experiment. In addition, you may need to sacrifice some complexity in order to keep things streamlined enough for a Builder (see e.g., `ratingscale.py`).

Your new Component class (in your file `newcomp.py`) should inherit from `BaseComponent` (in `_base.py`), `VisualComponent` (in `_visual.py`), or `KeyboardComponent` (in `keyboard.py`). You may need to rewrite some or all some of these methods, to override default behavior:

```
class NewcompComponent(BaseComponent): # or (VisualComponent)
    def __init__(...):
        super(NewcompComponent, self).__init__(...)
        ...
    def writeInitCode(self, buff):
    def writeRoutineStartCode(self, buff):
    def writeFrameCode(self, buff):
    def writeRoutineEndCode(self, buff):
```

Calling `super()` will create the basic default set of *params* that almost every component will need: *name*, *startVal*, *startType*, etc. Some of these fields may need to be overridden (e.g., *durationEstim* in `sound.py`). Inheriting from `VisualComponent` (which in turn inherits from `BaseComponent`) adds default visual params, plus arranges for Builder scripts to import `psychopy.visual`. If your component will need other libs, call `self.exp.requirePsychopyLib(['neededLib'])` (see e.g., `parallelPort.py`).

At the top of a component file is a dict named `_localized`. It contains mappings that allow a strict separation of internal string values (= used in logic, never displayed) from values used for display in the Builder interface (= for display only, possibly translated, never used in logic). The `.hint` and `.label` fields of `params['someParam']` should always be set to a localized value, either by using a dict entry such as `_localized['message']`, or via the globally available translation function, `_(‘message’)`. Localized values must **not** be used elsewhere in a component definition.

Very occasionally, you may also need to edit `settings.py`, which writes out the set-up code for the whole experiment (e.g., to define the window). For example, this was necessary for the `ApertureComponent`, to pass `allowStencil=True` to the window creation.

Your new Component writes code into a buffer that becomes an executable python file, `xxx_lastrun.py` (where `xxx` is whatever the experimenter specifies when saving from the Builder, `xxx.pysexp`). You will do a bunch of this kind of call in your `newcomp.py` file:

```
buff.writeIndented(your_python_syntax_string_here)
```

You have to manage the indentation level of the output code, see `experiment.IndentingBuffer()`.

`xxx_lastrun.py` is the file that gets built when you run `xxx.pysexp` from the Builder. So you will want to look at `xxx_lastrun.py` frequently when developing your component.

#### Name-space

There are several internal variables (i.e. names of Python objects) that have a specific, hardcoded meaning within `xxx_lastrun.py`. You can expect the following to be there, and they should only be used in the original way (or something will break for the end-user, likely in a mysterious way):



```
win    # the window
t      # time within the trial loop, referenced to `trialClock`
x, y   # mouse coordinates, but only if the experimenter uses a mouse component
```

Handling of variable names is under active development, so this list may well be out of date. (If so, you might consider updating it or posting a note to the PsychoPy Discourse developer forum.)

Preliminary testing suggests that there are 600-ish names from numpy or numpy.random, plus the following:

```
['KeyResponse', '__builtins__', '__doc__', '__file__', '__name__', '__package__',
→ 'buttons', 'core', 'data', 'dlg', 'event', 'expInfo', 'expName', 'filename', 'gui',
→ 'logFile', 'os', 'psychopy', 'sound', 't', 'visual', 'win', 'x', 'y']
```

Yet other names get derived from user-entered names, like *trials* → *thisTrial*.

### Params

*self.params* is a key construct that you build up in `__init__`. You need name, startTime, duration, and several other params to be defined or you get errors. ‘name’ should be of type ‘code’.

The *Param()* class is defined in *psychopy.app.builder.experiment.Param()*. A very useful thing that Params know is how to create a string suitable for writing into the .py script. In particular, the `__str__` representation of a Param will format its value (*.val*) based on its type (*.valType*) appropriately. This means that you don’t need to check or handle whether the user entered a plain string, a string with a code trigger character (\$), or the field was of type *code* in the first place. If you simply request the *str()* representation of the param, it is formatted correctly.

To indicate that a param (eg, *thisParam*) should be considered as an advanced feature, set its category to advanced: *self.params[‘thisParam’].categ = ‘Advanced’*. Then the GUI shown to the experimenter will automatically place it on the ‘Advanced’ tab. Other categories work similarly (*Custom*, etc).

During development, it can sometimes be helpful to save the params into the *xxx\_lastrun.py* file as comments, so you can see what is happening:

```
def writeInitCode(self, buff):
    # for debugging during Component development:
    buff.writeIndented("# self.params for aperture:\n")
    for p in self.params:
        try: buff.writeIndented("# %s: %s <type %s>\n" % (p, self.params[p].val, self.
→ params[p].valType))
        except: pass
```

A lot more detail can be inferred from existing components.

Making things loop-compatible looks interesting – see *keyboard.py* for an example, especially code for saving data at the end.

## 13.3.2 Notes & gotchas

**syntax errors in new\_comp.py:** The PsychoPy app will fail to start if there are syntax error in any of the components that are auto-detected. Just correct them and start the app again.

**param[.val]:** If you have a boolean variable (e.g., *my\_flag*) as one of your params, note that *self.param[“my\_flag”]* is always True (the param exists → True). So in a boolean context you almost always want the *.val* part, e.g., *if self.param[“my\_flag”.val]:*

However, you do not always want *.val*. Specifically, in a string/unicode context (= to trigger the self-formatting features of Param(s)), you almost always want “%s” % *self.param[“my\_flag”]*, without *.val*. Note that it’s better to do this via “%s” than *str()* because *str(self.param[“my\_flag”])* coerces things to type str (squashing unicode) whereas %s works for both str and unicode.

**Travis testing** Before submitting a pull request with the new component, you should regenerate the *componsTemplate.txt* file. This is a text file that lists the attributes of all of the user interface settings and options in the various components. It is used during the Travis automated testing process when a pull request is submitted to GitHub, allowing the detection of errors that may have been caused in refactoring. Your new component needs to have entries added to this file if the Travis testing is going to pass successfully.

To re-generate the file, cd to this directory `.../psychopy/tests/test_app/test_builder/` and run:

```
`python genComponsTemplate.py --out`
```

This will over-write the existing file so you might want to make a copy in case the process fails. *Compatibility issues:* As at May 2018, that script is not yet Python 3 compatible, and on a Mac you might need to use *pythonw*.

### 13.3.3 2. Icon: newcomp.png

Using your favorite image software, make an icon for your Component with a descriptive name, e.g., *newcomp.png*. Dimensions = 48 × 48. Put it in the components directory.

In *newcomp.py*, have a line near the top:

```
iconFile = path.join(thisFolder, 'newcomp.png')
```

### 13.3.4 3. Documentation: newcomp.rst

Just make a descriptively-named text file that ends in *.rst* (“restructured text”), and put it in *psychopy/docs/source/builder/components/*. It will get auto-formatted and end up at <http://www.psychopy.org/builder/components/newcomp.html>

## 13.4 Style-guide for coder demos

Each coder demo is intended to illustrate a key PsychoPy feature (or two), especially in ways that show usage in practice, and go beyond the description in the API. The aim is not to illustrate every aspect, but to get people up to speed quickly, so they understand how basic usage works, and could then play around with advanced features.

As a newcomer to PsychoPy, you are in a great position to judge whether the comments and documentation are clear enough or not. If something is not clear, you may need to ask a PsychoPy contributor for a description; email [psychopy-dev@googlegroups.com](mailto:psychopy-dev@googlegroups.com).

Here are some style guidelines, written for the OpenHatch event(s) but hopefully useful after that too. These are intended specifically for the coder demos, not for the internal code-base (although they are generally quite close).

The idea is to have clean code that looks and works the same way across demos, while leaving the functioning mostly untouched. Some small changes to function might be needed (e.g., to enable the use of ‘escape’ to quit), but typically only minor changes like this.

- Generally, when you run the demo, does it look good and help you understand the feature? Where might there be room for improvement? You can either leave notes in the code in a comment, or include them in a commit message.
- Standardize the top stuff to have 1) a shebang with python, 2) utf-8 encoding, and 3) a comment:

```
#!/usr/bin/env python
# -*- coding: utf-8 -*-

"""Demo name, purpose, description (1-2 sentences, although some demos need more
↪ explanation).
"""
```

For the comment / description, it's a good idea to read and be informed by the relevant parts of the API (see <http://psychopy.org/api/api.html>), but there's no need to duplicate that text in your comment. If you are unsure, please post to the dev list [psychopy-dev@googlegroups.com](mailto:psychopy-dev@googlegroups.com).

- Follow PEP-8 mostly, some exceptions:
  - current PsychoPy convention is to use camelCase for variable names, so don't convert those to underscores
  - 80 char columns can spill over a little. Try to keep things within 80 chars most of the time.
  - do allow multiple imports on one line if they are thematically related (e.g., *import os, sys, glob*).
  - inline comments are ok (because the code demos are intended to illustrate and explain usage in some detail, more so than typical code).
- Check all imports:
  - remove any unnecessary ones
  - replace *import time* with *from psychopy import core*. Use *core.getTime()* (= ms since the script started) or *core.getAbsTime()* (= seconds, unix-style) instead of *time.time()*, for all time-related functions or methods not just *time()*.
  - add *from \_\_future\_\_ import division*, even if not needed. And make sure that doing so does not break the demo!
- Fix any typos in comments; convert any lingering British spellings to US, e.g., change *colour* to *color*
- Prefer *if <boolean>:* as a construct instead of *if <boolean> == True:*. (There might not be any to change).
- If you have to choose, opt for more verbose but easier-to-understand code instead of clever or terse formulations. This is for readability, especially for people new to python. If you are unsure, please add a note to your commit message, or post a question to the dev list [psychopy-dev@googlegroups.com](mailto:psychopy-dev@googlegroups.com).
- Standardize variable names:
  - use *win* for the *visual.Window()*, and so *win.flip()*
- Provide a consistent way for a user to exit a demo using the keyboard, ideally enable this on every visual frame: use *if len(event.getKeys(['escape'])): core.quit()*. **Note:** if there is a previous *event.getKeys()* call, it can slurp up the 'escape' keys. So check for 'escape' first.
- Time-out after 10 seconds, if there's no user response and a timeout is appropriate for the demo (and a longer time-out might be needed, e.g., for *ratingScale.py*):

```
demoClock = core.clock() # is demoClock's time is 0.000s at this point
...
if demoClock.getTime() > 10.:
    core.quit()
```

- Most demos are not full screen. For any that are full-screen, see if it can work without being full screen. If it has to be full-screen, add some text to say that pressing 'escape' will quit.
- If displaying log messages to the console seems to help understand the demo, here's how to do it:

```
from psychopy import logging
...
logging.console.setLevel(logging.INFO) # or logging.DEBUG for even more stuff
```

- End a script with `win.close()` (assuming the script used a `visual.Window`), and then `core.quit()` even though it's not strictly necessary

## 13.5 Localization (I18N, translation)

PsychoPy is used worldwide. Starting with v1.81, many parts of PsychoPy itself (the app) can be translated into any language that has a unicode character set. A translation affects what the experimenter sees while creating and running experiments; it is completely separate from what is shown to the subject. Translations of the online documentation will need a completely different approach.

In the app, translation is handled by a function, `_translate()`, which takes a string argument. (The standard name is `_()`, but unfortunately this conflicts with `_` as used in some external packages that PsychoPy depends on.) The `_translate()` function returns a translated, unicode version of the string in the locale / language that was selected when starting the app. If no translation is available for that locale, the original string is returned (= English).

A locale setting (e.g., 'ja\_JP' for Japanese) allows the end-user (= the experimenter) to control the language that will be used for display within the app itself. (It can potentially control other display conventions as well, not just the language.) PsychoPy will obtain the locale from the user preference (if set), or the OS.

Workflow: 1) Make a translation from English (en\_US) to another language. You'll need a strong understanding of PsychoPy, English, and the other language. 2) In some cases it will be necessary to adjust PsychoPy's code, but only if new code has been added to the app and that code displays text. Then re-do step 1 to translate the newly added strings.

See notes in `psychopy/app/localization/readme.txt`.

### 13.5.1 Make a translation (.po file)

As a translator, you will likely introduce many new people to PsychoPy, and your translations will greatly influence their experience. Try to be completely accurate; it is better to leave something in English if you are unsure how PsychoPy is supposed to work.

To translate a given language, you'll need to know the standard 5-character code (see `psychopy/app/localization/mappings`). E.g., for Japanese, wherever LANG appears in the documentation here, you should use the actual code, i.e., "ja\_JP" (without quotes).

A free app called poedit is useful for managing a translation. For a given language, the translation mappings (from en\_US to LANG) are stored in a .po file (a text file with extension .po); after editing with poedit, these are converted into binary format (with extension .mo) which are used when the app is running.

- Start translation (do these steps once):

Start a translation by opening `psychopy/app/locale/LANG/LC_MESSAGE/messages.po` in Poedit. If there is no such .po file, create a new one:

- make a new directory `psychopy/app/locale/LANG/LC_MESSAGE/` if needed. Your LANG will be auto-detected within PsychoPy only if you follow this convention. You can copy metadata (such as the project name) from another .po file.

Set your name and e-mail address from "Preferences..." of "File" menu. Set translation properties (such as project name, language and charset) from Catalog Properties Dialog, which can be opened from "Properties..." of "Catalog" menu.

In poedit's properties dialog, set the "source keywords" to include `'_translate'`. This allows poedit to find the strings in PsychoPy that are to be translated.

To add paths where Poedit scans .py files, open "Sources paths" tab on the Catalog Properties Dialog, and set "Base path:" to `"../..../..../"` (= `psychopy/psychopy/`). Nothing more should be needed. If you've created new catalog, save your catalog to `psychopy/app/locale/LANG/LC_MESSAGE/messages.po`.

Probably not needed, but check anyway: Edit the file containing language code and name mappings, `psychopy/app/localization/mappings`, and fill in the name for your language. Give a name that should be familiar to people who read that language (i.e., use the name of the language as written in the language itself, not in `en_US`). About 25 are already done.

- Edit a translation:

Open the .po file with Poedit and press "Update" button on the toolbar to update newly added / removed strings that need to be translated. Select a string you want to translate and input your translation to "Translation:" box. If you are unsure where string is used, point on the string in "Source text" box and right-click. You can see where the string is defined.

- Technical terms should not be translated: Builder, Coder, PsychoPy, Flow, Routine, and so on. (See the Japanese translation for guidance.)
- If there are formatting arguments in the original string (`%s, %(first)i`), the same number of arguments must also appear in the translation (but their order is not constrained to be the original order). If they are named (e.g., `%(first)i`), that part should not be translated—here `first` is a python name.
- If you think your translation might have room for improvement, indicate that it is "fuzzy". (Saving Notes does not work for me on Mac, seems like a bug in poedit.)
- After making a new translation, saving it in poedit will save the .po file and also make an associated .mo file. You need to update the .mo file if you want to see your changes reflected in PsychoPy.
- The start-up tips are stored in separate files, and are not translated by poedit. Instead:
  - copy the default version (named `psychopy/app/Resources/tips.txt`) to a new file in the same directory, named `tips_LANG.txt`. Then replace English-language tips with translated tips. Note that some of the humor might not translate well, so feel free to leave out things that would be too odd, or include occasional mild humor that would be more appropriate. Humor must be respectful and suitable for using in a classroom, laboratory, or other professional situation. Don't get too creative here. If you have any doubt, best leave it out. (Hopefully it goes without saying that you should avoid any religious, political, disrespectful, or sexist material.)
  - in poedit, translate the file name: translate "tips.txt" as "tips\_LANG.txt"
- Commit both the .po and .mo files to github (not just one or the other), and any changed files (e.g., `tips_LANG`, `localization/mappings`).

## 13.5.2 Adjust PsychoPy's code

This is mostly complete (as of 1.81.00), but will be needed for new code that displays text to users of the app (experimenters, not study participants).

There are a few things to keep in mind when working on the app's code to make it compatible with translations. If you are only making a translation, you can skip this section.

- In PsychoPy's code, the language to be used should always be English with American spellings (e.g., "color").
- Within the app, the return value from `_translate()` should be used only for display purposes: in menus, tooltips, etc. A translated value should never be used as part of the logic or internal functioning of PsychoPy. It is purely a "skin". Internally, everything must be in `en_US`.

- Basic usage is exactly what you expect: `_translate("hello")` will return a unicode string at run-time, using mappings for the current locale as provided by a translator in a .mo file. (Not all translations are available yet, see above to start a new one.) To have the app display a translated string to the experimenter, just display the return value from the underscore translation function.
- The strings to be translated must appear somewhere in the app code base as explicit strings within `_translate()`. If you need to translate a variable, e.g., named `str_var` using the expression `_translate(str_var)`, somewhere else you need to explicitly give all the possible values that `str_var` can take, and enclose each of them within the translate function. It is okay for that to be elsewhere, even in another file, but not in a comment. This allows poedit to discover all the strings that need to be translated. (This is one of the purposes of the `_localized` dict at the top of some modules.)
- `_translate()` should not be given a null string to translate; if you use a variable, check that it is not `''` to avoid invoking `_translate('')`.
- Strings that contain formatting placeholders (e.g., `%d`, `%s`, `%.4f`) require a little more thought. Single placeholders are easy enough: `_translate("hello, %s") % name`.
- Strings with multiple formatting placeholders require named arguments, because positional arguments are not always sufficient to disambiguate things depending on the phrase and the language to be translated into: `_translate("hello, %(first)s %(last)s") % {'first': firstname, 'last': lastname}`
- Localizing drop-down menus is a little more involved. Such menus should display localized strings, but return selected values as integers (`GetSelection()` returns the position within the list). Do not use `GetStringSelection()`, because this will return the localized string, breaking the rule about a strict separation of display and logic. See Builder ParamDialogs for examples.

### 13.5.3 Other notes

When there are more translations (and if they make the app download large) we might want to manage things differently (e.g., have translations as a separate download from the app).

## 13.6 Adding a new Menu Item

Adding a new menu-item to the Builder (or Coder) is relatively straightforward, but there are several files that need to be changed in specific ways.

### 13.6.1 1. makeMenus()

The code that constructs the menus for the Builder is within a method named `makeMenus()`, within class `builder.BuilderFrame()`. Decide which submenu your new command fits under, and look for that section (e.g., File, Edit, View, and so on). For example, to add an item for making the Routine panel items larger, I added two lines within the View menu, by editing the `makeMenus()` method of class `BuilderFrame` within `psychopy/app/builder/builder.py` (similar for Coder):

```
self.viewMenu.Append(self.IDs.tbIncrRoutineSize, _("&Routine Larger\t%s") %self.app.
↳keys['largerRoutine'], _("Larger routine items"))
wx.EVT_MENU(self, self.IDs.tbIncrRoutineSize, self.routinePanel.increaseSize)
```

Note the use of the translation function, `_()`, for translating text that will be displayed to users (menu listing, hint).

## 13.6.2 2. wxIDs.py

A new item needs to have a (numeric) ID so that *wx* can keep track of it. Here, the number is *self.IDs.tbIncrRoutineSize*, which I had to define within the file *psychopy/app/wxIDs.py*:

```
tbIncrRoutineSize=180
```

It's possible that, instead of hard-coding it like this, it's better to make a call to *wx.NewIdRef()* – *wx* will take care of avoiding duplicate IDs, presumably.

## 13.6.3 3. Key-binding prefs

I also defined a key to use to as a keyboard short-cut for activating the new menu item:

```
self.app.keys['largerRoutine']
```

The actual key is defined in a preference file. Because psychopy is multi-platform, you need to add info to four different .spec files, all of them being within the *psychopy/preferences/* directory, for four operating systems (Darwin, FreeBSD, Linux, Windows). For *Darwin.spec* (meaning macOS), I added two lines. The first line is not merely a comment: it is also automatically used as a tooltip (in the preferences dialog, under key-bindings), and the second being the actual short-cut key to use:

```
# increase display size of Routines
largerRoutine = string(default='Ctrl++') # on Mac Book Pro this is good
```

This means that the user has to hold down the *Ctrl* key and then press the + key. Note that on Macs, 'Ctrl' in the spec is automatically converted into 'Cmd' for the actual key to use; in the .spec, you should always specify things in terms of 'Ctrl' (and not 'Cmd'). The default value is the key-binding to use unless the user defines another one in her or his preferences (which then overrides the default). Try to pick a sensible key for each operating system, and update all four .spec files.

## 13.6.4 4. Your new method

The second line within *makeMenus()* adds the key-binding definition into *wx*'s internal space, so that when the key is pressed, *wx* knows what to do. In the example, it will call the method *self.routinePanel.increaseSize*, which I had to define to do the desired behavior when the method is called (in this case, increment an internal variable and redraw the routine panel at the new larger size).

## 13.6.5 5. Documentation

To let people know that your new feature exists, add a note about your new feature in the CHANGELOG.txt, and appropriate documentation in .rst files.

Happy Coding Folks!!





## PSYCHOPY EXPERIMENT FILE FORMAT (.PSYEXP)

The file format used to save experiments constructed in PsychoPy builder was created especially for the purpose, but is an open format, using a basic xml form, that may be of use to other similar software. Indeed the builder itself could be used to generate experiments on different backends (such as Vision Egg, PsychToolbox or PyEPL). The xml format of the file makes it extremely platform independent, as well as moderately(?) easy to read by humans. There was a further suggestion to generate an XSD (or similar) [schema against which psyexp files could be validated](#). That is a low priority but welcome addition if you wanted to work on it(!) There is a basic XSD (XML Schema Definition) available in `psychopy/app/builder/experiment.xsd`.

The simplest way to understand the file format is probably simply to create an experiment, save it and open the file in an xml-aware editor/viewer (e.g. change the file extension from .psyexp to .xml and then open it in Firefox). An example (from the stroop demo) is shown below.

The file format maps fairly obviously onto the structure of experiments constructed with the [Builder](#) interface, as described [here](#). There are general [Settings](#) for the experiment, then there is a list of [Routines](#) and a [Flow](#) that describes how these are combined.

As with any xml file the format contains object *nodes* which can have direct properties and also child nodes. For instance the outermost node of the .psyexp file is the experiment node, with properties that specify the version of PsychoPy that was used to save the file most recently and the encoding of text within the file (ascii, unicode etc.), and with child nodes [Settings](#), [Routines](#) and [Flow](#).

### 14.1 Parameters

Many of the nodes described within this xml description of the experiment contain Param entries, representing different parameters of that Component. Nearly all parameter nodes have a *name* property and a *val* property. The parameter node with the name “advancedParams” does not have them. Most also have a *valType* property, which can take values ‘bool’, ‘code’, ‘extendedCode’, ‘num’, ‘str’ and an *updates* property that specifies whether this parameter is changing during the experiment and, if so, whether it changes ‘every frame’ (of the monitor) or ‘every repeat’ (of the Routine).

### 14.2 Settings

The Settings node contains a number of parameters that, in PsychoPy, would normally be set in the [Experiment settings](#) dialog, such as the monitor to be used. This node contains a number of [Parameters](#) that map onto the entries in that dialog.

## 14.3 Routines

This node provides a sequence of xml child nodes, each of which describes a *Routine*. Each Routine contains a number of children, each specifying a *Component*, such as a stimulus or response collecting device. In the *Builder* view, the *Routines* obviously show up as different tabs in the main window and the *Components* show up as tracks within that tab.

## 14.4 Components

Each *Component* is represented in the .psyexp file as a set of parameters, corresponding to the entries in the appropriate component dialog box, that completely describe how and when the stimulus should be presented or how and when the input device should be read from. Different *Components* have slightly different nodes in the xml representation which give rise to different sets of parameters. For instance the *TextComponent* nodes has parameters such as *colour* and *font*, whereas the *KeyboardComponent* node has parameters such as *forceEndTrial* and *correctIf*.

## 14.5 Flow

The Flow node is rather more simple. Its children simply specify objects that occur in a particular order in time. A Routine described in this flow must exist in the list of Routines, since this is where it is fully described. One Routine can occur once, more than once or not at all in the Flow. The other children that can occur in a Flow are LoopInitiators and LoopTerminators which specify the start and endpoints of a loop. All loops must have exactly one initiator and one terminator.

## 14.6 Names

For the experiment to generate valid PsychoPy code the name parameters of all objects (Components, Loops and Routines) must be unique and contain no spaces. That is, an experiment can not have two different Routines called 'trial', nor even a Routine called 'trial' and a Loop called 'trial'.

The Parameter names belonging to each Component (or the Settings node) must be unique within that Component, but can be identical to parameters of other Components or can match the Component name themselves. A TextComponent should not, for example, have multiple 'pos' parameters, but other Components generally will, and a Routine called 'pos' would also be also permissible.

```
<PsychoPy2experiment version="1.50.04" encoding="utf-8">
  <Settings>
    <Param name="Monitor" val="testMonitor" valType="str" updates="None"/>
    <Param name="Window size (pixels)" val="[1024, 768]" valType="code" updates="None"
    ↪"/>
    <Param name="Full-screen window" val="True" valType="bool" updates="None"/>
    <Param name="Save log file" val="True" valType="bool" updates="None"/>
    <Param name="Experiment info" val="{ 'participant': 's_001', 'session': 001 }"
    ↪valType="code" updates="None"/>
    <Param name="Show info dlg" val="True" valType="bool" updates="None"/>
    <Param name="logging level" val="warning" valType="code" updates="None"/>
    <Param name="Units" val="norm" valType="str" updates="None"/>
    <Param name="Screen" val="1" valType="num" updates="None"/>
  </Settings>
  <Routines>
```

(continues on next page)

(continued from previous page)

```

<Routine name="trial">
  <TextComponent name="word">
    <Param name="name" val="word" valType="code" updates="constant"/>
    <Param name="text" val="thisTrial.text" valType="code" updates="set every_
↪repeat"/>
    <Param name="colour" val="thisTrial.rgb" valType="code" updates="set every_
↪repeat"/>
    <Param name="ori" val="0" valType="code" updates="constant"/>
    <Param name="pos" val="[0, 0]" valType="code" updates="constant"/>
    <Param name="times" val="[0.5,2.0]" valType="code" updates="constant"/>
    <Param name="letterHeight" val="0.2" valType="code" updates="constant"/>
    <Param name="colourSpace" val="rgb" valType="code" updates="constant"/>
    <Param name="units" val="window units" valType="str" updates="None"/>
    <Param name="font" val="Arial" valType="str" updates="constant"/>
  </TextComponent>
  <KeyboardComponent name="resp">
    <Param name="storeCorrect" val="True" valType="bool" updates="constant"/>
    <Param name="name" val="resp" valType="code" updates="None"/>
    <Param name="forceEndTrial" val="True" valType="bool" updates="constant"/>
    <Param name="times" val="[0.5,2.0]" valType="code" updates="constant"/>
    <Param name="allowedKeys" val="['1','2','3']" valType="code" updates="constant
↪"/>
    <Param name="storeResponseTime" val="True" valType="bool" updates="constant"/>
    <Param name="correctIf" val="resp.keys==str(thisTrial.corrAns)" valType="code
↪" updates="constant"/>
    <Param name="store" val="last key" valType="str" updates="constant"/>
  </KeyboardComponent>
</Routine>
<Routine name="instruct">
  <TextComponent name="instrText">
    <Param name="name" val="instrText" valType="code" updates="constant"/>
    <Param name="text" val="&quot;Please press;&#10;1 for red ink,&#10;2 for_
↪green ink&#10;3 for blue ink&#10;(Esc will quit)&#10;&#10;Any key to continue&quot;
↪" valType="code" updates="constant"/>
    <Param name="colour" val="[1, 1, 1]" valType="code" updates="constant"/>
    <Param name="ori" val="0" valType="code" updates="constant"/>
    <Param name="pos" val="[0, 0]" valType="code" updates="constant"/>
    <Param name="times" val="[0, 10000]" valType="code" updates="constant"/>
    <Param name="letterHeight" val="0.1" valType="code" updates="constant"/>
    <Param name="colourSpace" val="rgb" valType="code" updates="constant"/>
    <Param name="units" val="window units" valType="str" updates="None"/>
    <Param name="font" val="Arial" valType="str" updates="constant"/>
  </TextComponent>
  <KeyboardComponent name="ready">
    <Param name="storeCorrect" val="False" valType="bool" updates="constant"/>
    <Param name="name" val="ready" valType="code" updates="None"/>
    <Param name="forceEndTrial" val="True" valType="bool" updates="constant"/>
    <Param name="times" val="[0, 10000]" valType="code" updates="constant"/>
    <Param name="allowedKeys" val="" valType="code" updates="constant"/>
    <Param name="storeResponseTime" val="False" valType="bool" updates="constant"/
↪>
    <Param name="correctIf" val="resp.keys==str(thisTrial.corrAns)" valType="code
↪" updates="constant"/>
    <Param name="store" val="last key" valType="str" updates="constant"/>
  </KeyboardComponent>
</Routine>
<Routine name="thanks">

```

(continues on next page)

(continued from previous page)

```

<TextComponent name="thanksText">
  <Param name="name" val="thanksText" valType="code" updates="constant"/>
  <Param name="text" val="&quot;Thanks!&quot;" valType="code" updates="constant
↪"/>

  <Param name="colour" val="[1, 1, 1]" valType="code" updates="constant"/>
  <Param name="ori" val="0" valType="code" updates="constant"/>
  <Param name="pos" val="[0, 0]" valType="code" updates="constant"/>
  <Param name="times" val="[1.0, 2.0]" valType="code" updates="constant"/>
  <Param name="letterHeight" val="0.2" valType="code" updates="constant"/>
  <Param name="colourSpace" val="rgb" valType="code" updates="constant"/>
  <Param name="units" val="window units" valType="str" updates="None"/>
  <Param name="font" val="arial" valType="str" updates="constant"/>
</TextComponent>
</Routine>
</Routines>
<Flow>
  <Routine name="instruct"/>
  <LoopInitiator loopType="TrialHandler" name="trials">
    <Param name="endPoints" val="[0, 1]" valType="num" updates="None"/>
    <Param name="name" val="trials" valType="code" updates="None"/>
    <Param name="loopType" val="random" valType="str" updates="None"/>
    <Param name="nReps" val="5" valType="num" updates="None"/>
    <Param name="trialList" val="[{'text': 'red', 'rgb': [1, -1, -1], 'congruent': ↪
↪1, 'corrAns': 1}, {'text': 'red', 'rgb': [-1, 1, -1], 'congruent': 0, 'corrAns': 1},
↪ {'text': 'green', 'rgb': [-1, 1, -1], 'congruent': 1, 'corrAns': 2}, {'text':
↪ 'green', 'rgb': [-1, -1, 1], 'congruent': 0, 'corrAns': 2}, {'text': 'blue', 'rgb': ↪
↪ [-1, -1, 1], 'congruent': 1, 'corrAns': 3}, {'text': 'blue', 'rgb': [1, -1, -1],
↪ 'congruent': 0, 'corrAns': 3}]" valType="str" updates="None"/>
    <Param name="trialListFile" val="/Users/jwp...troop/trialTypes.csv" valType="str
↪" updates="None"/>
  </LoopInitiator>
  <Routine name="trial"/>
  <LoopTerminator name="trials"/>
  <Routine name="thanks"/>
</Flow>
</PsychoPy2experiment>

```

## PYTHON MODULE INDEX

### p

- `psychopy.clock`, 201
- `psychopy.core`, 103
- `psychopy.data`, 204
- `psychopy.hardware`, 231
  - `psychopy.hardware.crs`, 233
  - `psychopy.hardware.egi`, 265
  - `psychopy.hardware.emulator`, 266
  - `psychopy.hardware.forp`, 270
  - `psychopy.hardware.iolab`, 271
  - `psychopy.hardware.joystick`, 272
  - `psychopy.hardware.minolta`, 276
  - `psychopy.hardware.pr`, 278
- `psychopy.info`, 284
- `psychopy.iohub.client`, 286
  - `psychopy.iohub.client.keyboard`, 292
- `psychopy.logging`, 330
- `psychopy.misc`, 335
- `psychopy.parallel`, 342
- `psychopy.preferences`, 345
- `psychopy.sound`, 346
- `psychopy.tools`, 350
  - `psychopy.tools.colorspectools`, 350
  - `psychopy.tools.coordinatetools`, 353
  - `psychopy.tools.filetools`, 354
  - `psychopy.tools.gltools`, 355
  - `psychopy.tools.imagetools`, 366
  - `psychopy.tools.mathtools`, 367
  - `psychopy.tools.monitorunittools`, 374
  - `psychopy.tools.plottools`, 375
  - `psychopy.tools.typetools`, 375
  - `psychopy.tools.unittools`, 375
  - `psychopy.tools.viewtools`, 377
- `psychopy.visual.windowframepack`, 198
- `psychopy.visual.windowwarp`, 199
- `pylink`, 281
- `pyxid`, 231



## Symbols

- `_EOS()` (`psychopy.sound.backend_sounddevice.SoundDeviceSound` method), 347
- `_Goggles()` (`psychopy.hardware.crs.bits.BitsPlusPlus` method), 234
- `_Goggles()` (`psychopy.hardware.crs.bits.BitsSharp` method), 244
- `_Logger` (class in `psychopy.logging`), 331
- `_RTBoxDecodeResponse()` (`psychopy.hardware.crs.bits.BitsSharp` method), 244
- `_ResetClock()` (`psychopy.hardware.crs.bits.BitsPlusPlus` method), 234
- `_ResetClock()` (`psychopy.hardware.crs.bits.BitsSharp` method), 244
- `_calcPosRendered()` (`psychopy.visual.BufferImageStim` method), 107
- `_calcPosRendered()` (`psychopy.visual.GratingStim` method), 117
- `_calcPosRendered()` (`psychopy.visual.ImageStim` method), 126
- `_calcPosRendered()` (`psychopy.visual.MovieStim` method), 134
- `_calcPosRendered()` (`psychopy.visual.RadialStim` method), 143
- `_calcPosRendered()` (`psychopy.visual.ShapeStim` method), 165
- `_calcPosRendered()` (`psychopy.visual.TextStim` method), 182
- `_calcSizeRendered()` (`psychopy.visual.BufferImageStim` method), 107
- `_calcSizeRendered()` (`psychopy.visual.GratingStim` method), 118
- `_calcSizeRendered()` (`psychopy.visual.ImageStim` method), 126
- `_calcSizeRendered()` (`psychopy.visual.MovieStim` method), 134
- `_calcSizeRendered()` (`psychopy.visual.RadialStim` method), 143
- `_calcSizeRendered()` (`psychopy.visual.ShapeStim` method), 165
- `_calcSizeRendered()` (`psychopy.visual.TextStim` method), 182
- `_channelCheck()` (`psychopy.sound.backend_sounddevice.SoundDeviceSound` method), 347
- `_checkFinished()` (`psychopy.data.QuestHandler` method), 219
- `_clip_range()` (`psychopy.hardware.joystick.XboxController` method), 273
- `_createOutputArray()` (`psychopy.data.TrialHandler` method), 207
- `_createOutputArrayData()` (`psychopy.data.TrialHandler` method), 207
- `_createSequence()` (`psychopy.data.TrialHandler` method), 207
- `_createTexture()` (`psychopy.visual.BufferImageStim` method), 108
- `_createTexture()` (`psychopy.visual.GratingStim` method), 118
- `_createTexture()` (`psychopy.visual.ImageStim` method), 126
- `_createTexture()` (`psychopy.visual.RadialStim` method), 143
- `_decodePress()` (`psychopy.hardware.forp.ButtonBox` class method), 271
- `_delete()` (`psychopy.hardware.emulator.ResponseEmulator` method), 266
- `_delete()` (`psychopy.hardware.emulator.SyncGenerator` method), 267
- `_doFit()` (`psychopy.data.FitCumNormal` method), 224
- `_doFit()` (`psychopy.data.FitLogistic` method), 223
- `_doFit()` (`psychopy.data.FitNakaRushton` method), 223
- `_doFit()` (`psychopy.data.FitWeibull` method), 222
- `_do_chunk()` (`psychopy.voicekey.OnsetVoiceKey` method), 383
- `_drawLUTtoScreen()` (`psychopy.hardware.crs.bits.BitsPlusPlus` method), 234
- `_drawLUTtoScreen()` (`psychopy.hardware.crs.bits.BitsSharp` method), 244
- `_drawTrigtoScreen()` (`psychopy.hardware.crs.bits.BitsPlusPlus` method), 234

<code>_drawTrigtoScreen()</code> (psychopy.hardware.crs.bits.BitsSharp method), 244	<code>_intensityDec()</code> (psychopy.data.QuestHandler method), 219
<code>_extractStatusEvents()</code> (psychopy.hardware.crs.bits.BitsSharp method), 244	<code>_intensityDec()</code> (psychopy.data.StairHandler method), 211
<code>_generateEvents()</code> (psychopy.hardware.forp.ButtonBox method), 271	<code>_intensityInc()</code> (psychopy.data.QuestHandler method), 219
<code>_getAllParamNames()</code> (psychopy.data.ExperimentHandler method), 204	<code>_intensityInc()</code> (psychopy.data.StairHandler method), 211
<code>_getDesiredRGB()</code> (psychopy.visual.BufferImageStim method), 108	<code>_loadAll()</code> (psychopy.monitors.Monitor method), 338
<code>_getDesiredRGB()</code> (psychopy.visual.GratingStim method), 118	<code>_makeIndices()</code> (psychopy.data.TrialHandler method), 207
<code>_getDesiredRGB()</code> (psychopy.visual.ImageStim method), 127	<code>_prepareMonoFrame()</code> (psychopy.visual.Rift method), 156
<code>_getDesiredRGB()</code> (psychopy.visual.RadialStim method), 143	<code>_process()</code> (psychopy.voicekey.OnsetVoiceKey method), 383
<code>_getDesiredRGB()</code> (psychopy.visual.ShapeStim method), 165	<code>_protectTrigger()</code> (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
<code>_getDesiredRGB()</code> (psychopy.visual.TextStim method), 183	<code>_protectTrigger()</code> (psychopy.hardware.crs.bits.BitsSharp method), 245
<code>_getExtraInfo()</code> (psychopy.data.ExperimentHandler method), 204	<code>_resolveMSAA()</code> (psychopy.visual.Rift method), 157
<code>_getHgVersion()</code> (in module psychopy.info), 285	<code>_restoreTrigger()</code> (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
<code>_getLoopInfo()</code> (psychopy.data.ExperimentHandler method), 204	<code>_restoreTrigger()</code> (psychopy.hardware.crs.bits.BitsSharp method), 245
<code>_getPolyAsRendered()</code> (psychopy.visual.BufferImageStim method), 108	<code>_selectWindow()</code> (psychopy.visual.BufferImageStim method), 108
<code>_getPolyAsRendered()</code> (psychopy.visual.GratingStim method), 118	<code>_selectWindow()</code> (psychopy.visual.GratingStim method), 118
<code>_getPolyAsRendered()</code> (psychopy.visual.ImageStim method), 127	<code>_selectWindow()</code> (psychopy.visual.ImageStim method), 127
<code>_getPolyAsRendered()</code> (psychopy.visual.MovieStim method), 134	<code>_selectWindow()</code> (psychopy.visual.MovieStim method), 134
<code>_getPolyAsRendered()</code> (psychopy.visual.RadialStim method), 143	<code>_selectWindow()</code> (psychopy.visual.RadialStim method), 143
<code>_getPolyAsRendered()</code> (psychopy.visual.ShapeStim method), 165	<code>_selectWindow()</code> (psychopy.visual.ShapeStim method), 165
<code>_getPolyAsRendered()</code> (psychopy.visual.TextStim method), 183	<code>_selectWindow()</code> (psychopy.visual.TextStim method), 183
<code>_getSha1hexDigest()</code> (in module psychopy.info), 285	<code>_send_command()</code> (pyxid.XidDevice method), 232
<code>_getStatusLog()</code> (psychopy.hardware.crs.bits.BitsSharp method), 245	<code>_set()</code> (psychopy.visual.BufferImageStim method), 108
<code>_getSvnVersion()</code> (in module psychopy.info), 286	<code>_set()</code> (psychopy.visual.GratingStim method), 118
<code>_getTime()</code> (psychopy.hardware.iolab.ButtonBox method), 271	<code>_set()</code> (psychopy.visual.ImageStim method), 127
<code>_getUserNameUID()</code> (in module psychopy.info), 286	<code>_set()</code> (psychopy.visual.MovieStim method), 134
<code>_granularRating()</code> (psychopy.visual.Slider method), 172	<code>_set()</code> (psychopy.visual.RadialStim method), 143
<code>_inWaiting()</code> (psychopy.hardware.crs.bits.BitsSharp method), 245	<code>_set()</code> (psychopy.visual.ShapeStim method), 166
<code>_intensity()</code> (psychopy.data.QuestHandler method), 219	<code>_set()</code> (psychopy.visual.TextStim method), 183
	<code>_setCurrentProcessInfo()</code> (psychopy.info.RunTimeInfo method), 285
	<code>_setExperimentInfo()</code> (psychopy.info.RunTimeInfo method), 285
	<code>_setHeaders()</code> (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
	<code>_setHeaders()</code> (psychopy.hardware.crs.bits.BitsSharp method), 245
	<code>_setLabelLocs()</code> (psychopy.visual.Slider method), 173



- [\\_setPythonInfo\(\)](#) (psychopy.info.RunTimeInfo method), 285
- [\\_setRadialAttribute\(\)](#) (psychopy.visual.RadialStim method), 143
- [\\_setSystemInfo\(\)](#) (psychopy.info.RunTimeInfo method), 285
- [\\_setTextNoShaders\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_setTextShaders\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_setTickLocs\(\)](#) (psychopy.visual.Slider method), 173
- [\\_setWindowInfo\(\)](#) (psychopy.info.RunTimeInfo method), 285
- [\\_set\\_baseline\(\)](#) (psychopy.voicekey.OnsetVoiceKey method), 383
- [\\_set\\_defaults\(\)](#) (psychopy.voicekey.OnsetVoiceKey method), 383
- [\\_set\\_signaler\(\)](#) (psychopy.voicekey.OnsetVoiceKey method), 384
- [\\_set\\_source\(\)](#) (psychopy.voicekey.OnsetVoiceKey method), 384
- [\\_set\\_tables\(\)](#) (psychopy.voicekey.OnsetVoiceKey method), 384
- [\\_set\\_tstate\\_lock\(\)](#) (psychopy.hardware.emulator.ResponseEmulator method), 266
- [\\_set\\_tstate\\_lock\(\)](#) (psychopy.hardware.emulator.SyncGenerator method), 267
- [\\_setupFrameBuffer\(\)](#) (psychopy.visual.Rift method), 157
- [\\_setupShaders\(\)](#) (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
- [\\_setupShaders\(\)](#) (psychopy.hardware.crs.bits.BitsSharp method), 245
- [\\_startHmdFrame\(\)](#) (psychopy.visual.Rift method), 157
- [\\_startNewPass\(\)](#) (psychopy.data.MultiStairHandler method), 215
- [\\_startOfFlip\(\)](#) (psychopy.visual.Rift method), 157
- [\\_statusBox\(\)](#) (psychopy.hardware.crs.bits.BitsSharp method), 245
- [\\_statusDisable\(\)](#) (psychopy.hardware.crs.bits.BitsSharp method), 245
- [\\_statusEnable\(\)](#) (psychopy.hardware.crs.bits.BitsSharp method), 245
- [\\_statusLog\(\)](#) (psychopy.hardware.crs.bits.BitsSharp method), 245
- [\\_terminate\(\)](#) (psychopy.data.MultiStairHandler method), 215
- [\\_terminate\(\)](#) (psychopy.data.QuestHandler method), 219
- [\\_terminate\(\)](#) (psychopy.data.StairHandler method), 211
- [\\_terminate\(\)](#) (psychopy.data.TrialHandler method), 207
- [\\_tessellate\(\)](#) (psychopy.visual.ShapeStim method), 166
- [\\_updateEverything\(\)](#) (psychopy.visual.RadialStim method), 143
- [\\_updateList\(\)](#) (psychopy.visual.BufferImageStim method), 108
- [\\_updateList\(\)](#) (psychopy.visual.GratingStim method), 118
- [\\_updateList\(\)](#) (psychopy.visual.ImageStim method), 127
- [\\_updateList\(\)](#) (psychopy.visual.MovieStim method), 134
- [\\_updateList\(\)](#) (psychopy.visual.RadialStim method), 143
- [\\_updateList\(\)](#) (psychopy.visual.ShapeStim method), 166
- [\\_updateList\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_updateListNoShaders\(\)](#) (psychopy.visual.BufferImageStim method), 108
- [\\_updateListNoShaders\(\)](#) (psychopy.visual.GratingStim method), 118
- [\\_updateListNoShaders\(\)](#) (psychopy.visual.ImageStim method), 127
- [\\_updateListNoShaders\(\)](#) (psychopy.visual.RadialStim method), 143
- [\\_updateListNoShaders\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_updateListShaders\(\)](#) (psychopy.visual.BufferImageStim method), 108
- [\\_updateListShaders\(\)](#) (psychopy.visual.GratingStim method), 118
- [\\_updateListShaders\(\)](#) (psychopy.visual.ImageStim method), 127
- [\\_updateListShaders\(\)](#) (psychopy.visual.RadialStim method), 143
- [\\_updateListShaders\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_updateMaskCoords\(\)](#) (psychopy.visual.RadialStim method), 144
- [\\_updatePerformanceStats\(\)](#) (psychopy.visual.Rift method), 157
- [\\_updateProjectionMatrix\(\)](#) (psychopy.visual.Rift method), 157
- [\\_updateTextureCoords\(\)](#) (psychopy.visual.RadialStim method), 144
- [\\_updateTrackingState\(\)](#) (psychopy.visual.Rift method), 157
- [\\_updateVertices\(\)](#) (psychopy.visual.BufferImageStim method), 108
- [\\_updateVertices\(\)](#) (psychopy.visual.GratingStim method), 118
- [\\_updateVertices\(\)](#) (psychopy.visual.ImageStim method), 127
- [\\_updateVertices\(\)](#) (psychopy.visual.MovieStim method), 135
- [\\_updateVertices\(\)](#) (psychopy.visual.RadialStim method), 144
- [\\_updateVertices\(\)](#) (psychopy.visual.ShapeStim method), 166
- [\\_updateVertices\(\)](#) (psychopy.visual.TextStim method), 183
- [\\_updateVerticesBase\(\)](#) (psychopy.visual.RadialStim method), 144

method), 144

## A

abort() (psychopy.data.ExperimentHandler method), 204

absTime (psychopy.visual.Rift attribute), 158

Adaptive staircase, 28

add() (psychopy.clock.Clock method), 202

add() (psychopy.core.Clock method), 104

addData() (psychopy.data.ExperimentHandler method), 204

addData() (psychopy.data.MultiStairHandler method), 215

addData() (psychopy.data.QuestHandler method), 219

addData() (psychopy.data.StairHandler method), 211

addData() (psychopy.data.TrialHandler method), 207

addField() (psychopy.gui.Dlg method), 230

addFixedField() (psychopy.gui.Dlg method), 230

addLevel() (in module psychopy.logging), 331

addLoop() (psychopy.data.ExperimentHandler method), 205

addOtherData() (psychopy.data.MultiStairHandler method), 215

addOtherData() (psychopy.data.QuestHandler method), 219

addOtherData() (psychopy.data.StairHandler method), 211

addResponse() (psychopy.data.MultiStairHandler method), 215

addResponse() (psychopy.data.QuestHandler method), 219

addResponse() (psychopy.data.StairHandler method), 212

addTarget() (psychopy.logging.\_Logger method), 331

addTrialHandlerRecord() (psychopy.iohub.client.ioHubConnection method), 290

AdvAudioCapture (class in psychopy.microphone), 333

alert() (in module pylink), 281

alignHoriz (psychopy.visual.TextStim attribute), 183

alignVert (psychopy.visual.TextStim attribute), 183

angle\_x (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311

angle\_x (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 308

angle\_x (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 313

angle\_y (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311

angle\_y (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309

angle\_y (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 313

angularCycles (psychopy.visual.RadialStim attribute), 144

angularPhase (psychopy.visual.RadialStim attribute), 144

angularRes (psychopy.visual.RadialStim attribute), 144

antialias (psychopy.visual.TextStim attribute), 183

Aperture (class in psychopy.visual), 105

apodize() (in module psychopy.voicekey), 385

applyEyeTransform() (psychopy.visual.Window method), 191

applyMatrix() (in module psychopy.tools.mathtools), 373

array2image() (in module psychopy.tools.imagetools), 366

attach() (in module psychopy.tools.gltools), 357

autoDraw (psychopy.visual.BufferImageStim attribute), 108

autoDraw (psychopy.visual.GratingStim attribute), 118

autoDraw (psychopy.visual.ImageStim attribute), 127

autoDraw (psychopy.visual.MovieStim attribute), 135

autoDraw (psychopy.visual.RadialStim attribute), 144

autoDraw (psychopy.visual.ShapeStim attribute), 166

autoDraw (psychopy.visual.TextStim attribute), 183

autoLog (psychopy.visual.BufferImageStim attribute), 108

autoLog (psychopy.visual.GratingStim attribute), 118

autoLog (psychopy.visual.ImageStim attribute), 127

autoLog (psychopy.visual.MovieStim attribute), 135

autoLog (psychopy.visual.RadialStim attribute), 144

autoLog (psychopy.visual.ShapeStim attribute), 166

autoLog (psychopy.visual.TextStim attribute), 183

average\_angle\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313

average\_angle\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

average\_angle\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313

average\_angle\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

average\_gaze\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 302, 313

average\_gaze\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

average\_gaze\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 303, 313

average\_gaze\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

average\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313

average\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

average\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313

average\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315

- average\_velocity\_xy (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313
- average\_velocity\_xy (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- ## B
- bandpass() (in module psychopy.voicekey), 385
- beep() (psychopy.hardware.crs.bits.BitsSharp method), 246
- beginRealTimeMode() (in module pylink), 281
- BinocularEyeSampleEvent (class in psychopy.iohub.devices.eyetracker), 301, 309, 325
- bitmapSave() (in module pylink), 281
- BitsPlusPlus (class in psychopy.hardware.crs.bits), 233
- BitsSharp (class in psychopy.hardware.crs.bits), 240
- blendmode (psychopy.visual.GratingStim attribute), 119
- blendmode (psychopy.visual.RadialStim attribute), 144
- blendMode (psychopy.visual.Window attribute), 191
- BlinkEndEvent (class in psychopy.iohub.devices.eyetracker), 316
- BlinkStartEvent (class in psychopy.iohub.devices.eyetracker), 315
- blitFBO() (in module psychopy.tools.gltools), 357
- bold (psychopy.visual.TextStim attribute), 183
- bootStraps() (in module psychopy.data), 225
- boundingBox (psychopy.visual.TextStim attribute), 184
- BufferImageStim (class in psychopy.visual), 106
- ButtonBox (class in psychopy.hardware.forp), 270
- ButtonBox (class in psychopy.hardware.iolab), 271
- ## C
- calculateNextIntensity() (psychopy.data.QuestHandler method), 219
- calculateNextIntensity() (psychopy.data.StairHandler method), 212
- calibrateZero() (psychopy.hardware.crs.colorcal.ColorCAL method), 264
- callOnFlip() (psychopy.visual.Window method), 191
- cart2pol() (in module psychopy.tools.coordinatetools), 354
- cart2sph() (in module psychopy.tools.coordinatetools), 354
- changeProjection() (psychopy.visual.windowwarp.Warper method), 200
- char (psychopy.iohub.client.keyboard.KeyboardPress attribute), 295
- char (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 296
- checkConfig() (psychopy.hardware.crs.bits.BitsSharp method), 246
- checkOK() (psychopy.hardware.minolta.LS100 method), 277
- cielab2rgb() (in module psychopy.tools.colorspectools), 351
- cielch2rgb() (in module psychopy.tools.colorspectools), 352
- Circle (class in psychopy.visual), 114
- clear\_response\_queue() (pyxid.ResponseDevice method), 232
- clearBuffer() (psychopy.hardware.forp.ButtonBox method), 271
- clearBuffer() (psychopy.visual.Window method), 192
- clearEvents() (in module psychopy.event), 227
- clearEvents() (psychopy.hardware.iolab.ButtonBox method), 272
- clearEvents() (psychopy.iohub.client.ioHubConnection method), 289
- clearEvents() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 299
- clearEvents() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 305
- clearEvents() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 322
- clearMemory() (psychopy.hardware.minolta.LS100 method), 277
- clearStatus() (psychopy.hardware.forp.ButtonBox method), 271
- clearTextures() (psychopy.visual.BufferImageStim method), 109
- clearTextures() (psychopy.visual.GratingStim method), 119
- clearTextures() (psychopy.visual.ImageStim method), 127
- clearTextures() (psychopy.visual.RadialStim method), 144
- clickReset() (psychopy.event.Mouse method), 226
- Clock (class in psychopy.clock), 202
- Clock (class in psychopy.core), 103
- clock() (psychopy.hardware.crs.bits.BitsSharp method), 246
- close() (psychopy.data.ExperimentHandler method), 205
- close() (psychopy.visual.Window method), 192
- closeGraphics() (in module pylink), 281
- closeMessageFile() (in module pylink), 281
- closeShape (psychopy.visual.ShapeStim attribute), 166
- cm2deg() (in module psychopy.tools.monitorunittools), 374
- cm2pix() (in module psychopy.tools.monitorunittools), 374
- color (psychopy.visual.BufferImageStim attribute), 109
- color (psychopy.visual.GratingStim attribute), 119
- color (psychopy.visual.ImageStim attribute), 127
- color (psychopy.visual.RadialStim attribute), 144
- color (psychopy.visual.ShapeStim attribute), 166

- ul style="list-style-type: none; padding-left: 0;">
- color (psychopy.visual.Slider attribute), 173
- color (psychopy.visual.TextStim attribute), 184
- color (psychopy.visual.Window attribute), 192
- ColorCAL (class in psychopy.hardware.crs.colorcal), 264
- colorSpace (psychopy.visual.BufferImageStim attribute), 109
- colorSpace (psychopy.visual.GratingStim attribute), 119
- colorSpace (psychopy.visual.ImageStim attribute), 128
- colorSpace (psychopy.visual.RadialStim attribute), 145
- colorSpace (psychopy.visual.ShapeStim attribute), 166
- colorSpace (psychopy.visual.TextStim attribute), 184
- colorSpace (psychopy.visual.Window attribute), 192
- complete() (psychopy.clock.StaticPeriod method), 203
- complete() (psychopy.core.StaticPeriod method), 105
- compress() (psychopy.microphone.AdvAudioCapture method), 333
- computeFrustum() (in module psychopy.tools.viewtools), 377
- concatenate() (in module psychopy.tools.mathtools), 371
- confInterval() (psychopy.data.QuestHandler method), 219
- contains() (psychopy.visual.BufferImageStim method), 110
- contains() (psychopy.visual.GratingStim method), 120
- contains() (psychopy.visual.ImageStim method), 129
- contains() (psychopy.visual.MovieStim method), 135
- contains() (psychopy.visual.RadialStim method), 146
- contains() (psychopy.visual.ShapeStim method), 166
- contains() (psychopy.visual.TextStim method), 185
- contrast (psychopy.visual.BufferImageStim attribute), 110
- contrast (psychopy.visual.GratingStim attribute), 120
- contrast (psychopy.visual.ImageStim attribute), 129
- contrast (psychopy.visual.RadialStim attribute), 146
- contrast (psychopy.visual.ShapeStim attribute), 167
- contrast (psychopy.visual.Slider attribute), 173
- contrast (psychopy.visual.TextStim attribute), 185
- controllerConnected() (psychopy.visual.Rift method), 158
- convertToPix() (in module psychopy.tools.monitorunittools), 374
- copyCalib() (psychopy.monitors.Monitor method), 338
- CountdownTimer (class in psychopy.clock), 202
- CountdownTimer (class in psychopy.core), 104
- CPU, 28
- createFBO() (in module psychopy.tools.gltools), 356
- createLight() (in module psychopy.tools.gltools), 363
- createMaterial() (in module psychopy.tools.gltools), 362
- createRenderbuffer() (in module psychopy.tools.gltools), 358
- createTexImage2D() (in module psychopy.tools.gltools), 359
- createTexImage2DMultisample() (in module psychopy.tools.gltools), 360
- createTrialHandlerRecordTable() (psychopy.iohub.client.ioHubConnection method), 290
- createVAO() (in module psychopy.tools.gltools), 361
- createVBO() (in module psychopy.tools.gltools), 360
- critical() (in module psychopy.logging), 331
- CRT, 28
- csv, 28
- currentTime() (in module pylink), 281
- currentUsec() (in module pylink), 282
- CustomMouse (class in psychopy.visual), 114
- ## D
- daemon (psychopy.hardware.emulator.ResponseEmulator attribute), 266
  - daemon (psychopy.hardware.emulator.SyncGenerator attribute), 267
  - data() (in module psychopy.logging), 331
  - debug() (in module psychopy.logging), 331
  - deg2cm() (in module psychopy.tools.monitorunittools), 374
  - deg2pix() (in module psychopy.tools.monitorunittools), 375
  - degrees() (in module psychopy.tools.unittools), 376
  - delCalib() (psychopy.monitors.Monitor method), 338
  - deleteFBO() (in module psychopy.tools.gltools), 357
  - deleteRenderbuffer() (in module psychopy.tools.gltools), 359
  - deleteTexture() (in module psychopy.tools.gltools), 360
  - deleteVAO() (in module psychopy.tools.gltools), 362
  - deleteVBO() (in module psychopy.tools.gltools), 362
  - depth (psychopy.visual.BufferImageStim attribute), 110
  - depth (psychopy.visual.GratingStim attribute), 121
  - depth (psychopy.visual.ImageStim attribute), 129
  - depth (psychopy.visual.MovieStim attribute), 135
  - depth (psychopy.visual.RadialStim attribute), 146
  - depth (psychopy.visual.ShapeStim attribute), 167
  - depth (psychopy.visual.TextStim attribute), 185
  - detect() (psychopy.voicekey.OnsetVoiceKey method), 384
  - device (psychopy.iohub.client.keyboard.KeyboardPress attribute), 295
  - device (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 296
  - displayLost (psychopy.visual.Rift attribute), 158
  - displayRefreshRate (psychopy.visual.Rift attribute), 158
  - dkl2rgb() (in module psychopy.tools.colorspectools), 350, 351
  - dklCart2rgb() (in module psychopy.tools.colorspectools), 350
  - Dlg (class in psychopy.gui), 229
  - DlgFromDict (class in psychopy.gui), 228
  - DotStim (class in psychopy.visual), 115
  - draw() (psychopy.visual.BufferImageStim method), 110



- draw() (psychopy.visual.GratingStim method), 121
- draw() (psychopy.visual.ImageStim method), 129
- draw() (psychopy.visual.MovieStim method), 135
- draw() (psychopy.visual.RadialStim method), 146
- draw() (psychopy.visual.ShapeStim method), 167
- draw() (psychopy.visual.Slider method), 173
- draw() (psychopy.visual.TextBox method), 177
- draw() (psychopy.visual.TextStim method), 185
- drawVAO() (in module psychopy.tools.gltools), 361
- driverFor (psychopy.hardware.crs.bits.BitsSharp attribute), 246
- driverFor (psychopy.hardware.crs.colorcal.ColorCAL attribute), 264
- duration (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 296
- duration (psychopy.iohub.devices.eyetracker.BlinkEndEvent attribute), 316
- duration (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 303, 312
- duration (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- ## E
- ElementArrayStim (class in psychopy.visual), 116
- enableEventReporting() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 299
- enableEventReporting() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 305
- enableEventReporting() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 322
- enableExtendedRealtime() (in module pylink), 282
- enablePCRSample() (in module pylink), 282
- end\_angle\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_angle\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_angle\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_angle\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_gaze\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_gaze\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- end\_gaze\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_gaze\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- end\_ppd\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_ppd\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_ppd\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313
- end\_ppd\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- end\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- end\_velocity\_xy (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313
- end\_velocity\_xy (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
- endOfFlip() (psychopy.visual.windowframepack.ProjectorFramePacker method), 198
- endRealTimeMode() (in module pylink), 282
- endRealTimeMode() (psychopy.hardware.pr.PR655 method), 279
- EnvelopeGrating (class in psychopy.visual), 163
- error() (in module psychopy.logging), 331
- eval() (psychopy.data.FitCumNormal method), 224
- eval() (psychopy.data.FitLogistic method), 223
- eval() (psychopy.data.FitNakaRushton method), 223
- eval() (psychopy.data.FitWeibull method), 222
- exp() (in module psychopy.logging), 332
- ExperimentHandler (class in psychopy.data), 204
- ere (psychopy.iohub.devices.eyetracker.BlinkEndEvent attribute), 316
- ere (psychopy.iohub.devices.eyetracker.BlinkStartEvent attribute), 315
- ere (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 302, 312
- ere (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 302, 311
- ere (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 308
- ere (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- ere (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 313
- EyeTracker (class in psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3), 298
- EyeTracker (class in psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink), 298

304  
EyeTracker (class in psy-  
chopy.iohub.devices.eyetracker.hw.tobii),  
321

## F

fadeOut() (psychopy.sound.backend\_pygame.SoundPygame  
method), 349  
farClip (psychopy.visual.Window attribute), 192  
fatal() (in module psychopy.logging), 332  
fileOpenDlg() (in module psychopy.gui), 230  
fileSaveDlg() (in module psychopy.gui), 231  
fillColor (psychopy.visual.ShapeStim attribute), 167  
fillColorSpace (psychopy.visual.ShapeStim attribute),  
167  
findPhotometer() (in module psychopy.hardware), 284  
firmwareVersion (psychopy.visual.Rift attribute), 158  
FitCumNormal (class in psychopy.data), 223  
fitGammaErrFun() (psy-  
chopy.monitors.GammaCalculator method),  
341  
fitGammaFun() (psychopy.monitors.GammaCalculator  
method), 341  
FitLogistic (class in psychopy.data), 222  
FitNakaRushton (class in psychopy.data), 223  
FitWeibull (class in psychopy.data), 222  
FixationEndEvent (class in psy-  
chopy.iohub.devices.eyetracker), 302, 311  
FixationStartEvent (class in psy-  
chopy.iohub.devices.eyetracker), 302, 311  
flac2wav() (in module psychopy.microphone), 335  
flip() (psychopy.visual.Rift method), 158  
flip() (psychopy.visual.Window method), 192  
flipHoriz (psychopy.visual.BufferImageStim attribute),  
110  
flipHoriz (psychopy.visual.TextStim attribute), 185  
flipVert (psychopy.visual.BufferImageStim attribute), 111  
flipVert (psychopy.visual.TextStim attribute), 186  
float\_uint16() (in module psychopy.tools.typetools), 375  
float\_uint8() (in module psychopy.tools.typetools), 375  
flush() (in module psychopy.logging), 332  
flush() (psychopy.hardware.crs.bits.BitsSharp method),  
246  
flush() (psychopy.logging.\_Logger method), 331  
flushDataStoreFile() (psy-  
chopy.iohub.client.ioHubConnection method),  
291  
flushGetkeyQueue() (in module pylink), 282  
font (psychopy.visual.TextStim attribute), 186  
fontFiles (psychopy.visual.TextStim attribute), 186  
fps() (psychopy.visual.Window method), 193  
fromFile() (in module psychopy.tools.filetools), 354  
fullscr (psychopy.visual.Window attribute), 193  
functionFromStaircase() (in module psychopy.data), 224

## G

gamma (psychopy.visual.Window attribute), 193  
GammaCalculator (class in psychopy.monitors), 341  
gammaCorrectFile (psy-  
chopy.hardware.crs.bits.BitsSharp attribute),  
246  
gammaFun() (in module psychopy.monitors), 342  
gammaInvFun() (in module psychopy.monitors), 342  
gammalsDefault() (psychopy.monitors.Monitor method),  
338  
gammaRamp (psychopy.visual.Window attribute), 193  
gaze\_x (psychopy.iohub.devices.eyetracker.FixationStartEvent  
attribute), 302, 311  
gaze\_x (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent  
attribute), 308  
gaze\_x (psychopy.iohub.devices.eyetracker.SaccadeStartEvent  
attribute), 313  
gaze\_y (psychopy.iohub.devices.eyetracker.FixationStartEvent  
attribute), 302, 311  
gaze\_y (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent  
attribute), 308  
gaze\_y (psychopy.iohub.devices.eyetracker.SaccadeStartEvent  
attribute), 313  
genDelimiter() (in module psychopy.tools.filetools), 355  
generalizedPerspectiveProjection() (in module psy-  
chopy.tools.viewtools), 379  
get\_a() (psychopy.hardware.joystick.XboxController  
method), 273  
get\_b() (psychopy.hardware.joystick.XboxController  
method), 273  
get\_back() (psychopy.hardware.joystick.XboxController  
method), 273  
get\_hat\_axis() (psychopy.hardware.joystick.XboxController  
method), 273  
get\_left\_shoulder() (psy-  
chopy.hardware.joystick.XboxController  
method), 274  
get\_left\_thumbstick() (psy-  
chopy.hardware.joystick.XboxController  
method), 274  
get\_left\_thumbstick\_axis() (psy-  
chopy.hardware.joystick.XboxController  
method), 274  
get\_named\_buttons() (psy-  
chopy.hardware.joystick.XboxController  
method), 274  
get\_next\_response() (pyxid.ResponseDevice method),  
232  
get\_right\_shoulder() (psy-  
chopy.hardware.joystick.XboxController  
method), 274  
get\_right\_thumbstick() (psy-  
chopy.hardware.joystick.XboxController  
method), 274

- get\_right\_thumbstick\_axis() (psychopy.hardware.joystick.XboxController method), 274
- get\_start() (psychopy.hardware.joystick.XboxController method), 274
- get\_trigger\_axis() (psychopy.hardware.joystick.XboxController method), 274
- get\_x() (psychopy.hardware.joystick.XboxController method), 274
- get\_xid\_device() (in module pyxid), 231
- get\_xid\_devices() (in module pyxid), 232
- get\_y() (psychopy.hardware.joystick.XboxController method), 274
- getAbsTime() (in module psychopy.clock), 201
- getAbsTime() (in module psychopy.core), 103
- getActualFrameRate() (psychopy.visual.Window method), 193
- getAllAxes() (psychopy.hardware.joystick.Joystick method), 275
- getAllButtons() (psychopy.hardware.joystick.Joystick method), 275
- getAllEntries() (psychopy.data.ExperimentHandler method), 205
- getAllHats() (psychopy.hardware.joystick.Joystick method), 275
- getAllMonitors() (in module psychopy.monitors), 341
- getAllRTBoxResponses() (psychopy.hardware.crs.bits.BitsSharp method), 246
- getAllStatusBoxResponses() (psychopy.hardware.crs.bits.BitsSharp method), 247
- getAllStatusEvents() (psychopy.hardware.crs.bits.BitsSharp method), 247
- getAllStatusValues() (psychopy.hardware.crs.bits.BitsSharp method), 248
- getAnalog() (psychopy.hardware.crs.bits.BitsSharp method), 248
- getAutoLog() (psychopy.visual.TextBox method), 178
- getAxis() (psychopy.hardware.joystick.Joystick method), 275
- getBackgroundColor() (psychopy.visual.TextBox method), 178
- getBaseTime() (psychopy.hardware.iolab.ButtonBox method), 272
- getBorderColor() (psychopy.visual.TextBox method), 178
- getBorderWidth() (psychopy.visual.TextBox method), 178
- getButton() (psychopy.hardware.joystick.Joystick method), 275
- getButtons() (psychopy.visual.Rift method), 158
- getCalibDate() (psychopy.monitors.Monitor method), 338
- getCalibMatrix() (psychopy.hardware.crs.colorcal.ColorCAL method), 264
- getColorSpace() (psychopy.visual.TextBox method), 178
- getConectedControllers() (psychopy.visual.Rift method), 158
- getConfiguration() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 299
- getConfiguration() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 305
- getConfiguration() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 323
- getDevice() (psychopy.iohub.client.ioHubConnection method), 288
- getDeviceSN() (psychopy.hardware.pr.PR655 method), 279
- getDeviceType() (psychopy.hardware.pr.PR655 method), 279
- getDft() (in module psychopy.microphone), 335
- getDigital() (psychopy.hardware.crs.bits.BitsSharp method), 248
- getDigitalWord() (psychopy.hardware.crs.bits.BitsSharp method), 249
- getDisplayedText() (psychopy.visual.TextBox method), 178
- getDisplayInformation() (in module pylink), 282
- getDistance() (psychopy.monitors.Monitor method), 338
- getDKL\_RGB() (psychopy.monitors.Monitor method), 338
- getDuration() (psychopy.sound.backend\_pygame.SoundPygame method), 349
- getEarlierTrial() (psychopy.data.TrialHandler method), 207
- getEnabled() (psychopy.hardware.iolab.ButtonBox method), 272
- getEvents() (psychopy.hardware.forp.ButtonBox method), 271
- getEvents() (psychopy.hardware.iolab.ButtonBox method), 272
- getEvents() (psychopy.iohub.client.ioHubConnection method), 289
- getEvents() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 299
- getEvents() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 306
- getEvents() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 323
- getExp() (psychopy.data.MultiStairHandler method), 215
- getExp() (psychopy.data.QuestHandler method), 220

- getExp() (psychopy.data.StairHandler method), [212](#)
- getExp() (psychopy.data.TrialHandler method), [207](#)
- getFloatv() (in module psychopy.tools.gltools), [365](#)
- getFontColor() (psychopy.visual.TextBox method), [178](#)
- getFutureTrial() (psychopy.data.TrialHandler method), [207](#)
- getGamma() (psychopy.monitors.Monitor method), [338](#)
- getGammaGrid() (psychopy.monitors.Monitor method), [338](#)
- getGlyphPositionForTextIndex() (psychopy.visual.TextBox method), [178](#)
- getHandTriggerValues() (psychopy.visual.Rift method), [159](#)
- getHat() (psychopy.hardware.joystick.Joystick method), [275](#)
- getHistory() (psychopy.visual.Slider method), [173](#)
- getHorzAlign() (psychopy.visual.TextBox method), [178](#)
- getHorzJust() (psychopy.visual.TextBox method), [179](#)
- getIndexTriggerValues() (psychopy.visual.Rift method), [159](#)
- getInfo() (psychopy.hardware.crs.bits.BitsSharp method), [249](#)
- getInfo() (psychopy.hardware.crs.colorcal.ColorCAL method), [265](#)
- getInterv() (in module psychopy.tools.gltools), [364](#)
- getInterpolated() (psychopy.visual.TextBox method), [179](#)
- getIRBox() (psychopy.hardware.crs.bits.BitsSharp method), [249](#)
- getKeys() (in module psychopy.event), [227](#)
- getKeys() (psychopy.iohub.client.keyboard.Keyboard method), [293](#)
- getLabel() (psychopy.visual.TextBox method), [179](#)
- getLastColorTemp() (psychopy.hardware.pr.PR655 method), [279](#)
- getLastError() (in module pylink), [282](#)
- getLastGazePosition() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), [299](#)
- getLastGazePosition() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyetracker.EyeTracker method), [306](#)
- getLastGazePosition() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), [323](#)
- getLastLum() (psychopy.hardware.pr.PR650 method), [278](#)
- getLastResetTime() (psychopy.clock.MonotonicClock method), [203](#)
- getLastResetTime() (psychopy.core.MonotonicClock method), [104](#)
- getLastSample() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), [300](#)
- getLastSample() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyetracker.EyeTracker method), [306](#)
- getLastSample() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), [324](#)
- getLastSpectrum() (psychopy.hardware.pr.PR650 method), [278](#)
- getLastSpectrum() (psychopy.hardware.pr.PR655 method), [280](#)
- getLastTristim() (psychopy.hardware.pr.PR655 method), [280](#)
- getLastUV() (psychopy.hardware.pr.PR655 method), [280](#)
- getLastXY() (psychopy.hardware.pr.PR655 method), [280](#)
- getLevel() (in module psychopy.logging), [332](#)
- getLevelsPost() (psychopy.monitors.Monitor method), [338](#)
- getLevelsPre() (psychopy.monitors.Monitor method), [338](#)
- getLinearizeMethod() (psychopy.monitors.Monitor method), [338](#)
- getLineSpacing() (psychopy.visual.TextBox method), [179](#)
- getLMS\_RGB() (psychopy.monitors.Monitor method), [338](#)
- getLoudness() (psychopy.microphone.AdvAudioCapture method), [333](#)
- getLum() (psychopy.hardware.crs.colorcal.ColorCAL method), [265](#)
- getLum() (psychopy.hardware.minolta.LS100 method), [277](#)
- getLum() (psychopy.hardware.pr.PR650 method), [278](#)
- getLumSeriesPR650() (in module psychopy.monitors), [341](#)
- getLumsPost() (psychopy.monitors.Monitor method), [338](#)
- getLumsPre() (psychopy.monitors.Monitor method), [339](#)
- getMarkerInfo() (psychopy.microphone.AdvAudioCapture method), [334](#)
- getMarkerOnset() (psychopy.microphone.AdvAudioCapture method), [334](#)
- getMarkerTime() (psychopy.monitors.Monitor method), [339](#)
- getMemoryUsage() (in module psychopy.info), [286](#)
- getMovieFrame() (psychopy.visual.Window method), [193](#)
- getMsPerFrame() (psychopy.visual.Window method), [194](#)
- getName() (psychopy.hardware.joystick.Joystick method), [275](#)
- getName() (psychopy.visual.TextBox method), [179](#)
- getNeedsCalibrateZero() (psychopy.hardware.crs.colorcal.ColorCAL method), [265](#)
- getNotes() (psychopy.monitors.Monitor method), [339](#)
- getNotes() (psychopy.hardware.joystick.Joystick method), [275](#)



- getNumButtons() (psychopy.hardware.joystick.Joystick method), 275
- getNumHats() (psychopy.hardware.joystick.Joystick method), 275
- getNumJoysticks() (in module psychopy.hardware.joystick), 275
- getOpacity() (psychopy.visual.TextBox method), 179
- getOpenGLInfo() (in module psychopy.tools.gltools), 365
- getOriginPathAndFile() (psychopy.data.MultiStairHandler method), 215
- getOriginPathAndFile() (psychopy.data.QuestHandler method), 220
- getOriginPathAndFile() (psychopy.data.StairHandler method), 212
- getOriginPathAndFile() (psychopy.data.TrialHandler method), 207
- getPackets() (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
- getPackets() (psychopy.hardware.crs.bits.BitsSharp method), 249
- getPos() (psychopy.event.Mouse method), 226
- getPosition() (psychopy.iohub.devices.eyetracker.hw.gazepoint.TripleTracker method), 300
- getPosition() (psychopy.iohub.devices.eyetracker.hw.sr\_research.EyeTracker method), 307
- getPosition() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 324
- getPosition() (psychopy.visual.TextBox method), 179
- getPressed() (psychopy.event.Mouse method), 226
- getPresses() (psychopy.iohub.client.keyboard.Keyboard method), 293
- getPriority() (psychopy.iohub.client.ioHubConnection method), 291
- getProcessAffinity() (psychopy.iohub.client.ioHubConnection method), 291
- getPsychopyVersion() (psychopy.monitors.Monitor method), 339
- getRAM() (in module psychopy.info), 286
- getRating() (psychopy.visual.Slider method), 173
- getRel() (psychopy.event.Mouse method), 226
- getReleases() (psychopy.iohub.client.keyboard.Keyboard method), 294
- getResponse() (psychopy.hardware.crs.bits.BitsSharp method), 250
- getRGBspectra() (in module psychopy.monitors), 341
- getRMS() (in module psychopy.microphone), 335
- getRT() (psychopy.visual.Slider method), 173
- getRTBoxResponse() (psychopy.hardware.crs.bits.BitsSharp method), 250
- getRTBoxResponses() (psychopy.hardware.crs.bits.BitsSharp method), 250
- getSize() (psychopy.visual.TextBox method), 179
- getSizePix() (psychopy.monitors.Monitor method), 339
- getSpectra() (psychopy.monitors.Monitor method), 339
- getSpectrum() (psychopy.hardware.pr.PR650 method), 279
- getStatus() (psychopy.hardware.crs.bits.BitsSharp method), 251
- getStatusBoxResponse() (psychopy.hardware.crs.bits.BitsSharp method), 251
- getStatusBoxResponses() (psychopy.hardware.crs.bits.BitsSharp method), 251
- getStatusEvent() (psychopy.hardware.crs.bits.BitsSharp method), 252
- getString() (in module psychopy.tools.gltools), 365
- getText() (psychopy.visual.TextBox method), 179
- getTextGridCellForCharIndex() (psychopy.visual.TextBox method), 179
- getTextGridCellPlacement() (psychopy.visual.TextBox method), 179
- getTextGridCellTextColor() (psychopy.visual.TextBox method), 179
- getTextGridCellLineWidth() (psychopy.visual.TextBox method), 180
- getTextGridCellStrokeWidth() (psychopy.visual.TextBox method), 180
- getTrackballStickValues() (psychopy.visual.Rift method), 159
- getTime() (in module psychopy.clock), 201
- getTime() (in module psychopy.core), 103
- getTime() (psychopy.clock.CountdownTimer method), 202
- getTime() (psychopy.clock.MonotonicClock method), 203
- getTime() (psychopy.core.CountdownTimer method), 104
- getTime() (psychopy.core.MonotonicClock method), 104
- getTime() (psychopy.iohub.client.ioHubConnection method), 291
- getTouches() (psychopy.visual.Rift method), 159
- getTrackingOriginType() (psychopy.visual.Rift method), 159
- getTrigIn() (psychopy.hardware.crs.bits.BitsSharp method), 252
- getUniqueEvents() (psychopy.hardware.forp.ButtonBox method), 271
- getUnitType() (psychopy.visual.TextBox method), 180
- getUseBits() (psychopy.monitors.Monitor method), 339
- getValidStrokeWidths() (psychopy.visual.TextBox method), 180
- getVertAlign() (psychopy.visual.TextBox method), 180
- getVertJust() (psychopy.visual.TextBox method), 180
- getVideoLine() (psychopy.hardware.crs.bits.BitsSharp method), 253
- getVisible() (psychopy.event.Mouse method), 226

- ul style="list-style-type: none; padding-left: 0;">
- getVolume() (psychopy.sound.backend\_pygame.SoundPygame method), 349
- getWheelRel() (psychopy.event.Mouse method), 226
- getWidth() (psychopy.monitors.Monitor method), 339
- getWindow() (psychopy.visual.TextBox method), 180
- getX() (psychopy.hardware.joystick.Joystick method), 275
- getY() (psychopy.hardware.joystick.Joystick method), 275
- getZ() (psychopy.hardware.joystick.Joystick method), 275
- GPU, 28
- GratingStim (class in psychopy.visual), 117
- groupFlipVert() (in module psychopy.visual.helpers), 125
- ## H
- hasInputFocus (psychopy.visual.Rift attribute), 160
  - haveInternetAccess() (in module psychopy.web), 386
  - headLocked (psychopy.visual.Rift attribute), 160
  - height (psychopy.visual.TextStim attribute), 186
  - horiz (psychopy.visual.Slider attribute), 173
  - hsv2rgb() (in module psychopy.tools.colorspectools), 351
- ## I
- ident (psychopy.hardware.emulator.ResponseEmulator attribute), 266
  - ident (psychopy.hardware.emulator.SyncGenerator attribute), 268
  - image (psychopy.visual.BufferImageStim attribute), 111
  - image (psychopy.visual.ImageStim attribute), 129
  - image2array() (in module psychopy.tools.imagetools), 366
  - ImageStim (class in psychopy.visual), 126
  - importConditions() (in module psychopy.data), 224
  - importData() (psychopy.data.QuestHandler method), 220
  - incTrials() (psychopy.data.QuestHandler method), 220
  - info() (in module psychopy.logging), 332
  - init\_device() (pyxid.XidDevice method), 232
  - inRealTimeMode() (in module pylink), 282
  - interpolate (psychopy.visual.BufferImageStim attribute), 111
  - interpolate (psychopy.visual.GratingStim attribute), 121
  - interpolate (psychopy.visual.ImageStim attribute), 129
  - interpolate (psychopy.visual.RadialStim attribute), 146
  - interpolate (psychopy.visual.ShapeStim attribute), 167
  - inverse() (psychopy.data.FitCumNormal method), 224
  - inverse() (psychopy.data.FitLogistic method), 223
  - inverse() (psychopy.data.FitNakaRushton method), 223
  - inverse() (psychopy.data.FitWeibull method), 222
  - invertQuat() (in module psychopy.tools.mathtools), 368
  - ioHubConnection (class in psychopy.iohub.client), 288
  - is\_alive() (psychopy.hardware.emulator.ResponseEmulator method), 266
  - is\_alive() (psychopy.hardware.emulator.SyncGenerator method), 268
  - isAlive() (psychopy.hardware.emulator.ResponseEmulator method), 266
  - isAlive() (psychopy.hardware.emulator.SyncGenerator method), 268
  - isAwake() (psychopy.hardware.crs.bits.BitsSharp method), 253
  - isComplete() (in module psychopy.tools.gltools), 357
  - isHmdMounted (psychopy.visual.Rift attribute), 160
  - isHmdPresent (psychopy.visual.Rift attribute), 160
  - isIndexPointing() (psychopy.visual.Rift method), 160
  - isOpen (psychopy.hardware.crs.bits.BitsSharp attribute), 253
  - isPressedIn() (psychopy.event.Mouse method), 226
  - isRecordingEnabled() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 300
  - isRecordingEnabled() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 307
  - isRecordingEnabled() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 324
  - isThumbUp() (psychopy.visual.Rift method), 160
  - isVisible (psychopy.visual.Rift attribute), 160
  - italic (psychopy.visual.TextStim attribute), 186
- ## J
- join() (psychopy.hardware.emulator.ResponseEmulator method), 266
  - join() (psychopy.hardware.emulator.SyncGenerator method), 268
  - join() (psychopy.voicekey.OnsetVoiceKey method), 384
  - Joystick (class in psychopy.hardware.joystick), 275
- ## K
- Keyboard (class in psychopy.iohub.client.keyboard), 292
  - KeyboardPress (class in psychopy.iohub.client.keyboard), 295
  - KeyboardRelease (class in psychopy.iohub.client.keyboard), 296
  - knownStyles (psychopy.visual.Slider attribute), 173
- ## L
- launchHubServer() (in module psychopy.iohub.client), 287
  - launchScan() (in module psychopy.hardware.emulator), 268
  - left\_angle\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 309
  - left\_angle\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 309

- left\_eye\_cam\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 325
- left\_eye\_cam\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 325
- left\_eye\_cam\_z (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 325
- left\_gaze\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 309, 325
- left\_gaze\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 309, 325
- left\_ppd\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- left\_ppd\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- left\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- left\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 310, 325
- left\_raw\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 309
- left\_raw\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 309
- left\_velocity\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- left\_velocity\_xy (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- left\_velocity\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310
- lerp() (in module psychopy.tools.mathtools), 367
- Line (class in psychopy.visual), 133
- lineariseLums() (psychopy.monitors.Monitor method), 339
- linearizeLums() (psychopy.monitors.Monitor method), 339
- lineColor (psychopy.visual.ShapeStim attribute), 167
- lineColorSpace (psychopy.visual.ShapeStim attribute), 167
- lineWidth (psychopy.visual.ShapeStim attribute), 168
- lms2rgb() (in module psychopy.tools.colorspacetools), 351
- loadAll() (psychopy.preferences.Preferences method), 345
- loadMovie() (psychopy.visual.MovieStim method), 135
- loadMtlFile() (in module psychopy.tools.gltools), 364
- loadObjFile() (in module psychopy.tools.gltools), 364
- loadUserPrefs() (psychopy.preferences.Preferences method), 345
- log() (in module psychopy.logging), 332
- log() (psychopy.logging.\_Logger method), 331
- LogFile (class in psychopy.logging), 330
- logOnFlip() (psychopy.visual.Window method), 194
- longName (psychopy.hardware.crs.bits.BitsSharp attribute), 253
- longName (psychopy.hardware.crs.colorcal.ColorCAL attribute), 265
- lookAt() (in module psychopy.tools.viewtools), 381
- lookupEvent (psychopy.data.ExperimentHandler method), 205
- LS100 (class in psychopy.hardware.minolta), 276
- makeDKL2RGB() (in module psychopy.monitors), 342
- makeImageStim() (in module psychopy.tools.imagetools), 366
- makeMVS2RGB() (in module psychopy.monitors), 342
- manufacturer (psychopy.visual.Rift attribute), 160
- markerPos (psychopy.visual.Slider attribute), 173
- mask (psychopy.visual.BufferImageStim attribute), 111
- mask (psychopy.visual.GratingStim attribute), 121
- mask (psychopy.visual.ImageStim attribute), 129
- mask (psychopy.visual.RadialStim attribute), 146
- maskParams (psychopy.visual.BufferImageStim attribute), 111
- maskParams (psychopy.visual.GratingStim attribute), 121
- maskParams (psychopy.visual.ImageStim attribute), 130
- maskParams (psychopy.visual.RadialStim attribute), 147
- maskFromQuad() (in module psychopy.tools.mathtools), 370
- mean() (psychopy.data.QuestHandler method), 220
- measure() (psychopy.hardware.crs.colorcal.ColorCAL method), 265
- measure() (psychopy.hardware.minolta.LS100 method), 277
- measure() (psychopy.hardware.pr.PR650 method), 279
- measure() (psychopy.hardware.pr.PR655 method), 280
- mergeFolder() (in module psychopy.tools.filetools), 354
- Method of constants, 28
- mode (psychopy.hardware.crs.bits.BitsSharp attribute), 253
- mode() (psychopy.data.QuestHandler method), 220
- modifiers (psychopy.iohub.client.keyboard.KeyboardPress attribute), 295
- modifiers (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 296
- Monitor (class in psychopy.monitors), 337
- monitorEDID (psychopy.hardware.crs.bits.BitsSharp attribute), 253
- monitorFramePeriod (psychopy.visual.Window attribute), 191
- MonocularEyeSampleEvent (class in psychopy.iohub.devices.eyetracker), 308
- MonotonicClock (class in psychopy.clock), 202
- MonotonicClock (class in psychopy.core), 104
- Mouse (class in psychopy.event), 225
- mouseMoved() (psychopy.event.Mouse method), 226
- mouseMoveTime() (psychopy.event.Mouse method), 226

mouseVisible (psychopy.visual.Window attribute), 194  
 MovieStim (class in psychopy.visual), 134  
 mro() (psychopy.visual.Aperture method), 106  
 mro() (psychopy.visual.Circle method), 114  
 mro() (psychopy.visual.CustomMouse method), 115  
 mro() (psychopy.visual.DotStim method), 116  
 mro() (psychopy.visual.ElementArrayStim method), 116  
 mro() (psychopy.visual.EnvelopeGrating method), 164  
 mro() (psychopy.visual.Line method), 133  
 mro() (psychopy.visual.NoiseStim method), 141  
 mro() (psychopy.visual.PatchStim method), 141  
 mro() (psychopy.visual.Polygon method), 141  
 mro() (psychopy.visual.Rect method), 154  
 mro() (psychopy.visual.SimpleImageStim method), 171  
 msecDelay() (in module pylink), 282  
 multiplyProjectionMatrixGL() (psychopy.visual.Rift method), 160  
 multiplyViewMatrixGL() (psychopy.visual.Rift method), 161  
 MultiStairHandler (class in psychopy.data), 214  
 multQuat() (in module psychopy.tools.mathtools), 368

## N

name (psychopy.hardware.crs.bits.BitsSharp attribute), 253  
 name (psychopy.hardware.emulator.ResponseEmulator attribute), 267  
 name (psychopy.hardware.emulator.SyncGenerator attribute), 268  
 name (psychopy.visual.BufferImageStim attribute), 111  
 name (psychopy.visual.GratingStim attribute), 121  
 name (psychopy.visual.ImageStim attribute), 130  
 name (psychopy.visual.MovieStim attribute), 135  
 name (psychopy.visual.RadialStim attribute), 147  
 name (psychopy.visual.ShapeStim attribute), 168  
 name (psychopy.visual.TextStim attribute), 186  
 nearClip (psychopy.visual.Window attribute), 194  
 newCalib() (psychopy.monitors.Monitor method), 339  
 next() (psychopy.data.MultiStairHandler method), 215  
 next() (psychopy.data.QuestHandler method), 220  
 next() (psychopy.data.StairHandler method), 212  
 next() (psychopy.data.TrialHandler method), 208  
 nextEntry() (psychopy.data.ExperimentHandler method), 205  
 NoiseStim (class in psychopy.visual), 139  
 normalize() (in module psychopy.tools.mathtools), 367

## O

OffsetVoiceKey (class in psychopy.voicekey), 384  
 OnsetVoiceKey (class in psychopy.voicekey), 383  
 opacity (psychopy.visual.BufferImageStim attribute), 111  
 opacity (psychopy.visual.GratingStim attribute), 121  
 opacity (psychopy.visual.ImageStim attribute), 130  
 opacity (psychopy.visual.MovieStim attribute), 136

opacity (psychopy.visual.RadialStim attribute), 147  
 opacity (psychopy.visual.ShapeStim attribute), 168  
 opacity (psychopy.visual.TextStim attribute), 186  
 openCustomGraphicsInternal() (in module pylink), 282  
 openGraphics() (in module pylink), 282  
 openMessageFile() (in module pylink), 282  
 openOutputFile() (in module psychopy.tools.filetools), 354  
 ori (psychopy.visual.BufferImageStim attribute), 111  
 ori (psychopy.visual.GratingStim attribute), 121  
 ori (psychopy.visual.ImageStim attribute), 130  
 ori (psychopy.visual.MovieStim attribute), 136  
 ori (psychopy.visual.RadialStim attribute), 147  
 ori (psychopy.visual.ShapeStim attribute), 168  
 ori (psychopy.visual.TextStim attribute), 186  
 orthoProjectionMatrix() (in module psychopy.tools.viewtools), 380  
 overlaps() (psychopy.visual.BufferImageStim method), 111  
 overlaps() (psychopy.visual.GratingStim method), 121  
 overlaps() (psychopy.visual.ImageStim method), 130  
 overlaps() (psychopy.visual.MovieStim method), 136  
 overlaps() (psychopy.visual.RadialStim method), 147  
 overlaps() (psychopy.visual.ShapeStim method), 168  
 overlaps() (psychopy.visual.TextStim method), 186  
 overlayPresent (psychopy.visual.Rift attribute), 161

## P

ParallelPort (class in psychopy.parallel), 343  
 parseSpectrumOutput() (psychopy.hardware.pr.PR650 method), 279  
 parseSpectrumOutput() (psychopy.hardware.pr.PR655 method), 280  
 PatchStim (class in psychopy.visual), 141  
 pause() (psychopy.hardware.crs.bits.BitsSharp method), 253  
 pause() (psychopy.sound.backend\_sounddevice.SoundDeviceSound method), 347  
 pause() (psychopy.visual.MovieStim method), 136  
 peak\_velocity\_xy (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313  
 peak\_velocity\_xy (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315  
 perspectiveProjectionMatrix() (in module psychopy.tools.viewtools), 380  
 phase (psychopy.visual.GratingStim attribute), 122  
 phase (psychopy.visual.RadialStim attribute), 147  
 pix2cm() (in module psychopy.tools.monitorunittools), 375  
 pix2deg() (in module psychopy.tools.monitorunittools), 375



- play() (psychopy.sound.backend\_pygame.SoundPygame method), 349
- play() (psychopy.sound.backend\_pyo.SoundPyo method), 348
- play() (psychopy.sound.backend\_sounddevice.SoundDevice method), 347
- play() (psychopy.visual.MovieStim method), 136
- playback() (psychopy.microphone.AdvAudioCapture method), 334
- playMarker() (psychopy.microphone.AdvAudioCapture method), 334
- plotFrameIntervals() (in module psychopy.tools.plottools), 375
- pointInPolygon() (in module psychopy.visual.helpers), 125
- pointToNdc() (in module psychopy.tools.viewtools), 381
- pol2cart() (in module psychopy.tools.coordinatetools), 354
- poll\_for\_response() (pyxid.ResponseDevice method), 232
- pollControllers() (psychopy.visual.Rift method), 161
- pollStatus() (psychopy.hardware.crs.bits.BitsSharp method), 253
- Polygon (class in psychopy.visual), 141
- polygonsOverlap() (in module psychopy.visual.helpers), 125
- pos (psychopy.visual.BufferImageStim attribute), 112
- pos (psychopy.visual.GratingStim attribute), 122
- pos (psychopy.visual.ImageStim attribute), 130
- pos (psychopy.visual.MovieStim attribute), 136
- pos (psychopy.visual.RadialStim attribute), 148
- pos (psychopy.visual.ShapeStim attribute), 168
- pos (psychopy.visual.Slider attribute), 173
- pos (psychopy.visual.TextStim attribute), 187
- poseToMatrix() (in module psychopy.tools.mathtools), 373
- posPix (psychopy.visual.TextStim attribute), 187
- ppd\_x (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311
- ppd\_x (psychopy.iohub.devices.eyetracker.MonocularEyeSaplingEvent attribute), 309
- ppd\_x (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 314
- ppd\_y (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311
- ppd\_y (psychopy.iohub.devices.eyetracker.MonocularEyeSaplingEvent attribute), 309
- ppd\_y (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 314
- PR650 (class in psychopy.hardware.pr), 278
- PR655 (class in psychopy.hardware.pr), 279
- Preferences (class in psychopy.preferences), 345
- pressEventID (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 296
- primeClock() (psychopy.hardware.crs.bits.BitsPlusPlus method), 234
- primeClock() (psychopy.hardware.crs.bits.BitsSharp method), 253
- printAsText() (psychopy.data.MultiStairHandler method), 215
- printAsText() (psychopy.data.QuestHandler method), 220
- printAsText() (psychopy.data.StairHandler method), 212
- printAsText() (psychopy.data.TrialHandler method), 208
- productName (psychopy.visual.Rift attribute), 161
- projectionMatrix (psychopy.visual.Rift attribute), 161
- projectionMatrix (psychopy.visual.Window attribute), 194
- ProjectorFramePacker (class in psychopy.visual.windowframepack), 198
- psychopy.clock (module), 201
- psychopy.core (module), 103
- psychopy.data (module), 204
- psychopy.hardware (module), 231
- psychopy.hardware.crs (module), 233
- psychopy.hardware.egi (module), 265
- psychopy.hardware.emulator (module), 266
- psychopy.hardware.forp (module), 270
- psychopy.hardware.iolab (module), 271
- psychopy.hardware.joystick (module), 272
- psychopy.hardware.minolta (module), 276
- psychopy.hardware.pr (module), 278
- psychopy.info (module), 284
- psychopy.iohub.client (module), 286
- psychopy.iohub.client.keyboard (module), 292
- psychopy.logging (module), 330
- psychopy.misc (module), 335
- psychopy.parallel (module), 342
- psychopy.preferences (module), 345
- psychopy.sound (module), 346
- psychopy.tools (module), 350
- psychopy.tools.colorspecttools (module), 350
- psychopy.tools.coordinatetools (module), 353
- psychopy.tools.filetools (module), 354
- psychopy.tools.glttools (module), 355
- psychopy.tools.imagetools (module), 366
- psychopy.tools.mathtools (module), 367
- psychopy.tools.monitorunittools (module), 374
- psychopy.tools.plottools (module), 375
- psychopy.tools.typetools (module), 375
- psychopy.tools.unittools (module), 375
- psychopy.tools.viewtools (module), 377
- psychopy.visual.windowframepack (module), 198
- psychopy.visual.windowwarp (module), 199
- pumpDelay() (in module pylink), 282
- pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311

pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309

pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 314

pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311

pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309

pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 313

pylink (module), 281

pyxid (module), 231

## Q

quantile() (psychopy.data.QuestHandler method), 220

quatFromAxisAngle() (in module psychopy.tools.mathtools), 370

quatToAxisAngle() (in module psychopy.tools.mathtools), 369

QuestHandler (class in psychopy.data), 217

quit() (psychopy.iohub.client.ioHubConnection method), 292

## R

radialCycles (psychopy.visual.RadialStim attribute), 148

radialPhase (psychopy.visual.RadialStim attribute), 148

RadialStim (class in psychopy.visual), 142

radians() (in module psychopy.tools.unittools), 375

rating (psychopy.visual.Slider attribute), 173

RatingScale (class in psychopy.visual), 151

raw\_x (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309

raw\_y (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309

raycastSphere() (psychopy.visual.Rift method), 161

read() (psychopy.hardware.crs.bits.BitsSharp method), 254

readData() (psychopy.parallel.ParallelPort method), 343

readline() (psychopy.hardware.crs.colorcal.ColorCAL method), 265

readPin() (psychopy.parallel method), 344

readPin() (psychopy.parallel.ParallelPort method), 343

rec709TF() (in module psychopy.tools.colorspacetools), 353

recenterTrackingOrigin() (psychopy.visual.Rift method), 162

record() (psychopy.microphone.AdvAudioCapture method), 334

recordFrameIntervals (psychopy.visual.Window attribute), 195

recordRating() (psychopy.visual.Slider method), 173

Rect (class in psychopy.visual), 154

removeTarget() (psychopy.logging.\_Logger method), 331

removeEvent() (psychopy.iohub.client.keyboard.Keyboard attribute), 294

requireInternetAccess() (in module psychopy.web), 386

resample() (psychopy.microphone.AdvAudioCapture method), 334

reset() (psychopy.clock.Clock method), 202

reset() (psychopy.clock.CountdownTimer method), 202

reset() (psychopy.core.CountdownTimer method), 104

reset() (psychopy.hardware.crs.bits.BitsPlusPlus method), 234

reset() (psychopy.hardware.crs.bits.BitsSharp method), 254

reset() (psychopy.microphone.AdvAudioCapture method), 334

reset() (psychopy.visual.Slider method), 173

resetBackground() (in module pylink), 282

resetClock() (psychopy.hardware.crs.bits.BitsPlusPlus method), 235

resetClock() (psychopy.hardware.crs.bits.BitsSharp method), 254

resetClock() (psychopy.hardware.iolab.ButtonBox method), 272

resetEyeTransform() (psychopy.visual.Window method), 195

resetPrefs() (psychopy.preferences.Preferences method), 345

resolution (psychopy.visual.Rift attribute), 162

response\_queue\_size() (pyxid.ResponseDevice method), 232

ResponseDevice (class in pyxid), 232

ResponseEmulator (class in psychopy.hardware.emulator), 266, 269

restoreBadPrefs() (psychopy.preferences.Preferences method), 345

rgb2dklCart() (in module psychopy.tools.colorspacetools), 351

rgb2lms() (in module psychopy.tools.colorspacetools), 351

Rift (class in psychopy.visual), 156

right\_angle\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310

right\_angle\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310

right\_eye\_cam\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 325

right\_eye\_cam\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 325

right\_eye\_cam\_z (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 326

right\_gaze\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 310, 325

right\_gaze\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 310, 325

attribute), 302, 310, 325  
 right\_ppd\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310  
 right\_ppd\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310  
 right\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310  
 right\_pupil\_measure1 (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 302, 310, 326  
 right\_raw\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 302, 310  
 right\_raw\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 302, 310  
 right\_velocity\_x (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310  
 right\_velocity\_xy (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 311  
 right\_velocity\_y (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 310  
 rms() (in module psychopy.voicekey), 385  
 rotationMatrix() (in module psychopy.tools.mathtools), 371  
 RTBoxAddKeys() (psychopy.hardware.crs.bits.BitsSharp method), 241  
 RTBoxCalibrate() (psychopy.hardware.crs.bits.BitsSharp method), 241  
 RTBoxClear() (psychopy.hardware.crs.bits.BitsSharp method), 241  
 RTBoxDisable() (psychopy.hardware.crs.bits.BitsSharp method), 241  
 RTBoxEnable() (psychopy.hardware.crs.bits.BitsSharp method), 241  
 RTBoxKeysPressed() (psychopy.hardware.crs.bits.BitsSharp method), 242  
 RTBoxResetKeys() (psychopy.hardware.crs.bits.BitsSharp method), 243  
 RTBoxSetKeys() (psychopy.hardware.crs.bits.BitsSharp method), 243  
 RTBoxWait() (psychopy.hardware.crs.bits.BitsSharp method), 243  
 RTBoxWaitN() (psychopy.hardware.crs.bits.BitsSharp method), 244  
 run() (psychopy.hardware.emulator.ResponseEmulator method), 267, 270  
 run() (psychopy.hardware.emulator.SyncGenerator method), 268, 270  
 runSetupProcedure() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 300  
 runSetupProcedure() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 307  
 runSetupProcedure() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 324  
 RunTimeInfo (class in psychopy.info), 284

## S

SampleEndEvent (class in psychopy.iohub.devices.eyetracker), 314  
 SampleStartEvent (class in psychopy.iohub.devices.eyetracker), 313  
 samples\_from\_file() (in module psychopy.voicekey), 385  
 samples\_from\_table() (in module psychopy.voicekey), 385  
 samples\_to\_file() (in module psychopy.voicekey), 385  
 save() (psychopy.monitors.Monitor method), 339  
 save() (psychopy.voicekey.OnsetVoiceKey method), 384  
 saveAppData() (psychopy.preferences.Preferences method), 345  
 saveAsExcel() (psychopy.data.MultiStairHandler method), 216  
 saveAsExcel() (psychopy.data.QuestHandler method), 220  
 saveAsExcel() (psychopy.data.StairHandler method), 212  
 saveAsExcel() (psychopy.data.TrialHandler method), 208  
 saveAsJson() (psychopy.data.MultiStairHandler method), 216  
 saveAsJson() (psychopy.data.QuestHandler method), 221  
 saveAsJson() (psychopy.data.StairHandler method), 213  
 saveAsJson() (psychopy.data.TrialHandler method), 209  
 saveAsPickle() (psychopy.data.ExperimentHandler method), 205  
 saveAsPickle() (psychopy.data.MultiStairHandler method), 216  
 saveAsPickle() (psychopy.data.QuestHandler method), 221  
 saveAsPickle() (psychopy.data.StairHandler method), 213  
 saveAsPickle() (psychopy.data.TrialHandler method), 209  
 saveAsText() (psychopy.data.MultiStairHandler method), 216  
 saveAsText() (psychopy.data.QuestHandler method), 221  
 saveAsText() (psychopy.data.StairHandler method), 213  
 saveAsText() (psychopy.data.TrialHandler method), 209  
 saveAsWideText() (psychopy.data.ExperimentHandler method), 205  
 saveAsWideText() (psychopy.data.TrialHandler method), 209  
 saveFrameIntervals() (psychopy.visual.Window method), 295  
 saveMon() (psychopy.monitors.Monitor method), 339

- saveMovieFrames() (psychopy.visual.Window method), 195
- saveUserPrefs() (psychopy.preferences.Preferences method), 345
- scaleMatrix() (in module psychopy.tools.mathtools), 371
- sd() (psychopy.data.QuestHandler method), 222
- seek() (psychopy.visual.MovieStim method), 136
- sendAnalog() (psychopy.hardware.crs.bits.BitsSharp method), 254
- sendCommand() (psychopy.iohub.devices.eyetracker.hw.srcamrapi.EyeTracker method), 307
- sendMessage() (psychopy.hardware.crs.bits.BitsSharp method), 255
- sendMessage() (psychopy.hardware.crs.colorcal.ColorCAL method), 265
- sendMessage() (psychopy.hardware.minolta.LS100 method), 277
- sendMessage() (psychopy.hardware.pr.PR650 method), 279
- sendMessage() (psychopy.hardware.pr.PR655 method), 280
- sendMessage() (psychopy.iohub.devices.eyetracker.hw.srcamrapi.EyeTracker method), 308
- sendMessageEvent() (psychopy.iohub.client.ioHubConnection method), 289
- sendMessageToFile() (in module pylink), 282
- sendTrigger() (psychopy.hardware.crs.bits.BitsPlusPlus method), 235
- sendTrigger() (psychopy.hardware.crs.bits.BitsSharp method), 255
- serialNumber (psychopy.visual.Rift attribute), 162
- setAmbientLight() (in module psychopy.tools.gltools), 364
- setAnalog() (psychopy.hardware.crs.bits.BitsSharp method), 255
- setAngularCycles() (psychopy.visual.RadialStim method), 148
- setAngularPhase() (psychopy.visual.RadialStim method), 148
- setAutoDraw() (psychopy.visual.BufferImageStim method), 112
- setAutoDraw() (psychopy.visual.GratingStim method), 122
- setAutoDraw() (psychopy.visual.ImageStim method), 131
- setAutoDraw() (psychopy.visual.MovieStim method), 136
- setAutoDraw() (psychopy.visual.RadialStim method), 148
- setAutoDraw() (psychopy.visual.ShapeStim method), 168
- setAutoDraw() (psychopy.visual.TextStim method), 187
- setAutoLog() (psychopy.visual.BufferImageStim method), 112
- setAutoLog() (psychopy.visual.GratingStim method), 122
- setAutoLog() (psychopy.visual.ImageStim method), 131
- setAutoLog() (psychopy.visual.MovieStim method), 137
- setAutoLog() (psychopy.visual.RadialStim method), 148
- setAutoLog() (psychopy.visual.ShapeStim method), 168
- setAutoLog() (psychopy.visual.TextBox method), 180
- setAutoLog() (psychopy.visual.TextStim method), 187
- setBackgroundColor() (psychopy.visual.TextBox method), 180
- setBlendmode() (psychopy.visual.GratingStim method), 122
- setBlendmode() (psychopy.visual.RadialStim method), 148
- setBorderColor() (psychopy.visual.TextBox method), 180
- setBorderWidth() (psychopy.visual.TextBox method), 180
- setBuffer() (psychopy.visual.Rift method), 162
- setBuffer() (psychopy.visual.Window method), 196
- setCalibDate() (psychopy.monitors.Monitor method), 339
- setCalibrationColors() (in module pylink), 283
- setCalibrationSounds() (in module pylink), 283
- setCameraPosition() (in module pylink), 283
- setColor() (psychopy.visual.BufferImageStim method), 112
- setColor() (psychopy.visual.GratingStim method), 122
- setColor() (psychopy.visual.ImageStim method), 131
- setColor() (psychopy.visual.RadialStim method), 148
- setColor() (psychopy.visual.ShapeStim method), 169
- setColor() (psychopy.visual.TextStim method), 187
- setContrast() (psychopy.hardware.crs.bits.BitsPlusPlus method), 235
- setContrast() (psychopy.hardware.crs.bits.BitsSharp method), 255
- setContrast() (psychopy.visual.BufferImageStim method), 112
- setContrast() (psychopy.visual.GratingStim method), 122
- setContrast() (psychopy.visual.ImageStim method), 131
- setContrast() (psychopy.visual.MovieStim method), 137
- setContrast() (psychopy.visual.RadialStim method), 148
- setContrast() (psychopy.visual.ShapeStim method), 169
- setContrast() (psychopy.visual.TextStim method), 187
- setCurrent() (psychopy.monitors.Monitor method), 339
- setData() (psychopy.hardware.labjacks.U3 method), 276
- setData() (psychopy.parallel method), 344
- setData() (psychopy.parallel.ParallelPort method), 343
- setDefaultClock() (in module psychopy.logging), 332, 333
- setDefaultView() (psychopy.visual.Rift method), 162
- setDepth() (psychopy.visual.BufferImageStim method), 112
- setDepth() (psychopy.visual.GratingStim method), 122
- setDepth() (psychopy.visual.ImageStim method), 131
- setDepth() (psychopy.visual.MovieStim method), 137
- setDepth() (psychopy.visual.RadialStim method), 148



- setDepth() (psychopy.visual.ShapeStim method), 169
- setDepth() (psychopy.visual.TextStim method), 187
- setDistance() (psychopy.monitors.Monitor method), 340
- setDKL() (psychopy.visual.BufferImageStim method), 112
- setDKL() (psychopy.visual.GratingStim method), 122
- setDKL() (psychopy.visual.ImageStim method), 131
- setDKL() (psychopy.visual.MovieStim method), 137
- setDKL() (psychopy.visual.RadialStim method), 148
- setDKL() (psychopy.visual.ShapeStim method), 169
- setDKL() (psychopy.visual.TextStim method), 187
- setDKL\_RGB() (psychopy.monitors.Monitor method), 340
- setDriftCorrectSounds() (in module pylink), 283
- setEnabled() (psychopy.hardware.iolab.ButtonBox method), 272
- setExclusive() (psychopy.event.Mouse method), 227
- setExp() (psychopy.data.MultiStairHandler method), 217
- setExp() (psychopy.data.QuestHandler method), 222
- setExp() (psychopy.data.StairHandler method), 214
- setExp() (psychopy.data.TrialHandler method), 210
- setFile() (psychopy.microphone.AdvAudioCapture method), 334
- setFillColor() (psychopy.visual.ShapeStim method), 169
- setFillRGB() (psychopy.visual.ShapeStim method), 169
- setFlip() (psychopy.visual.TextStim method), 187
- setFlipHoriz() (psychopy.visual.BufferImageStim method), 112
- setFlipHoriz() (psychopy.visual.MovieStim method), 137
- setFlipHoriz() (psychopy.visual.TextStim method), 187
- setFlipVert() (psychopy.visual.BufferImageStim method), 112
- setFlipVert() (psychopy.visual.MovieStim method), 137
- setFlipVert() (psychopy.visual.TextStim method), 187
- setFont() (psychopy.visual.TextStim method), 187
- setFontColor() (psychopy.visual.TextBox method), 180
- setGamma() (psychopy.hardware.crs.bits.BitsPlusPlus method), 236
- setGamma() (psychopy.hardware.crs.bits.BitsSharp method), 255
- setGamma() (psychopy.monitors.Monitor method), 340
- setGammaGrid() (psychopy.monitors.Monitor method), 340
- setHeight() (psychopy.visual.TextStim method), 188
- setHorzAlign() (psychopy.visual.TextBox method), 181
- setHorzJust() (psychopy.visual.TextBox method), 181
- setHudMode() (psychopy.visual.Rift method), 162
- setImage() (psychopy.visual.BufferImageStim method), 112
- setImage() (psychopy.visual.ImageStim method), 131
- setInterpolated() (psychopy.visual.TextBox method), 181
- setLevel() (psychopy.logging.LogFile method), 331
- setLevelsPost() (psychopy.monitors.Monitor method), 340
- setLevelsPre() (psychopy.monitors.Monitor method), 340
- setLights() (psychopy.hardware.iolab.ButtonBox method), 272
- setLineariseMethod() (psychopy.monitors.Monitor method), 340
- setLineColor() (psychopy.visual.ShapeStim method), 169
- setLineRGB() (psychopy.visual.ShapeStim method), 169
- setLineWidth() (psychopy.visual.ShapeStim method), 169
- setLMS() (psychopy.visual.BufferImageStim method), 112
- setLMS() (psychopy.visual.GratingStim method), 122
- setLMS() (psychopy.visual.ImageStim method), 131
- setLMS() (psychopy.visual.MovieStim method), 137
- setLMS() (psychopy.visual.RadialStim method), 149
- setLMS() (psychopy.visual.ShapeStim method), 169
- setLMS() (psychopy.visual.TextStim method), 188
- setLMS\_RGB() (psychopy.monitors.Monitor method), 340
- setLumsPost() (psychopy.monitors.Monitor method), 340
- setLumsPre() (psychopy.monitors.Monitor method), 340
- setLUT() (psychopy.hardware.crs.bits.BitsPlusPlus method), 236
- setLUT() (psychopy.hardware.crs.bits.BitsSharp method), 255
- setMarker() (psychopy.microphone.AdvAudioCapture method), 334
- setMask() (psychopy.visual.BufferImageStim method), 112
- setMask() (psychopy.visual.GratingStim method), 122
- setMask() (psychopy.visual.ImageStim method), 131
- setMask() (psychopy.visual.RadialStim method), 149
- setMaxAttempts() (psychopy.hardware.minolta.LS100 method), 277
- setMeanLum() (psychopy.monitors.Monitor method), 340
- setMode() (psychopy.hardware.minolta.LS100 method), 277
- setMouseType() (psychopy.visual.Window method), 196
- setMovie() (psychopy.visual.MovieStim method), 137
- setNotes() (psychopy.monitors.Monitor method), 340
- setOpacity() (psychopy.visual.BufferImageStim method), 113
- setOpacity() (psychopy.visual.GratingStim method), 123
- setOpacity() (psychopy.visual.ImageStim method), 131
- setOpacity() (psychopy.visual.MovieStim method), 137
- setOpacity() (psychopy.visual.RadialStim method), 149
- setOpacity() (psychopy.visual.ShapeStim method), 169
- setOpacity() (psychopy.visual.TextBox method), 181
- setOpacity() (psychopy.visual.TextStim method), 188
- setOri() (psychopy.visual.BufferImageStim method), 113
- setOri() (psychopy.visual.GratingStim method), 123
- setOri() (psychopy.visual.ImageStim method), 131
- setOri() (psychopy.visual.MovieStim method), 137

- setOri() (psychopy.visual.RadialStim method), 149
- setOri() (psychopy.visual.ShapeStim method), 169
- setOri() (psychopy.visual.TextStim method), 188
- setPerspectiveView() (psychopy.visual.Window method), 197
- setPhase() (psychopy.visual.GratingStim method), 123
- setPhase() (psychopy.visual.RadialStim method), 149
- setPin() (psychopy.parallel method), 344
- setPortAddress() (psychopy.parallel method), 343
- setPos() (psychopy.event.Mouse method), 227
- setPos() (psychopy.visual.BufferImageStim method), 113
- setPos() (psychopy.visual.GratingStim method), 123
- setPos() (psychopy.visual.ImageStim method), 131
- setPos() (psychopy.visual.MovieStim method), 137
- setPos() (psychopy.visual.RadialStim method), 149
- setPos() (psychopy.visual.ShapeStim method), 169
- setPos() (psychopy.visual.TextStim method), 188
- setPosition() (psychopy.visual.TextBox method), 181
- setPriority() (psychopy.iohub.client.ioHubConnection method), 291
- setProcessAffinity() (psychopy.iohub.client.ioHubConnection method), 291
- setPsychopyVersion() (psychopy.monitors.Monitor method), 340
- setRadialCycles() (psychopy.visual.RadialStim method), 149
- setRadialPhase() (psychopy.visual.RadialStim method), 149
- setReadOnly() (psychopy.visual.Slider method), 174
- setRecordingState() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 300
- setRecordingState() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyetracker.EyeTracker method), 308
- setRecordingState() (psychopy.iohub.devices.eyetracker.hw.tobii.EyeTracker method), 324
- setRGB() (psychopy.visual.BufferImageStim method), 113
- setRGB() (psychopy.visual.GratingStim method), 123
- setRGB() (psychopy.visual.ImageStim method), 131
- setRGB() (psychopy.visual.MovieStim method), 137
- setRGB() (psychopy.visual.RadialStim method), 149
- setRGB() (psychopy.visual.ShapeStim method), 169
- setRGB() (psychopy.visual.TextStim method), 188
- setRiftView() (psychopy.visual.Rift method), 162
- setRTBoxMode() (psychopy.hardware.crs.bits.BitsSharp method), 256
- setSF() (psychopy.visual.GratingStim method), 123
- setSF() (psychopy.visual.RadialStim method), 149
- setSize() (psychopy.visual.BufferImageStim method), 113
- setSize() (psychopy.visual.GratingStim method), 123
- setSize() (psychopy.visual.ImageStim method), 131
- setSize() (psychopy.visual.MovieStim method), 137
- setSize() (psychopy.visual.RadialStim method), 149
- setSize() (psychopy.visual.Rift method), 163
- setSize() (psychopy.visual.ShapeStim method), 169
- setSize() (psychopy.visual.TextStim method), 188
- setSizePix() (psychopy.monitors.Monitor method), 340
- setSound() (psychopy.sound.backend\_sounddevice.SoundDeviceSound method), 347
- setSpectra() (psychopy.monitors.Monitor method), 340
- setStatusBoxMode() (psychopy.hardware.crs.bits.BitsSharp method), 256
- setStatusBoxThreshold() (psychopy.hardware.crs.bits.BitsSharp method), 256
- setStatusEventParams() (psychopy.hardware.crs.bits.BitsSharp method), 256
- setTargetSize() (in module pylink), 283
- setTex() (psychopy.visual.GratingStim method), 123
- setTex() (psychopy.visual.RadialStim method), 149
- setText() (psychopy.visual.TextBox method), 181
- setText() (psychopy.visual.TextStim method), 188
- setTextGridLineColor() (psychopy.visual.TextBox method), 181
- setTextGridLineWidth() (psychopy.visual.TextBox method), 181
- setTrackinOrigin() (psychopy.visual.Rift method), 163
- setTrigger() (psychopy.hardware.crs.bits.BitsPlusPlus method), 236
- setTrigger() (psychopy.hardware.crs.bits.BitsSharp method), 257
- setTrigger() (psychopy.hardware.crs.bits.BitsPlusPlus method), 236
- setTriggerList() (psychopy.hardware.crs.bits.BitsSharp method), 257
- setupProxy() (in module psychopy.web), 386
- setUseBits() (psychopy.monitors.Monitor method), 340
- setUseShaders() (psychopy.visual.BufferImageStim method), 113
- setUseShaders() (psychopy.visual.GratingStim method), 123
- setUseShaders() (psychopy.visual.ImageStim method), 131
- setUseShaders() (psychopy.visual.MovieStim method), 137
- setUseShaders() (psychopy.visual.RadialStim method), 149
- setUseShaders() (psychopy.visual.ShapeStim method), 169
- setUseShaders() (psychopy.visual.TextStim method), 188
- setVertAlign() (psychopy.visual.TextBox method), 182

- setVertices() (psychopy.visual.ShapeStim method), 169
- setVertJust() (psychopy.visual.TextBox method), 182
- setVisible() (psychopy.event.Mouse method), 227
- setVolume() (psychopy.sound.backend\_pygame.SoundPygame method), 350
- setWidth() (psychopy.monitors.Monitor method), 340
- sf (psychopy.visual.GratingStim attribute), 123
- sf (psychopy.visual.RadialStim attribute), 149
- ShapeStim (class in psychopy.visual), 165
- shouldQuit (psychopy.visual.Rift attribute), 163
- shouldRecenter (psychopy.visual.Rift attribute), 163
- show() (psychopy.gui.Dlg method), 230
- show() (psychopy.gui.DlgFromDict method), 229
- shutdown() (psychopy.iohub.client.ioHubConnection method), 292
- SimpleImageStim (class in psychopy.visual), 171
- simulate() (psychopy.data.QuestHandler method), 222
- size (psychopy.visual.BufferImageStim attribute), 113
- size (psychopy.visual.GratingStim attribute), 123
- size (psychopy.visual.ImageStim attribute), 132
- size (psychopy.visual.MovieStim attribute), 137
- size (psychopy.visual.RadialStim attribute), 149
- size (psychopy.visual.Rift attribute), 163
- size (psychopy.visual.ShapeStim attribute), 170
- size (psychopy.visual.Slider attribute), 174
- size (psychopy.visual.TextStim attribute), 188
- size (psychopy.visual.Window attribute), 191
- slerp() (in module psychopy.tools.mathtools), 368
- Slider (class in psychopy.visual), 172
- slippage (psychopy.voicekey.OnsetVoiceKey attribute), 384
- smooth() (in module psychopy.voicekey), 385
- SoundDeviceSound (class in psychopy.sound.backend\_sounddevice), 346
- SoundPygame (class in psychopy.sound.backend\_pygame), 349
- SoundPyo (class in psychopy.sound.backend\_pyo), 348
- sph2cart() (in module psychopy.tools.coordinatestools), 354
- srgbTF() (in module psychopy.tools.colorspectools), 353
- StairHandler (class in psychopy.data), 210
- standby() (psychopy.hardware.iolab.ButtonBox method), 272
- start() (psychopy.clock.StaticPeriod method), 203
- start() (psychopy.core.StaticPeriod method), 105
- start() (psychopy.hardware.crs.bits.BitsSharp method), 258
- start() (psychopy.hardware.emulator.ResponseEmulator method), 267
- start() (psychopy.hardware.emulator.SyncGenerator method), 268
- start() (psychopy.voicekey.OnsetVoiceKey method), 384
- start\_angle\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_angle\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_angle\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_angle\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_gaze\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_gaze\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_gaze\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_gaze\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_ppd\_x (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_ppd\_x (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_ppd\_y (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_ppd\_y (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_pupil\_measure1\_type (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_pupil\_measure\_1 (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- start\_velocity\_xy (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 312
- start\_velocity\_xy (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
- startAnalog() (psychopy.hardware.crs.bits.BitsSharp method), 258
- startCustomTasklet() (psychopy.iohub.client.ioHubConnection method), 291
- started (psychopy.voicekey.OnsetVoiceKey attribute), 384
- startGoggles() (psychopy.hardware.crs.bits.BitsPlusPlus method), 237
- startGoggles() (psychopy.hardware.crs.bits.BitsSharp method), 258
- startOfFlip() (psychopy.visual.windowframepack.ProjectorFramePacker method), 198
- startRemoteMode() (psychopy.hardware.pr.PR655 method), 280
- startStimulusLog() (psychopy.hardware.crs.bits.BitsSharp method), 258

- startTrigger() (psychopy.hardware.crs.bits.BitsPlusPlus method), 237
  - startTrigger() (psychopy.hardware.crs.bits.BitsSharp method), 259
  - state (psychopy.iohub.client.keyboard.Keyboard attribute), 294
  - StaticPeriod (class in psychopy.clock), 203
  - StaticPeriod (class in psychopy.core), 104
  - status (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 302, 311, 326
  - status (psychopy.iohub.devices.eyetracker.BlinkEndEvent attribute), 316
  - status (psychopy.iohub.devices.eyetracker.BlinkStartEvent attribute), 315
  - status (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 313
  - status (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311
  - status (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309
  - status (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 315
  - status (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 314
  - statusBoxAddKeys() (psychopy.hardware.crs.bits.BitsSharp method), 259
  - statusBoxDisable() (psychopy.hardware.crs.bits.BitsSharp method), 260
  - statusBoxEnable() (psychopy.hardware.crs.bits.BitsSharp method), 260
  - statusBoxKeysPressed() (psychopy.hardware.crs.bits.BitsSharp method), 261
  - statusBoxResetKeys() (psychopy.hardware.crs.bits.BitsSharp method), 261
  - statusBoxSetKeys() (psychopy.hardware.crs.bits.BitsSharp method), 261
  - statusBoxWait() (psychopy.hardware.crs.bits.BitsSharp method), 261
  - statusBoxWaitN() (psychopy.hardware.crs.bits.BitsSharp method), 262
  - std() (in module psychopy.voicekey), 385
  - stop() (psychopy.hardware.crs.bits.BitsSharp method), 262
  - stop() (psychopy.microphone.AdvAudioCapture method), 334
  - stop() (psychopy.sound.backend\_pygame.SoundPygame method), 350
  - stop() (psychopy.sound.backend\_pyo.SoundPyo method), 349
  - stop() (psychopy.sound.backend\_sounddevice.SoundDeviceSound method), 347
  - stop() (psychopy.visual.MovieStim method), 138
  - stop() (psychopy.voicekey.OnsetVoiceKey method), 384
  - stopAnalog() (psychopy.hardware.crs.bits.BitsSharp method), 262
  - stopCustomTasklet() (psychopy.iohub.client.ioHubConnection method), 292
  - stopGoggles() (psychopy.hardware.crs.bits.BitsPlusPlus method), 237
  - stopGoggles() (psychopy.hardware.crs.bits.BitsSharp method), 263
  - stopStatusLog() (psychopy.hardware.crs.bits.BitsSharp method), 263
  - stopTrigger() (psychopy.hardware.crs.bits.BitsPlusPlus method), 238
  - stopTrigger() (psychopy.hardware.crs.bits.BitsSharp method), 263
  - stream (psychopy.sound.backend\_sounddevice.SoundDeviceSound attribute), 348
  - style (psychopy.visual.Slider attribute), 174
  - switchOn() (in module psychopy.microphone), 333
  - syncClocks() (psychopy.hardware.crs.bits.BitsPlusPlus method), 238
  - syncClocks() (psychopy.hardware.crs.bits.BitsSharp method), 264
  - SyncGenerator (class in psychopy.hardware.emulator), 267, 270
- ## T
- table\_from\_file() (in module psychopy.voicekey), 385
  - table\_from\_samples() (in module psychopy.voicekey), 385
  - table\_to\_file() (in module psychopy.voicekey), 385
  - temporalDithering (psychopy.hardware.crs.bits.BitsSharp attribute), 264
  - tex (psychopy.visual.GratingStim attribute), 124
  - tex (psychopy.visual.RadialStim attribute), 150
  - texRes (psychopy.visual.BufferImageStim attribute), 113
  - texRes (psychopy.visual.GratingStim attribute), 124
  - texRes (psychopy.visual.ImageStim attribute), 132
  - texRes (psychopy.visual.RadialStim attribute), 150
  - text (psychopy.visual.TextStim attribute), 188
  - TextBox (class in psychopy.visual), 176
  - TextStim (class in psychopy.visual), 182
  - time (psychopy.iohub.client.keyboard.KeyboardPress attribute), 296
  - time (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 297
  - time (psychopy.iohub.devices.eyetracker.BinocularEyeSampleEvent attribute), 301, 309, 325
  - time (psychopy.iohub.devices.eyetracker.BlinkEndEvent attribute), 316



- time (psychopy.iohub.devices.eyetracker.BlinkStartEvent attribute), 315
  - time (psychopy.iohub.devices.eyetracker.FixationEndEvent attribute), 302, 312
  - time (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 302, 311
  - time (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 308
  - time (psychopy.iohub.devices.eyetracker.SaccadeEndEvent attribute), 314
  - time (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 313
  - timeOnFlip() (psychopy.visual.Window method), 197
  - toFile() (in module psychopy.tools.filetools), 354
  - tone() (in module psychopy.voicekey), 385
  - trackerSec() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 301
  - trackerSec() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 308
  - trackerTime() (psychopy.iohub.devices.eyetracker.hw.gazepoint.gp3.EyeTracker method), 301
  - trackerTime() (psychopy.iohub.devices.eyetracker.hw.sr\_research.eyelink.EyeTracker method), 308
  - trackingOriginType (psychopy.visual.Rift attribute), 163
  - translationMatrix() (in module psychopy.tools.mathtools), 371
  - TrialHandler (class in psychopy.data), 206
  - type (psychopy.iohub.client.keyboard.KeyboardPress attribute), 296
  - type (psychopy.iohub.client.keyboard.KeyboardRelease attribute), 297
- ## U
- U3 (class in psychopy.hardware.labjacks), 276
  - uint8\_float() (in module psychopy.tools.typetools), 375
  - uncompress() (psychopy.microphone.AdvAudioCapture method), 335
  - units (psychopy.event.Mouse attribute), 227
  - units (psychopy.visual.BufferImageStim attribute), 113
  - units (psychopy.visual.GratingStim attribute), 124
  - units (psychopy.visual.ImageStim attribute), 132
  - units (psychopy.visual.MovieStim attribute), 138
  - units (psychopy.visual.RadialStim attribute), 150
  - units (psychopy.visual.ShapeStim attribute), 170
  - units (psychopy.visual.TextStim attribute), 188
  - units (psychopy.visual.Window attribute), 197
  - useFBO() (in module psychopy.tools.gltools), 358
  - useLights() (in module psychopy.tools.gltools), 363
  - useMaterial() (in module psychopy.tools.gltools), 363
  - useShaders (psychopy.visual.BufferImageStim attribute), 114
  - useShaders (psychopy.visual.GratingStim attribute), 124
  - useShaders (psychopy.visual.ImageStim attribute), 132
  - useShaders (psychopy.visual.MovieStim attribute), 138
  - useShaders (psychopy.visual.RadialStim attribute), 150
  - useShaders (psychopy.visual.ShapeStim attribute), 170
  - useShaders (psychopy.visual.TextStim attribute), 189
- ## V
- validate() (psychopy.preferences.Preferences method), 345
  - VBI, 28
  - VBI blocking, 28
  - VBI syncing, 28
  - velocity\_x (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309
  - velocity\_xy (psychopy.iohub.devices.eyetracker.FixationStartEvent attribute), 311
  - velocity\_xy (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309
  - velocity\_xy (psychopy.iohub.devices.eyetracker.SaccadeStartEvent attribute), 314
  - velocity\_y (psychopy.iohub.devices.eyetracker.MonocularEyeSampleEvent attribute), 309
  - vertices (psychopy.visual.ShapeStim attribute), 170
  - verticesPix (psychopy.visual.BufferImageStim attribute), 114
  - verticesPix (psychopy.visual.GratingStim attribute), 124
  - verticesPix (psychopy.visual.ImageStim attribute), 132
  - verticesPix (psychopy.visual.MovieStim attribute), 138
  - verticesPix (psychopy.visual.RadialStim attribute), 150
  - verticesPix (psychopy.visual.ShapeStim attribute), 170
  - verticesPix (psychopy.visual.TextStim attribute), 189
  - viewMatrix (psychopy.visual.Rift attribute), 163
  - viewMatrix (psychopy.visual.Window attribute), 197
  - viewPos (psychopy.visual.Window attribute), 198
  - visibleWedge (psychopy.visual.RadialStim attribute), 150
- ## W
- wait() (in module psychopy.clock), 202
  - wait() (in module psychopy.core), 103
  - wait\_for\_event() (psychopy.voicekey.OnsetVoiceKey method), 384
  - waitBlanking (psychopy.visual.Window attribute), 198
  - waitEvents() (psychopy.hardware.iolab.ButtonBox method), 272
  - waitForKeys() (psychopy.iohub.client.keyboard.Keyboard method), 294
  - waitForPresses() (psychopy.iohub.client.keyboard.Keyboard method), 295
  - waitForReleases() (psychopy.iohub.client.keyboard.Keyboard method), 295
  - waitKeys() (in module psychopy.event), 227
  - warn() (in module psychopy.logging), 332
  - warning() (in module psychopy.logging), 332
  - Warper (class in psychopy.visual.windowwrap), 199
  - wav2flac() (in module psychopy.microphone), 335

win (psychopy.hardware.crs.bits.BitsSharp attribute), 264  
win (psychopy.visual.BufferImageStim attribute), 114  
win (psychopy.visual.GratingStim attribute), 124  
win (psychopy.visual.ImageStim attribute), 132  
win (psychopy.visual.MovieStim attribute), 138  
win (psychopy.visual.RadialStim attribute), 151  
win (psychopy.visual.ShapeStim attribute), 170  
win (psychopy.visual.TextStim attribute), 189  
Window (class in psychopy.visual), 189  
wrapWidth (psychopy.visual.TextStim attribute), 189  
write() (psychopy.logging.LogFile method), 331

## X

XboxController (class in psychopy.hardware.joystick),  
273  
XidDevice (class in pyxid), 232  
xlsx, 28  
xydist() (in module psychopy.event), 228

## Z

zero\_crossings() (in module psychopy.voicekey), 385